



# Town of Johnstown

## TOWN COUNCIL REGULAR MEETING

450 S. Parish, Johnstown, CO  
Monday, April 17, 2023 at 7:00 PM

---

*MISSION STATEMENT: Enhancing the quality of life of our residents, businesses, and visitors through community focused leadership.*

---

### AGENDA

#### CALL TO ORDER

Pledge of Allegiance

#### ROLL CALL

#### AGENDA APPROVAL

#### SPECIAL PRESENTATIONS

- [1.](#) Arbor Day Proclamation
- [2.](#) Weld County Department of Public Health and Environment Presentation

#### PUBLIC COMMENT

*Members of the audience are invited to speak at the Council meeting. Public Comment is reserved for citizen comments on items not contained on the Public Hearing portion of the agenda. Citizen comments are limited to three (3) minutes per speaker. When several people wish to speak on the same position on a given item, they are requested to select a spokesperson to state that position.*

#### CONSENT AGENDA

*The Consent Agenda is a group of routine matters to be acted on with a single motion and vote. Council or staff may request an item be removed from the Consent Agenda and placed on the Regular Agenda for discussion.*

- [3.](#) April 3, 2023 Meeting Minutes
- [4.](#) Resolution 2023-20: Opposing Statewide Land Use And Zoning Preemptions In Senate Bill 23-213
- [5.](#) Agreement For Disaster-Emergency Mutual Aid and Disaster-Emergency Funding Assistance
- [6.](#) Water & Sewer Service Agreement - Sunbelt Rentals with MPV SBR Investors III, LLC
- [7.](#) March 2023 Financial Statements

#### TOWN MANAGER REPORT

#### TOWN ATTORNEY REPORT

The Community That Cares

[johnstown.colorado.gov](http://johnstown.colorado.gov)

P: 970.587.4664 | 450 S. Parish Ave, Johnstown CO 80534 | F: 970.587.0141

**OLD BUSINESS**

- [8.](#) Resolution 2023-16: Findings Of Fact and Conclusions Based Thereon With Respect to the Archdiocese Annexation Nos. 1-3

**NEW BUSINESS**

- [9.](#) Discussion - Water Policy

**PUBLIC HEARING**

- [10.](#) Ordinance 2023-244 regarding the Archdiocese Annexation Nos. 1-3
- [11.](#) Ordinance 2023-245 Approving PUD-MU Zoning for the properties known as Archdiocese Annexation Nos. 1-3
- [12.](#) Ordinance 2023-246 Approving the Outline Development Plan for Dove Solar
- [13.](#) Resolution 2023-17 Approving a Use by Special Review for the Dove Solar Array
- [14.](#) Ordinance 2023-247 Repealing Chapters 15, 16 and 17 of the Johnstown Municipal Code, and Readopting Chapter 17 of the Johnstown Municipal Code to adopt the Johnstown Land Use & Development Code by Reference

**COUNCIL REPORTS AND COMMENTS**

**MAYOR’S COMMENTS**

**INFORMATIONAL ITEMS**

- [15.](#) Informational Items

**ADJOURN**

---

**AMERICANS WITH DISABILITIES ACT NOTICE**

**In accordance with the Americans with Disabilities Act, and other applicable laws, persons who need accommodation in order to attend or participate in this meeting should contact Town Hall at (970) 587-4664 no later than 48 hours before the meeting in order to request such assistance.**

---





# Town of Johnstown

## Proclamation

**WHEREAS**, in 1872 the Nebraska Board of Agriculture established a special day to be set aside for the planting of trees; and

**WHEREAS**, this holiday, called Arbor Day, was first observed with the planting of more than a million trees in Nebraska; and

**WHEREAS**, Arbor Day is now observed throughout the nation and the world; and

**WHEREAS**, trees can be a solution to combating climate change by reducing the erosion of our precious topsoil by wind and water, cutting heating and cooling costs, moderating the temperature, cleaning the air, producing life-giving oxygen, and providing habitat for wildlife; and

**WHEREAS**, trees are a renewable resource giving us paper, wood for our homes, fuel for our fires, and countless other wood products; and

**WHEREAS**, trees in our towns and cities increase property values, enhance the economic vitality of business areas, and beautify our community; and

**WHEREAS**, trees – wherever they are planted – are a source of joy and spiritual renewal.

**NOW, THEREFORE**, BE IT RESOLVED BY THE TOWN COUNCIL OF THE TOWN OF JOHNSTOWN, COLORADO THAT:

I, Gary Lebsack, Mayor of the Town of Johnstown, Colorado do hereby proclaim April 28, 2023 as ARBOR DAY in the Town of Johnstown, and I urge all citizens to celebrate Arbor Day and to support efforts to protect our trees and woodlands, and plant trees to gladden the heart and promote the well-being of this and future generations.

TOWN OF JOHNSTOWN, COLORADO

By: \_\_\_\_\_  
Gary Lebsack, Mayor

The Community That Cares

[johnstown.colorado.gov](http://johnstown.colorado.gov)

P: 970.587.4664 | 450 S. Parish Ave, Johnstown CO 80534 | F: 970.587.0141





# Key Findings Overview

2022 Weld County Community Health Assessment Survey | Johnstown 04/17/2023






# Survey Overview & Methods




# What is a Community Health Assessment (CHA)?



- Provides **foundation** to improve the health of a population
- Tells the **community story**
- Identifies **health disparities** among different subpopulations and the factors that contribute to them
- **Supports the community's efforts** to achieve health equity
- Data obtained from a **variety of sources** using various data collection methods


# Since 2007, about **15,000** residents have participated in our triennial surveys



All Years - Full Mail Design, Multi-mode

# Questionnaire Covers These Areas & More


Item #2.



# How is the Weld CHS done?



Randomly selected households




One **adult** (age 18+) per household




**English** and **Spanish**



**Online** and **paper**



# How is the Weld CHS done?



Fielded **May – August** 2022



**Tailored responsive** mail-based design



**Geographic** sampling




**Repeated** mailing waves



# Weld CHS Data Collection Method

Item #2.



**No** incentives used




Up to **5** contacts by mail



Overall response rate: **11%**

# Region Highlight: Johnstown/Milliken

Item #2.



Esri, NASA, NGA, USGS, Esri, HERE, Garmin, SafeGraph, FAO, METI/NASA, USGS, EPA, NPS



Johnstown /  
Milliken






# Key Data Findings Preview



# Health Status and Conditions

Chronic Conditions & Self-Rated Health

# The prevalence of many chronic conditions have increased Item #2.



- Asthma
- Diabetes
- High Blood Pressure
- High Cholesterol

## Johnstown/Milliken



**23%** high blood pressure  
**24%** high cholesterol  
**13%** asthma  
**4%** diabetes

*Not significantly different  
from other regions*



# Self-rated health has worsened, the gap among Hispanic/Latino/a residents has widened

Item #2.






# Health Insurance and Use

Health Insurance & Delayed Care

# Countywide, 7.9% of adult residents said they did not have health insurance of any kind Item #2.

## Weld County Uninsured Rate



- ↑ 18-34-year-olds (10.7%)
- ↑ Hispanic/Latino/a residents (23.4%)
- ↑ Those with less than a HS diploma/GED (26.7%)

### Johnstown/Milliken

6.7% Uninsured

*Not significantly different from other regions*






# Nearly 1 in 3 residents said that they delayed or went without needed health care in the past year Item #2.

## Top reasons for delaying care:

- **Cost** (49.5%)
- **Appointment availability** (36.6%)
- **Time off work** (23.4%)



### Johnstown/Milliken


**28%** delayed or went without needed medical care

*Not significantly different from other regions*

# Healthy Lifestyle Behaviors

Fruit/Vegetable Intake, Perception of Walkability

# More than 80% of adult residents reported they did NOT eat the recommended number of fruit/vegetable servings per day



**Johnstown/Milliken\***

**87%** did NOT meet the 5(+) servings for f/v per day

*This was significantly worse than northern region (70%), Carbon Valley region (74%) and Windsor/Severance (75%)*

Over **1 in 3** residents reported they were concerned that there aren't enough sidewalks or trails to walk or bike in their community (34%)



**Johnstown/Milliken\***

**40%** were concerned that there aren't enough sidewalks or trails to walk or bike in their community

*This was significantly **worse** than northern region (29%) and Windsor/Severance (23%)*



# Social-Emotional Wellbeing

Mental Health Treatment, Frequent Mental Health Distress & Resiliency

# More residents who reported they needed behavioral health care actually sought treatment

Item #2.

## Johnstown/Milliken

61% of those residents sought treatment

55%  
2019




61%  
2022

Thought they needed care AND sought treatment

# Over 1 in 7 residents (15.2%) reported they had frequent mental health distress


If a resident reported they had 14 or more bad mental health days in the last 30 days → frequent mental health distress

**Johnstown/Milliken**  
**18%** reported frequent mental health distress  
*Not significantly different from other regions*




# Generally, adult residents in Weld County reported they had fair to good levels of resiliency Item #2.

## Stress Resistance



## Bounce Back



### Johnstown/Milliken

3.9 / 10 for stress resistance score

*Not significantly different from other regions*

### Johnstown/Milliken

2.3 / 5 for bounce back score

*Not significantly different from other regions*




# Risky Lifestyle Behaviors

Alcohol & Tobacco Use

Nearly 1 in 4 adults report binge-drinking in the past 30 days, higher than the statewide rate

**Johnstown/Milliken**  
**23%** reported binge-drinking  
*Not significantly different from other regions*

### Adults Reporting Binge-Drinking




About 14% of adults use some form of tobacco and 8% reported cigarette use

While overall tobacco use has decreased, vaping (e-cigarette) use has increased

**Johnstown/Milliken**  
8% reported cigarette use  
*Not significantly different from other regions*

Trends in Tobacco Product Use






# Health and Housing

Housing Instability, Housing Cost Burden

# One-third of residents say they spend more than 30% their income on mortgage or rent and utility payments Item #2.



**Johnstown/Milliken**  
**35%** reported housing cost burden  
*Not significantly different from other regions*

## I-25 Corridor

**38%** reported being worried or stressed about paying for housing at least rarely

*Not significantly different from other regions*



Over **2 in 5** residents were worried about paying rent or mortgage (**44.3%**) at least rarely



# Health, Community, and the Environment

Environmental Health Concerns and Air Quality




# Residents' leading environmental concern is **outdoor air quality**

## **62.2%** of Weld County adults are moderately or very concerned

**Johnstown/Milliken\***

**59%** reported being worried about the level of outdoor air quality

*\*Significantly **higher** than northern region of the count (51%) but lower than Carbon Valley (67%)*





# All Environmental Health Concerns Covered in 2022 Survey

Item #2.


Environmental Health-Related Concern	Percent Moderately or Very Concerned
Level of outdoor air quality	62.2%
Pollution from oil and gas operations	51.8%
Disposal of household hazardous waste in landfills	50.7%
Pollution from vehicles	49.0%
Pollution from agricultural operations	40.4%
Exposure to radon in your home	30.9%
Potential rabies exposure for you, your family, pets, or livestock	25.2%

# Emergency Preparedness

Need Help in Emergency



# Needing help in a emergency was higher in rural and Greeley/Evans regions of the county; lower in Johnstown/Milliken



Needing help in an emergency included residents who reported they would need help or assistance with evacuation transportation, medical assistance to maintain their health, and/or have medical equipment dependent on electricity



A scenic landscape featuring a calm lake in the foreground, reflecting the surrounding environment. The middle ground is filled with trees in various stages of autumn, with some showing vibrant yellow and orange foliage. In the background, a range of mountains is visible, with several peaks covered in snow under a clear blue sky. A large, prominent tree with bright yellow leaves stands on the right side of the lake. The overall atmosphere is peaceful and serene.

# Next Steps & Moving Forward



# Next Steps

## Key Findings Report

- Report will be available on our website
- Resident comments report
- COVID-19 key findings

## Online Data Dashboard

- Filter by topic, question, and see differences by demographic characteristics

## Focus Group Findings

- General healthcare access and behavioral healthcare access

## Mapping Analyses

- As needed for special analyses

# Highlight: Resident Comments

Top Themes



*What are the top three health concerns facing you, your family, and/or your community right now?*

---

1. Healthcare

---

2. COVID-19

---

3. Mental health

---

4. Aging

---

5. Safety, crime & drugs

---

6. Air quality

---

7. Inflation

---

8. Food

- **WCDPHE website:**  
<https://www.weld.gov/Government/Departments/Health-and-Environment>
- **2022 Weld Community Health Survey webpage:**  
<https://www.weld.gov/Government/Departments/Health-and-Environment/Data-and-Reports/Community-Health-Surveys/2022-Community-Health-Survey>
- **Leading Health Indicators dashboard:**  
<https://www.weld.gov/Government/Departments/Health-and-Environment/Data-and-Reports/Leading-Health-Indicator-Dashboard>

# Resources





**Thank you!**



# Vital Records

## Birth and Death Certificates

- Issues certified birth and death certificates for the state of Colorado as a local registrar



# Board of Public Health

The Board of Public Health reviews and makes recommendations regarding biosolids and septage applications, as well as variances for On-Site Wastewater Treatment Systems. Board meetings are at 9:00 a.m. the 4th Tuesday of each month.



# MISSION

We serve Weld County by cultivating partnerships to promote public health and environmental quality through the delivery of relevant, innovative, and cost-effective services.

# VISION

Everyone in Weld County has the opportunity to live their healthiest lives.

# VALUES

Determination      Integrity      Excellence

[www.weldhealth.org](http://www.weldhealth.org)




**Greeley:**  
1555 N. 17th Ave.  
Greeley, CO 80631  
(970) 400-6410

**Longmont:**  
4209 WCR 24 1/2  
Longmont, CO 80504  
(720) 652-4240



Item #2.

# WHAT IS PUBLIC HEALTH?



## Weld County Department of Public Health and Environment



**Public Health**  
Prevent. Promote. Protect.



# Clinical & Community Health Services



## Immunizations


- Routine and recommended vaccines for adults and children, as well as vaccines for travel abroad

## Nurse-Family Partnership (NFP)

- Nurse home visitors provide free support and resource navigation to qualified first-time moms starting in pregnancy through the 2nd birthday

## Reproductive Health/ Family Planning

- STI testing and treatment, pregnancy tests, birth control, well-woman exams, and HIV prevention treatments



## Women's Wellness Connection (WWC) and WISEWOMAN

- Free breast and cervical cancer screenings, as well as cardiovascular and diabetes screenings for uninsured or underinsured women

## Children with Special Health Care Needs

- Connects children with special health care needs and their families with support resources

## Presumptive Eligibility

- Immediate temporary medical coverage for children under 19 or pregnant women for up to 60 days



# Environmental Health Services

## Food Safety

- Licenses and inspects retail food establishments and teaches safe food-handling practices

## Animal-Related Diseases


- Investigates diseases that are spread from animals to humans to prevent further spread

## Disease Control and Prevention

- Investigates infectious diseases, responds to outbreaks, provides education and referrals, and documents disease incidence

## Health Inspections Programs

- Inspects for the safe operation of ambulance services, body art establishments, child care centers, and schools



## Lead Program

- Conducts home investigations involving children with elevated blood lead levels

## Air Quality Program

- Addresses air quality complaints, issues open burn permits, inspects stationary sources of air pollution, and monitors air quality



## Laboratory

- Provides microbiology and chemistry analyses for drinking water and wastewater

## Environmental Planning

- Reviews proposed land uses and provides expertise on the public health issues of a proposed development

## Waste Program

- Interacts with compost and solid waste facilities through land use planning, site inspections, and complaint investigations



## Hazardous Waste Disposal

- Offers free disposal of household products that can harm humans, animals, and the environment

## Septic Systems

- Permits, evaluates, and inspects new existing onsite wastewater treatment systems

Item #2.

## Biosolids and Septage

- Implements regulations and issues land application permits

# Health Education, Communication, & Planning



## Childhood Obesity Prevention

- Collaborates with municipalities and early education settings to promote healthy eating, physical activity, and breastfeeding

## Healthy Eating and Active Living

- Focuses on the built environment, policies, and systems influencing health and obesity prevention

## Cooking Matters

- Teaches those with a limited food budget to shop for and cook healthy, affordable meals

## Substance Abuse Prevention

- Prevents substance use among young people through effective programs and policies


## DRIVE SMART Weld County

- Works to reduce injuries and deaths from traffic crashes among teens



## WeldWAITS

- Educates teens about the benefits of delayed sexual debut and equips them with the skills needed to develop healthy relationships



## Data and Statistics

- The collection and analysis of various health indicators

45



# Town of Johnstown

## TOWN COUNCIL REGULAR MEETING

450 S. Parish, Johnstown, CO  
Monday, April 03, 2023 at 7:00 PM

---

### MINUTES

#### CALL TO ORDER

Mayor Gary Lebsack called the meeting to order at 7:00 p.m. and led the Pledge of Allegiance.

#### Pledge of Allegiance

#### ROLL CALL

Present:

Mayor Lebsack  
Councilmember Mellon  
Councilmember Molinar  
Councilmember Morris  
Councilmember Young

Absent:

Councilmember Dominguez  
Councilmember Berg

#### AGENDA APPROVAL

*Councilmember Mellon moved to approve the agenda.*

Councilmember Molinar seconded and the motion passed.

#### SPECIAL PRESENTATIONS

1. Business of the Month

Sarah Crosthwaite, Economic Development Manager presented Connected Chiropractic with Business of the Month.

#### PUBLIC COMMENT

Bob Cogswell spoke to crime in Johnstown.

Frank Eubanks sent in a comment regarding Mallard Ridge maintenance fee.

#### CONSENT AGENDA

*Councilmember Mellon moved to approve the consent agenda.*

Councilmember Morris seconded and the motion passed.

2. March 6, 2023 Meeting Minutes

3. March 20, 2023 Minutes

The Community That Cares

[johnstown.colorado.gov](http://johnstown.colorado.gov)

P: 970.587.4664 | 450 S. Parish Ave, Johnstown CO 80534 | F: 970.587.0141



4. Ordinance 2023-243 An Ordinance concerning Municipal Court procedures
5. Resolution No. 2023-15 Appointing Deputy Municipal Judges for the Municipal Court
6. Resolution 2023-19 Amending the Fiscal Year 2022 Budget
7. First Amendment to the Intergovernmental Agreement with Larimer County for Contributions to Roadway Improvements Concerning Maintenance of Public Roadway (LCR 14)
8. Second Amendment to Intergovernmental Agreement Between the Town Of Johnstown and the Little Thompson Water District
9. Intergovernmental Agreement with Larimer County For County Road 3
10. Agreement to perform an emergency repair on the WTP North Ground Storage Tank Emergency Repair with Tanco Engineering, Inc.
11. Water and Sewer Agreement for Trade at 2534, Amendment 1, Lot 3
12. Water and Sewer Service Agreement for Front Range Fire Rescue Station #1
13. February 2023 Financial Statements
14. March 2023 List of Bills

#### **TOWN MANAGER REPORT**

15. Town Manager's Report

Matt LeCerf, Town Manager, presented the monthly report. Mr. LeCerf asked Council if they would like staff to present a resolution in opposition of Senate Bill 2023-213.

#### **TOWN ATTORNEY REPORT**

There was no Town Attorney Report.

#### **NEW BUSINESS**

16. An Agreement Between the Town of Johnstown and D2C Architects for the Design and Expansion of the Police Department

Brian Phillips, Chief of Police, presented this agreement and noted it was a pre-design and proposed expansion for the Police Department. Chief Phillips noted the current lack of storage and office space or community room.

Council inquired on the timeline of the project, and expressed concern on ensuring that needs going forward will be met.

Eric Combs, Vice President of D2C Architects, noted they may be breaking ground early 2024 if not before, and are looking to design to the Police Department's future needs.

*Councilmember Morris moved to approve the Standard Form Agreement Between the Town and D2C Architects.*

Councilmember Mellon seconded and the motion passed.

17. A Guaranteed Maximum Price (GMP) Construction Award to Moltz Construction for the Central Wastewater Treatment Plan

Ellen Hilbig, Utilities Director, provided a history and overview of this project to Council.

*Councilmember Mellon moved to award the Construction Contract for the Central Wastewater Treatment Plant to Moltz Construction, Inc. for a Guaranteed Maximum Price (GMP) of \$52,804,817.00*

Councilmember Young seconded and the motion passed.

18. An Amendment to Construction Engineering Services with Aqua Engineering for the Central Wastewater Treatment Plant

Ms. Hilbig noted this additional amount covers the extended construction schedule.

*Councilmember Molinar moved to amend the Construction Engineering Services Contract with AQUA Engineering, Inc. with an additional amount not to exceed \$1,016,537.00.*

Councilmember Morris seconded and the motion passed.

19. RFP Award for Aquatic Center Feasibility Study

Mitzi McCoy, Deputy Town Manager, presented this proposal to Council and noted four bids were received to the Request for Proposal.

Council asked for confirmation that the community is interested in serving on the committee, which Ms. McCoy confirmed several applications have been received.

*Councilmember Mellon moved to approve awarding the Aquatic Center Feasibility Study to OLC Architecture, Interiors and Aquatics for a total amount not to exceed \$78,980.*

Councilmember Morris seconded and the motion passed.

20. Downtown Johnstown Branding & Wayfinding Project - Final Brand Presentation

Ms. Crosthwaite presented this item overviewing the project timeline and noted over 900 residents voted on the brand options. The Johnstown Downtown Development Association also reviewed the brand options and offer their support.

Council expressed support of the large, iconic "J", colors being used in the brand and asked for clarification on signage.

*Councilmember Mellon moved to support the adoption of the Downtown Johnstown Brand & Logo to be utilized for marketing purposes and representation of the Downtown Corridor.*

Councilmember Morris seconded and the motion passed.

21. Resolution 2023-16 Findings of Fact and Conclusions Regarding the Archdiocese Annexation No. 1 and Archdiocese Annexation No. 2

Kim Meyer, Planning and Building Director, noted needed mortifications have been brought up and asked that the Archdiocese Annexation items be continued to April 17, 2023.

*Councilmember Mellon moved to table this item to April 17, 2023*

Councilmember Young seconded and the motion passed.

## **PUBLIC HEARING**



22. Ordinance 2023-244 regarding the Archdiocese Annexation No. 1 and Archdiocese Annexation No. 2

Mayor Lebsack opened the public hearing.

Ms. Meyer asked that this item be continued to April 17, 2023 Council meeting.

Mayor Lebsack closed the public hearing.

*Councilmember Mellon moved to table Ordinance 2023-244 Regarding Archdiocese Annexation No. 1 and Archdiocese Annexation No. 2 until April 17, 2023*

Councilmember Morris seconded and the motion passed.

23. Ordinance 2023-245 Approving H-A Zoning for the property known as Archdiocese Annexation No. 1 and PUD-MU Zoning for the property known as Archdiocese Annexation No. 2

Mayor Lebsack opened the public hearing.

Ms. Meyer asked that this item be continued to April 17, 2023 Council meeting.

Mayor Lebsack closed the public hearing.

*Councilmember Molinar moved to table Ordinance 2023-245 until April 17, 2023*

Councilmember Mellon seconded and the motion passed.

24. Ordinance 2023-246 Approving the Outline Development Plan for Dove Solar

Mayor Lebsack opened the public hearing.

Ms. Meyer asked that this item be continued to April 17, 2023 Council meeting.

Mayor Lebsack closed the public hearing.

*Councilmember Young moved to table Ordinance 2023-246 until April 17, 2023*

Councilmember Mellon seconded and the motion passed.

25. Resolution 2023-17 Approving a Use by Special Review for the Dove Solar Array

Mayor Lebsack opened the public hearing.

Ms. Meyer asked that this item be continued to April 17, 2023 Council meeting.

Mayor Lebsack closed the public hearing.

*Councilmember Morris moved to table Resolution 2023-17 Approving a Use by Special Review for the Dove Solar Array to the April 17, 2023 meeting*

Councilmember Young seconded and the motion passed.

26. Resolution 2023-18 Approving the Preliminary/Final Subdivision Plat for Iron Horse Filing No. 3 (SUB21-0016)

Mayor Lebsack opened the public hearing.

Ms. Meyer presented this resolution to Council, noting the location was annexed in 2006. The Planning and Zoning Commission recommends approval and staff does not have any remaining concerns.

Mayor Lebsack opened the public hearing for comment for residents wishing to speak in favor of the item, to which there was none.

Mayor Lebsack opened the public hearing for comments opposed, to which there was none.

Mayor Lebsack closed the public hearing.

*Councilmember Mellon moved that the Town Council approve Resolution 2023-18 approving the Preliminary/Final Subdivision Plat for Iron Horse Filing No. 3.*

Councilmember Molinar seconded and the motion passed.

### **COUNCIL REPORTS AND COMMENTS**

Councilmember Morris expressed appreciation of the UCHealth Campus.

Councilmember Young noted the library is starting a remodel and updating landscaping.

Councilmember Mellon noted upcoming transportation meetings and the recent Johnstown Veterans Memorial dedication.

### **MAYOR'S COMMENTS**

There were no comments from Mayor Lebsack.

### **INFORMATION ONLY**

#### 27. Informational Items

Informational items were included in the packet.

### **EXECUTIVE SESSION**

#### 28. For discussion of a personnel matter under C.R.S. Section 24-6-402(4)(f) to Discuss Town Manager Evaluation

#### 29. An executive session to discuss the purchase of real property pursuant to C.R.S. Section 24-6-402(4)(a).

*Councilmember Young moved to adjourn into executive session per C.R.S. Section 24-6-402(4)(f) to Discuss Town Manager Evaluation and discuss the purchase of real property pursuant to C.R.S. Section 24-6-402(4)(a).*

Councilmember Molinar seconded and the motion passed.

Council reconvened at 8:51 and Mayor Lebsack noted nothing was discussed other than what was moved to be discussed and no action was taken.

### **ADJOURN**

Mayor Lebsack adjourned the April 3, 2023 Council meeting at 8:51 p.m.

---

Gary Lebsack, Mayor

---

Hannah Hill, Town Clerk



## TOWN COUNCIL CONSENT AGENDA COMMUNICATIONS

---

**AGENDA DATE:** April 17, 2023

**SUBJECT:** Resolution 2023-20: A Resolution Opposing Statewide Land Use and Zoning Preemption in Senate Bill 23-213

**ATTACHMENTS:** 1. Resolution 2023-20

**PRESENTED BY:** Matt LeCerf, Town Manager

---

### AGENDA ITEM DESCRIPTION:

Enclosed for your review and consideration is Resolution 2023-20. This resolution is in opposition to Senate Bill 23-213 which is a bill proposed during the current legislative session initiated by Governor Polis and sponsored by Senator Dominick Moreno (Majority Leader), Representative Iman Jodeh (Majority Co-Whip), and Representative Steven Woodrow. The bill if passed in its current form will preempt local control regarding Land Use and Zoning matters, making these issues a matter and concern of the State. The bill will control the manner and methods of development in our community, controlling density, parking, accessory dwelling units, and housing types.

Rather than identifying possible solutions that a best suited to be addressed locally, the State believes there is a one size fits all solution that flies in the face of local government efforts to solve the affordable housing crisis.

The Resolution presented, if adopted, will be sent to the Colorado Municipal League (CML) and other appropriate individuals and entities including the Governor's Office.

### LEGAL ADVICE:

CML provided an opposition template for the resolution which was modified to meet the Town's needs.

### FINANCIAL ADVICE:

*The Community That Cares*

[johnstown.colorado.gov](http://johnstown.colorado.gov)

P: 970.587.4664 | 450 S. Parish Ave, Johnstown CO 80534 | F: 970.587.0141



NA

**RECOMMENDED ACTION:** Approve Resolution 2023-20 opposing SB23-213.

---

*Reviewed and Approved for Presentation,*



\_\_\_\_\_  
Town Manager

**TOWN OF JOHNSTOWN, COLORADO  
RESOLUTION NO. 2023-20**

**RESOLUTION OPPOSING STATEWIDE LAND USE AND ZONING  
PREEMPTIONS IN SENATE BILL 23-213**

**WHEREAS**, the Town of Johnstown, Colorado (“Town”) is a Colorado home rule municipality, duly organized and existing under the laws of the State of Colorado and the Town’s Home Rule Charter; and

**WHEREAS**, the Town Council is the governing body of the Town and is vested with authority to administer the affairs of the Town; and

**WHEREAS**, for a century, the State of Colorado has committed both in statute and in the state constitution to the local control of land use planning and zoning because local governments are closest to the land and to the people that occupy the land; and

**WHEREAS**, zoning and land use cannot be viewed separately from the impacts of proposed uses of land on surrounding properties and a community as a whole, including the ability to ensure adequate water and utilities; to provide enough public safety services, schools, and recreational services; to make sure that sufficient and safe infrastructure is available to handle increased population or more intense uses; to align development with the community’s economic goals; to prevent displacement of existing people; to preserve important historical sites; and to protect open space and the environment in general; and

**WHEREAS**, on March 22, 2023, Senate Bill 23-213 was introduced; and

**WHEREAS**, Senate Bill 23-213 would place statewide mandates on hyper local land use matters and substitute the judgment of legislators and state regulators who lack the understanding needed to make the right decisions for the Town; and

**WHEREAS**, Senate Bill 23-213 would undermine long-range planning efforts and severely limit the Town’s ability to maintain reasonable zoning regulations to ensure a high quality of life and sound economic environment for current and future residents, workers, and business owners; and

**WHEREAS**, Senate Bill 23-213 silences the voices of the Town’s residents by taking away the right to be heard at public hearings on zoning matters or to use their constitutional rights of initiative or referendum to address zoning and land use matters; and

**WHEREAS**, the Town Council finds that adoption of this Resolution, opposing Senate Bill 23-231, is in the best interests of the Town.

**NOW, THEREFORE, BE IT RESOLVED BY THE TOWN COUNCIL OF THE TOWN OF JOHNSTOWN, COLORADO, THAT:**

Section 1. The Town of Johnstown’s position is that municipalities are best suited to determine appropriate zoning laws for their respective communities and that collaboration and cooperation – not top-down statewide mandates and giveaways to special interests – are the solution to Colorado’s affordable housing problem; and

Section 2. The Town of Johnstown firmly opposes Senate Bill 23-213 and strongly urges its legislators to vote NO on this unprecedented and irresponsible preemption.

PASSED, SIGNED, APPROVED, AND ADOPTED this \_\_\_ day of \_\_\_\_\_, 2023.

**ATTEST:**

**TOWN OF JOHNSTOWN, COLORADO**

By: \_\_\_\_\_  
Hannah Hill, Town Clerk

By: \_\_\_\_\_  
Gary Lebsack, Mayor





# Town of Johnstown

## TOWN COUNCIL CONSENT AGENDA COMMUNICATIONS

---

**AGENDA DATE:** April 17, 2023

**SUBJECT:** Agreement For Disaster-Emergency Mutual Aid and Disaster-Emergency Funding Assistance between the Town and the Larimer County Office Of Emergency Management

**ATTACHMENTS:** 1. Agreement for Disaster-Emergency Mutual Aid and Disaster-Emergency Funding Assistance

**PRESENTED BY:** Brian Phillips, Chief of Police

---

### AGENDA ITEM DESCRIPTION:

Each Party of this agreement has equipment and personnel trained and equipped to respond to situations involving an emergency. By this Agreement, the Parties intend to authorize and provide the terms for their mutual assistance in emergency situations, whether natural or man-made, which require resources in addition to those that can be provided by the Party in whose jurisdiction the emergency occurs. This Agreement is intended to allow for mutual aid between the Parties whenever there is an urgent or potentially significant situation that threatens the general welfare and good order of the public, public health, public safety, or property, including but not limited to “Disasters”, “State of Emergency”, or “Local Emergency.”

As of the date each party becomes a signatory to this Agreement, it shall then supersede and replace the following mutual aid agreements: Intergovernmental Agreement for Disaster-Emergency Mutual Aid and Disaster-Emergency Funding Assistance; Mutual Aid Agreement for Disaster Emergency Mutual Aid and Disaster-Emergency Funding Assistance.

### LEGAL ADVICE:

NA

### FINANCIAL ADVICE:

NA

*The Community That Cares*

[johnstown.colorado.gov](http://johnstown.colorado.gov)

P: 970.587.4664 | 450 S. Parish Ave, Johnstown CO 80534 | F: 970.587.0141

**RECOMMENDED ACTION:** Approve the Agreement for Disaster-Emergency Mutual Aid and Disaster-Emergency Funding Assistance.

---

*Reviewed and Approved for Presentation,*



\_\_\_\_\_  
Town Manager

AGREEMENT FOR DISASTER-EMERGENCY MUTUAL AID  
AND  
DISASTER-EMERGENCY FUNDING ASSISTANCE

This Agreement is made by and among the governmental entities and emergency management services and partners who are signatories hereto, all being entities lying within or in close proximity to northern Colorado and having a role in preparing for, responding to, and/or recovering from disasters and emergencies, and each a Party (referred to herein as the “Party” or the “Parties”).

**I. Purpose**

Each Party has equipment and personnel trained and equipped to respond to situations involving an emergency. By this Agreement, the Parties intend to authorize and provide the terms for their mutual assistance in emergency situations, whether natural or man-made, which require resources in addition to those that can be provided by the Party in whose jurisdiction the emergency occurs. This Agreement is intended to allow for mutual aid between the Parties whenever there is an urgent or potentially significant situation that threatens the general welfare and good order of the public, public health, public safety, property, or environment including but not limited to Disasters and Emergencies as those terms are defined in Title 24, Article 33.5, Part 7, Colorado Revised Statutes As of the date each party becomes a signatory to this Agreement, it shall then supersede and replace the following mutual aid agreements: *Intergovernmental Agreement for Disaster-Emergency Mutual Aid and Disaster-Emergency Funding Assistance*; *Mutual Aid Agreement for Disaster-Emergency Mutual Aid and Disaster-Emergency Funding Assistance*.

**II. Authority**

The authority for this Agreement is Section 18 of Article XIV of the Colorado Constitution; Section 6 of Article XX of the Colorado Constitution; Section 29-1-203, C.R.S., and provisions of the Colorado Disaster Emergency Act, Section 24-33.5-701, *et seq.*, C.R.S., as amended.

**III. Term**

This Agreement shall commence on the date that it is signed by at least two Parties and shall continue until such time as there are no longer at least two Parties to the Agreement. A Party may terminate its participation in this Agreement as set forth in Section XI, below.

**IV. Request for Assistance and Mutual Aid**

- a. In the event any Party determines a need for aid from any other Party in light of an emergency or disaster, such Party may request aid from any other Party as follows:
  - i. A request for assistance may be for any type of assistance or aid that the Requesting Party (Requesting Party) may deem necessary to respond to an emergency or disaster situation within its jurisdiction.



- ii. Any request for mutual aid or assistance shall include the following.
  - Statement of the nature and complexity of the subject need
  - Amount and type of equipment and/or personnel requested
  - Contact information
  - Duration needed
  - Location to which the equipment and/or personnel are to be dispatched

**V. Response to Request for Assistance and Mutual Aid**

- a. Upon receipt of a request for assistance, any other Party (Responding Party) may, in its sole discretion, provide personnel, equipment, materials, supplies, facilities, or other assistance to the Requesting Party.
- b. Any Responding Party reserves the right to recall its personnel, equipment, materials, supplies, facilities and other resources at any time and will, if practicable, give the Requesting Party at least twenty-four (24) hours advance notice.

**VI. Command & Control**

- a. It is the intent and Agreement of the Parties that the command structure and exchange of mutual aid provided for in this Agreement conform to the current standards of practice of the National Incident Management System (NIMS) and the Incident Command System (ICS).
- b. Parties responding with available resources and personnel will confer with the Requesting Party and report to the staging area designated by the Requesting Party. The Responding and Requesting Party will track the status of the appropriate resources accordingly.

**VII. Release of Resources**

Personnel and equipment of a Responding Party shall be released by the Requesting Party when the assistance is no longer required; or when the Responding Party requests the return of such resources. The release of all resources shall be communicated with the appropriate party and documented in the appropriate resource management system.

**VIII. Reimbursement and Compensation**

- a. First Twelve Hours of Response. Unless otherwise agreed in advance by the involved Parties, each Party will assume responsibility for its own expenses, including without limitation personnel and equipment costs, related to the provision of mutual aid during the first twelve (12) hours of the first operational period (Non-Reimbursable Costs). The first operational period is measured from the time of the initial dispatch, tone, or report of an incident to a response agency.
- b. After the First Twelve Hours of Response. Unless otherwise agreed in advance by the involved Parties, after the first twelve hours of the first operational period, the Requesting Party shall reimburse the Responding Party for the following costs associated with the response (Reimbursable Costs):

- i. Personnel Costs. Personnel costs, including salaries, hourly wages, overtime, and costs of fringe benefits.
  - ii. Equipment. An amount for the use of the Responding Party's equipment during the period of assistance according to the Schedule of Equipment Rates established in the Colorado Resource Rate Forms (CRFF) and or published by the Federal Emergency Management Agency (FEMA), <https://www.fema.gov/assistance/public/tools-resources/schedule-equipment-rates>www.fema.gov. Rates for equipment not referenced on the FEMA Schedule of Equipment Rates shall be as agreed upon by the involved Parties and based on actual recovery of costs.
  - iii. Materials and Supplies. The actual replacement cost or replacement in kind of the expended or non-returnable materials and supplies provided by the Responding Party, plus handling charges. The Responding Party shall not charge the Requesting Party for materials, supplies and reusable items that are returned to the Responding Party in a clean, damage-free condition. Reusable supplies that are returned to the Responding Party with damage must be treated as expendable supplies for purposes of cost reimbursement.
  - iv. Facilities. An amount for the use of the responding Party's full or partial use of a facility/property during the period of assistance.
- c. Tracking Reimbursable Costs. Tracking of personnel time, work/rest, and equipment, supply and facility costs shall be the responsibility of the Requesting Party. The Responding Party will be responsible for invoicing the Requesting Party after demobilization as per any financial agreement by both parties.
  - d. Reimbursement. The reimbursement of any Responding Party is not contingent on the Requesting Party's eligibility for or receipt of reimbursement from any federal or state agency. The Parties acknowledge that a Requesting Party will pursue all legal reimbursement available for costs associated with emergency and disaster response and recovery, including Reimbursable Costs incurred by Responding Parties. The Parties agree to cooperate with any Requesting Party as may be necessary to establish the necessity of the aid provided, and its reasonableness in light of the emergency situation. Parties involved in this Agreement shall, upon request of resources, determine financial terms and limitations through a separate document or through a pre-existing process outlined by the Emergency Management Agency or the Emergency Operations Center. This is typically done through a Request for Assistance Form or a 213RR Form, but may involve any written financial process used by the Requesting Party.

In addition, this Agreement shall not be construed as to limit or waive reasonable compensation or reimbursement for costs incurred under this Agreement that may be eligible for reimbursement by local, state or federal agencies or any other third parties.

Payment. Within ninety (90) days from the end of the period of assistance, a Responding Party shall provide the Requesting Party with an invoice that itemizes all Reimbursable Costs. The Requesting Party must pay the invoice in full on or

before the forty-fifth (45th) day following the billing date. Any amounts unpaid on the forty-sixth (46th) day following the billing date will be delinquent, and from that date forward will accrue interest at 2% per annum plus the bank prime loan rate in effect on the first date of delinquency, as reported in the Federal Reserve Statistical Release H.15, [www.federalreserve.gov/releases/H15/update/](http://www.federalreserve.gov/releases/H15/update/). Delinquent interest will be computed on an actual days/actual days basis. Upon agreement of the involved Parties, the payment deadlines may be extended if reimbursement from state or federal sources is pending and likely to occur.

- e. Financial Obligations. Pursuant to Colorado law, any financial obligations of a governmental entity under this Agreement, are subject to and contingent upon annual appropriation therefore.

## **IX. Additional Responsibilities**

- a. Agency Policy and Procedures. Each Party's personnel are responsible for following their agency's administrative policies and procedures. The parties hereto enter into this Agreement as separate and independent entities and each shall maintain that status through the term of this Agreement. Each Party remains responsible for all pay, entitlement, benefits, employment decisions, and worker's compensation benefits for its own personnel.
- b. Compliance with All Applicable Laws. Each Party shall be responsible at all times for compliance with all laws and regulations applicable to each of its actions hereunder. Each Party must, upon request by another involved Party, make available on a reasonable basis such information as may be required to ensure or show compliance with local, state and federal laws.
- c. Provisions for Responding Personnel. Within the written request for resources, the Agreement shall outline provisions required for personnel and equipment, including temporary housing, food and supplies necessary to perform the functions required. This may be outlined in the request as a need by the Requesting Party or as a need from the Responding Party. This should be outlined prior to any deployment of resources. If the Requesting Party cannot provide food or shelter for the said personnel, the Responding Party may secure the resources necessary to meet those needs and shall be entitled to reimbursement from the Requesting Party for such cost, not to exceed the state per diem rates.
- d. Nondiscrimination. No person with responsibilities in providing services or the operation of any activities under this Agreement will unlawfully discriminate against persons being assisted or requesting assistance on the basis of race, color, national origin, age, sex, religion, handicap, political affiliation or beliefs, or any other unlawful basis.

## **X. Disaster Planning and Interagency Cooperation**

- a. In order to enhance public safety, the protection of life, property and the environment, and in order to enhance the mutual aid capabilities contemplated in this Agreement, the Parties agree to do the following:
  - i. Prepare and keep current emergency planning documents, including jurisdictional or agency disaster response plans and recovery plans. The



Parties agree to cooperate in the development of each Party's Emergency Operations Plans.

- ii. To the extent possible, participate in the County emergency management activities which are designed to ensure coordinated disaster planning, response, and recovery. These activities may include the Local Emergency Planning Committee, multi-agency coordination systems, disaster risk and hazard assessment, training and education, and Incident Management Team support.
- iii. To the extent possible, provide a liaison to the county EOC during incidents that affect two or more Parties within the county to the extent allowed by the local emergency plans, staffing, and other budgetary considerations of the Parties. Liaisons may be provided virtually through EOC software management tools, telephone, or email.

#### **XI. Termination**

Any Party may terminate its participation in this Agreement without cause, and such termination will be effective on the date written notice is sent to the governing board of each Party. Termination will not negate any obligations that result from mutual aid provided or received prior to termination, including pending claims for reimbursement provided under this Agreement.

#### **XII. Non-Liability**

This Agreement shall not be construed to create a duty as a matter of law, contract, or otherwise for any Party to assume any liability for injury, property damage, or any other loss or damage that may occur by any action, or non-action taken, or service provided, to the public or any person, as a result of this Agreement. Nothing in this Agreement is intended nor shall be interpreted to waive any benefits or protections that may be available to any Party by the provisions of the Colorado Governmental Immunity Act, C.R.S. 24-10-101 *et. seq.*, as the same may be amended from time to time.

#### **XIII. Integration and Amendments**

This Agreement contains the entire understanding of the Parties, and the Parties agree that this Agreement may only be amended or altered by written agreement signed by the Parties' authorized representatives.

#### **XIV. Assignment /Transfer**

No Party shall assign or otherwise transfer this Agreement or any right or obligation herein without prior consent of the other Parties.

#### **XV. No Third Party Beneficiary**

This Agreement is made for the sole and exclusive benefit of the Parties hereto and nothing in this Agreement is intended to create or grant to any Third Party or person any right or claim for damage, or the right to bring or maintain any action at law, nor does any Party waive its immunities at law, including the rights, protections, limitations and immunities granted the Parties under the Colorado Governmental

Immunity Act, C.R.S. 24-10-101 *et. seq.*, as the same may be amended from time to time.

#### **XVI. Severability**

If any term, covenant, or condition of this Agreement is deemed by a court of competent jurisdiction to be invalid, void, or unenforceable, the remaining provisions of this Agreement shall be binding upon the Parties.

#### **XVII. Headings**

The section headings of this Agreement are inserted only as a matter of convenience and for reference. They do not define or limit the scope or intent of any provisions in this Agreement and shall not be construed to affect in any manner the terms and provisions herein.

#### **XVIII. Becoming a Party to this Agreement**

- a. Any governmental entity, as defined under Colorado law, may join in this Agreement after formal approval by the prospective party's governing body, notification to the Larimer County Office of Emergency Management of such approval, and notification by the Larimer County Office of Emergency Management to all other Parties. To the extent that local government entities outside of Larimer County choose to join in this Agreement, notification shall also be provided to office of emergency management in the county where the entity is located.
- b. Any non-governmental entity that has a role in preparing for, responding to, or recovering from emergencies or disasters may request to join in this Agreement after formal approval by the prospective party's governing body. Following such formal approval, the prospective party shall submit a request to join this Agreement to the Larimer County Office of Emergency Management. If the Larimer County Office of Emergency management determines the prospective party is properly joined in this Agreement, it shall notify each of the other Parties to this Agreement that the prospective party is joined as a Party.

#### **XIX. Execution**

This Agreement shall be executed by each Party on a separate signature page. This Agreement and the original signature pages shall be filed with and held by Larimer County Emergency Management or its successor agency, at 200 West Oak Street, Fort Collins, CO 80522. Copies of signature pages shall be provided to each Party, and such copies shall have the full force and effect as if they were originals. A copy of the full Agreement will be provided to the Colorado State Division of Homeland Security and Emergency Management.

INTERGOVERNMENTAL AGREEMENT  
FOR DISASTER-EMERGENCY MUTUAL AID  
AND  
DISASTER-EMERGENCY FUNDING ASSISTANCE

SIGNATURE PAGE

As outlined in the foregoing Intergovernmental Agreement, the below designated jurisdiction executes this Agreement on the most recent date indicated below.

PARTY:

---

By:

---

Title:

---

Date:

---

ATTEST AS TO SIGNATURES:

---

Title:

---

Date:

---





# Town of Johnstown

## TOWN COUNCIL CONSENT AGENDA COMMUNICATIONS

**AGENDA DATE:** April 17, 2023

**SUBJECT:** Water & Sewer Service Agreement – Sunbelt Rentals with MPV SBR Investors III, LLC

**ATTACHMENTS:** 1. Water and Sewer Service Agreement with Exhibits

**PRESENTED BY:** Kim Meyer, Planning & Development Director

### AGENDA ITEM DESCRIPTION:

The Developer, MPV SBR Investors III, LLC., has received administrative approval of a Site Development Plan for the Sunbelt Rentals Building, consisting of 2,728 sq. ft. of office space and 7,387 sq. ft. of industrial/flex use space in the Iron Horse area.

The annual in-building water demand is estimated at 0.99 acre-feet, with annual permanent irrigation demand at 0.62 acre-feet. These numbers were provided by the Developer and reviewed and accepted by the Town’s contract water engineering firm.

Development Component	Demand (AF/YR)	Consumption (AF/YR)
In-Building	0.99	0.05
Permanent Landscape Irrigation	0.62	0.53
<b>Total</b>	<b>1.61</b>	<b>0.58</b>

Potable water is allocated from the 2534 Master Association Water Bank for both in-building and irrigation. Evidence of the agreement and allocation of this water is incorporated as Exhibit B.

Water court transfer fees have been paid on water held in this bank.

### LEGAL ADVICE:

The Town Attorney drafted the Agreement.

The Community That Cares

www.TownofJohnstown.com

P: 970.587.4664 | 450 S. Parish Ave, Johnstown CO | F: 970.587.0141

**FINANCIAL ADVICE:**

NA

**RECOMMENDED ACTION:**

Approve the Water & Sewer Service Agreement for Sunbelt Rentals Building, with MPV SBR Investors III, LLC.

---

*Reviewed and Approved for Presentation,*



\_\_\_\_\_  
Town Manager

**WATER AND SEWER SERVICE AGREEMENT  
FOR  
SUNBELT RENTALS SITE DEVELOPMENT PLAN  
AT 3767 RONALD REAGAN BLVD.**

THIS WATER AND SEWER SERVICE AGREEMENT is made and entered into this \_\_\_\_\_ day of \_\_\_\_\_, 2023, by and between **MPV SBR INVESTORS III, LLC**, a North Carolina limited liability company (“Developer”), and **THE TOWN OF JOHNSTOWN**, a Colorado municipal corporation, (“Town”), collectively sometimes referred to as the “Parties.”

WITNESSETH:

WHEREAS, the Developer owns an interest in land located in a portion of Lots 2 and 3, Iron Horse Filing 2, Lot 1 Amended Subdivision more specifically described in the attached Exhibit A (“Subject Property”); and

WHEREAS, the Subject Property is being developed as Sunbelt Rentals and will consist of 2,728 ft<sup>2</sup> of general office space and 7,387 ft<sup>2</sup> of light industrial/flex use space together with 0.04 acre of spray-irrigated landscape, 0.15 acre of drip-irrigated landscape, and 0.29 acre of xeric-irrigated landscape (collectively, the “Project”); and

WHEREAS, Developer and the Town desire to set forth their agreement concerning water rights dedication, preliminary projections of water and sewer demand and a current commitment by the Town for water and sewer service for the Project.

NOW, THEREFORE, in consideration of the mutual promises hereinafter contained and other good and valuable consideration, the receipt and sufficiency of which is hereby acknowledged, and incorporating the foregoing recitals into the agreement, the Parties hereto agree as follows:

**1. Water and Sewer Demand Studies.** In compliance with the Town Water Rights Dedication Ordinance (“Ordinance”), Developer has submitted to the Town a preliminary water and sewer demand analysis for the Project. Said analysis was received by the Town, is on file with the Town and, as modified by the Town’s Water Engineer by memorandum dated October 24, 2022, is hereby accepted by the Town. The analysis sets forth the projected water and sewer demands for the Project as follows:

Development Component	Demand (AF/YR)	Consumption (AF/YR)
In-Building	0.99	0.05
Landscape Irrigation (Permanent)	0.62	0.53
Total	1.61	0.58

**2. Water Rights Dedication.** As a result of prior dedications of raw water credit, there is currently a surplus dedication credit with the Town sufficient to supply the potable water demands of the Project from the 2534 Master Association Water Bank. The Gerrard Family



Partnership, LLLP and Thompson Ranch Development Company have agreed that this credit shall be applied to meet the potable water demands of the Project. Evidence of the agreement is attached hereto and incorporated herein by reference as Exhibit B.

**3. Commitment to Serve.** Subject to Developer's performance of all the covenants contained herein and payment of all required fees, and the Developer's foregoing agreement, the Town commits to provide to the Project up to 0.99 acre-feet per year of water supply together with the corresponding sewer service for in-building use and up to 0.62 acre-feet per year water supply for landscape irrigation as detailed above.

**4. Payment of Water Court Transfer fees.** The Water Court transfer fee for both the potable water supply was previously paid to the Town as part of the 2534 Master Association Water Bank. However, in accordance with the Ordinance, additional fees may be required in connection with future development of any portion of the Subject Property.

**5. Notices.** All notices, demands, or other documents required or desired to be given, made or sent to either Party under this Agreement shall be made in writing, shall be deemed effective upon receipt and shall be personally delivered, sent by electronic mail, or mailed postage prepaid, certified mail, return receipt requested, as follows:

TO DEVELOPER:

MPV SBR Investors III, LLC  
2400 South Boulevard, Ste 300  
Charlotte, NC 28203-5773  
Email: bmurr@mpvre.com

TO THE TOWN:

Town of Johnstown  
c/o Town Clerk  
PO Box 609  
450 S. Parish Ave.  
Johnstown, CO 80534  
Email: Hhill@johnstownco.gov

WITH A COPY TO  
THE TOWN ATTORNEYS:

Avi Rocklin, Esq.  
Johnstown Town Attorney  
1437 N. Denver Avenue, #330  
Loveland, CO 80538  
Email: avi@rocklinlaw.com

Peter J. Ampe  
Hill & Robbins, P.C.  
3401 Quebec St., Suite 3400  
Denver, CO 80207  
Email: peterampe@hillandrobbs.com

The addresses for notices may be changed by written notice given to the other Party in the manner provided above.

**6. Default.** In the event of default by either Party hereunder the non-defaulting Party shall notify the defaulting Party in writing of such default(s), specifying the nature and extent thereof. If such default is not cured within thirty (30) days and the non-defaulting Party desires to seek recourse, the Parties shall participate in mediation, the costs of which shall be shared equally by both Parties. If mediation is not successful after a ninety-day period, either Party may then commence an action in a court of competent jurisdiction and shall be entitled to such remedies as are provided by law, including the Town's ordinances.

**7. Successors and Assigns.** The benefits and burdens of this Agreement shall respectively inure to and be binding upon the successors and assigns of the Parties hereto. This Agreement shall not be assigned without the prior written consent of the other party, which shall not be unreasonably withheld.

**8. Amendment or Modification.** No amendment or modification of this Agreement shall be of any force or effect unless in writing and executed by the Parties hereto with the same formality as this Agreement.

**9. Attorney's Fees and Costs.** If any judicial proceedings may hereafter be brought to enforce any of the provisions hereof, including an action for specific performance and/or damages, the Town, if the prevailing party, shall be entitled to recover the costs of such proceedings, including reasonable attorney's fees and reasonable expert witness fees.

**10. Waiver.** The waiver of any breach of any of the provisions of this Agreement by either Party shall not constitute a continuing waiver of any subsequent breach by said Party, concerning either the same or any other provision of this Agreement.

**11. Headings for Convenience Only.** Paragraph headings and titles contained herein are intended for convenience and reference only and are not intended to define, limit or describe the scope or intent of any provision of this Agreement.

**12. Non-severability.** Each paragraph of this Agreement is intertwined with the others and is not severable unless by mutual consent of the Parties hereto.

**13. Choice of Laws.** This Agreement and the rights and obligations of the Parties hereto shall be governed by the laws of the State of Colorado. Venue for any claim, proceeding or action shall be in Larimer or Weld County, State of Colorado.

**14. Entire Agreement and Authorization.** This Agreement constitutes the entire agreement between the Parties related to the subject matter hereof and any prior agreements pertaining thereto whether oral or written have been merged or integrated into this Agreement. Each of the undersigned represents to the others that he/she is authorized by his/her respective entity to execute this Agreement on behalf of that entity.

**15. No Presumption.** Each Party acknowledges that it has carefully read and reviewed the terms of this Agreement. Each Party acknowledges that the entry into and execution of this Agreement is of its own free and voluntary act and deed, without compulsion. Each Party

acknowledges that it has obtained, or has had the opportunity to obtain, the advice of legal counsel of its own choosing in connection with the negotiation and execution of this Agreement and with respect to all matters set forth herein. The Parties agree that this Agreement reflects the joint drafting efforts of all Parties and in the event of any dispute, disagreement or controversy arising from this agreement, the Parties shall be considered joint authors and no provision shall be interpreted against any Party because of authorship.

**16. Recordation.** This Agreement may be recorded by the Town at Developer's expense in the office of the Clerk and Recorder of Larimer County, Colorado, and, effective as of the date of such recordation, this Agreement shall run with the Subject Property, shall be binding upon the Parties hereto and the permitted successors and assigns of the Developer and shall constitute notice of this Agreement to all persons or entities not parties hereto.

\*IN WITNESS WHEREOF, the Parties have executed this Agreement the day and year first above written.

*Signatures follow on separate pages*





TOWN OF JOHNSTOWN, COLORADO,  
a municipal corporation

By: \_\_\_\_\_  
Gary Lebsack, Mayor

ATTEST:

By: \_\_\_\_\_  
Hannah Hill, Town Clerk

**EXHIBIT A**  
**SUBJECT PROPERTY**

LOT 2, OF AMENDMENT TO LOTS 2 & 3, IRON HORSE FILING TWO, LOT 1  
AMENDED SUBDIVISION, TOWN OF JOHNSTOWN, COUNTY OF LARIMER, STATE  
OF COLORADO

EXHIBIT B

RAW WATER CREDIT ALLOCATION ACKNOWLEDGMENT

This is to acknowledge and agree that the Town of Johnstown may allocate raw water credit from The Gerrard Family Limited Partnership, LLLP, and Thompson Ranch Development Company raw water credit account held by the Town of Johnstown, known as the "2534 Water Bank," to provide water service to the development known as Sunbelt Site Development Plan (DEV21-0011) and any successor occupant of the premises at the same location, pursuant to the Water and Sewer Service Agreement between MVP SBR INVESTORS III, LLC a North Carolina limited liability company, and the Town of Johnstown dated 3-23-2023.


The amount of such allocated raw water credit is calculated to be 1.61 acre-feet per year, subject to adjustment pursuant to the terms of the Water Sewer Service Agreement.

THE GERRARD FAMILY LIMITED PARTNERSHIP, LLLP

  
\_\_\_\_\_  
Nathan Gerrard, Partner  
The Gerrard Family Limited Partnership, LLLP

Dated: 3-21-2023

THOMPSON RANCH DEVELOPMENT COMPANY

  
\_\_\_\_\_  
Todd Williams, Vice President  
Thompson Ranch Development Company

Dated: 3-23-2023





Town of Johnstown, Colorado  
Statement of Revenues, Expenditures, and Changes in  
Fund Balances - General Fund  
Period Ending March 31, 2023  
Unaudited

Item #7.

<b>General Fund</b>	2023 Actuals March	2023 Adopted Budget	%
			Complete
Beginning Fund Balance*	87,924,330	87,924,330	
<b>Revenues:</b>			
Taxes & Fees	5,000,239	19,417,534	25.8%
Licenses & Permits	1,465,512	1,963,700	74.6%
Fines & Forfeitures	57,154	175,500	32.6%
Intergovernmental	5,442	25,000	21.8%
Earnings on Investment	421,552	15,000	2810.3%
Miscellaneous Revenue	121,481	757,500	16.0%
<i>Transfers In</i>	-	-	
Total Operating Revenues	7,071,381	22,354,234	31.6%
<b>Expenditures:</b>			
Legislative	208,358	831,440	25.1%
Town Manager	250,161	1,442,430	17.3%
Town Clerk	106,659	441,910	24.1%
Finance	106,498	450,870	23.6%
Planning	86,224	566,310	15.2%
Reimbursements	100,970	700,000	14.4%
Building Inspections	74,006	413,820	17.9%
Police	1,295,565	6,006,610	21.6%
Public Works	200,467	761,350	26.3%
Buildings	78,277	288,100	27.2%
<i>Transfers Out</i>	311,359	51,945,508	0.6%
Total Expenditures	2,818,545	63,848,348	4.4%
<b>Excess (Deficiency) of Revenues and Other Sources over Expenditures</b>	<b>4,252,836</b>	<b>(41,494,114)</b>	
Prior Period Adjustment			
<b>Ending Fund Balance*</b>	<b>92,177,166</b>	<b>46,430,216</b>	

\* - Unaudited

25% of the fiscal year has elapsed





Town of Johnstown, Colorado  
Statement of Revenues, Expenditures, and Changes in  
Fund Balances - Conservation Trust Fund  
Period Ending March 31, 2023  
Unaudited

Item #7.

	2023 Actuals March	2023 Adopted Budget	%
<b>Conservation Trust Fund</b>			Complete
Beginning Fund Balance*	132,112	132,112	
<b>Revenues:</b>			
Intergovernmental	37,214	82,000	45.4%
Earnings on Investment	980	50	1959.5%
Total Operating Revenues	38,194	82,050	46.5%
<b>Expenditures:</b>			
Operations	-	-	
Capital Outlay	-	-	
Total Expenditures	-	-	
<b>Excess (Deficiency) of Revenues and Other Sources over Expenditures</b>	<b>38,194</b>	<b>82,050</b>	
<b>Ending Fund Balance*</b>	<b>170,306</b>	<b>214,162</b>	

\* - Unaudited

25% of the fiscal year has elapsed





Town of Johnstown, Colorado  
 Statement of Revenues, Expenditures, and Changes in  
 Fund Balances - Parks and Open Space Fund  
 Period Ending March 31, 2023  
 Unaudited

Item #7.

Parks and Open Space Fund	2023 Actuals March	2023 Adopted Budget	% Complete
Beginning Fund Balance*	6,865,289	6,865,289	
<b>Revenues:</b>			
Taxes & Fees	489,069	786,030	62.2%
Miscellaneous Revenue	19,520	17,000	114.8%
Transfers In	0	50,000	0.0%
	541,855	855,530	63.3%
<b>Expenditures:</b>			
Operations	145,604	2,905,000	5.0%
Capital Outlay	159,767	1,024,940	15.6%
Transfers Out	-	-	
	305,371	3,929,940	7.8%
<b>Excess (Deficiency) of Revenues and Other Sources over Expenditures</b>	<b>236,484</b>	<b>(3,074,410)</b>	
<b>Ending Fund Balance*</b>	<b>7,101,773</b>	<b>3,790,879</b>	

\* - Unaudited

25% of the fiscal year has elapsed





Town of Johnstown, Colorado  
Statement of Revenues, Expenditures, and Changes in  
Fund Balances - Street and Alley Fund  
Period Ending March 31, 2023  
Unaudited

Item #7.

<b>Street and Alley Fund</b>	2023 Actuals March	2023 Adopted Budget	% Complete
Beginning Fund Balance*	17,606,494	17,606,494	
<b>Revenues:</b>			
Taxes & Fees	864,540	4,171,405	20.7%
Intergovernmental	72,537	1,290,000	5.6%
Charges for Services	244,749	945,000	25.9%
Capital Investment Fees	1,488,139	1,174,000	126.8%
Earnings on Investment	81,781	10,200	801.8%
Miscellaneous Revenues	-	-	0.0%
<b>Total Operating Revenues</b>	<b>2,751,746</b>	<b>9,040,605</b>	<b>30.4%</b>
<b>Expenditures:</b>			
Operations & Maintenance	559,787	3,698,790	15.1%
Capital	333,699	7,848,000	4.3%
<b>Total Expenditures</b>	<b>893,486</b>	<b>11,546,790</b>	<b>7.7%</b>
<b>Excess (Deficiency) of Revenues and Other Sources over Expenditures</b>	<b>1,858,261</b>	<b>(2,506,185)</b>	
<b>Ending Fund Balance*</b>	<b>19,464,755</b>	<b>15,100,309</b>	

\* - Unaudited

25% of the fiscal year has elapsed







Town of Johnstown, Colorado  
Statement of Revenues, Expenditures, and Changes in  
Fund Balances - Capital Projects Fund  
Period Ending March 31, 2023  
Unaudited

Item #7.

	2023 Actuals March	2023 Adopted Budget	%
<b>Capital Projects Fund</b>			Complete
Beginning Fund Balance*	12,343,821	12,343,821	
<b>Revenues:</b>			
Taxes and Fees	697,442	300,000	232.5%
Miscellaneous Revenue	-	-	
Interest	122,785	2,200	5581.2%
<i>Transfers In</i>	-	(50,000)	0.0%
	820,227	252,200	325.2%
<b>Expenditures:</b>			
Capital Outlay	2,135	2,511,500	0.0%
<i>Transfers Out</i>	-	-	0.0%
	2,135	2,511,500	0.1%
<b>Excess (Deficiency) of Revenues and Other Sources over Expenditures</b>	<b>818,092</b>	<b>(2,259,300)</b>	
<b>Ending Fund Balance*</b>	<b>13,161,913</b>	<b>10,084,521</b>	

\* - Unaudited

25% of the fiscal year has elapsed





Town of Johnstown, Colorado  
Statement of Revenues, Expenditures, and Changes in  
Fund Balances - Tax Allocation Fund  
Period Ending March 31, 2023  
Unaudited

Item #7.

Tax Allocation Fund	2023 Actuals March	2023 Adopted Budget	% Complete
Beginning Fund Balance*	41,435	41,435	
<b>Revenues:</b>			
Taxes & Fees	-	675,000	0.0%
Earnings on Investment	-	-	
Total Operating Revenues	-	675,000	0.0%
<b>Expenditures:</b>			
Miscellaneous	-	675,000	0.0%
Total Expenditures	-	675,000	0.0%
<b>Excess (Deficiency) of Revenues and Other Sources over Expenditures</b>	-	-	
 <b>Ending Fund Balance*</b>	 <b>41,435</b>	 <b>41,435</b>	

\* - Unaudited

25% of the fiscal year has elapsed





Town of Johnstown, Colorado  
Statement of Revenues, Expenditures, and Changes in  
Fund Balances - Water Fund  
Period Ending March 31, 2023  
Unaudited

Item #7.

<b>Water Fund</b>	2023 Actuals March	2023 Adopted Budget	%
			Complete
Beginning Cash Balance*	37,380,557	37,380,557	
<b>Revenues:</b>			
Charges for Services	828,323	4,555,000	18.2%
Total Operating Revenues	828,323	4,555,000	18.2%
<b>Expenses:</b>			
Administration	28,784	235,300	12.2%
Operations	682,918	4,365,350	15.6%
Capital Outlay	455,931	36,417,280	1.3%
Depreciation	108,697	970,000	11.2%
Transfers Out	-	600,000	
Total Operating Expenses	1,276,331	43,187,930	3.0%
Operating Income (Loss)	(448,007)	(38,632,930)	
<b>Non-Operating Revenues (Expenses)</b>			
Tap Fees	649,618	1,357,605	47.9%
Capital Investment Fees	555,057	1,147,945	48.4%
Misc. Revenues	15,290,830	71,226,500	21.5%
Interest Expense	173,911	20,000	869.6%
Total Non-Operating Revenues (Expenses)	16,669,416	73,752,050	22.6%
<b>Excess (Deficiency) of Revenues and Other Sources over Expenses</b>	<b>16,221,408</b>	<b>35,119,120</b>	
<b>Ending Cash Balance*</b>	<b>53,601,965</b>	<b>72,499,677</b>	

\* - Unaudited

25% of the fiscal year has elapsed





Town of Johnstown, Colorado  
Statement of Revenues, Expenditures, and Changes in  
Fund Balances - Sewer Fund  
Period Ending March 31, 2023  
Unaudited

Item #7.

<b>Sewer Fund</b>	2023 Actuals March	2023 Adopted Budget	%
			Complete
Beginning Cash Balance*	47,151,463	47,151,463	
<b>Revenues:</b>			
Charges for Services	820,115	3,181,500	25.8%
Total Operating Revenues	820,115	3,181,500	25.8%
<b>Expenses:</b>			
Administration	28,406	227,750	12.5%
Operations	428,167	2,087,960	20.5%
Capital Outlay	3,111,807	78,381,000	4.0%
Depreciation	57,379	1,200,000	4.8%
Debt Service	-	2,764,000	0.0%
Transfers Out	-	600,000	0.0%
Total Operating Expenses	3,625,760	85,260,710	4.3%
Operating Income (Loss)	(2,805,645)	(82,079,210)	
<b>Non-Operating Revenues (Expenses)</b>			
Capital Improvement Fees	1,326,145	3,218,560	41.2%
Misc. Revenues	11,857	18,900	62.7%
Interest Expense	696,183	100,000	696.2%
Debt Proceeds	-	50,000,000	
Total Non-Operating Revenues (Expenses)	2,034,185	53,337,460	3.8%
<b>Excess (Deficiency) of Revenues and Other Sources over Expenses</b>	<b>(771,459)</b>	<b>(28,741,750)</b>	
<b>Ending Cash Balance*</b>	<b>46,380,004</b>	<b>18,409,713</b>	

\* - Unaudited

25% of the fiscal year has elapsed







Town of Johnstown, Colorado  
Statement of Revenues, Expenditures, and Changes in  
Fund Balances - Drainage Fund  
Period Ending March 31, 2023  
Unaudited

Item #7.

<b>Drainage Fund</b>	2023 Actuals March	2023 Adopted Budget	% Complete
Beginning Cash Balance*	4,232,022	4,232,022	
<b>Revenues:</b>			
Charges for Services	129,319	500,000	25.9%
Total Operating Revenues	129,319	500,000	25.9%
<b>Expenses:</b>			
Administration	22,242	150,400	14.8%
Operations	33,592	493,025	6.8%
Capital Improvements	-	-	
Transfer Out	-	250,000	
Total Operating Expenses	55,834	893,425	6.2%
Operating Income (Loss)	73,485	(393,425)	
<b><u>Non-Operating Revenues (Expenses)</u></b>			
Capital Revenues	-	220,000	0.0%
Misc. Revenues	-	-	
Interest Expense	23,365	1,000	2336.5%
Total Non-Operating Revenues (Expenses)	23,365	221,000	10.6%
<b>Excess (Deficiency) of Revenues and Other Sources over Expenses</b>	<b>96,850</b>	<b>(172,425)</b>	
<b>Ending Cash Balance*</b>	<b>4,328,872</b>	<b>4,059,597</b>	

\* - Unaudited

25% of the fiscal year has elapsed





Town of Johnstown, Colorado  
Statement of Revenues, Expenditures, and Changes in  
Fund Balances - Cemetery Perpetual Fund  
Period Ending March 31, 2023  
Unaudited

Item #7.

<b>Cemetery Perpetual Fund</b>	2023 Actuals March	2023 Adopted Budget	%
			Complete
Beginning Fund Balance*	168,889	168,889	
<b>Revenues:</b>			
Miscellaneous Revenue	2,385	12,560	19.0%
Earnings on Investment	1,368	60	2280.1%
	3,753	12,620	29.7%
<b>Expenditures:</b>			
Operations & Maintenance	-	-	
Capital Outlay	-	-	
Transfers Out	-	-	
	-	-	
Total Expenditures	-	-	
<b>Excess (Deficiency) of Revenues and Other Sources over Expenditures</b>	<b>3,753</b>	<b>12,620</b>	
<b>Ending Fund Balance*</b>	<b>172,642</b>	<b>181,509</b>	

\* - Unaudited

25% of the fiscal year has elapsed





Town of Johnstown, Colorado  
Statement of Revenues, Expenditures, and Changes in  
Fund Balances - Library Fund  
Period Ending March 31, 2023  
Unaudited

Item #7.

Library Fund	2023 Actuals March	2023 Adopted Budget	% Complete
Beginning Fund Balance*	8,580,860	8,580,860	
<b>Revenues:</b>			
Intergovernmental	3,285	819,186	0.4%
Miscellaneous Revenue	6,205	11,000	56.4%
Capital Investment Fees	388,701	439,410	88.5%
Interest	54,457	75,000	72.6%
<i>Transfers In</i>	201,681	1,243,246	16.2%
Total Operating Revenues	654,329	2,587,842	25.3%
<b>Expenditures:</b>			
Operations	162,970	1,821,000	8.9%
Capital Outlay	-	-	0.0%
Total Expenditures	162,970	1,821,000	8.9%
<b>Excess (Deficiency) of Revenues and Other Sources over Expenditures</b>	<b>491,359</b>	<b>766,842</b>	
<b>Ending Fund Balance*</b>	<b>9,072,219</b>	<b>9,347,702</b>	

\* - Unaudited

25% of the fiscal year has elapsed





Town of Johnstown, Colorado  
Statement of Revenues, Expenditures, and Changes in  
Fund Balances - Recreation Center Fund  
Period Ending March 31, 2023  
Unaudited

Item #7.

Recreation Center Fund	2023 Actuals March	2023 Adopted Budget	% Complete
Beginning Fund Balance*	922,738	922,738	
<b>Revenues:</b>			
State Grants	-	0	
Transfers In	-	77,262	
Earnings on Investment	-	-	
	-	-	
Total Operating Revenues	-	77,262	
<b>Expenditures:</b>			
Operations & Maintenance	176,687	500,000	35.3%
Capital Outlay	-	-	
	-	-	
Total Expenditures	176,687	500,000	35.3%
<b>Excess (Deficiency) of Revenues and Other Sources over Expenditures</b>	<b>(176,687)</b>	<b>(422,738)</b>	
<b>Ending Fund Balance*</b>	<b>746,051</b>	<b>500,000</b>	

\* - Unaudited

25% of the fiscal year has elapsed







# Town of Johnstown

## TOWN COUNCIL AGENDA COMMUNICATIONS

---

**AGENDA DATE:** April 17, 2023

**SUBJECT:** Resolution 2023-16 regarding the Archdiocese Annexation Nos. 1-3

**ACTION PROPOSED:** Consider Resolution 2023-16 Findings of Fact and Conclusions based thereon with respect to the Archdiocese Annexation Nos. 1-3

**ATTACHMENTS:**

1. Resolution 2023-16
2. Vicinity Map

**PRESENTED BY:** Kim Meyer, Planning & Development Director

---

### AGENDA ITEM DESCRIPTION:

An annexation petition and application materials were received by the Town in July 2022 to annex approximately 82.59 acres, located west of Weld County Road 19, and north of Weld County Road 44. Following the Substantial Compliance hearing on February 6, 2023, the applicant modified their annexation request and associated application to reflect a decrease in the area to be annexed to 47.49 acres.

The annexation plats have been revised to reflect an updated proposal including such modifications necessary to remain in compliance with the annexation requirements, notably the splitting this serial annexation from two parts into three parts to maintain required contiguity.

The submittal materials have been reviewed and found by Town Staff and the Town Attorney to be in compliance with C.R.S. §31-12-107(1). This resolution sets forth the findings of fact and conclusions that the area is eligible for annexation and may be annexed by ordinance.

### LEGAL ADVICE:

Resolution was prepared by the Town Attorney.

### FINANCIAL ADVICE:

NA

The Community That Cares

[johnstown.colorado.gov](http://johnstown.colorado.gov)

P: 970.587.4664 | 450 S. Parish Ave, Johnstown CO 80534 | F: 970.587.0141

**RECOMMENDED ACTION:**

Approval of Resolution 2023-16 Findings of Fact and Conclusions based thereon with respect to the Archdiocese Annexation No. 1-3.

**SUGGESTED MOTIONS:**

**For Approval**

I move that the Town Council approve Resolution 2023-16 Findings of Fact and Conclusions based thereon with respect to the Archdiocese Annexation No 1-3.

**For Denial**

I move that the Town Council deny Resolution 2023-16.

*Reviewed and Approved for Presentation,*



---

Town Manager

**TOWN OF JOHNSTOWN, COLORADO  
RESOLUTION NO. 2023-16**

**FINDINGS OF FACT AND CONCLUSIONS BASED THEREON  
WITH RESPECT TO THE ARCHDIOCESE ANNEXATION NOS. 1-3**

**WHEREAS**, the Town of Johnstown, Colorado (“Town”) is a Colorado home rule municipality, duly organized and existing under the laws of the State of Colorado and the Town’s Home Rule Charter; and

**WHEREAS**, the Town Council is vested with authority to administer the affairs of the Town; and

**WHEREAS**, the Archdiocese of Denver, a Colorado corporation sole (the “Archdiocese”), submitted a Petition for Annexation of real property situated in a portion of Sections 15 and 16, Township 4 North, Range 67 West of the 6<sup>th</sup> P.M., County of Weld, State of Colorado, consisting of approximately 82.59 acres, known as the “Archdiocese Annexation No. 1 and Archdiocese Annexation No. 2 and Archdiocese Annexation No. 3;” and

**WHEREAS**, on February 6, 2023, by Resolution No. 2023-06, the Town Council found the Petition for Annexation to be in substantial compliance with C.R.S. § 31-12-107(1); and

**WHEREAS**, subsequent thereto, the Archdiocese modified its request and only seeks to annex 47.49 acres of the 82.59 acres into the municipal boundaries of the Town; and

**WHEREAS**, consistent with the foregoing, the Archdiocese seeks to annex a portion of the North Half of the Northeast Quarter of Section 16 and a portion of the West Half of the Northwest Quarter of Section 16, Township 4 North, Range 67 West of the 6<sup>th</sup> P.M., County of Weld, State of Colorado, consisting of approximately 47.49 acres, as more particularly described on Exhibit A, attached hereto and incorporated herein by reference, known as the “Archdiocese Annexation Nos. 1-3;”

**WHEREAS**, on April 17, 2023, after due notice, the Town Council conducted a public hearing and, based on the evidence contained in the official file, the official records of the Town and the evidence produced at the hearing, desires to enter the following findings of fact and conclusions with the respect to the Archdiocese Annexation Nos. 1-3.

**NOW, THEREFORE, BE IT RESOLVED BY THE TOWN COUNCIL OF THE TOWN OF JOHNSTOWN, COLORADO, THAT:**

The Town Council hereby sets forth its findings of fact and conclusions with respect to the Archdiocese Annexation Nos. 1-3.

## FINDINGS OF FACT

1. The requirements of the applicable parts of C.R.S. § 31-12-104 and C.R.S. § 31-12-105 have been met including the following:
  - A. Not less than one-sixth of the perimeter of the area proposed to be annexed is contiguous with the Town as shown on the annexation map. Contiguity is to be established by the annexation of three parcels in a series.
  - B. A community of interest exists between the area proposed to be annexed and the Town due to the proximity of the area to the Town, the desires of the owners to annex and the fact that it is within the planning area contemplated in the Johnstown Area Comprehensive Plan.
  - C. The area will be urbanized in the near future and the area is capable of being fully integrated with the Town.
  - D. Although less than fifty (50%) percent of the adult residents of the area proposed to be annexed make use of Town facilities, the landowners of the area proposed for annexation, while presently agricultural, plan to develop the land in less than five (5) years, and urban services, which are currently being provided to other citizens of the Town, may be provided to citizens of the proposed annexed area on the same terms and conditions as the services are made available to other citizens. The Town is able to provide water service and the Town's sewer system can be extended to the property annexed with the same standards as the current sewer system serving other citizens. Police and other municipal services can be provided as well.
  - E. No land held in identical ownership has been divided into separate parts. No land with a valuation of over \$200,000 has been included without written consent. No annexation proceedings concerning this area have been commenced by any other municipality.
  - F. This annexation will not result in any detachment of area from any school district.
  - G. No part of the area to be annexed extends any more than three (3) miles from the existing Town boundaries. The Town has in place a plan for that area as required by C.R.S. § 31-1-105.
  - H. The entire widths of any streets to be annexed are included within the annexation.
2. No petition for annexation election has been submitted and an election is not required pursuant to C.R.S. § 31-12-107(2). An annexation agreement has been submitted.
3. The Town Council has determined that additional terms and conditions will not be imposed.
4. The Petition was signed by the owners of 100% of the property to be annexed exclusive of streets and alleys.
5. Notice of this hearing has been given as required by C.R.S. § 31-12-108.
6. An Annexation Impact Report was submitted to the Weld County Board of County Commissioners and County Attorney pursuant to C.R.S. § 31-12-108.5.



**CONCLUSIONS**

- 1. The area proposed for annexation is eligible for annexation pursuant to applicable parts of C.R.S. § 31-12-104.
- 2. None of the limitations of C.R.S. § 31-12-105 apply to restrict annexation.
- 3. Said Archdiocese Annexation Nos. 1-3 may be annexed by Ordinance pursuant to C.R.S. § 31-12-111, without an election under C.R.S. § 31-12-107(2).

PASSED, SIGNED, APPROVED, AND ADOPTED THIS \_\_\_ day of \_\_\_\_\_, 2023.

ATTEST:

TOWN OF JOHNSTOWN, COLORADO

By: \_\_\_\_\_  
Hannah Hill, Town Clerk

By: \_\_\_\_\_  
Gary Lebsack, Mayor

**EXHIBIT A****PROPERTY DESCRIPTION:****ARCHDIOCESE ANNEXATION No. 1**

An area of land being a portion of the Northwest Quarter of the Northeast Quarter (NW1/4NE1/4) of Section Sixteen (16), Township Four North (T.4N.), Range Sixty-seven West (R.67W.) of the Sixth Principal Meridian (6th P.M.), County of Weld, State of Colorado, being more particularly described as follows;

COMMENCING at the North Quarter corner of said Section 16 and assuming the North line of the Northeast at the North Quarter corner of said Section 16 and assuming the North line of the Northeast Quarter (NE1/4) of said Section 16 as monumented by a #6 rebar with a 3.25" aluminum cap stamped LS 7242 at the West aluminum cap stamped LS 7242 at the West end and a 2.5" aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing aluminum cap stamped LS 13155 at the East end, as bearing South 88°26'46" East, being a grid bearing of the Colorado State Plane Coordinate System, North Zone, North American Datum 1983 (2011), a distance of 2722.98 feet, with all other bearings contained herein being relative thereto.

The lineal dimensions as contained herein are based upon the "U.S. Survey Foot".

THENCE South 01°04'34" East along the West line of the NE1/4 of said Section 16 a distance of 1054.41 feet to the POINT OF BEGINNING;

THENCE South 79°32'21" East a distance of 673.25 feet;

THENCE South 77°23'12" West a distance of 673.25 feet to the Center North Sixteenth corner of said Section 16;

THENCE North 01°04'34" West along the West line of the NW1/4NW1/4 a distance of 269.30 feet to the POINT OF BEGINNING.

Said area of land contains 2.04 Acres (+/-88,822 sq.ft.) and is subject to any rights-of-way or other easements of record as now existing on said described parcel of land.

AND

**ARCHDIOCESE ANNEXATION No. 2**

An area of land being a portion of the North Half of the Northeast Quarter (N1/2NE1/4) of Section Sixteen (16), Township Four North (T.4N.), Range Sixty-seven West (R.67W.) of the Sixth Principal Meridian (6th P.M.), County of Weld, State of Colorado, being more particularly described as follows;

COMMENCING at the North Quarter corner of said Section 16 and assuming the North line of the Northeast at the North Quarter corner of said Section 16 and assuming the North line of the Northeast Quarter (NE1/4) of said Section 16 as monumented by a #6 rebar with a 3.25" aluminum cap stamped LS 7242 at the West aluminum cap stamped LS 7242 at the West end and a 2.5" aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing aluminum cap stamped LS 13155 at the East end, as bearing South 88°26'46" East, being a grid bearing of the Colorado State Plane Coordinate System, North Zone, North American Datum 1983 (2011), a distance of 2722.98 feet, with all other bearings contained herein being relative thereto.

The lineal dimensions as contained herein are based upon the "U.S. Survey Foot".

THENCE South 01°04'34" East along the West line of the NE1/4 of said Section 16 a distance of 1054.41 feet to the POINT OF BEGINNING;

THENCE South 89°01'10" East a distance of 1357.98 feet;

THENCE North 00°54'49" West a distance of 756.16 feet;

THENCE North 90°00'00" East a distance of 376.23 feet;

THENCE North 00°00'16" East a distance of 274.14 feet to the North line of said N1/2NE1/4;

THENCE South 88°26'46" East along said North line a distance of 466.38 feet;  
 THENCE South 00°44'27" East a distance of 1301.34 feet to the South line of said N1/2NE1/4;  
 THENCE North 89°01'10" West along said South line a distance of 2200.27 feet to the Center North Sixteenth corner of said Section 16;  
 THENCE North 77°23'12" East a distance of 673.25 feet;  
 THENCE North 79°32'21" West a distance of 673.25 feet to the POINT OF BEGINNING.

Said area of land contains 29.24 Acres (+/-1,273,591 sq.ft.) and is subject to any rights-of-way or other easements of record as now existing on said described parcel of land.

AND

### **ARCHDIOCESE ANNEXATION No. 3**

An area of land being a portion of the Northeast Quarter of the Northeast Quarter (NE1/4NE1/4) of Section Sixteen (16) and a portion of the West Half of the Northwest Quarter (W1/2NW1/4) of Section Fifteen (15), both of Township Four North (T.4N.), Range Sixty-seven West (R.67W.) of the Sixth Principal Meridian (6th P.M.), County of Weld, State of Colorado, being more particularly described as follows;

COMMENCING at the North Quarter corner of said Section 16 and assuming the North line of the Northeast at the North Quarter corner of said Section 16 and assuming the North line of the Northeast Quarter (NE1/4) of said Section 16 as monumented by a #6 rebar with a 3.25" aluminum cap stamped LS 7242 at the West aluminum cap stamped LS 7242 at the West end and a 2.5" aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing aluminum cap stamped LS 13155 at the East end, as bearing South 88°26'46" East, being a grid bearing of the Colorado State Plane Coordinate System, North Zone, North American Datum 1983 (2011), a distance of 2722.98 feet, with all other bearings contained herein being relative thereto.

The lineal dimensions as contained herein are based upon the "U.S. Survey Foot".

THENCE South 88°26'46" East along the North line of the NE1/4 of said Section 16 a distance of 2208.80 feet to the POINT OF BEGINNING;  
 THENCE continuing South 88°26'46" East along said North line a distance of 514.19 feet to the Northeast corner of said Section 16;  
 THENCE South 89°22'30" East along the approximate North line of said W1/2NW1/4 of Section 15 a distance of 30.01 feet to the East right-of-way line of County Road Nineteen (19);  
 THENCE South 00°44'50" East along said East right-of-way line a distance of 1296.39 feet to the Easterly extension of the South line of said NE1/4NE1/4 of Section 16;  
 THENCE North 89°01'10" West along said Easterly extension a distance of 30.01 feet to the North Sixteenth corner of said Sections;  
 THENCE continuing North 89°01'10" West along said South line of the NE1/4NE1/4 a distance of 514.15 feet;  
 THENCE North 00°44'27" West a distance of 1301.34 feet to the North line of said NE1/4NE1/4 of Section 16 and to the POINT OF BEGINNING.

Said area of land contains 16.21 Acres (+/-706,259 sq.ft.) and is subject to any rights-of-way or other easements of record as now existing on said described parcel of land.

PREPARED BY:

**Lat40°, Inc.**

**Professional Land Surveyors**


6250 W. 10<sup>th</sup> Street, Unit 2

Greeley, CO 80634

(970) 515-529

# ARCHDIOCESE ANNEX, ZONING AND DOVE SOLAR ODP AND USR

Item #8.







# Town of Johnstown

## TOWN COUNCIL AGENDA COMMUNICATIONS

---

**AGENDA DATE:** April 17, 2023

**SUBJECT:** Discussion – Water Policy

**ACTION PROPOSED:** Discussion and General Direction Requested

**ATTACHMENTS:** 1. Water Policy – UPDATED  
2. Water Policy – Original (March 18 Version)

**PRESENTED BY:** Matt LeCerf, Town Manager

---

**AGENDA ITEM DESCRIPTION:**

Town Council hosted and participated in a Strategic Planning Retreat on Saturday, March 18. One of the many topics discussed was the creation of a Water Policy to be presented to the voters for consideration and inclusion into the Home Rule Charter. While there are several methods to amend the Home Rule Charter, Section 7.5 permits for this to be accomplished by Town Council through the approval of an Ordinance authorizing the submitting of a question to the registered electors of the Town.

Included are the Water Policy declarations that were presented to the Council for an initial review and critique. These were generated in concert with the Town’s Water Attorney and Water Resources Engineer. They have been further adjusted slightly by our Town Attorney to fit the Home Rule Charter. These six (6) policy statements would create a very high level policy for water to be included in the Home Rule Charter. This assumes that:

1. Council desires to present these items to the voters in an upcoming ballot referendum; and
2. The voters approved the water policy question proposed.

Based on a conversation with the Town Attorney, we believe that the question to adopt a Water Policy, to be included in the Home Rule Charter, can be proposed in one single question that would encompass the 6 elements of the policy.

During the meeting on March 18, Council was generally supportive of the water policy, but did have a discussion related to item (F) which contemplates the amount of surplus the Town should have available in its portfolio. The initial language of item F read as follows:

- *The Town will maintain a water portfolio that will be greater than or equal to 1.2 times the acre foot volume treated at the Johnstown Water Treatment Plant each year.*

The Community That Cares

johnstown.colorado.gov

P: 970.587.4664 | 450 S. Parish Ave, Johnstown CO 80534 | F: 970.587.0141

The language in the updated version reads as follows:

- *The Town shall endeavor to maintain a water portfolio greater than or equal to 1.2 times the acre-foot volume of water treated at the Johnstown Water Treatment Plant during each calendar year.*

During the retreat, there were ideas and thoughts if a finite amount of surplus should be removed from the Charter provisions given the potential for the Town to be a regular purchaser of water and instead “set a strategic water reserve” on a regular yearly interval. Also, brought up was if the water should be defined by what is delivered or treated wholistically, recognizing that from time to time we utilize interconnects with other partners during peak seasonal demands and just identifying the Johnstown Water Treatment may not be fully representative of actual water consumption in the Town.

Based on the feedback from Council this evening, Staff would like to secure direction on the following questions:

1. Is the policy complete and what changes should be made to the policy based on the items that may need clarity?
2. Should Staff bring back an Ordinance on May 1 for consideration by the Town Council to include this policy at the April 2024 election?

**LEGAL ADVICE:**

NA

**FINANCIAL ADVICE:**

NA

**RECOMMENDED ACTION:** Staff desires the feedback/direction from Council based on the two items in the agenda description.

---

*Reviewed and Approved for Presentation,*

\_\_\_\_\_  
Town Manager

## 16.4 – Water Policy

- A. Any person, legal entity or political body who seeks an extension of water service, annexation of land to the Town or a change in land use, if such change in use will increase the demand for water service, shall dedicate a sufficient amount of acceptable raw water to the Town; except that, for good cause shown, as determined by the Town Council, the Town may accept cash-in-lieu of the required raw water dedication in an amount at least equal to the fair market value of water rights sold.
- B. The Town shall protect the Town’s water rights by, when warranted and economically feasible, filing water court actions to change the decreed use of such water to allow for municipal uses and participating in third party cases to protect the Town’s then existing water portfolio.
- C. The Town may provide more raw water credit for the dedication of water rights that, at the time of dedication, allow for municipal uses than water rights that do not allow for municipal uses.
- D. The Town shall not sell or otherwise transfer the Town’s water rights unless the Town receives, at a minimum, an equivalent yield on a water exchange; except that, in addition to the sale to allow for cash-in-lieu of the required water dedication as provided in Paragraph A above, the Town may sell water rights to fund capital improvement projects related to the treatment or distribution of water or wastewater.
- E. The Town shall endeavor to retain sufficient water resources above the Town’s annual water demands to ensure that the Town will have adequate water supplies in times of extended drought.
- F. The Town shall endeavor to maintain a water portfolio greater than or equal to 1.2 times the acre-foot volume of water treated at the Johnstown Water Treatment Plant during each calendar year.

The Town of Johnstown continues to acknowledge that the acquisition and protection of water resources for the health and protection of its current and future citizens is of paramount importance. Therefore, the Town adopts the following requirements and conditions:

A. Developers of new housing, commercial, or other projects must dedicate sufficient water to the Town to supply the raw water necessary to supply such projects. In certain circumstances, where the Town determines the economic benefit to the Town is sufficient, the Town may provide the necessary water for development under such terms and conditions as the Town decides.

B. The Town will continue to act to protect water rights under its control through the water court process including by filing additional cases to change the decreed use of the water where necessary and entering into other cases to protect its then existing water portfolio.

C. The Town recognizes that water rights that have been changed to allow municipal use within the current or future boundaries of the Town provide more certainty and so a greater value to the Town and so a differential in Single Family Equivalent (SFE) and Water Court Costs is appropriate.

D. The Town will not sell or otherwise transfer any water rights it acquires through dedication or from purchase, except when necessary to fund capital improvement projects directly related to supplying water for current or future development and supplying the waste water treatment associated with those uses. However, the Town will retain sufficient water resources above the Town's annual need to assure that the Town will have adequate water supplies in times of extended drought.

E. Except as set forth in #4, above, the Town will not transfer any water outside of its ownership and portfolio unless the Town receives, at a minimum, an equivocal drop for drop yield on the water exchange.

F. The Town will maintain a water portfolio that will be greater than or equal to 1.2 times the acre foot volume treated at the Johnstown Water Treatment Plant each year.





# Town of Johnstown

## TOWN COUNCIL AGENDA COMMUNICATIONS

---

- AGENDA DATE:** April 17, 2023
- SUBJECT:** Ordinance 2023-244 regarding the Archdiocese Annexation Nos. 1-3
- ACTION PROPOSED:** Hold Public Hearing and Consider Ordinance 2023-244 Annexing certain unincorporated lands located in Weld County, known as the Archdiocese Annexation Nos. 1-3, containing approx. 47.49 acres.
- ATTACHMENTS:**
1. Ordinance 2023-244
  2. Vicinity Map
  3. Petition
  4. Annexation Maps Nos. 1, 2 and 3
  5. PZC Agenda Memorandum for Annexation & Zoning
  6. Staff Presentation
- PRESENTED BY:** Kim Meyer, Planning & Development Director
- 

### AGENDA ITEM DESCRIPTION:

The Town has received a petition for annexation from the owner, for the Archdiocese Annexation Nos. 1-3 (Attachment 3), located in Weld County. The property is west of Weld County Road 19, and north of Weld County Road 44, adjacent to and excluding the Little Thompson/Hillsborough reservoir and ditch. (Attachment 2).

This proposed area of annexation meets the eligibility and contiguity requirements of CRS 31-104 and 105, and is bordered by Johnstown along the western boundary (Attachment 4).

This original proposed annexation consisted of 82.59 acres, comprised of two Archdiocese Annexation, Nos. 1 and 2. Following discussions with the Town of Milliken, and Extension Irrigation Company (Little Thompson/Hillsborough Reservoir and the Ditch), a portion of this Archdiocese parcel has been excluded by deed from the subject annexation. The resulting annexation is a series of three annexations that build upon one another for contiguity purposes, and comprise a 47.49 acre annexation, in total. All documentation has been updated accordingly and has received acceptance by parties in interest, and is reflected in the documents presented.

The Planning & Zoning Commission (PZC) held a public hearing on February 15, 2023, to consider the previous configuration of the subject annexations, as stated above. The Planning & Zoning Commission Agenda Memorandum (Attachment 5) provides background and historical use of the property. The property has been undeveloped agricultural land within unincorporated Weld County, with some limited oil and gas

facilities. Based upon the materials submitted, analysis, and findings, the PZC approved a motion recommending to Town Council approval of this annexation request.

The Johnstown Review Committee reviewed this project and provided redlines and comments, which have been addressed by the Applicant. Full referral packets, required per C.R.S., were sent via registered mail to the Weld County Board of County Commissioners, the County Attorney, and all Special Districts.

This petition and application for annexation is accompanied by companion requests, on this Council agenda, for Establishment of Zoning to PUD-MU (Mixed Use), as well as an Outline Development Plan and Use by Special Review to permit development of a community scale solar facility on a portion of this annexation area. An annexation agreement will be presented concurrent with the second reading of the ordinance, which includes the provision for dedication of additional right of way along the County Road 19 frontage of this parcel to be executed and recorded on or after the effective date of this annexation.

**LEGAL ADVICE:**

Ordinance was prepared by the Town Attorney.

**FINANCIAL ADVICE:**

NA

**RECOMMENDED ACTION:**

Planning & Zoning Commission recommended, and Town Staff supports, Approval of Ordinance 2023-244 Annexing approximately 47.49 acres, known as the Archdiocese Annexation Nos. 1-3 on First Reading.

**SUGGESTED MOTIONS:**


**For Approval**

I move that the Town Council approve Ordinance 2023-244, on First Reading.

**For Denial**

I move that the Town Council deny Ordinance 2023-244.

*Reviewed and Approved for Presentation,*

  
\_\_\_\_\_  
Town Manager

**TOWN OF JOHNSTOWN, COLORADO**  
**ORDINANCE NO. 2023-244**

**ANNEXING CERTAIN UNINCORPORATED LANDS LOCATED IN PORTIONS OF THE NORTH HALF OF THE NORTHEAST QUARTER OF SECTION 16 AND THE WEST HALF OF THE NORTHWEST QUARTER OF SECTION 15, TOWNSHIP 4 NORTH, RANGE 67 WEST OF THE 6TH P.M., COUNTY OF WELD, STATE OF COLORADO, CONSISTING OF APPROXIMATELY 47.49 ACRES, AND KNOWN RESPECTIVELY AS THE ARCHDIOCESE ANNEXATION NOS. 1-3.**

**WHEREAS**, the Town of Johnstown, Colorado (“Town”) is a Colorado home rule municipality, duly organized and existing under the laws of the State of Colorado and the Town’s Home Rule Charter; and

**WHEREAS**, the Town Council is vested with authority to administer the affairs of the Town; and

**WHEREAS**, by Resolution No. 2023-06, the Town Council found a petition for annexation of certain property situated in a portion of Sections 15 and 16, Township 4 North, Range 67 West of the 6<sup>th</sup> P.M., County of Weld, State of Colorado, consisting of approximately 82.59 acres, known as the “Archdiocese Annexation No. 1 and Archdiocese Annexation No. 2,” to be in substantial compliance with C.R.S. § 31-12-107(1); and

**WHEREAS**, subsequent thereto, the Archdiocese modified its request and only seeks to annex 47.49 acres of the 82.59 acres into the municipal boundaries of the Town in order to exclude lands which contain the Little Thompson/Hillsborough Reservoir and Ditch; and

**WHEREAS**, consistent with the foregoing, the Archdiocese seeks to annex a Portion of the North Half of the Northeast Quarter of Section 16 and a Portion of the West Half of the Northwest Quarter of Section 15, Township 4 North, Range 67 West of the 6<sup>th</sup> P.M., County of Weld, State of Colorado, consisting of approximately 47.49 acres, as more particularly described on Exhibit A, attached hereto and incorporated herein by reference, known as the “Archdiocese Annexation Nos. 1-3;”

**WHEREAS**, after notice pursuant to C.R.S. § 31-12-108, on April 17, 2023, the Town Council held a public hearing on the proposed annexation to determine if the annexation complies with C.R.S. §§ 31-12-104 and 105; and

**WHEREAS**, the Town Council has determined that the requirements of C.R.S. § 31-12-104 and 105 have been met, that an election is not required and that no additional terms or conditions are to be imposed on the annexed area.

**NOW, THEREFORE, BE IT ORDAINED BY THE TOWN COUNCIL OF THE TOWN OF JOHNSTOWN, COLORADO, THAT:**

**Section 1.** The annexation of certain unincorporated property situated in a Portion of the North Half of the Northeast Quarter of Section 16 and a Portion of the West Half of the Northwest Quarter of Section 15, Township 4 North, Range 67 West of the 6<sup>th</sup> P.M., County of Weld, State of Colorado, consisting of approximately 47.49 acres, being more particularly described on Exhibit A, known as the Archdiocese Annexation Nos. 1-3, be and the same is hereby approved and said unincorporated area is hereby incorporated and made a part of the Town of Johnstown, Colorado.

**Section 2.** The annexation of such unincorporated area to the Town of Johnstown, Colorado shall be complete and effective on the effective date of this Ordinance, except for the purpose of general property taxes, and shall be effective as to general property taxes on and after the first day of January, 2024.

**Section 3.** Within thirty (30) days of the effective date of this Ordinance, the Town Clerk be and is hereby authorized and directed to:

- A. File one copy of the annexation map with the original of the annexation ordinance in the office of the Town Clerk; and
- B. File three certified copies of the annexation ordinance and map of the area annexed containing a legal description of such area with the Weld County Clerk and Recorder.

**Section 4.** This Ordinance shall take effect as provided by State law.

**INTRODUCED AND APPROVED** on first reading by the Town Council of the Town of Johnstown, Colorado, this \_\_ day of \_\_\_\_\_, 2023.

**TOWN OF JOHNSTOWN, COLORADO**

**ATTEST:**

By: \_\_\_\_\_  
Hannah Hill, Town Clerk

By: \_\_\_\_\_  
Gary Lebsack, Mayor

**PASSED UPON FINAL APPROVAL AND ADOPTED** on second reading by the Town Council of the Town of Johnstown, Colorado, this \_\_\_\_\_ day of \_\_\_\_\_, 2023.

**TOWN OF JOHNSTOWN, COLORADO**

**ATTEST:**

By: \_\_\_\_\_  
Hannah Hill, Town Clerk

By: \_\_\_\_\_  
Gary Lebsack, Mayor

**EXHIBIT A****PROPERTY DESCRIPTION:****ARCHDIOCESE ANNEXATION No. 1**

An area of land being a portion of the Northwest Quarter of the Northeast Quarter (NW1/4NE1/4) of Section Sixteen (16), Township Four North (T.4N.), Range Sixty-seven West (R.67W.) of the Sixth Principal Meridian (6th P.M.), County of Weld, State of Colorado, being more particularly described as follows;

COMMENCING at the North Quarter corner of said Section 16 and assuming the North line of the Northeast at the North Quarter corner of said Section 16 and assuming the North line of the Northeast Quarter (NE1/4) of said Section 16 as monumented by a #6 rebar with a 3.25" aluminum cap stamped LS 7242 at the West end and a 2.5" aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing aluminum cap stamped LS 13155 at the East end, as bearing South 88°26'46" East, being a grid bearing of the Colorado State Plane Coordinate System, North Zone, North American Datum 1983 (2011), a distance of 2722.98 feet, with all other bearings contained herein being relative thereto.

The lineal dimensions as contained herein are based upon the "U.S. Survey Foot".

THENCE South 01°04'34" East along the West line of the NE1/4 of said Section 16 a distance of 1054.41 feet to the POINT OF BEGINNING;  
 THENCE South 79°32'21" East a distance of 673.25 feet;  
 THENCE South 77°23'12" West a distance of 673.25 feet to the Center North Sixteenth corner of said Section 16;  
 THENCE North 01°04'34" West along the West line of the NW1/4NW1/4 a distance of 269.30 feet to the POINT OF BEGINNING.

Said area of land contains 2.04 Acres (+/-88,822 sq.ft.) and is subject to any rights-of-way or other easements of record as now existing on said described parcel of land.

AND

**ARCHDIOCESE ANNEXATION No. 2**

An area of land being a portion of the North Half of the Northeast Quarter (N1/2NE1/4) of Section Sixteen (16), Township Four North (T.4N.), Range Sixty-seven West (R.67W.) of the Sixth Principal Meridian (6th P.M.), County of Weld, State of Colorado, being more particularly described as follows;

COMMENCING at the North Quarter corner of said Section 16 and assuming the North line of the Northeast at the North Quarter corner of said Section 16 and assuming the North line of the Northeast Quarter (NE1/4) of said Section 16 as monumented by a #6 rebar with a 3.25"



aluminum cap stamped LS 7242 at the West aluminum cap stamped LS 7242 at the West end and a 2.5" aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing aluminum cap stamped LS 13155 at the East end, as bearing South 88°26'46" East, being a grid bearing of the Colorado State Plane Coordinate System, North Zone, North American Datum 1983 (2011), a distance of 2722.98 feet, with all other bearings contained herein being relative thereto.

The lineal dimensions as contained herein are based upon the "U.S. Survey Foot".

THENCE South 01°04'34" East along the West line of the NE1/4 of said Section 16 a distance of 1054.41 feet to the POINT OF BEGINNING;  
 THENCE South 89°01'10" East a distance of 1357.98 feet;  
 THENCE North 00°54'49" West a distance of 756.16 feet;  
 THENCE North 90°00'00" East a distance of 376.23 feet;  
 THENCE North 00°00'16" East a distance of 274.14 feet to the North line of said N1/2NE1/4;  
 THENCE South 88°26'46" East along said North line a distance of 466.38 feet;  
 THENCE South 00°44'27" East a distance of 1301.34 feet to the South line of said N1/2NE1/4;  
 THENCE North 89°01'10" West along said South line a distance of 2200.27 feet to the Center North Sixteenth corner of said Section 16;  
 THENCE North 77°23'12" East a distance of 673.25 feet;  
 THENCE North 79°32'21" West a distance of 673.25 feet to the POINT OF BEGINNING.

Said area of land contains 29.24 Acres (+/-1,273,591 sq.ft.) and is subject to any rights-of-way or other easements of record as now existing on said described parcel of land.

AND

### **ARCHDIOCESE ANNEXATION No. 3**

An area of land being a portion of the Northeast Quarter of the Northeast Quarter (NE1/4NE1/4) of Section Sixteen (16) and a portion of the West Half of the Northwest Quarter (W1/2NW1/4) of Section Fifteen (15), both of Township Four North (T.4N.), Range Sixty-seven West (R.67W.) of the Sixth Principal Meridian (6th P.M.), County of Weld, State of Colorado, being more particularly described as follows;

COMMENCING at the North Quarter corner of said Section 16 and assuming the North line of the Northeast at the North Quarter corner of said Section 16 and assuming the North line of the Northeast Quarter (NE1/4) of said Section 16 as monumented by a #6 rebar with a 3.25" aluminum cap stamped LS 7242 at the West aluminum cap stamped LS 7242 at the West end and a 2.5" aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing aluminum cap stamped LS 13155 at the East end, as bearing South 88°26'46" East, being a grid bearing of the Colorado State Plane Coordinate System, North Zone, North American Datum 1983 (2011), a distance of 2722.98 feet, with all other bearings contained herein being relative thereto.

The lineal dimensions as contained herein are based upon the "U.S. Survey Foot".

THENCE South 88°26'46" East along the North line of the NE1/4 of said Section 16 a distance of 2208.80 feet to the POINT OF BEGINNING;  
THENCE continuing South 88°26'46" East along said North line a distance of 514.19 feet to the Northeast corner of said Section 16;  
THENCE South 89°22'30" East along the approximate North line of said W1/2NW1/4 of Section 15 a distance of 30.01 feet to the East right-of-way line of County Road Nineteen (19);  
THENCE South 00°44'50" East along said East right-of-way line a distance of 1296.39 feet to the Easterly extension of the South line of said NE1/4NE1/4 of Section 16;  
THENCE North 89°01'10" West along said Easterly extension a distance of 30.01 feet to the North Sixteenth corner of said Sections;  
THENCE continuing North 89°01'10" West along said South line of the NE1/4NE1/4 a distance of 514.15 feet;  
THENCE North 00°44'27" West a distance of 1301.34 feet to the North line of said NE1/4NE1/4 of Section 16 and to the POINT OF BEGINNING.


Said area of land contains 16.21 Acres (+/-706,259 sq.ft.) and is subject to any rights-of-way or other easements of record as now existing on said described parcel of land.

PREPARED BY:

**Lat40°, Inc.**  
**Professional Land Surveyors**  
6250 W. 10<sup>th</sup> Street, Unit 2  
Greeley, CO 80634  
(970) 515-529

# ARCHDIOCESE ANNEX, ZONING AND DOVE SOLAR ODP AND USR

Item #10.



**PETITION FOR ANNEXATION**  
**To the Town of Johnstown**  
(Weld County)

The undersigned, in accordance with Article 12, Chapter 31, CRS, as amended, hereby petition the Town Council of the Town of Johnstown, Colorado, for annexation to the Town of Johnstown the unincorporated territory more particularly described below, currently known as **WELD COUNTY PARCEL NO. 105916100039**, and in support of said Petition, your petitioners allege that:

- (1) It is desirable and necessary that the following described territory be annexed to the Town of Johnstown, Colorado:

See Exhibit A attached hereto and made a part hereof.

- (2) Not less than one-sixth (1/6) of the perimeter of that area proposed to be annexed is contiguous with the Town of Johnstown, Colorado.
- (3) A community of interest exists between the territory proposed to be annexed and the Town of Johnstown, Colorado.
- (4) The territory proposed to be annexed is urban or will be urbanized in the near future;
- (5) The territory proposed to be annexed is integrated or is capable of being integrated with the Town of Johnstown, Colorado;
- (6) The signatures of the Petition comprise one hundred percent (100%) of the landowners of the territory to be included in the area proposed to be annexed and said landowners attesting to the facts and agreeing to the conditions herein contained will negate the necessity of any annexation election;
- (7) No land held in identical ownership, whether consisting of one tract or parcel of real estate or two or more contiguous tracts or parcels of real estate:
- (a) Is divided into separate parts or parcels without the written consent of the landowner or landowners thereof, unless such tracts or parcels are separated by a dedicated street, road or other public way;
- (b) Comprising twenty (20) acres or more and which, together with the building and improvements situated thereon has an assessed value in excess of Two Hundred Thousand Dollars (\$200,000.00) for ad valorem tax purposes to be annexed without the written consent of the landowner or landowners.

- (8) No part of the area proposed to be annexed is more than three miles from a point on the municipal boundary, as such was established more than one year before this annexation will take place;
- (9) The area proposed to be annexed comprises more than ten acres and an impact report as provided in Section 31-12-105.5, CRS, as amended, is required.
- (10) The area proposed to be annexed is located within Weld County, School District RE 5-J, Northern Colorado Water Conservancy District, Little Thompson Water District, Front Range Fire Rescue Fire Protection District, Aims Junior College District, and Weld County Library District, and no others;
- (11) The mailing address of each signer, the legal description of the land owned by each signer and the date of signing of each signature are all shown on this Petition;
- (12) Accompanying this Petition are five (5) prints of the area proposed to be following information:
  - (a) A written legal description of the boundaries of the area proposed to be annexed;
  - (b) A map showing the boundary of the area proposed to be annexed, such map prepared and containing the seal of a registered engineer or land surveyor;
  - (c) Within the annexation boundary map there is shown the location of each ownership tract in unplatted land, and if part or all of the area is to be platted at the time of the effectiveness of the annexation (as opposed to after such effectiveness), then the boundaries and the plat number of plots or of lots and blocks are shown;
  - (d) Next to the boundary of the area proposed to be annexed is drawn the contiguous boundary of the Town of Johnstown, and the contiguous boundary of any other municipality abutting the area proposed to be annexed;
  - (e) The dimensions of the contiguous boundaries are shown on the map.
  - (f) A proposed drainage plan and a proposed utilities plan.
- (13) The territory to be annexed is not presently a part of any incorporated city, city and county, or town;






STATE OF COLORADO )  
 )ss  
COUNTY OF Denver )

Subscribed and sworn to before me this 27<sup>th</sup> day of July,  
2022 by Keith Parsons as COO, Attorney in fact for of  
Archbishop Samuel J. Aquila, Archbishop of Denver on behalf of  
\_\_\_\_\_.

WITNESS my hand and official seal.

My commission expires: June 25, 2025

Christina Marie Buches  
NOTARY PUBLIC  
STATE OF COLORADO  
NOTARY ID# 20214025358  
MY COMMISSION EXPIRES JUNE 25, 2025

  
\_\_\_\_\_  
Notary Public

**EXHIBIT A**

Legal Description: PART OF THE NORTH HALF OF THE NORTHEAST QUARTER OF SECTION 16, TOWNSHIP 4 NORTH, RANGE 67 WEST OF THE 6<sup>TH</sup> P.M., COUNTY OF WELD, STATE OF COLORADO



# ARCHDIOCESE ANNEXATION No. 1 - 3

Part of the North Half of the Northeast Quarter of Section 16, Township 4 North, Range 67 West of the 6th P.M., County of Weld, State of Colorado

### PROPERTY DESCRIPTION - ARCHDIOCESE ANNEXATION No. 1

An area of land being a portion of the Northwest Quarter of the Northeast Quarter (NW1/4NE1/4) of Section Sixteen (16), Township Four North (T.4N.), Range Sixty-seven West (R.67W.) of the Sixth Principal Meridian (6th P.M.), County of Weld, State of Colorado, being more particularly described as follows:

**COMMENCING** at the North Quarter corner of said Section 16 and assuming the North line of the Northeast Quarter (NE1/4) of said Section 16 as monumented by a #6 rebar with a 3.25" aluminum cap stamped LS 7242 at the West end and a 2.5" aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing South 88°26'46" East, being a grid bearing of the Colorado State Plane Coordinate System, North Zone, North American Datum 1983 (2011), a distance of 2722.98 feet, with all other bearings contained herein being relative thereto.

The lineal dimensions as contained herein are based upon the "U.S. Survey Foot".

THENCE South 01°04'34" East along the West line of the NE1/4 of said Section 16 a distance of 1054.41 feet to the **POINT OF BEGINNING**.

THENCE South 79°32'21" East a distance of 673.25 feet;  
THENCE South 77°23'12" West a distance of 673.25 feet to the Center North Sixteenth corner of said Section 16;  
THENCE North 01°04'34" West along the West line of the NW1/4NW1/4 a distance of 269.30 feet to the **POINT OF BEGINNING**.

Said area of land contains 2.04 Acres (+/-88,822 sq.ft.) and is subject to any rights-of-way or other easements of record as now existing on said described parcel of land.

### OWNER'S APPROVAL

Know all men by these presents, that I/we, Archdiocese of Denver, being the sole owner(s) of the land described herein, have caused said land to be annexed under the name of **ARCHDIOCESE ANNEXATION No. 1-3**.

IN WITNESS WHEREOF, we have hereunto set our hands and seals this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

Archdiocese of Denver by Keith Parsons COO,  
Attorney in Fact for Most Reverend Samuel J. Aquila, S.T.L., Archbishop of Denver

### NOTARIAL CERTIFICATE

STATE OF \_\_\_\_\_ )  
COUNTY OF \_\_\_\_\_ )SS

The foregoing instrument was acknowledged before me by Keith Parsons COO, Attorney in Fact for Most Reverend Samuel J. Aquila, S.T.L., Archbishop of Denver

this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_. Witness my hand and seal.

My commission expires \_\_\_\_\_ Notary Public

### TOWN COUNCIL APPROVAL

This map to be known as **ARCHDIOCESE ANNEXATION No. 1-3** is approved and accepted to the Town of Johnstown, Colorado by ordinance number \_\_\_\_\_, passed and adopted on final reading at the regular meeting of the Town Council of the Town of Johnstown, Colorado, held on the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.


BY: \_\_\_\_\_ Mayor Seal Attest: \_\_\_\_\_ Town Clerk

### SURVEYOR'S STATEMENT

I, Jason S. Allee, a Colorado Licensed Professional Land Surveyor, do hereby state that this Annexation Map was prepared from an actual survey under my personal supervision, that the monumentation as indicated hereon was found or set as shown, and that the foregoing plat is an accurate representation thereof, all this to the best of my knowledge, information and belief.


**PRELIMINARY**

Sheet 1 of 3  
Jason S. Allee—On behalf of Lat40°, Inc.  
Colorado Licensed Professional  
Land Surveyor No. 38479




VICINITY MAP  
SCALE - 1"=2000'

### VICINITY LEGEND



### LEGEND



### SURVEYOR'S NOTES

#### 1. BASIS OF BEARINGS AND LINEAL UNIT DEFINITION

Assuming the North line of the Northeast Quarter (NE1/4) of Section 16, T.4., R.67W., as monumented by a #6 rebar with a 3.25" aluminum cap stamped LS 7242 at the West end and a 2.5" aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing South 88°26'46" East, being a Grid Bearing of the Colorado State Plane Coordinate System, North Zone, North American Datum 1983 (2011), a distance of 2722.98 feet with all other bearings contained herein relative thereto.

The lineal dimensions as contained herein are based upon the "U.S. Survey Foot".

2. This Annexation Map does not represent a Monumented Land Survey by Lat40°, Inc. It is intended to depict the described parcels and their relationship with the existing Town of Johnstown town limits


3. The area of Annexation is within the following Special Districts:  
Thompson River Park and Recreation District  
West Greeley Conservation District

### TITLE COMMITMENT NOTE


This survey does not constitute a title search by Lat40°, Inc. to determine ownership or easements of record. For all information regarding easements, rights-of-way and title of records, Lat40°, Inc. relied upon Title Commitment File Number N0034909-858-ES, Amendment No. 1, having an effective date of June 23, 2022, as prepared by Fidelity National Title Insurance Company to delineate the aforesaid information.

### NOTICE:

According to Colorado law, you must commence any legal action based upon any defect in this survey within three years after you discover such defect. In no event, may any action based upon any defect in this survey be commenced more than ten years after the date of the certificate shown hereon. (13-80-105 C.R.S.)



ANNEXATION TABLE	
CONTIGUOUS BOUNDARY	269.30 L.F.
TOTAL BOUNDARY PERIMETER	1615.80 L.F.
1/6 OF PERIMETER	269.30 L.F.
ANNEXATION RATIO	1 to 6,000
TOTAL LAND AREA	2.04 Acres



LAT40°, Inc.  
Professional Land Surveyors  
6250 W. 10th Street, Unit 2  
Greeley, CO 80634  
O: 970-515-5294

REVISIONS	
DESCRIPTION:	DATE:

**ARCHDIOCESE ANNEXATION No. 1-3**  
ARCHDIOCESE PROPERTY - JOHNSTOWN, CO  
WELD COUNTY - SECTION 16, T.4N., R.67W.  
ARCHDIOCESE OF DENVER  
1300 SOUTH STEELE STREET, DENVER, CO 80210

DRAWN BY: LD  
CHECKED BY: JA


SCALE: AS NOTED  
PROJECT #: 2023108

DATE: 3/28/2023  
SHEET: 1 OF 3



# ARCHDIOCESE ANNEXATION No. 1 - 3

Part of the North Half of the Northeast Quarter of Section 16, Township 4 North, Range 67 West of the 6th P.M., County of Weld, State of Colorado



RED MOUNTAIN ANNEXATION #4  
RECEPTION No. 2866968

ARCHDIOCESE ANNEXATION No. 1

ARCHDIOCESE ANNEXATION No. 2  
29.24 Acres (±1,273,591 sq.ft.)

COUNTY ROAD 46  
S 00°44'27" E 2592.40'

**PROPERTY DESCRIPTION - ARCHDIOCESE ANNEXATION No. 2**

An area of land being a portion of the North Half of the Northeast Quarter (N1/2NE1/4) of Section Sixteen (16), Township Four North (T.4N.), Range Sixty-seven West (R.67W.) of the Sixth Principal Meridian (6th P.M.), County of Weld, State of Colorado, being more particularly described as follows:

**COMMENCING** at the North Quarter corner of said Section 16 and assuming the North line of the Northeast Quarter (NE1/4) of said Section 16 as monumented by a #6 rebar with a 3.25" aluminum cap stamped LS 7242 at the West end and a 2.5" aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing South 88°26'46" East, being a grid bearing of the Colorado State Plane Coordinate System, North Zone, North American Datum 1983 (2011), a distance of 2722.98 feet, with all other bearings contained herein being relative thereto.

The lineal dimensions as contained herein are based upon the "U.S. Survey Foot".

THENCE South 01°04'34" East along the West line of the NE1/4 of said Section 16 a distance of 1054.41 feet to the **POINT OF BEGINNING**;

THENCE South 89°01'10" East a distance of 1357.98 feet;

THENCE North 00°54'49" West a distance of 756.16 feet;

THENCE North 90°00'00" East a distance of 376.23 feet;

THENCE North 00°00'16" East a distance of 274.14 feet to the North line of said N1/2NE1/4;

THENCE South 88°26'46" East along said North line a distance of 466.38 feet;

THENCE South 00°44'27" East a distance of 1301.34 feet to the South line of said N1/2NE1/4;

THENCE North 89°01'10" West along said South line a distance of 2200.27 feet to the Center North Sixteenth corner of said Section 16;

THENCE North 77°23'12" East a distance of 673.25 feet;

THENCE North 79°32'21" West a distance of 673.25 feet to the **POINT OF BEGINNING**.

Said area of land contains 29.24 Acres (±1,273,591 sq.ft.) and is subject to any rights-of-way or other easements of record as now existing on said described parcel of land.

ANNEXATION TABLE	
CONTIGUOUS BOUNDARY	1346.50
TOTAL BOUNDARY PERIMETER	8079.00
1/6 OF PERIMETER	1346.50
ANNEXATION RATIO	1 to 6,000
TOTAL LAND AREA	29.94

**LEGEND**

- ANNEXATION BOUNDARY
- EASEMENT
- SECTION LINE
- QUARTER SECTION LINE
- FRACTIONAL SECTION LINE
- RIGHT-OF-WAY
- ADDITIONAL RIGHT-OF-WAY
- ADJACENT PROPERTY LINE
- EXISTING TOWN LIMITS
- FOUND ALIQUOT CORNER AS DESCRIBED
- FOUND WITNESS CORNER AS DESCRIBED
- FOUND MONUMENT AS DESCRIBED
- CALCULATED POSITION
- EXISTING PLUGGED & ABANDONED WELL

**LEGEND**

- FOUND ALIQUOT CORNER AS DESCRIBED
- FOUND WITNESS CORNER AS DESCRIBED
- FOUND MONUMENT AS DESCRIBED
- CALCULATED POSITION
- EXISTING PLUGGED & ABANDONED WELL

EAST QUARTER CORNER SECTION 16, T.4N., R.67W. FOUND #6 REBAR WITH 2.0" ALUMINUM CAP LS 22097 CALCULATED POSITION 0.7'± BELOW GRADE IN MONUMENT BOX

SCALE - 1"=100'

SHEET SIZE: 24X36

Sheet 2 of 3  
**PRELIMINARY**  
 Jason S. Allie-On behalf of Lat40°, Inc.  
 Colorado Licensed Professional  
 Land Surveyor No. 38479



**LAT40°, Inc.**  
 Professional Land Surveyors  
 6250 W. 10th Street, Unit 2  
 Greeley, CO 80634  
 O: 970-515-5294

REVISIONS	
DESCRIPTION:	DATE:


**ARCHDIOCESE ANNEXATION No. 1-3**  
 ARCHDIOCESE PROPERTY - JOHNSTOWN, CO  
 WELD COUNTY - SECTION 16, T.4N., R.67W.  
 ARCHDIOCESE OF DENVER  
 1300 SOUTH STEELE STREET, DENVER, CO 80210

DRAWN BY: LD  
 CHECKED BY: JA  
 SCALE: AS NOTED  
 PROJECT #: 2023108  
 DATE: 3/28/2023  
 SHEET: 2 OF 3



# ARCHDIOCESE ANNEXATION No. 1 - 3

Part of the North Half of the Northeast Quarter of Section 16, and a Portion of the West Half of the Northwest Quarter of Section 15, Township 4 North, Range 67 West of the 6th P.M., County of Weld, State of Colorado



### PROPERTY DESCRIPTION - ARCHDIOCESE ANNEXATION No. 3

An area of land being a portion of the Northeast Quarter of the Northeast Quarter (NE1/4NE1/4) of Section Sixteen (16) and a portion of the West Half of the Northwest Quarter (W1/2NW1/4) of Section Fifteen (15), both of Township Four North (T.4N.), Range Sixty-seven West (R.67W.) of the Sixth Principal Meridian (6th P.M.), County of Weld, State of Colorado, being more particularly described as follows:

COMMENCING at the North Quarter corner of said Section 16 and assuming the North line of the Northeast Quarter (NE1/4) of said Section 16 as monumented by a #6 rebar with a 3.25" aluminum cap stamped LS 7242 at the West end and a 2.5" aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing South 88°26'46" East, being a grid bearing of the Colorado State Plane Coordinate System, North Zone, North American Datum 1983 (2011), a distance of 2722.98 feet, with all other bearings contained herein being relative thereto.

The lineal dimensions as contained herein are based upon the "U.S. Survey Foot".

THENCE South 88°26'46" East along the North line of the NE1/4 of said Section 16 a distance of 2208.80 feet to the POINT OF BEGINNING;

THENCE continuing South 88°26'46" East along said North line a distance of 514.19 feet to the Northeast corner of said Section 16;

THENCE South 89°22'30" East along the approximate North line of said W1/2NW1/4 of Section 15 a distance of 30.01 feet to the East right-of-way line of County Road Nineteen (19);

THENCE South 00°44'50" East along said East right-of-way line a distance of 1296.39 feet to the Easterly extension of the South line of said NE1/4NE1/4 of Section 16;

THENCE North 89°01'10" West along said Easterly extension a distance of 30.01 feet to the North Sixteenth corner of said Section 16;

THENCE continuing North 89°01'10" West along said South line of the NE1/4NE1/4 a distance of 514.15 feet;


THENCE North 00°44'27" West a distance of 1301.34 feet to the North line of said NE1/4NE1/4 of Section 16 and to the POINT OF BEGINNING.

Said area of land contains 16.21 Acres (±706,259 sq.ft.) and is subject to any rights-of-way or other easements of record as now existing on said described parcel of land.

### LEGEND

	ANNEXATION BOUNDARY		FOUND ALIQUOT CORNER AS DESCRIBED
	EASEMENT		FOUND WITNESS CORNER AS DESCRIBED
	SECTION LINE		FOUND MONUMENT AS DESCRIBED
	QUARTER SECTION LINE		CALCULATED POSITION
	FRACTIONAL SECTION LINE		EXISTING PLUGGED & ABANDONED WELL
	RIGHT-OF-WAY		
	ADDITIONAL RIGHT-OF-WAY		
	ADJACENT PROPERTY LINE		
	EXISTING TOWN LIMITS		

ANNEXATION TABLE	
CONTIGUOUS BOUNDARY	1301.34 L.F.
TOTAL BOUNDARY PERIMETER	3686.09 L.F.
1/6 OF PERIMETER	614.35 L.F.
ANNEXATION RATIO	1 to 2.833
TOTAL LAND AREA	16.21 Acres



SHEET SIZE: 24X36

Sheet 3 of 3  
Jason S. Allae-On behalf of Lat40°, Inc.  
Colorado Licensed Professional  
Land Surveyor No. 38479



LAT40°, Inc.  
Professional Land Surveyors  
6250 W. 10th Street, Unit 2  
Greeley, CO 80634  
O: 970-515-5294

REVISIONS	
DESCRIPTION:	DATE:

ARCHDIOCESE ANNEXATION No. 1-3		
ARCHDIOCESE PROPERTY - JOHNSTOWN, CO		
WELD COUNTY - SECTION 16, T.4N., R.67W.		
ARCHDIOCESE OF DENVER		
1300 SOUTH STEELE STREET, DENVER, CO 80210		
DRAWN BY: LD	SCALE: AS NOTED	DATE: 3/28/2023
CHECKED BY: JA	PROJECT #: 2023108	SHEET: 3 OF 3



# Town of Johnstown

## PLANNING & ZONING COMMISSION AGENDA MEMORANDUM

---

<b>DESCRIPTION:</b>	Archdiocese Annexation Nos. 1 and 2 & Establishment of Zoning (HA-Holding Ag and PUD-MU)
<b>PROJECT NO:</b>	ANX22-0003
<b>LOCATION:</b>	South of WCR 46.5 and the Little Thompson Reservoir, west of WCR 19
<b>APPLICANT:</b>	Archbishop of Denver
<b>STAFF:</b>	Kim Meyer, Planning & Development Director
<b>HEARING DATE:</b>	February 15, 2023

---

### ATTACHMENTS

- 1- Vicinity Map
- 2- Annexation Map
- 3- Zoning Map
- 4- COGCC Map

### PROJECT SUMMARY

The Applicant requests Annexation for approximately 82.6 acres of land in Weld County, in two “serial” annexations of 41.06 acres and 41.53. Establishment of zoning is proposed in two parts, with the eastern portion of the property, proposed to support a solar facility with PUD-MU (Mixed Use) zoning; and the western portion proposed to remain in ag production, with an H-A (Holding Ag) zoning district.

An Outline Development Plan as well as an application for a Use by Special Review (USR) for a Solar Facility have also been received and reviewed for this property. These will also be heard concurrently by Planning & Zoning Commission and the Town Council.

### PROPERTY BACKGROUND

The property is located south of Weld County Rd (WCR) 46.5 and west of WCR 19 (Attachment 1). The subject property is presently zoned A - Agricultural in unincorporated Weld County and is being used as farm land. It is bordered to the north by the Hillsborough/Little Thompson Reservoir, to the west by incorporated areas of Johnstown, with the rest being adjacent to unincorporated Weld County and adjacent to the Milliken Growth Management Boundary. The right of way for County Road 46 to the north and east, that just touches this parcel, is already annexed into Milliken.

The Community That Cares

johnstown.colorado.gov

P: 970.587.4664 | 450 S. Parish Ave, Johnstown CO 80534 | F: 970.587.0141

**SURROUNDING ZONING & LAND USE**

North: A – Agricultural (Weld County), Hillsborough/Little Thompson Reservoir  
South: A – Agricultural (Weld County)  
East: A – Agricultural (Weld County)  
West: PUD (Johnstown) with Oil & Gas Well Pads

**LAND USE HISTORY**

Historically, this property has been used for farming and continues as that use today.

**OIL & GAS**

COGCC (Oil & Gas) online maps show existing abandoned and plugged and abandoned wells on-site, Attachment 4. These sites are also shown on the Annexation and Zoning maps, as well as an easement for a Kerr-McGee pipeline that bisects the property.

**IRRIGATION DITCHES**

The Hillsborough/Little Thompson Reservoir, owned and managed by the Extension (Hillsborough) Ditch Company, is partially located on the northwest corner of this property. These are some emergent wetlands along the banks of that water body, identified by the Colorado Wetland Inventory as part of the Colorado Natural Heritage Program.

<https://csurams.maps.arcgis.com/apps/webappviewer/index.html?id=a8e43760cb934a5084e89e46922580cc>

**FLOODPLAIN**

The subject property is not located in any floodplain area.

**PUBLIC NOTICE & AGENCY REFERRALS**

Notice for the Planning & Zoning Commission hearing was published in the local paper of widest circulation, the Johnstown Breeze, on Thursday, January 26, 2023. This notice provided the date, time, and location of the Planning and Zoning Commission hearing, as well as a description of the project. Notices were mailed to all property owners within 500 feet of the property in question. This notice included a map of the project area. Full state-required annexation packets will be mailed to the county and all taxing districts in advance of the scheduled Council hearing on March 20, 2023.

This project was referred to the Johnstown Review Committee as well as Weld County, Milliken, the Weld RE-5J School District, Little Thompson Water, Xcel and TDS.

**NEIGHBORHOOD MEETING**

No neighborhood meeting was held for this annexation and zoning.

**PROJECT DESCRIPTION & ANALYSIS**

**Annexation**

This 82.6-acre Annexation (Attachment 2) encompasses the full ownership of the Archdiocese in this immediate area, as well as extending across the full existing ROW for Weld CR 19. A dedication of additional ROW, to accommodate future arterial build-out along the parcel frontage, is included with the proposed annexation agreement that the Council will review concurrently with this Annexation request.

The annexation is being considered by the Town for the following reasons:

- 1. At least 1/6 of the area to be annexed for each individual annexation is contiguous to the Town of Johnstown boundary.

2. The property is located within the Town of Johnstown Growth Management Area.
3. The Town is capable of providing water, sewer, and police service to the property.
4. The Town is authorized to annex the area without an election under Section 30(b) of Article II of the Colorado Constitution.

A Resolution finding Substantial Conformance with C.R.S. requirements and setting the public hearing was approved by Town Council on February 6, 2023.

### **Zoning & Development Standards**

The current zoning for the property is Agricultural in unincorporated Weld County. There are no known existing conditional uses or uses by special review that apply to the property.

The applicant requests two separate zones – H-A- Holding Ag and PUD-MU – upon annexation. (Attachment 3) Zone H-A would permit the owner to continue using the property for agricultural uses. The PUD zoning has an associated Outline Development Plan being proposed, as well, that would permit a solar facility to be developed on the site. Additional future development will be required to create subdivision plats and development plans, to be reviewed and approved by the Town through public hearing processes. Detailed engineering and construction plans are part of that future technical review.

This area of the Johnstown Growth Management Area is indicated for Low or Very Low Intensity and Density types of development. The continuation of agricultural uses into the future, as well as the use of the area for very low intensity energy resource development are in alignment with this designation and intention. Staff has no outstanding concerns related to this Annexation and Establishment of Zoning.

### **RECOMMENDED PLANNING AND ZONING COMMISSION FINDINGS AND MOTIONS**

Staff recommends that the Planning and Zoning Commission send a recommendation for Approval to Town Council for the Annexation and Establishment of H-A and PUD-MU Zoning based upon the following findings:

1. The area is contiguous to the Town of Johnstown along at least 1/6 of its boundaries.
2. The property is located within the Town of Johnstown Growth Management Area.
3. The Town can adequately and efficiently provide utility and police services.
4. The property is eligible for annexation without election pursuant to the Colorado Constitution Article II, Section 30(b).

#### **Recommended Motion: Motion to Approve:**

Based on the application materials received, analysis and presentations at this hearing, and findings noted in this staff memorandum, I move that the Planning & Zoning Commission recommend Approval to the Town Council for the Archdiocese Annexation and Establishment of H-A and PUD-MU Zoning Districts for this property.

#### **Motion to Recommend Approval on Annexation, and modification of Zoning District:**

I move that the Commission recommend to the Town Council Approval of the Archdiocese Annexation and to Establish Zoning on the property.

#### **Motion to Recommend Denial:**

I move that the Commission recommend to the Town Council Denial of the Archdiocese Annexation and Establishment of Zoning.






# Town of Johnstown

# ARCHDIOCESE ANNEXATION NOS. 1-3

Annexation  
TOWN COUNCIL  
April 17, 2023


# VICINITY MAP

- West of CR 19 – 0.5 mile south of CR 46 ½
- Approx. 46.6 Acres
- Current in Weld County: Zoned A (Agricultural)
- Hillsborough Ditch & Little Thompson Reservoir to NW (excluded)



# ANNEXATION MAP NOS. 1-3

Item #10.



- Has required 1/6 min. Contiguity, per C.R.S.
- No Platting required at this time.
- CR 19 Right of Way to be dedicated as part of proposed Annexation Agreement




Town of Johnstown  
johnstown.colorado.gov | 970-587-4664



# ANNEXATION MAP NO. 1

Item #10.

- 2.04 acres
- Connects to Red Mountain Annexation No. 4 to the west.






# ANNEXATION MAP NO. 2

Item #10.

- 29.24 acres
- Connects to Archdiocese Annexation No. 1 to the west.




Town of Johnstown  
johnstown.colorado.gov | 970-587-4664

# ANNEXATION MAP NO. 3


Item #10.

- 16.21 acres
- Connects to Archdiocese Annexation No. 2 to the west.



Town of Johnstown  
johnstown.colorado.gov | 970-587-4664

# ASSOCIATED PROJECTS



- Accompanying:
- Zoning to PUD-MU
  - Outline Development Plan
  - Use by Special Review
  - Sporadic oil and gas




Town of Johnstown  
[johnstown.colorado.gov](http://johnstown.colorado.gov) | 970-587-4664

# ANALYSIS & RECOMMENDATION

Item #10.

- Johnstown Review Committee (JRC) included Town staff, Weld County, Milliken, LTWD
- Annexation areas meet State statute requirements and falls within the Johnstown GMA.
- PZC recommends Approval



*Low intensity uses (ag & solar) are in alignment with the Johnstown Area Comprehensive Plan*



Town of Johnstown  
johnstown.colorado.gov | 970-587-4664





# Town of Johnstown

## TOWN COUNCIL AGENDA COMMUNICATIONS

---

- AGENDA DATE:** April 17, 2023
- SUBJECT:** Ordinance 2023-245 Approving PUD-MU Zoning for the properties known as Archdiocese Annexation Nos. 1-3
- ACTION PROPOSED:** Hold Public Hearing and Consider Ordinance 2023-245 on First Reading Approving PUD-MU Zoning for the properties known as Archdiocese Annexation Nos. 1-3
- ATTACHMENTS:**
1. Ordinance 2023-245
  2. Vicinity Map
  3. Zoning Map
  4. PZC Agenda Memorandum (2-15-23)
  5. Staff Presentation
- PRESENTED BY:** Kim Meyer, Planning & Development Director
- 

### AGENDA ITEM DESCRIPTION:

In conjunction with a Petition for Annexation for the Archdiocese Annexation Nos. 1- 3, the Town has received a request to establish zoning the property. The property is west of Weld County Road 19, and north of Weld County Road 44, adjacent to and excluding the Little Thompson/Hillsborough reservoir (Attachment 2).

As noted with the associated annexation, there were recent modifications to the project from the original request. The request presented currently reflects all final revisions.

All lands that are part of the subject Annexation would establish the PUD-MU (Mixed-Use) zoning (Attachment 3). A separate Outline Development Plan is being proposed to further define the PUD zoning on this property.

The Planning & Zoning Commission (PZC) held a public hearing on February 15, 2023, to consider the zoning for the prior lands being considered as the Archdiocese Annexation Nos. 1 and 2 (Case ANX22-0003) – as H-A and PUD-MU, at that time. The Planning & Zoning Commission Agenda Memorandum for the annexation and zoning (Attachment 5) provides background and historical use of the property.

The Community That Cares

[johnstown.colorado.gov](http://johnstown.colorado.gov)

P: 970.587.4664 | 450 S. Parish Ave, Johnstown CO 80534 | F: 970.587.0141

Based upon the materials submitted, analysis, and findings, the PZC approved a motion recommending to Town Council approval of this zoning request. Town Staff feels that the proposed revisions are substantially similar in spirit to the request recommended by the PZC, and did not present these revisions to the commission for further review.

**LEGAL ADVICE:**

Ordinance was prepared by the Town Attorney.

**FINANCIAL ADVICE:**

NA

**RECOMMENDED ACTION:**

The Planning & Zoning Commission recommended, and Town Staff supports, Approval of Ordinance 2023-245 Approving PUD-MU Zoning for the property known as Archdiocese Annexation Nos. 1, 2 and 3, on First Reading.

**SUGGESTED MOTIONS:**

**For Approval**

I move to approve PUD-MU Zoning for the property known as Archdiocese Annexation Nos. 1, 2 and 3 on First Reading.

**For Denial**

I move that the Town Council deny Ordinance 2023-245.

*Reviewed and Approved for Presentation,*

  
Town Manager

**TOWN OF JOHNSTOWN, COLORADO  
ORDINANCE NO. 2023-245**

**APPROVAL OF PUD-MU ZONING OF THE PROPERTY KNOWN AS THE ARCHDIOCESE ANNEXATION NOS. 1-3, LOCATED IN A PORTION OF THE NORTH HALF OF THE NORTHEAST QUARTER OF SECTION 16, AND A PORTION OF THE NORTHWEST QUARTER OF THE NORTHWEST QUARTER OF SECTION 15, TOWNSHIP 4 NORTH, RANGE 67 WEST OF THE 6<sup>TH</sup> P.M., COUNTY OF WELD, STATE OF COLORADO, CONSISTING OF APPROXIMATELY 47.49 ACRES**

**WHEREAS**, the Town of Johnstown, Colorado (“Town”) is a Colorado home rule municipality, duly organized and existing under the laws of the State of Colorado and the Town’s Home Rule Charter; and

**WHEREAS**, the Town Council is vested with authority to administer the affairs of the Town; and

**WHEREAS**, the Town Council approved the annexation of certain property situated in portions of the North Half of the Northeast quarter of Section 16 and the West Half of the Northwest Quarter of Section 15, Township 4 North, Range 67 West of the 6th P.M., County of Weld, State of Colorado, consisting of approximately 47.49 acres, and known respectively as the Archdiocese Annexation Nos. 1-3, being more particularly described on Exhibit A; and

**WHEREAS**, in conjunction with annexation, the Archdiocese of Denver, a Colorado corporation sole, the property owner, applied for Planned Unit Development (“PUD-MU”) zoning of the property known as the Archdiocese Annexation Nos., 1, 2 and 3; and

**WHEREAS**, pursuant to state law, upon annexation, the Town Council must zone the property within ninety (90) days; and

**WHEREAS**, the Town’s Planning and Zoning Commission held a hearing and recommended approval of PUD-MU zoning for the property known as the Archdiocese Annexation Nos. 1, 2 and 3; and

**WHEREAS**, on April 17, 2023, the Town Council held a public hearing to determine appropriate zoning for the property and, based upon the evidence received at the hearing, finds that the requested zoning of the of the property known as the Archdiocese Annexation Nos. 1, 2 and 3 to PUD-MU conforms to the Town’s Comprehensive Plan.

**NOW, THEREFORE, BE IT ORDAINED BY THE TOWN COUNCIL OF THE TOWN OF JOHNSTOWN, COLORADO, THAT:**

- 1. Archdiocese Annexation No. 1 Zoning. Zoning of the property known as the Archdiocese Annexation No. 1 and more particularly described on the attached Exhibit A shall hereby be designated as Planned Unit Development – Mixed Use.

- 2. Archdiocese Annexation No. 2 Zoning. Zoning of the property known as the Archdiocese Annexation No. 2 and more particularly described on the attached Exhibit A shall hereby be designated as Planned Unit Development – Mixed Use.
- 3. Archdiocese Annexation No. 3 Zoning. Zoning of the property known as the Archdiocese Annexation No. 3 and more particularly described on the attached Exhibit A shall hereby be designated as Planned Unit Development – Mixed Use.
- 4. Effective Date. This Ordinance, after its passage on final reading, shall be numbered, recorded, published and posted as required by the Home Rule Charter of the Town of Johnstown, Colorado (“Charter”) and the adoption, posting and publication shall be authenticated by the signature of the Mayor and the Town Clerk. This Ordinance shall become effective upon the later of the following: (i) final passage as provided by the Charter or (ii) the effective date of the annexation of the property known as the Archdiocese Annexation No. 1, Archdiocese Annexation No. 2, and Archdiocese Annexation No. 3. At such time, the Town Clerk is directed to file this Ordinance with the real estate records of the Weld County Clerk and Recorder. Copies of the entire Ordinance are available at the office of the Town Clerk.

**INTRODUCED AND APPROVED** on first reading by the Town Council of the Town of Johnstown, Colorado, this \_\_ day of \_\_\_\_\_, 2023.

**TOWN OF JOHNSTOWN, COLORADO**

**ATTEST:**

By: \_\_\_\_\_  
Hannah Hill, Town Clerk

By: \_\_\_\_\_  
Gary Lebsack, Mayor

**PASSED UPON FINAL APPROVAL AND ADOPTED** on second reading by the Town Council of the Town of Johnstown, Colorado, this \_\_\_\_\_ day of \_\_\_\_\_, 2024.

**TOWN OF JOHNSTOWN, COLORADO**

**ATTEST:**

By: \_\_\_\_\_  
Hannah Hill, Town Clerk

By: \_\_\_\_\_  
Gary Lebsack, Mayor



## EXHIBIT A

### PROPERTY DESCRIPTION

An area of land being a portion of the North Half of the Northeast Quarter (N1/2NE1/4) of Section Sixteen (16) and a portion of the West Half of the Northwest Quarter (W1/2NW1/4) of Section 15, Township Four North (T.4N.), Range Sixty-seven West (R.67W.) of the Sixth Principal Meridian (6th P.M.), County of Weld, State of Colorado, being more particularly described as follows;

COMMENCING at the North Quarter corner of said Section 16 and assuming the North line of the Northeast at the North Quarter corner of said Section 16 and assuming the North line of the Northeast Quarter (NE1/4) of said Section 16 as monumented by a #6 rebar with a 3.25" aluminum cap stamped LS 7242 at the West end and a 2.5" aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing aluminum cap stamped LS 13155 at the East end, as bearing South 88°26'46" East, being a grid bearing of the Colorado State Plane Coordinate System, North Zone, North American Datum 1983 (2011), a distance of 2722.98 feet, with all other bearings contained herein being relative thereto.

The lineal dimensions as contained herein are based upon the "U.S. Survey Foot".

THENCE South 88°26'46" East along said North line of the NE1/4 a distance of 1742.42 feet to the POINT OF BEGINNING;

THENCE continuing South 88°26'46" East along said North line a distance of 980.56 feet to the Northeast corner of said Section 16;

THENCE South 89°22'30" East along the approximate North line of the W1/2NW1/4 of said Section 15 a distance of 30.01 feet to the East right-of-way line of County Road Nineteen (19);

THENCE South 00°44'50" East along said East right-of-way line a distance of 1296.39 feet to the Easterly extension of the South line of the N1/2NE1/4 of said Section 16;

THENCE North 89°01'10" West along said Easterly extension a distance of 30.01 feet to the North Sixteenth corner of said Section 16;

THENCE North 89°01'10" West along the South line of said N1/2NE1/4 a distance of 2714.42 feet to the Center North Sixteenth corner of Section 16;

THENCE North 01°04'34" West along the West line of said N1/2NE1/4 a distance of 269.30 feet;

THENCE South 89°01'10" East a distance of 1357.98 feet;

THENCE North 00°54'49" West a distance of 756.16 feet;


THENCE North 90°00'00" East a distance of 376.23 feet;

THENCE North 00°00'16" East a distance of 274.14 feet to the North line of the N1/2NE1/4 of said Section 16 and to the POINT OF BEGINNING.

Said area of land contains 47.49 Acres (+/-2,068,673 sq.ft.) and is subject to any rights-of-way or other easements of record as now existing on said described parcel of land.

# ARCHDIOCESE ANNEX, ZONING AND DOVE SOLAR ODP AND USR

Item #11.











# Town of Johnstown

## PLANNING & ZONING COMMISSION AGENDA MEMORANDUM

---

**DESCRIPTION:** Archdiocese Annexation Nos. 1 and 2 & Establishment of Zoning (HA-Holding Ag and PUD-MU)

**PROJECT NO:** ANX22-0003

**LOCATION:** South of WCR 46.5 and the Little Thompson Reservoir, west of WCR 19

**APPLICANT:** Archbishop of Denver

**STAFF:** Kim Meyer, Planning & Development Director

**HEARING DATE:** February 15, 2023

---

### ATTACHMENTS

- 1- Vicinity Map
- 2- Annexation Map
- 3- Zoning Map
- 4- COGCC Map

### PROJECT SUMMARY

The Applicant requests Annexation for approximately 82.6 acres of land in Weld County, in two “serial” annexations of 41.06 acres and 41.53. Establishment of zoning is proposed in two parts, with the eastern portion of the property, proposed to support a solar facility with PUD-MU (Mixed Use) zoning; and the western portion proposed to remain in ag production, with an H-A (Holding Ag) zoning district.

An Outline Development Plan as well as an application for a Use by Special Review (USR) for a Solar Facility have also been received and reviewed for this property. These will also be heard concurrently by Planning & Zoning Commission and the Town Council.

### PROPERTY BACKGROUND

The property is located south of Weld County Rd (WCR) 46.5 and west of WCR 19 (Attachment 1). The subject property is presently zoned A - Agricultural in unincorporated Weld County and is being used as farm land. It is bordered to the north by the Hillsborough/Little Thompson Reservoir, to the west by incorporated areas of Johnstown, with the rest being adjacent to unincorporated Weld County and adjacent to the Milliken Growth Management Boundary. The right of way for County Road 46 to the north and east, that just touches this parcel, is already annexed into Milliken.



**SURROUNDING ZONING & LAND USE**

North: A – Agricultural (Weld County), Hillsborough/Little Thompson Reservoir  
South: A – Agricultural (Weld County)  
East: A – Agricultural (Weld County)  
West: PUD (Johnstown) with Oil & Gas Well Pads

**LAND USE HISTORY**

Historically, this property has been used for farming and continues as that use today.

**OIL & GAS**

COGCC (Oil & Gas) online maps show existing abandoned and plugged and abandoned wells on-site, Attachment 4. These sites are also shown on the Annexation and Zoning maps, as well as an easement for a Kerr-McGee pipeline that bisects the property.

**IRRIGATION DITCHES**

The Hillsborough/Little Thompson Reservoir, owned and managed by the Extension (Hillsborough) Ditch Company, is partially located on the northwest corner of this property. These are some emergent wetlands along the banks of that water body, identified by the Colorado Wetland Inventory as part of the Colorado Natural Heritage Program.

<https://csurams.maps.arcgis.com/apps/webappviewer/index.html?id=a8e43760cb934a5084e89e46922580cc>

**FLOODPLAIN**

The subject property is not located in any floodplain area.

**PUBLIC NOTICE & AGENCY REFERRALS**

Notice for the Planning & Zoning Commission hearing was published in the local paper of widest circulation, the Johnstown Breeze, on Thursday, January 26, 2023. This notice provided the date, time, and location of the Planning and Zoning Commission hearing, as well as a description of the project. Notices were mailed to all property owners within 500 feet of the property in question. This notice included a map of the project area. Full state-required annexation packets will be mailed to the county and all taxing districts in advance of the scheduled Council hearing on March 20, 2023.

This project was referred to the Johnstown Review Committee as well as Weld County, Milliken, the Weld RE-5J School District, Little Thompson Water, Xcel and TDS.

**NEIGHBORHOOD MEETING**

No neighborhood meeting was held for this annexation and zoning.

**PROJECT DESCRIPTION & ANALYSIS**

**Annexation**

This 82.6-acre Annexation (Attachment 2) encompasses the full ownership of the Archdiocese in this immediate area, as well as extending across the full existing ROW for Weld CR 19. A dedication of additional ROW, to accommodate future arterial build-out along the parcel frontage, is included with the proposed annexation agreement that the Council will review concurrently with this Annexation request.

The annexation is being considered by the Town for the following reasons:

- 1. At least 1/6 of the area to be annexed for each individual annexation is contiguous to the Town of Johnstown boundary.

2. The property is located within the Town of Johnstown Growth Management Area.
3. The Town is capable of providing water, sewer, and police service to the property.
4. The Town is authorized to annex the area without an election under Section 30(b) of Article II of the Colorado Constitution.

A Resolution finding Substantial Conformance with C.R.S. requirements and setting the public hearing was approved by Town Council on February 6, 2023.

**Zoning & Development Standards**

The current zoning for the property is Agricultural in unincorporated Weld County. There are no known existing conditional uses or uses by special review that apply to the property.

The applicant requests two separate zones – H-A- Holding Ag and PUD-MU – upon annexation. (Attachment 3) Zone H-A would permit the owner to continue using the property for agricultural uses. The PUD zoning has an associated Outline Development Plan being proposed, as well, that would permit a solar facility to be developed on the site. Additional future development will be required to create subdivision plats and development plans, to be reviewed and approved by the Town through public hearing processes. Detailed engineering and construction plans are part of that future technical review.

This area of the Johnstown Growth Management Area is indicated for Low or Very Low Intensity and Density types of development. The continuation of agricultural uses into the future, as well as the use of the area for very low intensity energy resource development are in alignment with this designation and intention. Staff has no outstanding concerns related to this Annexation and Establishment of Zoning.

**RECOMMENDED PLANNING AND ZONING COMMISSION FINDINGS AND MOTIONS**

Staff recommends that the Planning and Zoning Commission send a recommendation for Approval to Town Council for the Annexation and Establishment of H-A and PUD-MU Zoning based upon the following findings:

1. The area is contiguous to the Town of Johnstown along at least 1/6 of its boundaries.
2. The property is located within the Town of Johnstown Growth Management Area.
3. The Town can adequately and efficiently provide utility and police services.
4. The property is eligible for annexation without election pursuant to the Colorado Constitution Article II, Section 30(b).

**Recommended Motion: Motion to Approve:**

Based on the application materials received, analysis and presentations at this hearing, and findings noted in this staff memorandum, I move that the Planning & Zoning Commission recommend Approval to the Town Council for the Archdiocese Annexation and Establishment of H-A and PUD-MU Zoning Districts for this property.

**Motion to Recommend Approval on Annexation, and modification of Zoning District:**

I move that the Commission recommend to the Town Council Approval of the Archdiocese Annexation and to Establish Zoning on the property.

**Motion to Recommend Denial:**

I move that the Commission recommend to the Town Council Denial of the Archdiocese Annexation and Establishment of Zoning.



# Town of Johnstown

# ARCHDIOCESE ANNEXATION NOS. 1-3 - ZONING


ESTABLISHMENT OF ZONING

TOWN COUNCIL

April 17, 2023


# VICINITY MAP

- West of CR 19 – 0.5 mile south of CR 46 ½
- Approx. 46.6 Acres
- Current in Weld County: Zoned A (Agricultural)
- Hillsborough Ditch & Little Thompson Reservoir to NW (excluded)





# ZONING MAP



Accompanying:

- Outline Development Plan & Use by Special Review
- Sporadic oil and gas




Town of Johnstown  
johnstown.colorado.gov | 970-587-4664

# ANALYSIS & RECOMMENDATION

Item #11.

- Johnstown Review Committee (JRC) included Town staff, Weld County, Milliken, LTWD
- Zoning will permit continued ag use as well as ODP for Solar as an interim use.
- PZC recommends Approval



*Low intensity uses (ag & solar) are in alignment with the Johnstown Area Comprehensive Plan*



*Town of Johnstown*  
johnstown.colorado.gov | 970-587-4664



# Town of Johnstown

## TOWN COUNCIL AGENDA COMMUNICATIONS

---

- AGENDA DATE:** April 17, 2023
- SUBJECT:** Ordinance 2023-246 Approving the Outline Development Plan for Dove Solar
- ACTION PROPOSED:** Hold Public Hearing and Consider Ordinance 2023-246 Approving the Outline Development Plan for Dove Solar, on First Reading
- ATTACHMENTS:**
1. Ordinance 2023-246
  2. Vicinity Map
  3. Dove Solar Outline Development Plan (ODP)
  4. PZC Agenda Memorandum
  5. Staff Presentation
- PRESENTED BY:** Kim Meyer, Planning & Development Director
- 

### AGENDA ITEM DESCRIPTION:

The Town has received an application for consideration of the Dove Solar Outline Development Plan (ODP) encompassing approximately 46.6 acres of land known as the Archdiocese Annexation Nos. 1-3 (47.49 Acres total, including CR 19 right-of-way). The property is west of Weld County Road 19, and north of Weld County Road 44, adjacent to and excluding of the Little Thompson/Hillsborough reservoir (Attachment 2).

The proposed Outline Development Plan shows the intent to develop an interim use for a community solar facility, proposed as a Use by Special Review, on about 31 acres of the eastern half of the site with farming and ag operations continuing on the remaining portions, until future development occurs. (Attachment 4)

The Planning & Zoning Commission (PZC) held a public hearing on February 15, 2023, to consider the annexation, zoning, ODP, and the USR. The Planning & Zoning Commission Agenda Memorandum (Attachment 4) provides background and historical use of the property.

Based upon the materials submitted, analysis, and findings, the PZC recommends approval of the Dove Solar Outline Development Plan to the Town Council.

The Community That Cares

[johnstown.colorado.gov](http://johnstown.colorado.gov)

P: 970.587.4664 | 450 S. Parish Ave, Johnstown CO 80534 | F: 970.587.0141

The Johnstown Review Committee reviewed this project and provided redlines and comments, which have been adequately addressed by the Applicant. Staff has no remaining outstanding concerns.

**LEGAL ADVICE:**

Ordinance was prepared by the Town Attorney

**FINANCIAL ADVICE:**

NA

**RECOMMENDED ACTION:**

Planning & Zoning Commission recommends, and Staff agrees with, approval of Ordinance 2023-246 Approving the Outline Development Plan for Dove Solar, on First Reading.

**SUGGESTED MOTIONS:**

**For Approval**

I move that the Town Council Ordinance 2023-246 Approving the Outline Development Plan for Dove Solar, on First Reading.

**For Denial**

I move that the Town Council deny Ordinance 2023-246.

*Reviewed and Approved for Presentation,*

  
\_\_\_\_\_  
Town Manager



**TOWN OF JOHNSTOWN, COLORADO  
ORDINANCE NO. 2023-246**

**APPROVING DOVE SOLAR OUTLINE DEVELOPMENT PLAN FOR PROPERTY LOCATED IN A PORTION OF THE NORTH HALF OF THE NORTHEAST QUARTER OF SECTION 16, AND A PORTION OF THE NORTHWEST QUARTER OF THE NORTHWEST QUARTER OF SECTION 15, TOWNSHIP 4 NORTH, RANGE 67 WEST OF THE 6TH P.M., COUNTY OF WELD, STATE OF COLORADO, CONSISTING OF APPROXIMATELY 46.60 ACRES**

**WHEREAS**, the Town of Johnstown, Colorado (“Town”) is a Colorado home rule municipality, duly organized and existing under the laws of the State of Colorado and the Town’s Home Rule Charter; and

**WHEREAS**, the Town Council is vested with authority to administer the affairs of the Town; and

**WHEREAS**, Sun Solar, LLC, a Colorado limited liability company (“Applicant”), on behalf of the property owner, the Archdiocese of Denver, a Colorado corporation sole, submitted an application to the Town for approval of an Outline Development Plan for a development known as Dove Solar (“Dove Solar Outline Development Plan”), located in a Portion of the North Half of the Northeast Quarter of Section 16, Township 4 North, Range 67 West of the 6<sup>th</sup> P.M., County of Weld, State of Colorado and a Portion of the Northwest Quarter of the Northwest Quarter of Section 15, Township 4 North, Range 67 West of the 6<sup>th</sup> P.M., County of Weld, State of Colorado, consisting of approximately 46.60 acres (“Property”); and

**WHEREAS**, by Ordinance No. 2023-244, the Town Council approved the annexation of the Property; and

**WHEREAS**, on February 15, 2023, the Planning and Zoning Commission held a public hearing and recommended approval of the Dove Solar Outline Development Plan; and

**WHEREAS**, on April 17, 2023, the Town Council held a public hearing concerning approval of the Dove Solar Outline Development Plan; and

**WHEREAS**, after considering the Planning and Zoning Commission’s recommendation for approval, reviewing the file and conducting such public hearing, Town Council found that the Dove Solar Outline Development Plan satisfies the factors set forth in the Johnstown Municipal Code and is consistent with the Johnstown Area Comprehensive Plan; and

**WHEREAS**, based on the foregoing, the Town Council desires to approve the Dove Solar Outline Development Plan.

**NOW, THEREFORE, BE IT ORDAINED BY THE TOWN COUNCIL OF THE TOWN OF JOHNSTOWN, COLORADO, THAT:**

**Section 1. P.U.D. Outline Development Plan Approval.** The Dove Solar Outline Development Plan, concerning property located in a Portion of the North Half of the Northeast Quarter of Section 16, Township 4 North, Range 67 West of the 6<sup>th</sup> P.M., County of Weld, State of Colorado, and a Portion of the Northwest Quarter of the Northwest Quarter of Section 15, Township 4 North, Range 67 West of the 6<sup>th</sup> P.M., County of Weld, State of Colorado, consisting of approximately 46.60 acres, attached hereto and incorporated herein by reference as Exhibit A, is hereby approved.

**Section 2. Effective Date.** This Ordinance, after its passage on final reading, shall be numbered, recorded, published and posted as required by the Home Rule Charter of the Town of Johnstown, Colorado (“Charter”) and the adoption, posting and publication shall be authenticated by the signature of the Mayor and the Town Clerk. This Ordinance shall become effective upon the later of: (i) final passage of the Ordinance as provided by the Charter or (ii) annexation of the Property. Copies of the entire Ordinance are available at the office of the Town Clerk.

**INTRODUCED AND APPROVED** on first reading by the Town Council of the Town of Johnstown, Colorado, this \_\_\_\_\_ day of \_\_\_\_\_, 2023.

**TOWN OF JOHNSTOWN, COLORADO**

**ATTEST:**

By: \_\_\_\_\_  
Hannah Hill, Town Clerk

By: \_\_\_\_\_  
Gary Lebsack, Mayor

**PASSED UPON FINAL APPROVAL AND ADOPTED** on second reading by the Town Council of the Town of Johnstown, Colorado, this \_\_\_\_\_ day of \_\_\_\_\_, 2023.

**TOWN OF JOHNSTOWN, COLORADO**


**ATTEST:**

By: \_\_\_\_\_  
Hannah Hill, Town Clerk

By: \_\_\_\_\_  
Gary Lebsack, Mayor

# ARCHDIOCESE ANNEX, ZONING AND DOVE SOLAR ODP AND USR

Item #12.



# OUTLINE DEVELOPMENT PLAN DOVE SOLAR

Part of the North Half of the Northeast Quarter of Section 16,  
Township 4 North, Range 67 West of the 6th P.M.,  
Town of Johnstown, State of Colorado

**PROPERTY DESCRIPTION**

An area of land being a portion of the North Half of the Northeast Quarter (N1/2NE1/4) of Section Sixteen (16), Township Four North (T.4N.), Range Sixty-seven West (R.67W.) of the Sixth Principal Meridian (6th P.M.), County of Weld, State of Colorado, being more particularly described as follows;

COMMENCING at the North Quarter corner of said Section 16 and assuming the North line of the Northeast Quarter (NE1/4) of said Section 16 as monumented by a #6 rebar with a 3.25" aluminum cap stamped LS 7242 at the West end and a 2.5" aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing South 88°26'46" East, being a grid bearing of the Colorado State Plane Coordinate System, North Zone, North American Datum 1983 (2011), a distance of 2722.98 feet, with all other bearings contained herein being relative thereto.

The lineal dimensions as contained herein are based upon the "U.S. Survey Foot."

THENCE South 88°26'46" East along said North line of the NE1/4 a distance of 1742.42 feet to the POINT OF BEGINNING;

THENCE continuing South 88°26'46" East along said North line a distance of 980.56 feet to the Northeast corner of said Section 16;

THENCE South 00°44'50" East along the East line of said N1/2NE1/4 a distance of 1296.20 feet to the North sixteenth corner of Section 16;

THENCE North 89°01'10" West along the South line of said N1/2NE1/4 a distance of 2714.42 feet to the Center North Sixteenth corner of Section 16;

THENCE North 01°04'34" West along the West line of said N1/2NE1/4 a distance of 269.30 feet;

THENCE South 89°01'10" East a distance of 1357.98 feet;

THENCE North 00°54'49" West a distance of 756.16 feet;

THENCE North 90°00'00" East a distance of 376.23 feet;

THENCE North 00°00'16" East a distance of 274.14 feet to the North line of the N1/2NE1/4 of said Section 16 and to the POINT OF BEGINNING.

Said area of land contains 46.60 Acres (+/-2,029,784 sq.ft.) and is subject to any rights-of-way or other easements of record as now existing on said described parcel of land.

**GENERAL NOTES**

- A. ALL UNPLATTED PROPERTY SHALL REQUIRE A TOWN SUBDIVISION APPROVAL PROCESS PRIOR TO ANY ADDITIONAL USES AND BUILDING PERMITS, BEYOND THE PROPOSED AGRICULTURAL AND SOLAR USES.

**PROJECT INTENT**

THE INTENT OF THIS OUTLINE DEVELOPMENT PLAN (ODP) IS TO PROVIDE AN INTERIM DEVELOPMENT SCHEME TO THE 46.60 ACRE DOVE SOLAR PROJECT. DOVE SOLAR IS ENVISIONED AS 46.60 ACRES OF MIXED USE DEVELOPMENT WITH AN INTERIM SOLAR FIELD. THIS DOCUMENT WILL GUIDE THE OVERALL CHARACTER OF DOVE SOLAR TO ENSURE THE QUALITY AND COHESIVENESS DESIRED IN THIS EMERGING PART OF NORTHERN COLORADO. THE INTERIM SOLAR FIELD WILL BE LOCATED ON THE EASTERN PORTION OF THE SITE.


**APPROVALS**

TOWN COUNCIL

THIS OUTLINE DEVELOPMENT PLAN, TO BE KNOWN AS DOVE SOLAR ODP, IS APPROVED AND ACCEPTED BY THE TOWN OF JOHNSTOWN, BY ORDINANCE NUMBER \_\_\_\_\_, PASSED AND ADOPTED ON FINAL READING BY REGULAR MEETING OF THE TOWN COUNCIL OF THE TOWN OF JOHNSTOWN, COLORADO HELD ON THE \_\_\_\_\_ DAY OF \_\_\_\_\_, 20\_\_\_\_\_.

BY: \_\_\_\_\_ ATTEST: \_\_\_\_\_  
MAYOR TOWN CLERK

**VICINITY MAP**



**RELATIONSHIP TO TOWN CODE & DEVELOPMENT STANDARDS**

THE PROVISIONS OF THIS PUD SHALL PREVAIL AND GOVERN DEVELOPMENT TO THE EXTENT PERMITTED BY THE TOWN OF JOHNSTOWN MUNICIPAL CODE. WHERE STANDARDS, DETAILS, AND GUIDELINES OF THE PUD - OUTLINE, PRELIMINARY, OR FINAL DEVELOPMENT PLANS - DO NOT CLEARLY ADDRESS A SPECIFIC SUBJECT OR ARE SILENT, THE JOHNSTOWN MUNICIPAL AND OTHER STANDARDS, REGULATIONS, AND GUIDELINES SHALL BE USED. ALL PROPOSED DEVELOPMENT IS SUBJECT TO TOWN OF JOHNSTOWN REVIEW PROCEDURES.

DATE  
3/28/2023

SRC087084

PROJECT NAME  
**DOVE SOLAR LLC**

PROJECT LOCATION  
CR 46 & CR 19  
JOHNSTOWN, CO 80534



SHEET NAME

COVER

SHEET NUMBER

ODP-1

SHEET SIZE

24"x36"





# OUTLINE DEVELOPMENT PLAN DOVE SOLAR

Part of the North Half of the Northeast Quarter of Section 16,  
Township 4 North, Range 67 West of the 6th P.M.,  
Town of Johnstown, State of Colorado

**OUTLINE DEVELOPMENT PLAN (ODP) USES:**

1. FUTURE DEVELOPMENT WILL REQUIRE AN AMENDMENT TO THIS ODP TO ESTABLISH USES, DENSITIES, AND INTENSITIES OF USE AS WELL AS MEET ALL TOWN DEVELOPMENT STANDARDS.
2. PA-1 SOLAR USE AREA
  - A. THE SOLAR USE AREA (PA-1) SHOWN ON THIS ODP IS AN INTERIM USE (20-40 YEARS, OR AS EXTENDED BY PRIVATE AGREEMENT) AND SHALL OBTAIN A SEPARATE SPECIAL USE (USR) APPROVAL FROM THE TOWN OF JOHNSTOWN. THE SPECIAL/CONDITIONAL USE APPLICATION SHALL SHOW ALL DETAIL RELATED TO THE THIS INTERIM USE, SUCH AS BUT NOT LIMITED TO LAYOUT, ACCESS, LANDSCAPING STANDARDS.
  - B. MINIMUM STANDARDS
    - i. 20-FOOT SETBACK OF SOLAR EQUIPMENT FROM PROPERTY LINES
    - ii. 8-FOOT DECORATIVE WILDLIFE FENCE AROUND PERIMETER OF SOLAR FIELD
    - iii. LOW-GRADE NATIVE SEED MIX WITHIN THE SOLAR FIELD AREA
  - C. A TOWN-APPROVED DECOMMISSIONING AND RECLAMATION PLAN AND DUST AND WEED MITIGATION PLAN IS REQUIRED WITH THE THE SOLAR USE BY SPECIAL REVIEW PROJECT.



DATE <b>3/28/2023</b>	
LEGEND	
	INTERIM SOLAR
	HILLSBOROUGH DITCH CO RESERVOIR
	EXISTING PATHWAY
	ARCHDIOCESE OF DENVER PARCEL
<b>SRC087084</b>	
PROJECT NAME <b>DOVE SOLAR LLC</b>	PROJECT LOCATION CR 46 & CR 19 JOHNSTOWN, CO 80534
SUNSHARE LLC 1724 GILPIN ST, DENVER, CO 80218 (800)793-0786	
SHEET NAME <b>CONCEPT SITE PLAN</b>	
SHEET NUMBER <b>ODP-2</b>	
SHEET SIZE <b>24"x36"</b>	





# Town of Johnstown

## PLANNING & ZONING COMMISSION AGENDA MEMORANDUM

---

**DESCRIPTION:** Dove Solar Outline Development Plan  
**PROJECT NO:** ANX22-0003  
**LOCATION:** South of WCR 46.5 and the Little Thompson Reservoir, west of WCR 19  
**APPLICANT:** SunSolar (Applicant) / Archbishop of Denver (Owner)  
**STAFF:** Kim Meyer, Planning & Development Director  
**HEARING DATE:** February 15, 2023

---

### ATTACHMENTS

- 1- Vicinity Map
- 2- Outline Development Plan

### PROJECT SUMMARY

The Applicant requests the approval of an Outline Development Plan (ODP) for approximately 82.6 acres of land being considered for annexation to the Town of Johnstown, as the Archdiocese Annexation Nos. 1 and 2. (Attachment 2) Zoning proposed for the site includes approximately half the acreage as H-A, Holding Agriculture, for ongoing agricultural uses; and the other half as PUD-MU, Planned Unit Development Mixed Use. This ODP would apply to the PUD zone district of that property and permit the development of a 30± acre solar field.

The ODP permits only an Agricultural Area, and the Solar Use Area as an interim (20-40 years) use prior to future development that may occur on-site. Rezoning and subdivision, as well as extensive engineering would be required in the future to accommodate additional uses and development.

### PROPERTY BACKGROUND

The property is located south of Weld County Rd (WCR) 46.5 and west of WCR 19. The subject property is presently zoned A - Agricultural in unincorporated Weld County and is being used as farm land. It is bordered to the north by the Hillsborough/Little Thompson Reservoir, to the west by incorporated areas of Johnstown, with the rest being adjacent to unincorporated Weld County and adjacent to the Milliken Growth Management Boundary. (Attachment 1)

### SURROUNDING ZONING & LAND USE

North: A – Agricultural (Weld County), Hillsborough/Little Thompson Reservoir  
South: A – Agricultural (Weld County)  
East: A – Agricultural (Weld County)  
West: PUD (Johnstown) with Oil & Gas Well Pads

The Community That Cares

[johnstown.colorado.gov](http://johnstown.colorado.gov)

P: 970.587.4664 | 450 S. Parish Ave, Johnstown CO 80534 | F: 970.587.0141

**LAND USE HISTORY**

Historically, this property has been used for farming and continues as that use today.

**OIL & GAS**

COGCC (Oil & Gas) online maps show existing abandoned and plugged and abandoned wells on-site. These sites are also shown on the Annexation and Zoning maps.

**IRRIGATION DITCHES**

The Hillsborough/Little Thompson Reservoir, owned and managed by the Extension (Hillsborough) Ditch Company, is partially located on the northwest corner of this property. These are some emergent wetlands along the banks of that water body, identified by the Colorado Wetland Inventory as part of the Colorado Natural Heritage Program.

<https://csurams.maps.arcgis.com/apps/webappviewer/index.html?id=a8e43760cb934a5084e89e46922580cc>

The reservoir and surrounding areas of interest are located in the H-A zoning district area and will be undisturbed by the proposed solar use on the PUD-MU zoned area.

**FLOODPLAIN**

The subject property is not located in any floodplain area.

**PUBLIC NOTICE & AGENCY REFERRALS**

Notice for the Planning & Zoning Commission hearing was published in the local paper of widest circulation, the Johnstown Breeze, on Thursday, January 26, 2023. This notice provided the date, time, and location of the Planning and Zoning Commission hearing, as well as a description of the project. Notices were mailed to all property owners within 500 feet of the property in question. This notice included a map of the project area.

This project was referred to the Johnstown Review Committee as well as Weld County, Milliken, the Weld RE-5J School District, Little Thompson Water, Xcel and TDS.

**NEIGHBORHOOD MEETING**

No neighborhood meeting was held for this ODP project.

**PROJECT DESCRIPTION & ANALYSIS**

As noted in the summary above the proposed Dove Solar Outline Development Plan allows for continued ag use, as well as the development of an “interim” solar facility. Current solar contracts with Xcel have been offered as 20-year terms with potential to extend.

As proposed in the accompanying USR (Use by Special Review) for the solar facility, the facility would encompass about 30 acres of land, and be sited to accommodate the oil and gas facility that is in the process of being plugged and abandoned. The use would utilize the existing access to WCR 19 that has been used previously to access the oil and gas site.

No other uses are proposed with this ODP. The uses included within the ODP would not create the need for any utility, transportation, or other public services.

This area of the Johnstown Growth Management Area is indicated for Low or Very Low Intensity and Density types of development. The continuation of agricultural uses into the future, as well as the use of

the area for very low intensity energy resource development are in alignment with this designation and intention. Staff has no outstanding concerns related to this proposed Dove Solar ODP.

### **RECOMMENDED PLANNING AND ZONING COMMISSION FINDINGS AND MOTIONS**

Staff recommends that the Planning and Zoning Commission send a recommendation for Approval to Town Council for the Dove Solar Outline Development Plan based upon the following findings:

1. The proposed uses are in alignment with the Future Land Use Plan within the Area Johnstown Comprehensive Plan.
2. The proposed uses do not require significant public services to be provided by the Town or other public entities.
3. The proposed uses have the ability to be designed to meet all Town codes, regulations and requirements for that type of development.
4. The proposed uses provide an interim use to property that may prove suitable for a different type of development in the future.

#### **Recommended Motion: Motion to Approve**

Based on the application materials received, analysis and presentations at this hearing, and findings noted in this staff memorandum, I move that the Planning & Zoning Commission recommend Approval to the Town Council for the Dove Solar Outline Development Plan.

#### **Motion to Recommend Denial**

I move that the Commission recommend to the Town Council Denial of the Dove Solar Outline Development Plan.





# Town of Johnstown

# DOVE SOLAR ODP

Outline Development Plan (ODP)


TOWN COUNCIL

March 20, 2023

# VICINITY MAP

Item #12.

- West of CR 19 – 0.5 mile south of CR 46 ½
- Approx. 46.6 Acres
- Current in Weld County: Zoned A (Agricultural)
- Hillsborough Ditch & Little Thompson Reservoir to NW (excluded)






# OUTLINE DEVELOPMENT PLAN

Item #12.

- ODP includes minimum standards for the solar facility (setbacks, fencing, seeding)
- Future rezoning and subdivision required for further site development
- The proposed uses in this ODP do not require any utility, transportation, or other public services.

- PA-1 ~46.6 AC
  - Solar Use Area (Interim; 20-40 years)




Town of Johnstown  
johnstown.colorado.gov | 970-587-4664

# STAFF ANALYSIS

Item #12.

- Johnstown Review Committee (JRC) included Town staff, Town traffic, civil, and water engineers, Weld County, Milliken, LTWD, Xcel, TDS, Weld School Dist RE-5J
- The Outline Development Plan is in conformance with Town codes, standards and regulations.
- PZC recommends Approval



*Low intensity uses (ag & solar) are in alignment with the Johnstown Area Comprehensive Plan*



Town of Johnstown  
johnstown.colorado.gov | 970-587-4664





# Town of Johnstown

## TOWN COUNCIL AGENDA COMMUNICATIONS

---

- AGENDA DATE:** April 17, 2023
- SUBJECT:** Resolution 2023-17 Approving a Use by Special Review for the Dove Solar Array
- ACTION PROPOSED:** Hold Public Hearing and Consider Resolution 2023-17 Approving a Use by Special Review for the Dove Solar Array
- ATTACHMENTS:**
1. Resolution 2023-17
  2. Vicinity Map
  3. Site Plan
  4. USR Narrative
  5. Dust & Weed Management Plan
  6. Decommissioning Plan
  7. PZC Agenda Memorandum for Use by Special Review
  8. Staff Presentation
- PRESENTED BY:** Kim Meyer, Planning & Development Director
- 

### AGENDA ITEM DESCRIPTION:

The applicant, SunSolar, LLC, requests approval of a Use by Special Review for an approximately 31-acre solar array facility, intended as a 20-40 year interim use which would be in conformance with the Dove Solar Outline Development Plan. The property is west of Weld County Road 19, and north of Weld County Road 44, encompassing a total of 46.60 acres (Attachment 2).

The facility footprint is proposed to be constructed on the eastern portion of the parcel, pulling access from an existing oil & gas drive, and will continue farming operations on the remaining portions until future development occurs. (Attachment 3-4). The site plan provides for fire district-approved access and turnaround, and underground collection line, and open wildlife fencing.

The Johnstown Municipal Code does not mention a facility/use such as a solar farm within our zoning code, nor any development standards to apply thereto. Staff worked with the Applicant and Owner, through the process of annexation, zoning, outline development plan, and subdivision, to create the Dove Solar ODP that allows a solar facility as an “interim” use, with a USR (Use by Special Review) process. Based on review of a prior solar facility (SunCatcher), Staff required provision of a Dust and Weed mitigation plan, as well as a Decommissioning Plan that would remove the equipment and restore the property, minus some minor grading modifications, to its predevelopment state (Attachments 5 & 6). The Town Engineer

The Community That Cares

[johnstown.colorado.gov](http://johnstown.colorado.gov)

P: 970.587.4664 | 450 S. Parish Ave, Johnstown CO 80534 | F: 970.587.0141

reviewed and approved of the grading and drainage plans, which make minor changes to the grade, without significantly affecting the historical patterns or volumes.

The Planning & Zoning Commission held a public hearing on February 15, 2023, to consider this Use by Special Review project (USR22-0002). The Planning & Zoning Commission Agenda Memorandum (Attachment 7) provides additional background and analysis. The Commission approved a motion to recommend to Town Council approval of this Use by Special Review.

**RECOMMENDED FINDINGS:**

The Council finds this Use by Special Review for the Dove Solar Array to be consistent with the Town’s Comprehensive Plan and compatible with existing surrounding and probable future land uses, and that the special use will not cause an unreasonable demand on the Town’s services, unreasonably affect traffic flow and parking, or adversely affect the general public welfare.

**LEGAL ADVICE:**

Resolution was prepared by the Town Attorney.

**FINANCIAL ADVICE:**

NA

**RECOMMENDED ACTION:**

The Planning and Zoning Commission recommended, and Staff concurs, with a recommendation for Approval of Resolution 2023-17 Approving a Use by Special Review for the Dove Solar Array.

**SUGGESTED MOTIONS:**


**For Approval**

I move that the Town Council approve Resolution 2023-17.

**For Denial**

I move that the Town Council deny Resolution 2023-17.

*Reviewed and Approved for Presentation,*

  
\_\_\_\_\_  
Town Manager

**TOWN OF JOHNSTOWN, COLORADO  
RESOLUTION NO. 2023-17**

**APPROVING A USE BY SPECIAL REVIEW FOR SUN SOLAR, LLC FOR A SOLAR FACILITY TO BE KNOWN AS “DOVE SOLAR ARRAY” AND SITUATED IN PART OF THE NORTH HALF OF THE NORTHEAST QUARTER OF SECTION 16, TOWNSHIP 4 NORTH, RANGE 67 WEST OF THE 6<sup>TH</sup> P.M., COUNTY OF WELD, STATE OF COLORADO, CONSISTING OF APPROXIMATELY 31 ACRES.**

**WHEREAS**, the Town of Johnstown, Colorado (“Town”) is a Colorado home rule municipality, duly organized and existing under the laws of the State of Colorado and the Town’s Home Rule Charter; and

**WHEREAS**, the Town Council is the governing body of the Town and is vested with authority to administer the affairs of the Town; and

**WHEREAS**, Sun Solar, LLC, a Colorado limited liability company, submitted an application to the Town for a use by special review for a 31-acre solar facility to be known as “Dove Solar” and situated in part of the North Half of the Northeast Quarter of Section 16, Township 4 North, Range 67 West of the 6<sup>th</sup> P.M., County of Weld, State of Colorado, consisting of approximately 46.60 acres, as more particularly described on Exhibit A attached hereto and incorporated herein by reference (“Property”); and

**WHEREAS**, by Ordinance No. 2023-244, the Town Council approved the annexation of the Property; by Ordinance No. 2023-245, the Town Council approved planned unit development – mixed use (PUD-MU) zoning of the Property; and, by Ordinance No. 2023-246, the Town Council approved the Dove Solar Outline Development Plan (“ODP”) for the Property; and

**WHEREAS**, on February 15, 2023, the Planning and Zoning Commission held a public hearing and voted to recommend approval of the use by special review; and

**WHEREAS**, on April 17, 2023, the Town Council held a public hearing and, after considering the Planning and Zoning Commission’s recommendation, reviewing the file, and conducting such public hearing, found that the special use is consistent with the Town’s Comprehensive Plan and compatible with existing surrounding and probable future land uses, and that the special use will not cause an unreasonable demand on the Town’s services, unreasonably affect traffic flow and parking or adversely affect the general public welfare; and

**WHEREAS**, based on the foregoing, the Town Council desires to approve the use by special review.

**NOW, THEREFORE, BE IT RESOLVED BY THE TOWN COUNCIL OF THE TOWN OF JOHNSTOWN, COLORADO, THAT:**

**Section 1:** Sun Solar, LLC’s application for a use by special review for a solar facility to be known as “Dove Solar,” situated on approximately 31 acres of the Property as depicted on the

Use by Special Review (USR) – Dove Solar, LLC Site Plan dated January 31, 2023, is hereby approved.

**Section 2:** This Resolution shall be effective upon the effective date of the annexation of the Property.

PASSED, SIGNED, APPROVED, AND ADOPTED this \_\_\_ day of \_\_\_\_\_, 2023.

**ATTEST:** **TOWN OF JOHNSTOWN, COLORADO**

By: \_\_\_\_\_  
Hannah Hill, Town Clerk

By: \_\_\_\_\_  
Gary Lebsack, Mayor



**EXHIBIT A**  
**PROPERTY DESCRIPTION**

An area of land being a portion of the North Half of the Northeast Quarter (N1/2NE1/4) of Section Sixteen (16), Township Four North (T.4N.), Range Sixty-seven West (R.67W.) of the Sixth Principal Meridian (6th P.M.), County of Weld, State of Colorado, being more particularly described as follows;

**COMMENCING** at the North Quarter corner of said Section 16 and assuming the North line of the Northeast Quarter (NE1/4) of said Section 16 as monumented by a #6 rebar with a 3.25" aluminum cap stamped LS 7242 at the West end and a 2.5" aluminum pipe with a 3.25" aluminum cap stamped LS 13155 at the East end, as bearing South 88°26'46" East, being a grid bearing of the Colorado State Plane Coordinate System, North Zone, North American Datum 1983 (2011), a distance of 2722.98 feet, with all other bearings contained herein being relative thereto.

The lineal dimensions as contained herein are based upon the "U.S. Survey Foot."

THENCE South 88°26'46" East along said North line of the NE1/4 a distance of 1742.42 feet to the **POINT OF BEGINNING**;

THENCE continuing South 88°26'46" East along said North line a distance of 980.56 feet to the Northeast corner of said Section 16;

THENCE South 00°44'50" East along the East line of said N1/2NE1/4 a distance of 1296.20 feet to the North sixteenth corner of Section 16;

THENCE North 89°01'10" West along the South line of said N1/2NE1/4 a distance of 2714.42 feet to the Center North Sixteenth corner of Section 16;

THENCE North 01°04'34" West along the West line of said N1/2NE1/4 a distance of 269.30 feet;

THENCE South 89°01'10" East a distance of 1357.98 feet;

THENCE North 00°54'49" West a distance of 756.16 feet;

THENCE North 90°00'00" East a distance of 376.23 feet;

THENCE North 00°00'16" East a distance of 274.14 feet to the North line of the N1/2NE1/4 of said Section 16 and

to the **POINT OF BEGINNING**.

Said area of land contains 46.60 Acres (+/-2,029,784 sq.ft.) and is subject to any rights-of-way or other easements of record as now existing on said described parcel of land.




# USE BY SPECIAL REVIEW - DOVE SOLAR LLC

## 5000 kW-AC (5981.04 kW-DC) SOLAR ARRAY PROJECT


PART OF THE NORTH HALF OF THE NORTHEAST QUARTER OF SECTION 16, TOWNSHIP 4 NORTH,  
RANGE 67 WEST OF THE 6TH P.M., TOWN OF JOHNSTOWN, STATE OF COLORADO



REV	DATE	DNW	ENG.	CHK.	DESCRIPTION
0	02/22/22	WA	AFH		FOR PERMIT
1	05/16/22	MM	AFH		FOR PERMIT
2	09/20/22	MM	AFH		FOR PERMIT
3	10/31/22	MM	AFH		FOR PERMIT



- FRONT RANGE FIRE RESCUE NOTES:**
1. THE PROPOSED NEW SOLAR FACILITY SHALL BE PROVIDED WITH A TOWN-ISSUED STREET ADDRESS, WHICH SHALL BE CLEARLY POSTED AT THE ACCESS ROAD POINT OF CONNECTION WITH WCR 19 SO IT IS VISIBLE FROM BOTH DIRECTIONS OF TRAVEL. THE ADDRESS NEEDS TO BE POSTED AS SOON AS THE SITE IS OCCUPIED WITH CONTRACTORS.
  2. IF NONE IS EXISTING, A FIRE HYDRANT WITHIN 600 FEET OF THE ACCESS ROAD, PREFERABLY ON WCR 19 AT THE SITE ACCESS ROAD, SHALL BE PROVIDED.
  3. THE SOLAR FACILITY'S ACCESS ROADWAY SHALL BE A MINIMUM OF 20 FEET WIDE, AS SPECIFIED IN THE ADOPTED 2018 INTERNATIONAL FIRE CODE.
  4. THE FIRE APPARATUS ACCESS ROAD SHALL BE ENGINEERED AND MAINTAINED TO SUPPORT AN 80,000-POUND FIRE APPARATUS IN ALL WEATHER CONDITIONS. REFER TO GEOTECHNICAL ENGINEERING REPORT BY TERRACON DATED SEPTEMBER 21ST, 2022 FOR ROADWAY CONSTRUCTION SPECIFICATIONS.
  5. THE FACILITY IS FULLY FENCED WITH A GATE PROVIDE OFF THE ACCESS ROADWAY. THE FIRE DISTRICT SHALL BE PROVIDED ACCESS THROUGH THIS GATE WITH EITHER AN APPROVED KNOX PADLOCK OR A KNOX KEY SWITCH.
  6. THE SITE SHALL BE MAINTAINED WITH A REGULAR MOWING PROGRAM TO ENSURE THAT LIGHTER FUELS, SUCH AS GRASSES AND WEEDS, ARE MAINTAINED AT APPROPRIATE HEIGHTS THAT DISCOURAGE THE SPREAD OF FIRE THROUGHOUT THE SITE AND PREVENT ACCIDENTAL FIRES OR SPREAD OF FIRES BEYOND THE SITE PERIMETER. REFER TO THE FACILITY SAFETY PLAN.



**SHEET LIST TABLE**

SHEET NUMBER	SHEET TITLE
T.100	COVER
C.101	SEEDING AND FENCING PLAN
E.101	SIGNS
C0.1	LEGEND, NOTES, & ABBREV.
C1.0	CIVIL SITE PLAN
CE1.0	GRADING, UTILITY & EROSION CONTROL PLAN
CE1.1	DETAILED GRADING PLAN
CD1.0	SWMP & SITE DETAILS
CD1.1	DETAILS

**FRONT RANGE FIRE RESCUE**


REVIEWED AND ACCEPTED: \_\_\_\_\_ Date \_\_\_\_\_

**TOWN OF JOHNSTOWN**


REVIEWED AND ACCEPTED: \_\_\_\_\_ Date \_\_\_\_\_  
Town Engineer, Town of Johnstown

REVIEWED AND ACCEPTED: \_\_\_\_\_ Date \_\_\_\_\_  
Director of Planning and Development, Town of Johnstown

REVIEWED AND ACCEPTED: \_\_\_\_\_ Date \_\_\_\_\_  
Public Works Department, Town of Johnstown



NOTE:  
1. DIMENSIONS ARE APPROXIMATE.



DOVE SOLAR LLC  
40.318276, -104.889787, JOHNSTOWN CO 80543  
COVER



**ANDREW HUMPHREY ENGINEERING**  
PO Box 18430 • Golden, CO 80402 • 303.590.9376  
www.AndrewHumphreyEngineering.com


JOB NO. 2021.136 SCALE AS SHOWN

T.100










REV	DATE	DWN	ENG	CHK	DESCRIPTION
0	5/18/22	MGS	KMH	KJC	FIRST SUBMITTAL
1	9/22/22	KMH	KMH	KJC	VILLAGE COMMENTS
2	10/4/22	KMH	KMH	KJC	VILLAGE COMMENTS
3	11/21/22	KMH	KMH	KJC	FIRE DIST. COMMENTS

**DOVE SOLAR LLC**  
 40.318252, -104.886743 WELD COUNTY, CO 80543  
**CIVIL SITE PLAN**



**ANDREW HUMPHREY ENGINEERING**  
 PO Box 18430 • Golden, CO 80402 • 303.590.5976  
 www.AndrewHumphreyEngineering.com

JOB NO. SRC083130  
 SCALE 1" = 80'  
**C1.0**





**HORIZONTAL CONTROL NOTES:**


- ALL DIMENSIONS AND RADI ARE TO EDGE OF DRIVEWAY OR PROPOSED FENCE.
- CONTRACTOR TO REPAIR/REPLACE ALL DAMAGE TO EXISTING FLATWORK OR SITE FEATURES NOT INTENDED FOR DEMOLITION.
- REFER TO GRADING AND DRAINAGE PLAN FOR FURTHER INFORMATION PERTAINING TO CURB & GUTTER, CHASES, AND DRAINAGE PANS.

**HORIZONTAL CONTROL LEGEND**


▬ GRVEL DRIVE







REC. NO. 2904660  
 ±60' X 80' UTILITY EASEMENT  
 BOOK 1134, REC. NO. 02076231  
 REC. NO. 2904660



**GRADING AND DRAINAGE NOTES:**

- CONTRACTOR TO FIELD VERIFY ALL EXISTING UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION. REFER TO GENERAL NOTES FOR UTILITY LOCATION AND PROTECTION.
- REFER TO HORIZONTAL CONTROL PLAN FOR FURTHER INFORMATION PERTAINING TO CURB & GUTTER, CHASES, AND DRAINAGE PANS.
- CONTRACTOR IS RESPONSIBLE FOR RESTORING ALL DISTURBED AREAS TO THEIR ORIGINAL CONDITIONS.
- ALL SPOT ELEVATIONS ARE TO FINISHED GRADE OR FLOWLINE UNLESS OTHERWISE SPECIFIED.
- IF WALL IS SHOWN, TG DENOTES THE FINISHED GRADE ADJACENT TO THE HIGH SIDE OF THE WALL. BG DENOTES THE FINISHED GRADE ADJACENT TO THE LOW SIDE OF THE WALL. REFER TO ARCH PLANS/DETAILS FOR WALL ELEVATIONS BEYOND THE ADJACENT FINISHED GRADES (EXPOSED WALL, CAP/FOOTER, ETC.)

**EROSION AND SEDIMENTATION NOTES:**

- CONTRACTOR IS RESPONSIBLE FOR INSTALLING AND MAINTAINING ALL CONTROLS DURING INITIAL, INTERIM, AND FINAL CONDITIONS.
- ALL CONTROLS SHALL BE INSTALLED WITHIN THE PROPERTY LINES UNLESS OTHERWISE SPECIFIED. WHEN CONSTRUCTION ACTIVITIES DISTURB ADJACENT AND/OR RIGHT-OF-WAY PROPERTIES, COORDINATION WITH PROPERTY OWNERS IS REQUIRED PRIOR TO CONSTRUCTION.

**EROSION CONTROL BMP SEQUENCING:**

INITIAL (PRIOR TO CONSTRUCTION)


- INSTALL SILT FENCE
- INSTALL CWA
- INSTALL VTC

INTERIM (DURING CONSTRUCTION)

- MAINTAIN ALL BMP'S

FINAL (AFTER CONSTRUCTION)

- REMOVE SILT FENCE
- REMOVE CWA
- REMOVE VTC
- PERMANENT SEEDING FOR ALL DISTURBED AREAS



SEE SHEET CE1.0 FOR EXTENTS OF SITE GRADING

2.0' (TYP)  
 SOLAR ARRAYS (RE:ELEC, TYP)  
 EXISTING PUBLIC ROADWAY  
 @ 20' PIPELINE RIGHT-OF-WAY  
 KERR-MCGEE GATHERING LLC  
 REC. NO. 3759781

N1/2NE1/4  
 SECTION 16, T1S  
 ALL DISTURBED AREAS SHALL BE RESEDED PER WELD COUNTY REQUIREMENTS. (TYP)  
 SCHULTZ STATE 16-1 (PA)

**PARENT PARCEL INFORMATION:**

Owner: Archdiocese of Denver  
 Parcel Number 105911010059

ELEVATIONS SHOWN AT CORNERS OF PAD ARE GROUND ELEVATIONS. PAD MAY BE ELEVATED FROM ELEVATIONS SHOWN. (RE:ELEC)

GRAVEL DRIVE SHOWN NORTH OF THIS LOCATION SHALL MATCH EXISTING GRADES


GRAVEL DRIVE SHOWN EAST OF THIS LOCATION SHALL MATCH EXISTING GRADES

40 LF 18" CLASS V RCP CULVERT WITH FES INSTALLED TO MATCH EXIST ROADSIDE SWALE. (MIN 18" COVER)

BASIS OF BEARIN  
 S 00°44'50" E 259

AREA  
 3,122,637 sq. ft.

J:\3473.2a\Drawings\3473.2c-01-085-00.dwg, 11/21/2022, 12:04 PM, KMH



REV	DATE	BY	CHK	DESCRIPTION
0	5/18/22	MGS	KJC	FIRST SUBMITTAL
1	9/22/22	KMH	KJC	VILLAGE COMMENTS
2	10/4/22	KMH	KJC	VILLAGE COMMENTS
3	11/21/22	KMH	KJC	FIRE DIST. COMMENTS

DOVE SOLAR LLC  
 40.318252, -104.886743 WELD COUNTY, CO 80543  
 DETAILED GRADING PLAN



ANDREW HUMPHREY ENGINEERING  
 PO Box 18430 • Golden, CO 80402 • 303.590.5976  
 www.AndrewHumphreyEngineering.com

JOB NO. 2022.0XX SCALE 1" = 40'

SRC083130

CE1.1





Use by Special Development Standards  
for  
Dove Solar Facility  
 Johnstown, Weld County, Colorado  
 June 2022

SunShare, LLC, a Colorado limited liability company, is pleased to present our application for a Zoning Permit for a Medium-Scale Solar Energy Facility (“SEF”) on property owned by the Archdiocese of Denver located on approximately 30 acres of Parcel ID No. 105916100039 in the northeast corner of Section 16, Township 4 N, Range 67 W in Weld County, CO.

The current zoning on the parcel is Agricultural (A), however the landowner does not possess any water rights for this parcel. SunShare has executed a lease agreement with the Archdiocese of Denver for a joint solar facility which will provide solar energy to the Archdiocese’s housing recipients.

This 5,000 kW-AC (5,976 kW-DC) project will use standard photovoltaic technologies that have been proven safe and effective through deployment across the United States in thousands of utility or commercial-scale solar developments. The solar panels are mounted to single-axis tracking arrays, which sit parallel to the ground and follow the path of the sun across the sky. The panels face east in the morning, lay flat at noon, and face west in the evening. The tracking arrays produce DC current, which is converted into AC current by inverters for synchronization and delivery of energy into the utility’s distribution grid at a utility transformer. The modules utilize a non-reflective glass which eliminates glare concerns and all electrical cables on the improved area will be buried, except for the direct current string wires that connect between solar collectors, direct current collection circuits between rows of solar arrays that are no more than four (4) feet above grade crossings, substations, switch yards, and circuits voltages greater than 34.5 kilovolts (where necessary.) There will be no permanent employees on site during operation, and maintenance visits are expected to occur quarterly on average.

The appearance of the solar arrays is uniform and symmetrical. Solar panels will not exceed ten (10) feet in height above the grade, at maximum tilt. The facility will be constructed in accordance with IBC 2021 and NEC 2020 and will be surrounded by an 8’ high game fence made of 4’ X 4” reinforced mesh.

This project is in discussions with the relevant oil and gas entities to build within the setbacks surrounding their infrastructure. All other setbacks are in accordance with the development standards and are identified on T.100 of the Sketch Plan. Fence details are on page C.102 of the Sketch Plan. All oil and gas facility and pipeline owners have been identified and contacted. All adjacent area landowners within 500





ft of the project area have been contacted with no known objections to date.

Access to the facility will be from the east off Weld County Road 19 via a 20' wide all-weather access driveway. The entrance to the site will include a 20' wide all-weather access driveway with an emergency hammerhead turnaround. SunShare will apply for any necessary access permit prior to construction.

This project site has areas where the slope exceeds the acceptable limit for solar panels. As a result, cut and fill work will take place once permitted to create a level space. This SEF will abide by all dust mitigation standards laid out by the County and/or Town.

Following the eventual decommissioning of this project, this land will be left more suitable for farming due to its improved topography. The project is not located within any FEMA designated Special Flood Hazard Areas. The Stormwater Management shall be addressed via the attached Surface Drainage Analysis. Conceptual design details can be found in the enclosed Sketch Plan, T.100.

This site currently houses a pivot irrigation system for agricultural purposes. The pivot will be easily adjusted to avoid the SEF and will still be fully capable of supplying water to any surrounding crops.

The operational life of an SEF is generally between 20-40 years. The SEF has an initial 20-year contract with Public Service Company of Colorado (Xcel) to sell power into the Xcel Electric grid, and the major equipment components have warranty options up to 30 years, with a useful life of 35-40 years. Upon decommissioning, SunShare will entirely remove all SEF components (fencing, steel racking, cabling, solar panels and associated interconnection equipment) and undertake measures to restore the land to its original state.

SunShare will obtain all required permits and approvals, including utility interconnection agreements, prior to commencing construction. The project's engineers and general contractor will be made up of local experienced and individuals licensed in Colorado, who will ensure that all required codes and standards are followed throughout the design and construction. The project will comply with all applicable provisions by Johnstown. SunShare looks forward to working with Johnstown to successfully complete this proposed development and bring the benefits of community solar energy to the Town.





## Use by Special Review - Medium Scale Solar Energy Facility Questionnaire for Dove Solar LLC, PID 105916100039

### 1. Explain the proposed use and business name.

SunShare LLC, d/b/a Dove Solar LLC proposes a Medium-Scale Solar Energy Facility (SEF) to be placed at Weld County PID 105916100039. The SEF will have a nameplate capacity of 5,000 kW AC and will cover approximately 30 acres on the east side of the total parcel.

This project has the explicit purpose of benefiting low-income and energy burdened families. 100% of the energy generated from this project will go to households that are qualified as low-income or nonprofit and religious organizations that provide essential services to these households. The recipients of the energy will receive savings on their monthly electricity bills. A secondary benefit of the project will be to provide job training for individuals looking to enter the solar and electrical trades.

### 2. Explain the need for the proposed use.

This project meets a multitude of needs in the community:

- Energy costs disproportionately impact low-income households and drain resources from low-income services organizations. This project is being developed to help solve this issue. In addition to being the landowner, the Archdiocese of Denver is helping to develop the project and will be directing a large portion of the electricity and savings to its large network of low-income service organizations that are operating in Weld County and who are eager to participate in the project. These organizations include schools that serve low-income students, homeless shelters, and food banks, among others.
- The Parcel Landowner (the Archdiocese of Denver) is interested in being annexed by the Town of Johnstown so long as this solar facility is also permitted with the annexation
- The Landowner (the Archdiocese of Denver) does not have water rights for the property and is therefore unable to secure any significant financial value from the land. The lease revenue paid the landowner will enable them to hold on to the land for the long term and have revenue that can be dedicated for the funding of services for low-income households.
- Households, Businesses, and Nonprofits in Colorado have not traditionally had a choice in who their utility provider is and where their energy comes from. Community solar solves this issue by providing ratepayers with an opportunity for choice, and an option to choose locally generated electricity.
- The Town of Johnstown, Weld County, and Colorado as a whole, are experiencing massive growth in electricity consumption. More electricity generation is needed to meet this need. Local solar projects like this help the state and county diversify its electricity sources and have local generation that result in a more stable and resilient grid. Weld County has long been the energy capital of Colorado and adding solar in the County will further diversify the County's energy mix and further its role as an energy leader in Colorado.



- Weld County’s Comprehensive plan specifically calls out a goal of supporting “*responsible energy and mineral development.*” This project meets the definition of responsible (see answer to question 21).
- The Town of Johnstown’s comprehensive plan calls for energy projects, specially calling for “*flexible regulations that accommodate evolving economic trends and industries, and attract new business interests and investment (e.g., renewable energy...)*”.

**3. Describe the current and previous use of the land.**

The specific location of the project has historically been used for oil and natural gas extraction and agriculture. This land is not currently incorporated into the city limits of any city in Weld County.

Occidental Petroleum Corporation previously drilled on this land for oil and natural gas resources. They have since plugged and abandoned the 2 wells present which remain onsite, abandoned the pipeline which remains (underground) onsite, and fully removed the battery that was previously onsite. This site is no longer used for oil and gas activity.

The Landowner is currently leasing the land to a Tennent Farmer who traditionally farms barley crops. The Landowner does not have water rights for this parcel and is therefore unable to secure any significant value from its current agricultural use.

The western side of this parcel (where we do not intend to develop) houses additional agriculture, as well as an irrigation reservoir.

**4. Describe the proximity of the proposed use to residences.**

There are no residences within 500 feet of the proposed SEF. The area overall is rural with limited residential buildings and units. The closest homes are over eight tenths of a mile away and will experience no impacts from the SEF.

**5. Describe the hours and days of operation (i.e., Monday thru Friday 8:00 a.m. to 5:00 p.m.).**

Once construction is complete, the SEF will continuously operate 24/7, but will produce power only during daylight hours. The proposed SEF will use single-axis trackers, which will angle the solar modules accordingly as the sun shifts in the sky. These trackers allow for maximized energy production. While the array will be running all day, it will create no disturbances. Solar arrays are nearly silent and produce no smoke, smog, vapors, or dust. Construction will run during normal business hours for the duration of about 3 months.

**6. Describe the number of employees including full-time, part-time and contractors. If shift work is proposed, detail number of employees, schedule and duration of shifts.**

During construction: Construction during daytime hours will range from 7 to 14 during the early mobilization and site preparation stage with site construction workers peaking at 50 to 60 workers midway through the project and reducing back down to 7 and 14 workers during the final commissioning and testing stage.



Once operational: The SEF will have a maintenance crew visit once quarterly (or as needed if damage occurs due to weather), otherwise the SEF will be unmanned.

**7. Describe the maximum number of users, patrons, members, buyers or other visitors that the site will accommodate at any one time.**

N/A. This proposed use will be for energy production only and will not host patrons, etc.

**8. List the types and maximum numbers of animals to be on the site at any one time (for dairies, livestock, confinement operations, kennels, etc.).**

SunShare values the prominence of agriculture in Weld County, and we often make efforts to support the industry when constructing SEFs. One practice that we offer at our SEF is working with a local sheep rancher (with whom we have a pre-existing partnership), offering our site as grazing land for his sheep. This allows for the SEF site's vegetation to be maintained, while benefitting a local rancher (rather than employing mechanical mowers). We will have to complete a more thorough analysis of the current vegetation of the area to determine if there is enough growth for the sheep, and if it is all safe for the sheep.

Should we move forward with sheep grazing, there will be approximately 60 sheep present onsite. The site will be fully fenced in, containing the sheep, and the rancher will have access to the site whenever needed. The sheep will visit for a few weeks at a time, as frequently as needed onsite.

**9. List the types and number of operating and processing equipment.**

There will be a total of 11,076 540w monocrystalline modules, forty 125kVA inverters, and 142 rows of single-axis trackers. The system consists of string level DC to AC conversion inverters, two main equipment pads with AC Recombiners, switchgear and MV step up transformers that connect to Xcel's grid.

**10. List the types, number and uses of the existing and proposed structures.**

There are no existing structures onsite. There will be no structures associated with the proposed solar facility other than the solar array itself, which will be used for energy generation.

**11. Describe the size of any stockpile, storage or waste areas.**

During the construction phase, there will be a materials and equipment laydown yard located on the interior of the facility. This laydown area will be approximately 50' X 250' in size. When the construction is completed, there will be in place a metal connex container for storing spare modules and other spare parts.

**12. If storage or warehousing is proposed, what type of items will be stored?**

*Response: A steel container (8' X 40') is being proposed to store equipment and spare parts for the solar facility. The container is proposed to be positioned in the interior of the solar*



arrays, which should lessen its visual impact. The container will be painted a light tan to help blend the container with the natural environment.

**13. Describe where and how storage and/or stockpile of wastes, chemicals, and/or petroleum will occur on this site.**

*Response: N/A - There will be no stockpiles of wastes, chemicals, or petroleum associated with this facility.*

**14. If there will be fuel storage on site, indicate the gallons and the secondary containment. State the number of tanks and gallons per tank.**

*Response: N/A – There will be no fuel storage associated with this facility.*

**15. Describe the method and time schedule of removal or disposal of debris, junk and other wastes associated with the proposed use.**

During the construction phase, waste will be stored in refuse dumpsters, which will be emptied on a regular basis or as needed. Once the facility is operational, there will be no waste or refuse produced from the solar operation.

**16. Include a timetable showing the periods of time required for the construction of the operation.**

- Solar Facility Components First Deliver Day 1
- Perimeter Fence Installation Day 1 to Day 11
- Solar Panel Foundation Installation Day 1 to Day 30
- Racking, Trenching, Wiring Day 30 to Day 64
- Solar Panel Installation Day 64 to Day 94
- Inspection & Set Meters Day 94 to Day 99
- System Testing & Commissioning Day 99 to Day 109

**17. Describe the proposed and existing lot surface type and the square footage of each type (i.e., asphalt, gravel, landscaping, dirt, grass, buildings).**

The west side of the parcel is currently a reservoir and farmed agriculture. This will not change as we are not impacting this area whatsoever.

The subject area (30 acres on the east side of the parcel) is currently agricultural land and will need to be re-seeded within the construction area. Following the completion of the construction for each phase, disturbed areas within the limits of construction, such as roadcuts, utility trenches, and other areas where vegetation has been removed, altered, or eliminated, will be reseeded with native seed mix. There will be approximately 9,339 square feet of gravel access including the hammerhead turnaround. In addition, there will be a gravel laydown area that is approximately 12,500 square feet, for a total of 21,839 square feet of gravel surface area. There will be two (2) concrete transformer pads, each measuring approximately 48 square feet, for a total of 96 square feet of concrete area.





**18. How many parking spaces are proposed? How many handicap-accessible parking spaces are proposed?**

There will be two (2) internal parking spaces for vehicles servicing the facility. There will be no ADA parking spaces, as this is not a facility for general public use.

**19. Describe the existing and proposed fencing and screening for the site including all parking and outdoor storage areas.**

To comply with the National Electric Code, there will be an 8' tall game fence installed around the entire perimeter of the site. The fence and gate will be constructed of 4" X 4" welded rod material. The two (2) internal parking spaces will be screened by the solar array. There will be no outdoor storage associated with this proposed solar facility.

**20. Describe the existing and proposed landscaping for the site.**

The entire affected area of the parcel has been used for agricultural purposes and has been covered by crops, by unplanted land, and oil and gas infrastructures such as wells and batteries. The remainder of the parcel has also been used for agriculture or houses a reservoir. The unaffected area's landscaping will not change. Once the construction phase is completed, the affected area within the solar facility fence will be seeded with a native seed mixture. As previously mentioned, there are no residences or commercial buildings nearby, so screening trees and shrubs will not be needed.

**21. Describe reclamation procedures to be employed as stages of the operation are phased out or upon cessation of the Use by Special Review activity.**

Once the site is no longer used for the proposed solar facility, the panels, racking, cabling, inverters, and all associated equipment will be removed from the site and recycled and/or disposed of in a responsible manner. The site will be returned to the condition it was in prior to the solar facility being constructed with the exception of certain site improvements desired by the landowner or system design such as re-grading and leveling. Solar leaves behind no ground contamination, so there will be no hazardous elements left behind on the land.

**22. Describe the proposed fire protection measures.**

The subject property is within the Front Range Fire Rescue Fire Protection District. Fire access within the facility will be via a 20'-wide gravel driveway, with a hammerhead turnaround at the end of the drive. Grasses within the solar facility will be mowed as needed, to help prevent the spread of range fires.

**23. Explain how this proposal will be compatible with future development of the surrounding area or adopted master plans of affected municipalities.**

The subject parcel falls within the Intergovernmental Agreement Boundary for the towns of Johnstown and Milliken, though it is just outside the town limits for either town. The



landowner is interested in allowing annexation of the parcel by the Town of Johnstown so long as it is inclusive of approval of this proposed SEF.

This proposal is compatible with the 2021 Comprehensive Plan (CP) for the Town of Johnstown. The Town's CP includes the following goal:

"W1.1. Collaborate interdepartmentally to create flexible regulations that accommodate evolving economic trends and industries, and attract new business interests and investment (e.g., renewable energy, business incubators, artists/makers spaces, synergistic businesses, etc.)." (Page 36). This goal shows the Town's great willingness and interest in supporting and fostering new energy sources, such as solar. Additionally, the CP sites that it received feedback from its residents requesting "Focus on sustainable industry[ies] and honor our agricultural heritage by being good stewards of the land" (Page 18). Our proposed SEF supports this request from residents as it will create no environmental contamination. Additionally, the land beneath the array will be planted with a native seed mix, supporting the native vegetation of Weld County.

Additionally, the proposed solar facility will be in place for approximately 20-40 years (depending on possible operation extensions). Following the decommissioning of the SEF, the land will be free and clear for any potential uses that the Town of Johnstown may want to pursue with the landowner, such as commercial or residential development. The freed land will allow for the Town to implement new and different goals, as well as expand its footprint.

**24. Explain how this proposal impacts the protection of the health, safety and welfare of the inhabitants of the neighborhood and the County.**

This development will positively impact the health, safety, and welfare of the inhabitants of the surrounding area, the Town, and County.

The SEF will create no airborne or ground contaminants, making it nonhazardous for residents near and far. The SEF is also nearly silent when operating, thus it will not contribute to any noise pollution. The SEF will produce local electricity without adding any pollution to the air.

Most importantly, however, this SEF will generate a source of revenue and energy savings that will help provide affordable housing, food, and resources to those who are struggling and are qualified as low-income. This project has the explicit purpose of benefiting low-income and energy burdened families. 100% of the energy generated from this project will go to households that are qualified as low-income or nonprofit and religious organizations that provide essential services to these households. The recipients of the energy will receive savings on their monthly electricity bills.

**25. Explain how this proposal complies with Article V and Article XI of Chapter 23 if the proposal is located within any Overlay Zoning District (Airport, Geologic Hazard, or**



**Historic Townsites Overlay Districts) or a Special Flood Hazard Area identified by maps officially adopted by the County.**

N/A – The subject property is not located within any Overlay Zoning District or Special Flood Hazard Area.

**27. Detail known State or Federal permits required for your proposed use(s) and the status of each permit. Provide a copy of any application or permit.**

SunShare will need to apply for the following permits to complete this SEF:

Local/County:

- Building permit
- Grading permit
- Access permit
- ROW Agreement or Road Maintenance Agreement, if deemed necessary

State:

- CDPHE SWPPP

# Dust and Weed Mitigation Plan

For a Medium-Scale Solar Facility  
Dove Solar, LLC

Case Number: USR Number – USR22-0003  
Archdiocese of Denver (Parcel ID No. 105916100039)

Prepared for:  
TOWN OF JOHNSTOWN  
PO BOX 609  
JOHNSTOWN CO 80534

Prepared by:  
SunShare, LLC  
Denver, Colorado



Date Prepared: November 2022



## 1.0 Overview

As a condition of approval for the Site-Specific Development Plan and Use by Special Review Permit, the Town of Johnstown required that SunShare prepare a *Dust and Weed Mitigation Plan* for the solar facility, that is to be reviewed and approved by the Johnstown Review Committee. The intent of this *Dust and Weed Mitigation Plan* is to provide a comprehensive plan for control of dust, noxious weeds, and any drainage issues that could cause erosion from the solar facility.

### 1.1 Dust Mitigation During the Construction Phase

Water tankers will be used to help control dust while the construction activities are occurring on the site. During the construction of the facility, SunShare will exercise BMPs to limit fugitive dust from being airborne and traveling beyond the property lines. Dust control efforts will be monitored by the site foreman on a regular basis to ensure fugitive dust is adequately controlled. Water spray will be applied, as needed, to unpaved areas during periods of dry weather. Care will be taken not to over-apply water and create mud. Vehicle tracking devices will be installed at truck exit drives. Vehicles operating on the site during the construction phase will limit their speed to 15 mph or less, to minimize dust emissions.

### 1.2 Noxious Weed Management

The Colorado Department of Agriculture (CDA) requires landowners to prevent the spread of State Listed Noxious Weeds. Construction activities on the site have the potential to introduce new noxious weed species to the site, or spread existing species on to or off of the site. This noxious weed management program was developed to prevent further spread of noxious weeds. SunShare will comply with CDA regulations through implementation of this plan. Periodic reviews and updates to this plan will be completed as necessary to keep it current with noxious weed control issues. This plan will be implemented throughout the life of the solar facility.

Appropriate management actions will be implemented whenever noxious weed species are observed growing within the project area. The goals of weed management are to:

- 1.) Identify and manage noxious weeds within and immediately adjacent to the project areas to be disturbed and after the area has been reclaimed;
- 2.) Conduct pre-treatment and post-treatment evaluations, and continue or modify treatment measures as necessary;
- 3.) Minimize the potential for transportation and importation of noxious weed species;

- 4.) Educate field personnel in order to encourage compliance with weed management program goals and assist with identification and control efforts.

To prevent or minimize the infestation and spread periodic inspections of the project area during the beginning, middle, and end of the growing season will evaluate presence or absence, degree of invasion, and the response of previous treatments. SunShare's operational staff will conduct regular site inspections and ensure implementation of this plan. Specific treatment methodologies and timetables will be developed based on species of concern, location and extent of the infestation(s), and other pertinent factors.

## 1.2 (a) Noxious Weed Prevention

Noxious weeds are spread through dispersal of seed and/or transport of plant propagules (i.e. spores, seeds, roots, etc.). The most effective way to control noxious weeds is to prevent their introduction into the site in the first place. A combination of methods and practices will be employed to prevent the introduction of weed species and their regeneration within the project area.

The following methods and practices may be employed, either singly or in combination, to prevent the introduction of weeds into the solar site:

- 1.) A thorough cleaning of equipment will be conducted before entering the project area to prevent the introduction of seed and plant propagules from other sites;
- 2.) Seed mixtures used for revegetation or temporary site stabilization will be free of noxious weeds;
- 3.) Hay, straw, and/or other materials used for mulch or other purposes will be certified weed free;
- 4.) A periodic inspection will be conducted to identify any new weed infestations that may have occurred. Any new infestations will be scheduled for management before they become well established and/or spread;
- 5.) Communication and coordination with adjacent land holders whose property is infested with noxious weeds that may threaten the site should occur. Establishing partnerships for weed management within the local area is essential for successful long-term weed management;
- 6.) Noxious and pest weed infestations that threaten natural and reclaimed areas will be treated with accepted Integrated Weed Management (IWM) methods. These methods are further discussed below.

## 1.2 (b) Integrated Weed Management (IWM)

An Integrated Weed Management approach will be implemented for treatment of noxious weeds within the project area. An IWM approach enables selection of one or more weed management methods based on site specific environmental conditions and control needs. The following weed management methods will be considered for the project area:

- 1.) Cultural – Planting native or desirable plant species for site colonization and promoting healthy vegetation communities in reclaimed areas. Prevent unnecessary disturbance through precise planning of construction projects and other activities. Prompt revegetation of disturbed areas.
- 2.) Mechanical – Mowing, pulling, disking, and plowing may be used on weedy species for which these treatments are effective.
- 3.) Biological – Introduction of insects or other biologic agents which are known to inhibit or prevent reproduction of noxious weed species. If biological agents are employed, control methods will be coordinated with the Colorado Department of Agricultural Insectary in Palisade, Colorado.
- 4.) Chemical – Application of appropriate herbicides by a licensed applicator. All herbicides will be applied in accordance with the manufacturer’s label and in accordance with Colorado laws.

In some cases, only one control method may be warranted, while in other cases a combination of control methods may be appropriate. Control methods selected will be dependent upon species of concern, and the location and extent of the infestation.

The use of IWM methods will protect pollinators, reduce hazards to wildlife, reduce the possibility of herbicide resistance, and minimize persistence and mobility of herbicides in the soil. Weed control methods and practices will be applied in a manner that conforms to applicable federal, state, and local laws.

## 1.2 (b) 1 – Cultural Control

Germination and establishment of noxious weeds can be reduced by following accepted revegetation and vegetation management techniques that favor the growth of desirable plants. These include prompt seeding and revegetation of disturbed areas with appropriate seed mixes, maintaining optimum fertility and moisture levels, planting at optimum density of pure live seed, minimizing use of fertilizers, and selecting suitable species for revegetation. Minimizing areas of disturbance and exposed soil prevents opportunities for aggressive species to establish.

A revegetation plan has been developed for the site that utilizes native species that are well-adapted to the site. Seeding native species in conjunction with other management practices will provide some level of competition with noxious weeds, and minimize the opportunity for new infestations to become established.

## 1.2 (b) 2 – Mechanical Control

Mechanical Control of noxious weeds can be an effective tool to physically disrupt noxious weed growth and seed development. A combination of mechanical methods may be used including tilling or disking, mowing, hand-held weed trimmers, mulching, hand-pulling, hoeing, or livestock grazing. Mechanical weed control practices must be applied with correct timing to maximize their effectiveness in preventing vegetation development or seed production.

Annual weedy species may be readily controlled with mowing or physical removal. Perennial species such as Dalmatian toadflax have extensive root systems. For such weed species, mowing may only control seed production without seriously affecting the plant's survival. Mowing after seed production has occurred may spread the plants. Disking or tilling areas containing perennial noxious species may increase the area of infestation due to root sprouting. In most cases, mechanical control methods used alone are not effective against noxious weed species.

## 1.2 (b) 3 – Biological Control

Biological control of noxious weeds can be an effective tool to physically disrupt plant growth and seed development. A combination of biological methods may be used including introduction of insect weed predators and species-specific plant diseases. Biological weed control methods and practices will be applied with appropriate timing to maximize their effectiveness in preventing seed production. It must be noted that the use of biological controls normally does not eradicate an infestation of weeds; rather they are capable of reducing weed species vigor and reproduction. The Colorado Department of Agriculture's Biological Pest Control Program has on-going biological control programs for several noxious weed species. Note, the use of insect bio-controls typically require large populations of the target weed to sustain the population of bio-control agents. Biological controls should not be expected to eliminate the entire infestation of a noxious weed, but instead to bring the infestation down to a more manageable level.

## 1.2 (b) 4 – Chemical Control

Chemical control of noxious and pest weeds can be an effective tool to disrupt plant growth and seed development. Herbicides can kill targeted species, prevent development and/or germination of noxious weed seed, can be used with minimal disturbance to soils, and in some cases, can be selective to specific species or groups of plants. Herbicides must be applied at the



appropriate time to maximize their effectiveness in preventing seed production, for disrupting plant establishment and growth, or achieving kill of noxious species. To avoid development of resistance to a particular herbicide through repeated use over prolonged periods of time, herbicides with varying modes of action to be used. Also, herbicides will be applied according to manufacturer's label recommendations (i.e. application rate, method, and timing) to prevent development of plant resistance. Herbicide selection will be based on weed emergence, timing of application, past applications, and ground and weather conditions during the applications.

Successful IWM begins with an understanding of the target plant species and the environment within which it grows. Next, the physiologic effects of an herbicide on plant growth and development must be understood. Understanding a pesticide's chemical nature is also important in minimizing impacts to non-target species, the applicator, endangered species, and pollinators, as well as surface water runoff hazards and leaching into groundwater. Every herbicide label contains information regarding environmental hazards. This information will be evaluated for each herbicide considered for use at the site and herbicides will be selected which pose minimal to no environmental hazards.

All pesticides will be handled with care, and applied by qualified personnel. Properly identifying the weed problem and the most effective chemical control method for use during the plant growth cycle is critical to effective weed control. Equipment will be properly calibrated before herbicides are applied and appropriate Personal Protective Equipment (PPE) will be used. Empty containers will be disposed of promptly, safely and according with product labeling.

Herbicides vary in the amount of time after an application before it is safe to re-enter the treated area without protective clothing and equipment. The site re-entry time is affected by the rate of application, size of the area treated and the amount of time to be spent in the field. For the safety of employees and contractors, the Restricted Entry Interval (REI) listed on the herbicide's label will be followed. Appropriate herbicide application records will be maintained as specified by the CDA.

## 1.2 (c) – Monitoring and Follow-Up

Even with effective weed management strategies, it often takes several seasons to eradicate or bring weed populations to an acceptable level. With well-established infestations, it is likely that a seed bank has developed in the soil capable of producing new plants for many years. An infestation of weeds can easily re-invade treated areas in one growing season if control and treatment activities are prematurely curtailed. Weed management efforts should be carried out over an adequate number of growing seasons to realize effective weed management within the target area.

As with all weed management, this multi-season effort is best served by effective documentation of control efforts and continued vigilance in successive seasons of management.

Information can be used to modify treatment priorities and weed management strategies over time. Vigilance is required against new infestations that may be moving into the site. These new sources of infestation may be worked into prevention and management plans as necessary.

This weed management plan will be modified over time as site conditions change. Weed management strategies and priorities can be modified as weed infestations change in response to continued control efforts.

## 1.3 – Drainage and Erosion Control

Installation of the solar facility will not alter existing drainage patterns or flow rates on the site and runoff water quality will not be impacted by the solar facility components. Installation of water quality or detention facilities would require clearing, grubbing, grading and reseeding of a portion of the site and would likely increase the potential for erosion, sediment transport and concentrated flow. Accordingly, water quality and detention are not recommended for this project.

Appropriate temporary (construction-related) erosion and sedimentation control Best Management Practices (BMPs), will be applied during the construction phase of the project. The BMPs will be inspected on a regular basis to ensure proper functionality.

Prepared by: **Richard L. Miller, AICP**  
**Development Manager**

# Decommissioning/Reclamation Plan

For a USR Permit  
Dove Solar LLC

Case Number: USR22-0003  
Archdiocese of Denver (Parcel ID No. 105916100039)

Prepared for:  
TOWN OF JOHNSTOWN  
PO BOX 609  
JOHNSTOWN CO 80534

Prepared by:  
SunShare, LLC  
Denver, Colorado



Date Prepared: November 2022

## 1.0 Overview

As a condition of approval for the Site-Specific Development Plan and Use by Special Review Permit, Johnstown required that SunShare prepare a *Decommissioning/Reclamation Plan* for the solar facility, that is to be reviewed and approved by the Johnstown Review Committee. The intent of this *Decommissioning/Reclamation Plan* is to provide a comprehensive plan for removal of the solar facility after its useful life and/or the termination of power generation operations; and to return the subject property to conditions that existed prior to the solar facility's construction.

The solar power generation facility has an estimated useful life of 30 years or more, with an opportunity for a life of 50 years or more with equipment replacement and repowering. At the end of the useful life of the facility, SunShare will cease power generation, decommission the facility, and remove the components of the facility from the subject property. The site will be reclaimed and returned to the agricultural use that existed prior to the facility being constructed.

This *Decommissioning/Reclamation Plan* is subject to refinement should future best practices or alternate methods be developed by the solar industry, during the life of this facility. SunShare will follow solar industry standards and best management practices (BMPs) that exist at the time of decommissioning and reclamation of the site.

### 1.1 Procedures for Decommissioning the Solar Facility After Useful Life & Termination of Power Generation

The solar facility consists of numerous recyclable materials, including glass, semiconductor material, steel, aluminum, copper, and plastics. When the facility reaches the end of its operational life, the component parts can be dismantled, and for the most part, salvaged or recycled at properly licensed facilities.

Some site features, such as internal roads, driveways, drainage features/improvements, and electrical interconnections may remain on the site, depending upon the anticipated future use of the property. All such improvements, that are scheduled to remain after the decommissioning of the site, will be approved by the JRC.



The following steps will be followed in the decommissioning of the solar facility:

- Approximately one year prior to the planned decommissioning of the facility, SunShare will schedule a pre-closure meeting with the JRC to discuss the process for the site decommissioning and restoration. The final decommissioning details will be developed through consultation with the JRC and other departments and agencies that have jurisdiction over activities in the decommissioning process. Any required permits will be obtained prior to implementation of the *Decommissioning/Reclamation Plan*.
- Appropriate temporary (construction-related) erosion and sedimentation control BMPs will be applied during the decommissioning phase of the project. The BMPs will be inspected on a regular basis to ensure proper functionality.
- Effectively, the decommissioning of the solar facility proceeds in reverse order of the installation:
  1. A site-specific health and safety plan shall be developed, prior to beginning decommissioning activities, which incorporates the specific sequence and procedures to be followed.
  2. Coordination with local departments and agencies to develop route plans and obtain necessary permits for the transportation of materials and equipment to and from the site.
  3. The solar facility shall be disconnected from the utility grid. This process will be coordinated with Xcel Energy.
  4. PV modules shall be disconnected, collected and transported to a properly licensed recycling facility.
  5. Above ground and underground electrical interconnection and distribution cabling shall be removed and salvaged or recycled off-site at an approved recycling facility.
  6. The aluminum racking that supports the PV modules shall be removed and salvaged or recycled off-site at an approved recycling facility.

7. PV module support steel and support posts shall be removed and salvaged or recycled off-site at an approved recycling facility.
8. Electrical and electronic devices, including transformers, semiconductors materials, inverters, and batteries, shall be removed and salvaged or recycled off-site at an approved recycling facility.
9. Concrete foundations shall be removed and will be recycled off-site at an approved concrete recycling facility.
10. Fencing shall be removed and will be recycled off-site at an approved recycling facility.
11. The site will be restored to its original condition, including any necessary sculpting of soils to match existing natural contours and the re-seeding of native grasses. Any soil that had been re-located for construction purposes will be redistributed on the site or used for landscaping purposes. Soils will be compacted for those areas where foundations or piers have been removed.

## 1.2 Equipment to be Used for the Decommissioning of the Solar Facility

The decommissioning of the solar facility will be undertaken using traditional heavy construction equipment, including front-end loaders, bull dozers, cranes, excavators (track-mounted and rubber-tired), water tankers, trucks, and pick-ups. Semi-trucks will be used to transport materials to off-site salvage or recycle centers.

## 1.3 Dust Mitigation During the Decommissioning Phase

Water tankers will be used to help control dust while the decommissioning activities are occurring on the site. During the decommissioning of the facility, SunShare will exercise BMPs to limit fugitive dust from being airborne and traveling beyond the property lines. Dust control efforts will be monitored by the site foreman on a regular basis to ensure fugitive dust is adequately controlled. Water spray will be applied, as needed, to unpaved areas during periods of dry weather. Care will be taken not to over-apply water and create mud. Vehicle tracking devices will be installed at truck exit drives, per the requirements of the Town. Vehicles

operating on the site during the decommissioning phase will limit their speed to 15 mph or less, to minimize dust emissions.

### 1.4 Decommissioning/Reclamation Cost Estimates

Decommissioning/reclamation cost estimates, which shall be updated every five (5) years from the establishment and submittal of the Security, shall include all costs associated with the dismantlement, recycling, and safe disposal of facility components and site reclamation activities, including the following elements:

Decommissioning:

Fencing	\$3000.00
Structures	\$60,000.00
Modules	\$30,000.00
Electrical	\$20,000.00
Site Restoration	\$25,000.00
<b>Total</b>	<b>\$138,000.00</b>

Clarifications – Inclusions and Exclusions

1. Based on project drawings provided.
2. Includes the specified appropriate project management and mobilization to adhere to the project schedule.
3. Breakouts provided for accounting purposes only.
4. All work is to be done in a single phase.
5. Includes recycling of steel, aluminum, modules and copper.
6. Includes restoration of the site back to like conditions before the solar array was installed.

Scope specifically includes:

1. Electrical permit fees included.
2. Removal and disposal of game fence.
3. Removal of racking support structure and foundations.
4. Module removal, package and recycle.
5. Removal of electrical distribution equipment, transformers and electrical equipment pads.
6. Removal of electrical DC string wiring and AC underground.
7. Site restoration.
8. Safety and protection as required.

9. Waste disposal fees and containers.
10. Temporary Restrooms and site facilities for workers.

**Specifically excludes:**

1. Payment and Performance Bond.
2. All utility specific tie in work to disconnect the site outside of property.
3. Engineering, fees, errors, omissions additional design intent not clearly delivered or identified on the referenced drawings.
4. Import or export of soils.





# Town of Johnstown

## PLANNING & ZONING COMMISSION AGENDA MEMORANDUM

---

**DESCRIPTION:** Dove Solar LLC – Solar Array Project Use by Special Review  
**PROJECT NO:** USR22-0002  
**LOCATION:** South of WCR 46.5 and the Little Thompson Reservoir, west of WCR 19  
**APPLICANT:** SunSolar (Applicant) / Archbishop of Denver (Owner)  
**STAFF:** Kim Meyer, Planning & Development Director  
**HEARING DATE:** February 15, 2023

---

### ATTACHMENTS

- 1- Vicinity Map
- 2- USR Site Plan
- 3- USR Narrative
- 4- Decommissioning & Reclamation Plan
- 5- Dust and Weed Mitigation Plan

### PROJECT SUMMARY

The Applicant requests the approval of a Use by Special Review (Attachment 2) for approximately 30 acres of land that is also under concurrent consideration for annexation, zoning and an ODP with the Town of Johnstown - as the Archdiocese Annexation Nos. 1 and 2. The Dove Solar Outline Development Plan would allow for the use of a solar facility on the eastern half of that subject property.

### PROPERTY BACKGROUND

The property is located south of Weld County Rd (WCR) 46.5 and west of WCR 19. The subject property is presently zoned A - Agricultural in unincorporated Weld County and is being used as farm land. It is bordered to the north by the Hillsborough/Little Thompson Reservoir, to the west by incorporated areas of Johnstown, with the rest being adjacent to unincorporated Weld County and adjacent to the Milliken Growth Management Boundary. (Attachment 1)

### SURROUNDING ZONING & LAND USE

North: A – Agricultural (Weld County), Hillsborough/Little Thompson Reservoir  
 South: A – Agricultural (Weld County)  
 East: A – Agricultural (Weld County)  
 West: PUD (Johnstown) with Oil & Gas Well Pads

### LAND USE HISTORY

Historically, this property has been used for farming and continues as that use today.

**OIL & GAS**

COGCC (Oil & Gas) online maps show existing abandoned and plugged and abandoned wells on-site. These sites are also shown on the USR site plans.

**IRRIGATION DITCHES**

The Hillsborough/Little Thompson Reservoir, owned and managed by the Extension (Hillsborough) Ditch Company, is partially located on the northwest corner of this property. These are some emergent wetlands along the banks of that water body, identified by the Colorado Wetland Inventory as part of the Colorado Natural Heritage Program.

(<https://csurams.maps.arcgis.com/apps/webappviewer/index.html?id=a8e43760cb934a5084e89e46922580cc>)

The reservoir and surrounding areas of interest are located in the H-A zoning district area and will be undisturbed by the proposed solar use on the PUD-MU zoned area.

**FLOODPLAIN**

The subject property is not located in any floodplain area.

**PUBLIC NOTICE & AGENCY REFERRALS**

Notice for the Planning & Zoning Commission hearing was published in the local paper of widest circulation, the Johnstown Breeze, on Thursday, January 26, 2023. This notice provided the date, time, and location of the Planning and Zoning Commission hearing, as well as a description of the project. Notices were mailed to all property owners within 500 feet of the property in question. This notice included a map of the project area.

This project was referred to the Johnstown Review Committee as well as Weld County, Milliken, the Weld RE-5J School District, Little Thompson Water, Xcel, and TDS.

**NEIGHBORHOOD MEETING**

No neighborhood meeting was held for this USR project.

**PROJECT DESCRIPTION & ANALYSIS**

The proposed USR applies to the 5,000 kW-AC solar array project use that Dove Solar is anticipating installing on this property. This array will consist of approximately 142 rows of over 11,000 modules. This non-reflective array equipment will be installed in the typical rows of arrays, with a maximum height of 10 feet at full tilt. The fencing will be an 8-foot tall game fence of 4x4 inch reinforced mesh. Native seed mix will be cultivated and maintained onsite post construction, with

The total project site, inside the fence, is a little over 30 acres in size, with overall dimensions of approximately 1183 feet wide (east-to-west) and just under 1300 feet north-to-south. This comprises the full frontage of the property along CR 19. The front fencing along the roadway is anticipated to be setback approximately 45-70 feet from the ultimate right-of-way, with another 30 feet to the nearest equipment.

The use would utilize the existing access from CR 19 and creates the needed hammerhead turnaround for the Fire District on-site. No utilities or additional accesses are needed to serve this use. Electrical cables serving the site will be buried underground.

The Use by Special Review would permit this use to continue for up to 40 years from the time the facility is complete and in operation. Any proposed change to the use or additional development plans would initiate a new review by the Town and our reviewing agencies at that time. At the time of decommissioning, the user is required to remove all equipment and improvements and return the site to its current undeveloped state.

The Site Plan is also accompanied by grading and stormwater plans that have been reviewed and approved by the Town Engineer, as well as a Project Narrative, Decommissioning & Reclamation Plan, and Dust and Weed Mitigation Plan (Attachments 3, 4 & 5).

This area of the Johnstown Growth Management Area is indicated for Low or Very Low Intensity and Density types of development. The use of the area for low intensity energy resource development is in alignment with this designation and intention. Staff has no outstanding concerns related to this proposed Dove Solar LLC – Solar Array Project Use by Special Review.

### **RECOMMENDED PLANNING AND ZONING COMMISSION FINDINGS AND MOTIONS**

Staff recommends that the Planning and Zoning Commission send a recommendation for Approval to Town Council for the Dove Solar LLC – Solar Array Project Use by Special Review based upon the following findings, per JMC Sec 17-200:

1. The Special Use is in alignment with the Future Land Use Plan within the Area Johnstown Comprehensive Plan.
2. The Special Use will be compatible with existing surrounding and probably future land uses in the area.
3. The Special Use will not cause any unreasonable demand on Town services.
4. The Special Use will not unreasonable or adversely affect traffic flow in the surrounding area.
5. The Special Use has been designed to meet all Town codes, regulations and requirements for that type of development.
6. The Special Use provides a meaningful interim use, to up 40 years, to the subject property; which may then develop in accordance with future land use compatibility, and town plans and codes in place at that time.

#### **Recommended Motion: Motion to Approve**

Based on the application materials received, analysis and presentations at this hearing, and findings noted in this staff memorandum, I move that the Planning & Zoning Commission recommend Approval to the Town Council for the Dove Solar LLC – Solar Array Project Use by Special Review.

#### **Motion to Recommend Denial**

I move that the Commission recommend to the Town Council Denial of the Dove Solar LLC – Solar Array Project Use by Special Review.



# Town of Johnstown

## DOVE SOLAR ARRAY PROJECT USR

Use by Special Review (USR)


TOWN COUNCIL

April 17, 2023



# VICINITY MAP

- West of CR 19
- ½ mile south of CR 46 ½
- Within the proposed Dove Solar ODP
- Proposed 31 Acre Solar Facility
- Ditch & Reservoir not affected by USR






# SITE PLAN

Item #13.

- 5 MW-AC Solar Facility
- 142 rows/11,000 modules
- 10' Max height of equipment
- 40-year term on USR permit
- 20 Year contract with Xcel, may be renewed.
- Access via private drive w/ Hammerhead per Fire Code
- Oil and gas facilities integrated
- 20' wide gravel access road w/ gate & vehicle tracking control




Town of Johnstown  
johnstown.colorado.gov | 970-587-4664

# LANDSCAPE & SCREENING PLAN

Item #13.

- Existing Ag along nearby County Roads
- 1400' to nearest residence
- 8' Wildlife Fencing (4" mesh)
- Native seed under panels
- Dust/weed & Decommissioning /Reclamation Plans
- Electric cabling to be buried
- Front fence to be setback 45-70' from ultimate ROW, Additional 30' to solar equipment.




Town of Johnstown  
johnstown.colorado.gov | 970-587-4664



# STAFF ANALYSIS

Item #13.

- Johnstown Review Committee (JRC) included Town staff, Town traffic, civil, and water engineers, Weld County, Milliken, LTWD, Xcel, TDS, Weld School Dist RE-5J
- USR is in conformance with Town codes, standards and regulations.
- PZC Recommend Approval



*Low intensity uses (ag & solar) are in alignment with the Johnstown Area Comprehensive Plan*



Town of Johnstown  
johnstown.colorado.gov | 970-587-4664





# Town of Johnstown

## TOWN COUNCIL AGENDA COMMUNICATIONS

---

**AGENDA DATE:** April 17, 2023

**SUBJECT:** Consideration and Public Hearing for Ordinance 2023-247 Repealing Chapters 15, 16 and 17 of the Johnstown Municipal Code, and Readopting Chapter 17 of the Johnstown Municipal Code to adopt the Johnstown Land Use & Development Code by Reference

**ACTION PROPOSED:** Approval of Ordinance 2023-247

**ATTACHMENTS:**

1. Ordinance 2023-247
2. Johnstown Land Use & Development Code (Part I & II)
3. Section Map (Comparison to current code)
4. Staff Presentation

**PRESENTED BY:** Kim Meyer, Planning & Development Director

---

### AGENDA ITEM DESCRIPTION:

The Town Council authorized the drafting of an updated Land Use & Development Code in the 2022 budget, and Town Staff and consultants have been diligently working on a complete rewrite of Johnstown Municipal Code, Chapter 15 - Annexation, Chapter 16 – Zoning, and Chapter 17 – Subdivision. These chapters are proposed as a single, more cohesive code document that addresses all areas related to land use, zoning, and development in the Town.

The proposed ordinance would repeal the current Johnstown Municipal Code Chapters 15, 16, and 17 related to Annexation, Zoning, and Subdivision, reserve Chapters 15 and 16 for future use, and replace these code sections as an updated Chapter 17 that references an external municipal code document, to be named the “Johnstown Land Use & Development Code” (Attachments 1 & 2). This code more cohesively and clearly governs and describes the Town’s zoning districts, land uses, processes, and development standards with up-to-date code language and design standards integrated into the code, replacing a patchwork of outdated, poorly organized, and confusing code sections with separate design guidelines.

*Background.* The Town Council adopted a new Johnstown Area Comprehensive Plan in late 2021, and the code rewrite follows this effort to create codes that will begin to incrementally implement the themes and goals identified within that document. MultiStudio, the consultants, created an Engagement Plan, performed a Code Assessment to identify gaps, and provided a Regulatory Conformance Report in 2022. Town Staff and the consultants have also conducted several community open houses, and work sessions with the Steering Committee, Planning & Zoning Commission, and Town Council over the past year to gain insight and feedback on a variety of topics and issues that were identified as important to the community.

*Overview.* The proposed Land Use & Development Code (LUDC) document is being adopted by reference in the ordinance, and is presented as a separate standalone document. The purpose of utilizing an external code document is to ensure proper presentation and formatting of clarifying graphics which support the design-oriented content, easy-to-read tables, and accommodate other more complex formatting issues. This format provides the opportunity for a more user-friendly code experience, more economical and efficient code amendments over time, and the ability to present this oft-used document to our citizens, businesses, and development community in an easier to use electronic PDF format.

A Section Map document (Attachment 3) provides a quick view summary of the proposed Articles of the proposed Chapter 17 LUDC and references the topics as they are currently arranged within Chapters 15, 16, & 17 with high level summary that briefly explain the new section.

Many of the general planning and development process and concepts exist in our current code language, but with insufficient description of intent, objectives, and review criteria to adequately give staff and decision-makers the ability to support a thorough review and detailed analysis. There have also been significant changes in the legal landscape with regard to several issues, notably the regulation of signs (“content neutral”) and oil and gas facilities, and these changes will be better reflected in the proposed codes, based on current statutes, rules, and case law.

*Consistency.* Town Staff worked with the consultants to maintain as much consistency with current regulations and guidelines as possible, to keep the day-to-day impact of the updated code somewhat limited in terms of what an existing business, resident, or developer may notice. For example, the area of permitted wall or freestanding signs is comparable to the prior code, and Staff considered the existing body of signage in Johnstown to inform the proposed code; development review processes and requirements will be largely comparable;

The code contemplates and permits existing PUDs and previously-approved projects that will continue to move through our existing processes and systems using the current PUD standards. Staff is actively talking with those who may choose to vacate those PUDs and utilize the new code, with the intent throughout this process to create a usable flexible code that provided many of the

benefits of a PUD, without the long term administrative and enforcement complexities of managing dozens of unique sets of standards.

*Noteworthy Changes.*

- New and transitioning zoning districts will mark a distinct shift for Johnstown. All existing zoning districts, except PUD, will transition to a comparable district, as noted in the LUDC (i.e., “SF-1” = “R-1”, remaining a single family detached zone). Unused districts were removed. Additional districts are proposed to permit a wider range of scale, intensity, and density to be reflected in our “straight zones” – expanding to 4 residential zones, 3 mixed use zones (commercial and residential), and 2 industrial zones (Article 4).
- Design issues within overall neighborhood layout of streets and open spaces, as well as architectural considerations for residential and non-residential development, have been integrated into this LUDC to replace the early-2000s “Town Design Guidelines” that tended to be light on specifics and requirements and challenging to administer and implement. Major themes of masonry and high-quality materials, minimum area of windows on elevations, entry features, and mixing street character, open spaces and connected trails to create neighborhood character are all included in this proposed code.
- Housing Diversity. Multiple housing units types as well a minimum mix of housing types are introduced in an effort to create more livable, interesting, and integrated neighborhoods.
- Clarification of processes with a specific descriptions of applicability, review criteria, procedure, and effects of decisions. The introduction of “Alternative Compliance” speaks to creating the ability to provide limited flexibility from strict interpretation of the code, allowing for the consideration and evaluation of innovative and creative design solutions that meet the intent and design objectives of the stated code standards.
- Expansion of definitions (Article 11) that help clarify uses and specific terminology.

*Next Steps & Expectations.*

- Town Staff will begin implementation and application of this code with new developments and develop worksheets and guides to assist the development community. We intend to host a meeting, or a series of meetings if needed, with our development community in late Spring / early Summer.
- Johnstown utilized the PUD zoning district as a default zone for annexing properties for nearly 20 years, and it leaves our zoning map dotted with undeveloped and unplanned PUD zones that may not reflect the current context or intent of the Town, as reflected in the Comprehensive Plan, or where a similar pattern of development may be achieved with the LUDC. Staff anticipates further analysis and the potential to propose updated zoning districts, as a legislative action, where a different district may serve to implement current Town development and land use goals.

- Town Staff anticipates finding small errors and omissions as we begin to actively implement this code. We also intend to stay abreast of emerging trends in new land use & legal issues, and design and development issues and will propose regular amendments to address those in an effort to maintain the long-term relevancy of this code such that a full wholesale overhaul, as proposed with this LUDC, is not required again for the foreseeable future.
- Given the complexity and scope of this proposed LUDC, Staff will continue to coordinate with the Town Attorney on their review. The consultant who drafted the code is a planner and a land use attorney, and Staff feels confident in the overall legal validity of the code, as proposed, but anticipates nuanced and town-specific comments to yet emerge from an internal legal review that may result in proposed amendments.
- Development is dynamic and there are always new opportunities or concerns that develop over time. From a broad lens, Staff can see the potential for future code efforts to accommodate consideration for uses such as solar facilities, surface mining, large-scale industrial development, finalized floodplain study and revised panels expected in 2023, future housing initiatives, and small-area planning efforts to maintain or develop a specific character in a given area.

**LEGAL ADVICE:**

Ordinance was prepared by the Town Attorney.

Consulting counsel, Chris Brewster, J.D., AICP, with MultiStudio, Inc., prepared the proposed Johnstown Land Use & Development Code.

**FINANCIAL ADVICE:**

NA

**RECOMMENDED ACTION:**

Approval of Ordinance 2023-247 Repealing Chapters 15, 16 and 17 of the Johnstown Municipal Code, and Readopting Chapter 17 of the Johnstown Municipal Code to adopt the Johnstown Land Use & Development Code by Reference



**SUGGESTED MOTIONS:**

**For Approval**

I move that the Town Council Approve Ordinance 2023-247 Repealing Chapters 15, 16 and 17 of the Johnstown Municipal Code, and Readopting Chapter 17 of the Johnstown Municipal Code to adopt the Johnstown Land Use & Development Code by Reference, on First Reading.

**To Remand back to Staff**

I move that the Town Council remand this Ordinance and proposed Johnstown Land Use & Development Code back to Town Staff for further revisions and consideration based on the discussions and input received.

**To Deny**

I move that the Town Council Deny Ordinance 2023-247.

---

*Reviewed and Approved for Presentation,*



---

Town Manager

**TOWN OF JOHNSTOWN, COLORADO**

**ORDINANCE NO. 2023-247**

**AN ORDINANCE REPEALING CHAPTERS 15, 16 AND 17 OF THE JOHNSTOWN MUNICIPAL CODE, READOPTING CHAPTER 17 OF THE JOHNSTOWN MUNICIPAL CODE TO ADOPT THE JOHNSTOWN LAND USE & DEVELOPMENT CODE BY REFERENCE THEREIN AND ADOPTING THE JOHNSTOWN LAND USE & DEVELOPMENT CODE**

**WHEREAS**, the Town of Johnstown, Colorado (“Town”) is a Colorado home rule municipality, duly organized and existing under the laws of the State of Colorado and the Town’s Home Rule Charter; and

**WHEREAS**, the Town Council is vested with authority to administer the affairs of the Town; and

**WHEREAS**, based on the recommendation of the Town Planning and Development Director, on or about August 16, 2021, the Town Council retained Gould Evans, Inc., a Kansas corporation, n/k/a Multistudio, Inc., a Kansas corporation (“Gould Evans”), to prepare an updated land use and development code for the Town to replace Chapters 15, 16 and 17 of the Johnstown Municipal Code; and

**WHEREAS**, in order to draft a land use and development code that satisfies the needs, expectations and desires of the Town, Gould Evans worked diligently with Town staff and, through numerous work sessions, obtained extensive input from the Town Council as well as input from the public and developers; and

**WHEREAS**, based on such input, Gould Evans drafted an updated land use and development code, referred to as the “Johnstown Land Use & Development Code;” and

**WHEREAS**, on April 17, 2023, after due notice to the public, the Town Council held a public hearing to consider adoption of the Johnstown Land Use & Development Code; and

**WHEREAS**, after considering the evidence presented at the public hearing and reviewing the Johnstown Land Use & Development Code, the Town Council finds that adoption of the Johnstown Land Use & Development Code promotes the public health, safety and welfare of the Town, implements the strategies and objectives of the Town Council and is consistent with the goals set forth in the *Johnstown Area Comprehensive Plan*; and

**WHEREAS**, for the foregoing reasons, the Town Council desires to adopt the Johnstown Land Use & Development Code to replace the rules and regulations contained in Chapters 15, 16 and 17 of the Johnstown Municipal Code; and

**WHEREAS**, the Town Council further finds, determines and declares that this Ordinance is promulgated under the general police power of the Town, that it is promulgated for the preservation of the public health, safety, welfare and property and that this Ordinance is in the best interests of the citizens of the Town.

**NOW, THEREFORE, BE IT ORDAINED BY THE TOWN COUNCIL OF THE TOWN OF JOHNSTOWN, COLORADO, AS FOLLOWS:**

**Section 1. Repeal.** Chapters 15, 16 and 17 of the Johnstown Municipal Code are hereby repealed in their entirety.

**Section 2. Reservation.** Chapters 15 and 16 of the Johnstown Municipal Code are hereby reserved for subsequent use.

**Section 3. Readoption.** Chapter 17 of the Johnstown Municipal Code is hereby readopted to read in full as follows:

**CHAPTER 17 – LAND USE AND DEVELOPMENT CODE**

**Article I – Adoption.**

**Sec. 17-1 – Adoption by Reference.**

The Johnstown Land Use & Development Code is hereby adopted by reference and incorporated with the same force and effect as if fully set forth herein. A copy of the Johnstown Land Use & Development Code is on file at the office of the Town Clerk and is available on the Town’s website at [www.johnstown.colorado.gov](http://www.johnstown.colorado.gov).

**Section 4. Johnstown Land Use & Development Code.** The Johnstown Land Use & Development Code, attached hereto and incorporated herein by reference as Exhibit A, is hereby adopted. The Johnstown Land Use & Development Code shall hereinafter regulate land use and development in the Town and supersede and replace the rules and regulations previously contained in Chapters 15, 16 and 17 of the Johnstown Municipal Code.

**Section 5. Penalty Provision.** Section 17-1-8(C) of the Johnstown Land Use & Development Code provides as follows:

**Penalty.** Any person violating any of the provisions of this code shall be deemed guilty of such violation and upon conviction, shall be penalized as provided in Article IV of Chapter 1 of the Johnstown Municipal Code. Each day of a violation shall constitute a separate offense, and any owner or other person employed in connection with a violation shall be guilty of a separate offense. The Town shall further have the right to maintain suits or actions in any court of competent jurisdiction for the purposes of enforcing these regulations and to abate any potential nuisance, including preliminary or permanent

injunctions. These penalties are not exclusive of any other remedy available under any applicable local, state, or federal law, and it is within the discretion of the Town to seek alternative and/or cumulative sanctions or remedies.

**Section 6. Severability.** If any part or provision of this Ordinance, or its application to any person or circumstance, is adjudged to be invalid or unenforceable, the invalidity or unenforceability of such part, provision, or application shall not affect any of the remaining parts, provisions or applications of this Ordinance that can be given effect without the invalid provision, part or application, and, to this end, the provisions and parts of this Ordinance are declared to be severable.

**Section 7. Code revisions.** Minor changes such as the format and other changes to unify the revised Land Use & Development Code may be necessary. The Town Clerk is hereby authorized to make such changes, provided that neither the intent nor substantive content will be altered by such changes.

**Section 8. Publication; Effective Date.** This Ordinance, after its passage on final reading, shall be numbered, recorded, published and posted as required by the Town’s Home Rule Charter and the adoption, posting and publication shall be authenticated by the signature of the Mayor and the Town Clerk. This Ordinance shall become effective upon final passage as provided by the Home Rule Charter of the Town of Johnstown, Colorado. Copies of the entire Ordinance are available at the office of the Town Clerk.

**INTRODUCED, AND APPROVED** on first reading by the Town Council of the Town of Johnstown, Colorado, this \_\_\_\_ day of \_\_\_\_\_, 2023.

**TOWN OF JOHNSTOWN, COLORADO**

**ATTEST:**

By: \_\_\_\_\_  
Hannah Hill, Town Clerk

By: \_\_\_\_\_  
Gary Lebsack, Mayor

**PASSED UPON FINAL APPROVAL AND ADOPTED** on second reading by the Town Council of the Town of Johnstown, Colorado, this \_\_\_\_ day of \_\_\_\_\_, 2023.

**TOWN OF JOHNSTOWN, COLORADO**

**ATTEST:**

By: \_\_\_\_\_  
Hannah Hill, Town Clerk

By: \_\_\_\_\_  
Gary Lebsack, Mayor



---

# TOWN OF JOHNSTOWN



## LAND USE AND DEVELOPMENT CODE (LUDC)

ADOPTED MAY 2023

AS REFERENCED IN CHAPTER 17  
OF THE JOHNSTOWN MUNICIPAL CODE





**Article 1 General Provisions**

- 17-1-1 Title
- 17-1-2 Authority
- 17-1-3 Purposes
- 17-1-4 Applicability
- 17-1-5 Administration
- 17-1-6 Interpretation
- 17-1-7 Nonconformities
- 17-1-8 Enforcement

**Article 2 Procedures**

- 17-2-1 General – All Applications
- 17-2-2 Platting
- 17-2-3 Rezoning
- 17-2-4 Planned Development
- 17-2-5 Site Development Plan
- 17-2-6 Alternative Compliance
- 17-2-7 Use by Special Review
- 17-2-8 Variances
- 17-2-9 Appeal of Administrative Decisions
- 17-2-10 Text Amendments
- 17-2-11 Vested Property Rights
- 17-2-12 Annexation & Establishment of Zone District(s)

**Article 3 Subdivision & Community Design**

- 17-3-1 Street Design
- 17-3-2 Open & Civic Space Design
- 17-3-3 Blocks & Lots
- 17-3-4 Required Improvements
- 17-3-5 Community Facilities & Fees

**Article 4 Zone Districts & Uses**

- 17-4-1 Establishment of Zone Districts
- 17-4-2 Permitted Uses / Use Table
- 17-4-3 Specific Use Standards
- 17-4-4 Accessory Uses
- 17-4-5 District Performance Standards

**Article 5 Residential Development & Design**

- 17-5-1 Intent & Applicability
- 17-5-2 Residential Building Types
- 17-5-3 Neighborhood Design
- 17-5-4 Courtyard Pattern
- 17-5-5 Conservation Pattern
- 17-5-6 Manufactured & Small Format Housing District



**Article 6: Nonresidential Development & Design**

- 17-6-1 Intent & Applicability
- 17-6-2 Nonresidential Development Standards
- 17-6-3 Frontage Design
- 17-6-4 Building Design
- 17-6-5 Open Space Design
- 17-6-6 Specific Frontage & Design Plans

**Article 7 Access & Parking**

- 17-7-1 Intent & Applicability
- 17-7-2 Access & Circulation
- 17-7-3 Required Parking
- 17-7-4 Parking Design

**Article 8 Landscape Design**

- 17-8-1 Intent & Applicability
- 17-8-2 Landscape Requirements
- 17-8-3 Buffers & Screens
- 17-8-4 Plant Specifications
- 17-8-5 Fences & Walls

**Article 9 Signs**

- 17-9-1 Intent & Applicability
- 17-9-2 Exempt Signs
- 17-9-3 Permitted Sign Types & Allowances
- 17-9-4 Standards for Specific Signs
- 17-9-5 General Standards – All Signs

**Article 10 Supplemental Standards**

- 17-10-1 Wireless Communication Facilities
- 17-10-2 Floodplain Management & Flood Damage Preventions
- 17-10-3 Natural Resource Extraction & Energy Development

**Article 11 Definitions**

- 17-11-1 Description of Uses
- 17-11-2 Defined Terms
- 17-11-3 Design & Architecture Terms



## CHAPTER 17 – LAND USE AND DEVELOPMENT CODE

### Article 1. General Provisions

- 17-1-1 Title
  - 17-1-2 Authority
  - 17-1-3 Purposes
  - 17-1-4 Applicability
  - 17-1-5 Administration
  - 17-1-6 Interpretation
  - 17-1-7 Nonconformities
  - 17-1-8 Enforcement
- 

#### 17-1-1 Title

This Chapter is known as the Johnstown Land Use & Development Code. References to “this code,” “the development code,” “the land use code,” “the zoning code,” or “these regulations” shall be considered a reference to the Johnstown Land Use & Development Code.

#### 17-1-2 Authority

- A. **Authority.** The Johnstown Land Use & Development Code is adopted through the powers granted in the Johnstown Home Rule Charter (“Charter”), and in accordance with the general purposes and authority granted by Colorado Revised Statutes, Title 31, Article 23 Planning and Zoning. The Town of Johnstown recognizes that zoning is a local and municipal matter and intends that this code supersedes any conflicting general law of the State of Colorado within its jurisdiction.
- B. **Jurisdiction.** The Johnstown Land Use & Development Code applies to all structures, uses, and land within the incorporated area of the Town of Johnstown, as depicted on the official zoning map, and other maps accompanying the Town’s plans and policies. The provisions of this code that apply to subdivisions, and the planning and design of major streets, shall apply to all land within the legal boundaries of the Town and all land within three miles of the corporate limits of the Town, if not located in any other municipality’s authorized jurisdiction.

#### 17-1-3 Purposes

This development code is adopted to promote the public safety, health, and general welfare for the Town of Johnstown and its citizens and businesses. Specifically, the regulations have the following purposes:

- A. Implement the Comprehensive Plan, and other plans and programs authorized under the guidance of the Comprehensive Plan.
- B. Ensure long-term value and the physical, social, and economic well-being of residents and businesses through coordinated public and private investment.





- C. Promote planning and urban design that emphasizes distinct places and unique elements of community character throughout Johnstown.
- D. Provide parks, trails, natural areas, and civic spaces and organize development around systems of connected open spaces.
- E. Secure proper arrangement and design of streets to shape efficient development patterns, implement multimodal networks, coordinate with existing and planned streets, and improve mobility and access.
- F. Divide the Town into zones and districts that promote the character, intensity, and development patterns of distinct places identified in the Comprehensive Plan.
- G. Regulate and restrict the development and use of buildings and land within each zoning district to create compatibility within districts and transitions between complimentary districts, uses, and buildings.
- H. Secure adequate provisions for water, storm drainage, wastewater facilities and other public improvements based upon local, state, and federal requirements.

#### 17-1-4 Applicability

- A. **General Applicability.** It shall be unlawful to conduct any development or use of land until all specified development review processes have been followed, all applicable standards have been fulfilled, and all required approvals, permits or other authorizations have been issued.
- B. **Transition Provisions.** The following rules shall determine the transition from previous regulations to the current code:
  - 1. *Applications.* Any application submitted prior to the effective date, and determined a complete application by the Director, shall be reviewed and processed according to the prior standards and procedures. An application submitted prior to the effective date, but determined incomplete, shall be resubmitted and processed according to the regulations in effect at the time of submittal of a complete application.
  - 2. *Prior Approvals.* All permits, site development plans, or other approvals issued prior to the effective date of this code shall remain effective, subject to any prior expiration provision of the specific application. Any changes, or amendments to a prior approval requested after the effective date of this code shall be subject to all provisions of this code.
  - 3. *Plats.* Any approved preliminary plat may continue to advance to final plat according to the procedures of this code and as presented on the approved preliminary plat unless:
    - a. A major amendment is proposed to the preliminary plat; or
    - b. Any final plat proposes a substantial change to the preliminary plat.
  - 4. *Use by Special Review.* Any use operating under a use by special review or other approval that may be limited to a specific duration or conditions under prior regulations may continue for that specified duration or according to the conditions. Any changes or subsequent approvals of these uses upon expiration of that period shall be processed according to this code. A use existing legally prior to the effective date of this code, but which is now classified as Use by Special Review, shall be considered as having Use by



Special Review approval according to this code based on the extent of the existing operations.

5. **Planned Unit Developments.** All preliminary and final development plans and design guidelines approved within the previous Planned Unit Development (PUD) zoning districts shall remain in effect. Subsequent approvals needed for ongoing development under the PUDs shall be processed according to the previously applicable to PUD progression for outline, preliminary, and final development plans. Amendments to approved PUDs and design guidelines, or future development or redevelopment within PUDs, may be processed according to the terms of the current development code, and the prior PUD plans be voided and superseded. Alternatively, Planned Unit Developments may be rezoned by the Town according to the current code, and the prior PUD plans be voided and superseded.
6. **Continuation of Enforcement.** Any violations of a previously valid regulation that continues after adoption of this code may be enforced as provided by this code. The Town may, in its discretion, enforce either the previous regulation or the standards of this Code.

**D. Severability.**

1. If a valid and final court decision declares any part of this development code to be invalid, that ruling shall not affect any other provisions of this development code not specifically included in that ruling.
2. If a valid and final court decision declares that the application of this development code to a particular property or structure is invalid, that ruling shall not affect the application of the regulations to any other property or structure, or to development with different circumstances.
3. No provision of this code shall enable any circumstance that is unlawful under superseding federal or state law. If any section, subsection, sentence, clause, phrase, or portion of this code is now or in the future superseded or preempted by state or federal law, or found by a valid final court decision unauthorized, such provision shall be interpreted and applied as required by law.

**17-1-5 Administration**

**A. Staff.** The following Town Staff positions are responsible for administering specific aspects of this code.

1. **Planning Director.** Pursuant to Article 8 and administrative authority granted by the Town Manager, the Planning Director (Director) is responsible for general administration of the development code and is the principal interpretation and enforcement official of these regulations. The Director may consult with any other department or relevant outside agencies to coordinate any plans, policies and programs that impact the Comprehensive Plan or this code.
2. **Johnstown Review Committee.** The Town Manager or Director may assemble the Johnstown Review Committee, for any applications that the Town Manager or Director determines require referral, review, and comment from any of other departments or external agencies. The committee generally includes the Public Works Director, Utilities Director, Town Engineer, Building Official, public safety representatives, and staff from



any other relevant departments or their authorized representatives on a project-specific basis.

- B. **Planning & Zoning Commission.** The Planning and Zoning Commission is the appointed body of the Town responsible for long-range and comprehensive planning, as well as review, recommendations and decisions on implementation of the Comprehensive Plan and development code. The Planning and Zoning Commission is established according to the Municipal Code.
- C. **Board of Adjustment.** The Board of Adjustment was created under the authority of C.R.S. 31-23-307. The Board of Adjustment is established pursuant to these regulations and is empowered to hear and decide the following appeals as specified in Article 2:
  1. Grant variances to the strict application of the standards in this code; and
  2. Hear and decide appeals when an error is alleged in any order or determination made by the Director in the interpretation or enforcement of this code.

### 17-1-6 Interpretation

- A. **Rules of Construction.** The following rules shall be use in the application and interpretation of this code, unless the usage in a specific standard or context clearly indicates otherwise:
  1. All words shall have the customary dictionary meaning, unless specifically defined in these regulations.
  2. The present tense includes the future tense, and the future tense includes the present tense.
  3. The singular includes the plural, and the plural includes the singular.
  4. Lists of examples prefaced by “including the following,” “such as,” or other similar clauses shall not be construed as exclusive or exhaustive and shall not preclude an interpretation of the list to include other similar and non-mentioned examples.
  5. The conjunctive “and” in a list means that all apply; the conjunctives “or” and “and/or” mean the provisions may apply singly or in any combination; and the conjunctive “either ..or” means the provisions apply singly but not in combinations.
  6. When calculations to determine a requirement of something that cannot be divisible (i.e. parking space, trees) results in fractions, it shall be rounded up to the nearest whole number if the standard is expressed as a minimum requirement and rounded down to the nearest whole number if the standard is expressed as a maximum allowance.
  7. “Shall,” “will” or “must” is mandatory; “should” or “may” is permissive but a recommended method to best meet the standard or achieve the intent of the standard.
  8. A reference to an administrative official shall refer to that official, or their official designee, and all references to specific town officials may also include any other designee of the Town Manager.
  9. Any reference to other official local, state or federal government rules or regulations shall include the current versions of those regulations, provided they remain binding on the Town, or where not binding, remain consistent with the purposes, intent, and objectives included in these regulations.
  10. References to a person shall include individuals, partnerships, agencies, corporations or other legal entities and the owner, tenant, occupant, principal, partners, officers, employees, agents, and representatives of any legal entity.
- B. **Conflicts.** All provisions shall be considered the minimum requirements to promote the public health, safety and welfare. In case of a conflict between these regulations and any other adopted rule, regulation or code of the Town, the higher standard shall apply. In deciding of which standard is higher, the official may consider which is more specific; which is more consistent with



the Comprehensive Plan; which is more consistent with the purposes, intent and objectives of these regulations; and which best promotes the public health, safety and welfare.

- C. **Computations of Time.** The following rules apply to any computation of time, unless a specific section of these regulations indicates otherwise:
1. The day of the act that commences a time period shall not be counted.
  2. The last day of the time period shall be included, unless it is a Saturday, Sunday or legal Town holiday, in which case the next working day shall end the time period. In all other cases Saturday, Sunday or legal Town holidays count in the time period.
  3. Whenever any time period is expressed for a formal submittal to the Town, the time period shall end at 5:00 p.m. on the last day of that time period.
  4. Any time period expressed in years shall include a full calendar year from the act that commences the time period.
- D. **Interpretation of Zoning Map.** Where uncertainty exists with respect to any boundary on the zoning district map, the following rules shall apply:
1. Boundaries approximately following streets or other rights of way or rivers or streams; the centerlines or extension of these centerlines shall be the boundaries.
  2. Boundaries indicated as approximately following property lines - the platted or other official legal line of that property shall be the boundaries unless the property boundaries on the map have been substantially altered.
  3. Boundaries approximately following Town limits shall be interpreted as following the actual Town limits.
  4. Boundaries that split any platted lots - the lot shall be interpreted in the district designated to the majority of the lot. In the case of an equal split, the Director shall determine the appropriate zoning based on consideration of the Comprehensive Plan, the context, the surrounding existing uses, and the likelihood of change in context or existing uses in the future.
  5. Boundaries that split any unplatted property - any future platting of property may generally follow the zoning boundary and then each resulting property may assume the zoning applicable to the majority of the resulting lot actual platted boundary, or where any resulting lots have significant discrepancies with zoning boundaries, rezoning may be required.
- E. **Non-regulatory Provisions.** Intent statements, design objectives, graphics, and commentary such as captions to graphics or notes in tables, are an aid to interpretation of the standards and criteria. In the event of a conflict between the intent statements, design objectives, graphics or commentary and a specific standard, the specific standard shall control unless the context and intent clearly indicate otherwise.
- F. **Resources, Guides, & Industry Standards.** Resources, guides, and industry standards that are recognized as a reputable authority in the planning, development and urban design professions, may be used to supplement interpretation of this code. They shall be subject to the approval of the Director upon a determination that the content is consistent with the policies of the Comprehensive Plan and the purposes, intent, and design objectives of these regulations. Any resource, guide, or industry standard approved by the Director shall be listed in Appendix A, and at least one copy shall be kept on file with the Planning and Development Department. The use of these guides shall only be to the extent that it is consistent with the purposes, intent and design objectives expressed in these regulations, and shall not be used to otherwise modify or conflict with any specific standard in these regulations.





## 17-1-7 Nonconformities

- A. **Intent.** The Town permits existing uses, buildings and lots that were created legally and in conformance with then-applicable requirements, but do not conform to the current applicable requirements of these regulations, to continue to be put to productive use. The Town's intent is to bring as many aspects of these nonconformities into compliance with current regulations as is reasonably practical. The intent of this section is to balance the interests of property owners in past investments, discourage investment that expands or reinforces non-conforming situations, and promote investment consistent with the Comprehensive Plan and these regulations.
- B. **Nonconforming Uses.** Uses that were legally initiated or established prior to the adoption or amendment of this code, but which would otherwise not be continued under the current terms of this code, may continue to exist subject to the following:
1. The use shall not be expanded beyond the current size any specific area of the site or lot where it was legally established, beyond any existing building or structure, or within any building or structure where any structural changes expand the exterior footprint of a building or structure. The Director may consider an exception based on the following findings:
    - a. The enlargement of the structure or buildings is only to facilitate conforming uses or activities, and does not otherwise allow, encourage or promote expansion or increase impacts of the nonconforming use;
    - b. The enlargement of the structure or buildings may allow for an addition to a detached house to enhance the livability, provided it does not add more than 50% of the original building square footage.
  2. Any accessory use to a principal nonconforming use shall not be permitted absent the principal use, and continuation of accessory uses shall not avoid any abandonment period for the nonconforming principal use. No additional accessory building or use not present when the nonconforming use was established shall be permitted, unless in conformance with these regulations.
  3. If active and continuous operations are not carried on during a period of 1 year, the use shall not be reestablished and all subsequent uses shall be in conformance with the provisions of this code.
    - a. Intent to resume active and continuous uses shall not count towards reestablishing the use. Evidence of a continuous business license is not sufficient to maintain use for this purpose. A business use must be operational to be considered active.
    - b. A nonconforming home occupation shall be considered abandoned if the occupants of the dwelling who were conducting the use discontinue either their occupancy of the dwelling or the nonconforming home occupation.
    - c. At the time any nonconforming, individual mobile home existing on a private lot is removed or is vacated, the use shall be deemed abandoned and shall not be returned or occupied except in compliance with this code.
    - d. A change of operator or sale of use shall not be considered discontinued, provided that neither the previous or current business or owner combined to cease operation for 1 year or more.
  4. No person shall move a nonconforming use within the same parcel or to another parcel unless the relocation conforms to this code.
  5. Any change of use shall be to a conforming use, and at that time the nonconforming use shall be abandoned. The Director may consider and authorize a change to a lesser



nonconforming use considering the extent, intensity, or operations of the use, provided it does not otherwise include investments that extend the period that the property is not conforming to this code.

6. Any structure in which a nonconforming use is carried on that is damaged to the extent of more than 50% of the current replacement value shall not be restored to support the nonconforming use with the exception of detached houses and duplexes, which may be replaced at its prior size as evidenced by records of the county assessor or other official record.
7. Any new activity that triggers specific site design standards shall require full compliance with that site design standard in order for the nonconforming use to continue, and the presence of a nonconforming use shall not be used to justify not meeting other applicable standards.

C. **Nonconforming Structures.** Structures other than signs that were legally constructed prior to the adoption or amendment of this code, but which could not be constructed under the current terms of this code, may continue to exist subject to the following:

1. Rehabilitation or expansion of the structure that increases the degree of nonconformity is prohibited. Other rehabilitation or expansions may occur provided that they comply with all other requirements of this code; are not detrimental to the purposes, intent and objectives of the standards; and do not negatively impact development in conformance with this code on adjacent property. In general, no repairs or alterations that exceed 50% of the replacement value of the structure shall be permitted.
2. If damaged by 50% or less of its total replacement cost, the structure may be restored to its original condition if a permit is obtained within 120 days of the damaging event and work is completed prior to expiration of the permit.
3. If the structure is determined obsolete or substandard by virtue of any applicable code beyond this chapter, and the cost of improvement or restoration is 50% or more of the current replacement value, then the right to maintain the nonconformance shall terminate.
4. Structures granted variances from the dimensional standards are not considered nonconforming and are not subject to the limitations of this section, provided that the structure and owner comply with any terms of the variance and the circumstances surrounding the variance have not substantially changed.

D. **Nonconforming Site Conditions.** Any site condition associated with a conforming use or structure (such as parking, landscape, open space or other non-building site characteristic) in existence prior to these regulations, but which are not compliant with the standards of these regulations, may continue to exist subject to the following:

1. Any change of use or expansion of use shall require compliance with the current development standards up to the maximum extent possible, considering the level of investment needed to support the new use and the extent of area being impacted by work to support the new use.
2. Any site development activity on a portion of a site shall require compliance with the new standards up to that proportion that is subject to the development activity. For example, a site that is not compliant with the landscape standards must meet the landscape standards prorated to the portion of the site where development activity occurs, but the remainder of the site may remain nonconforming.



3. Any change of use, building or site design element that triggers a screening requirement shall require 100% compliance with all screening standards applicable to the site.
  4. Where any investment is greater than 50% of the current replacement value of the site or can reasonably be interpreted as impacting more than 50% of any one component of the site, the site or that component shall be brought into full compliance with these standards.
- E. **Nonconforming Lots.** Any lots platted legally prior to the adoption or amendment of this code, but which could not be platted under the current requirements of this code, may continue to exist and be used for the uses permitted in the current zone district, provided development can meet other development standards.
- F. **Nonconforming Signs.** Existing signs which do not conform to the specific provisions of these regulations are designated as nonconforming signs. Nonconforming signs must be brought into compliance with this code or must be removed when any of the following conditions exist:
1. When the property or premises upon which the sign is located is vacant for a period of at least 120 days.
  2. When a sign and/or sign structure is damaged or destroyed in a monetary amount which exceeds 50% of its total replacement cost or becomes a hazard or potential hazard.
  3. When there is a zone change initiated by the business or property owner.
  4. When a sign and/or sign structure is abandoned for more than 120 days, including empty frames.
  5. When an existing structure upon which the sign is located is relocated, replaced, or changed in size, location, height or setback.
  6. When the sign itself is relocated, replaced, or changed in size, location, height or setback.
  7. The structure or size of the sign is altered in any way except towards compliance with these regulations. This does not refer to change of copy or normal maintenance.
  8. When improvements are being made to 50% percent or more of the facade of a building on which a nonconforming sign is located.
- G. **Burden of Proof.** The burden shall be on the applicant to establish that the nonconformity was established lawfully and the entitlement to continuation of nonconforming situations or completion of nonconforming projects according to this section. Owners of nonconformities may request a “certificate of legal nonconforming status” by filing an application with the Director.

### 17-1-8 Enforcement

- A. **Violations.** It shall be unlawful for any building, structure, site element or use of land to be constructed, altered, maintained, or otherwise initiated in violation of these regulations. It shall be unlawful for any person to do or cause:
1. Any act or thing prohibited by these regulations;
  2. Omit any act or thing required by these regulations; and
  3. Interfere in any manner with persons in performance of a right or duty granted or imposed by these regulations, maintained, or otherwise initiated in violation of these regulations.
- B. **Enforcement.** The Town may investigate and initiate proper actions or proceedings to prevent or terminate any activity or condition that is in violation of these regulations, including withhold any permits or licenses, revoke or suspend any permits or licenses previously granted, issue stop work orders, cease action on pending development application or permits, correct or abate the



nuisance, withhold any public improvements, or penalize and initiate legal proceedings to prevent the continuance of unlawful actions or conditions.

- C. **Penalty.** Any person violating any of the provisions of this code shall be deemed guilty of such violation and upon conviction, shall be penalized as provided in the Johnstown Municipal Code. Each day of a violation shall constitute a separate offense, and any owner or other person employed in connection with a violation shall be guilty of a separate offense. The Town shall further have the right to maintain suits or actions in any court of competent jurisdiction for the purposes of enforcing these regulations and to abate any potential nuisance, including preliminary or permanent injunctions. These penalties are not exclusive of any other remedy available under any applicable local, state, or federal law, and it is within the discretion of the Town to seek alternative and/or cumulative sanctions or remedies.





Article 2. Applications & Procedures

- 17-2-1 General – All Applications
- 17-2-2 Platting
- 17-2-3 Rezoning
- 17-2-4 Planned Development
- 17-2-5 Site Development Plan
- 17-2-6 Alternative Compliance
- 17-2-7 Use by Special Review
- 17-2-8 Variance
- 17-2-9 Appeals of Administrative Decision
- 17-2-10 Text Amendments
- 17-2-11 Vested Property Rights
- 17-2-12 Annexation & Establishment of Zone District

Table 2-1: Procedures Summary

	Eligible Applicants			Pre-application Meeting	Neighborhood Meeting	Notice			Review Body			
	Owner	PC	TC			Post	Publish	Mail	Staff	PC	TC	BoA
<b>Minor Subdivision (17-2-2.C)</b>	■			☑					D		A	
<b>Preliminary Plat (17-2-2.D)</b>	■			☑	☑	☑	☑	☑	R	R/PH	D/PH	
<b>Final Plat (17-2-2.E)</b>	■					☑	☑	☑	R		D/PH	
<b>Rezone (17-2-3)</b>	■	■	■	☑	☑	☑	☑	☑	R	R/PH	D/PH	
<b>Planned Development (17-2-4)</b>	■	■	■	☑	☑	☑	☑	☑	R	R/PH	D/PH	
<b>Site Development Plan (17-2-5)</b>	■			☑					D	A		
<b>Alternative Compliance (17-2-6)</b>	■			☑		Based on procedures of related application						
<b>Use by Special Review (17-2-7)</b>	■			☑	☑	☑	☑	☑	R	R/PH	D/PH	
<b>Variance (17-2-8)</b>	■			☑		☑	☑	☑	R			D/PH
<b>Appeal of Administrative Decision (17-2-9)</b>	■	■	■			--	--	--				D/PH
<b>Text Amendment (17-2-10)</b>		■	■				☑		R	R/PH	D/PH	
<b>Vested Property Right (17-2-11)</b>	■			☑					R	R	D/PH	
<b>Annexation &amp; Establishment of Zone District (17-2-12)</b>	■		■	☑		☑	☑	☑	R	R/PH	D/PH	

☑ = Required  
 ■ = Authorized  
 PC = Planning & Zoning Commission  
 TC = Town Council  
 BoA = Board of Adjustment

R = Review and Recommending Authority  
 D = Decision Making Authority  
 A = Appeal of Decision  
 PH = Public Hearing Required



---

## 17-2-1 General – All Applications

### A. Applications & Fees

1. **Forms.** Applications required under this code shall be submitted to the Planning and Development Department on forms supplied by the Department. The Director is authorized to establish application forms and submittal requirements to ensure all applications can be evaluated for conformance with this code. The Director may waive the requirement for any information on standard forms at the time of application, due to the routine nature of the application or due to the context of a particular application making the information inapplicable for review against the criteria.
2. **Fees.** Applications shall be accompanied by a non-refundable fee established by the Town's current Fee Schedule. Any application that does not include the required fee shall be returned to the applicant as incomplete. Fees shall not be required for applications initiated by the staff on behalf of the Planning and Zoning Commission or Town Council. In addition to any application fee established, applicants shall cover the direct expenses incurred by the Town in the review and processing of the application, including external consultants necessary and publication costs, in accordance with the Johnstown Municipal Code.
3. **Eligible Applicants.** Table 2-1 indicates applicants eligible for each particular application under this code, which may include the following:
  - a. **Owner.** The record owner of property that is the subject of the application or that owner's agent authorized by written permission of the owner.
  - b. **Planning and Zoning Commission.** The Planning and Zoning Commission, acting on its own initiative or through recommendations brought to it by town staff.
  - c. **Town Council.** The Town Council acting on its own initiative or through recommendations brought to it by town staff.

### B. Concurrent Applications.

When a project requires approvals under more than one type of application, the Director may determine that each application may run concurrently based on the following:

1. The similarity of information required for each type of application, or where they require different information, the ability to coordinate information, review criteria and decisions under each application.
2. The similarity of notice, timing, procedures, meetings and review bodies required for each application.
3. The ability of the staff and review bodies to make effective and well-informed decisions when reviewing the applications concurrently and comprehensively.

In cases where the Director determines applications may run concurrently, the application shall be processed through the highest review level of any of the associated applications. Approvals may be contingent on final decisions and subsequent approvals of the highest concurrent review, except that decisions of lesser applications may stand alone regardless of the outcome of higher-level decisions they may be considered final provided all procedures and criteria of that particular application are satisfied. Otherwise, no decision shall be considered final until the last of the related decisions has been made.

### C. Pre-application Meeting.

Pre-application meetings may be requested for any application and shall be required as indicated in Table 2-1. A required pre-application meeting may be waived at the Director's discretion and upon the applicant's request, for any application that is routine in nature and where the topics below can be addressed by general correspondence. Preapplication discussions are informational and non-binding, and assist applicants with further required due diligence on formal application requirements. Applicants shall confer with the Director and other



town staff or officials designated by the Director, to discuss the general nature of the proposal, including:

1. How the proposed project meets the goals of the Comprehensive Plan, or other specific plans or policies applicable to the area.
2. The applicant’s vision and understanding of the market for the proposed project.
3. The proposed uses, general site layout, and conceptual or anticipated design of buildings, including how the project relates to surrounding sites and public spaces.
4. How the project will contribute to the area and further the intent of the zoning district.
5. Planning and infrastructure impacts demands and impacts.
6. Development review processes and review criteria.
7. Opportunities to improve designs or coordinate the preliminary concepts with other private or public investments in the area.

D. **Neighborhood Meeting.** A neighborhood meeting shall be required as indicated in Table 2-1.

1. The Director may waive the requirement for a neighborhood meeting where the application will not impact the character of development or nature of activities in the area, or where information about the project is adequately presented in other means.
2. The Director may request a neighborhood meeting for other projects not required by Table 2-1 where the nature of the project is particularly complex or presents potential impacts on property in the vicinity.
3. Neighborhood meeting scheduling, notice, content, and record-keeping shall be coordinated with other procedures required for the application, and according to any Town policies on community engagement.

E. **Staff Review.** Upon receipt of an application or resubmittal, the Director shall take the following steps:

1. **Determination of Complete Application.** The Directory shall conduct a cursory review of the application to determine if the submittal is complete.
  - a. If an application is determined incomplete, the Director shall notify the applicant of the specific ways in which the application is deficient within 10 business days from the submittal date. No further processing of the application shall occur until the deficiencies are corrected. If a deficient application is not corrected within 30 days of the notice, the incomplete application may be considered withdrawn.
  - b. If an application is complete, it shall be processed for formal review.
2. **Staff Review.**
  - a. Applications may require review by the Johnstown Review Committee (JRC) as established in Section 17-1-5, and the Director may determine that any application can be reviewed by the JRC when it affects issues or facilities significant to other departments and outside agencies.
  - b. The Director may determine if other referral agencies are appropriate based on the application and has discretion to add any other relevant or applicable agency to the list. In general, the following agencies may be requested to review and comment:
    - (1) Adjacent county and municipal governments
    - (2) State of Colorado Department offices
    - (3) Gas and electric utilities
    - (4) Telecommunications and cable providers
    - (5) Public safety agencies (police, fire, health, emergency medical services)
    - (6) School district(s)
    - (7) Water and sewer utilities
    - (8) Ditch companies



- (9) Special districts; and
        - (10) Other local, state, or federal government agencies or impacted entities
      - c. Failure to receive comments from referral agencies may allow the Director to delay the application. However, if the applicant demonstrates sufficient due diligence in attaining comments, the Director may interpret the failure to comment as consent to the application by the agency.
      - d. The applicant shall be responsible for coordinating all subsequent requirements or comment, agreements, plans, or fees required to satisfy agency requirements, and for notifying any agency prior to final review of any changes that may affect their comments on initial plans.
  - 3. **Staff Comments.** The Director shall coordinate a staff review after receipt of a complete application and may provide the applicant the following information in writing:
    - a. Comments or recommended changes based on the results of any referral agency comments, neighborhood meetings, or staff review.
    - b. A list of any additional information necessary to support the application or address any comments or recommended changes.
    - c. If the applicant chooses not to address any comment or recommended change, a written statement shall be included with the resubmittal that demonstrates a good faith effort to address the issue and provide reasonable rationale why the comment cannot be addressed. The applicant may request to schedule the application for official review based on this rationale.
    - d. If the applicant fails to submit revisions or otherwise address any comments from the Planning and Development Department in writing for more than 120 days, the Director may determine the application withdrawn and the review terminated. Any further action will require a new application and fees.
  - 4. **Scheduling.** Applications that have completed JRC or staff review, and addressed comments or recommended changes, shall be scheduled for further review according to these regulations.
  - 5. **Staff Report.** The Director shall prepare a staff report for applications that require review and decisions by other review bodies. The report shall identify the appropriate policies, plans, regulations and review criteria, and identify relevant facts of the application. The Director shall publish or otherwise make the report available to the applicant and public prior to the review body meeting, in association with the public meeting agenda and packet.
- F. **Notice.** Notice shall be provided for each application as indicated in Table 2-1, which shall provide the date, time, place of the meeting, and general information on the application including the location and type of application. Notices for concurrent projects may be combined into a single notice. Required notices shall meet the following requirements, in addition to the general agenda publication:
- 1. **Published.** Where published notice is required, at least 10 days prior to the public hearing or meeting, the Town Clerk shall publish the notice in the newspaper of general circulation.
  - 2. **Posted.** Where posted notice is required, notice shall be posted on the property or near the proposed site, visible to surrounding properties and the general public from adjacent public ways, according to the following:
    - a. The Director shall determine the number, type, and specific location of signs based on the context of the property.
    - b. The applicant shall ensure that signs are posted at least 10 days prior to the public hearing or meeting.





- c. The applicant shall make a reasonable, good faith effort to maintain posted notice throughout the proceedings.
  - 3. **Mailed.** The Town shall mail notice, as a courtesy, for applications as indicated in Table 2-1, including the date, time, place of the meeting; the general location of the subject property; the type or general nature of the application; and the location and contact where additional details may be found. Notice shall be sent by regular mail to the following, at least 10 days prior to the hearing or review meeting:
    - a. All property owners within 500 feet shown by the records of the county assessor;
    - b. For USR applications and other situations where the Director determines that additional notice may be appropriate due to the context or nature of the project, the distance for property owner notifications may be increased up to 2,000 feet.
  - 4. **Surface Development Notification.** Where mailed notice is required by state statutes for any project related to mineral estate owner identified on the county tax assessor's records or who has filed in the office of the county clerk and recorder a request for notification, the applicant shall be responsible for notice. The applicant shall certify to the Town that notice has been provided as required by this code and Colorado law prior to a public hearing, public meeting, or administrative decision.
  - 5. **Additional Hearing or Meeting Dates.** For any application where mailed or published notice is required by this code or Colorado law, and the reviewing authority adjourns or continues to the review to a certain date, time and location, no new notice shall be required.
  - 6. **Failure of Notice.** Any failure of published, posted, or mailed notice shall not invalidate any subsequent process or decision in the Director's discretion. In making this decision, the Director shall consider whether:
    - a. Good faith efforts were made to comply with notice, and the failure of notice was beyond the applicant's or Town's control;
    - b. Technical errors in the notice were made, but constructive and actual notice was available to all interested parties; or
    - c. The failure of notice is not otherwise instrumental to the proceedings, criteria, or record established for the decision.
- G. **Public Hearings.** Where public hearings are required by Table 2-1, the following procedures apply:
  - 1. The hearing shall be conducted, and a record of the proceedings shall be preserved.
  - 2. Any interested person or party may appear and be heard in person or by agent.
  - 3. The review body may request testimony or a report on the application from any government official or agency, or any other person with information pertinent to the application.
  - 4. A public hearing for which proper notice was given may be continued to a later date without again requiring notice provided in this section if the specific date, time and place of the continued hearing is announced at the original hearing.
- H. **Action by Review Bodies.** Review bodies shall take the actions indicated in Table 2-1. A review body may take any action on the application consistent with notice given or criteria in this Article, or recommend such action when the review body is a recommending body, including the following:



1. Approve the application.
  2. Approve the application, with conditions or modifications that make it more consistent with the standards and approval criteria.
  3. Deny the application, with specific reasons for the denial.
  4. Continue the application to allow further analysis. The continuation period shall not be more than 60 days from the original review without consent of the applicant.
  5. Remand the application back to staff for reprocessing, should the application lack sufficient quality or pertinent information to make a decision.
- I. **Appeals.** Where no appeal is designated in Table 2-1, the decision shall be final and only appealed as authorized by law. Any final decision made under this code by an administrative official may be appealed through an Administrative Appeal application according to 17-2-9 and Table 2-1. Where a review body is designated as the appellate body in Table 2-1, the following appeal procedures apply:
1. Appeals shall be filed with the Director within 15 days of the decision.
  2. Appeals shall identify the exact provisions in dispute and whether it is incorrect due to one or more of the following:
    - a. It was against the express standards of this development code;
    - b. It was an unreasonable interpretation or application of the standards or review criteria;
    - c. It was erroneous, based on the record and facts reviewed by the decision-making body; or
    - d. It was otherwise clearly contrary to law.
  3. The following persons and entities shall have standing to appeal the action of the review body:
    - a. The applicant;
    - b. The Town Manager, on behalf of any public official, department, or public body;
    - c. Any other person who was aggrieved and materially affected by the decision, and otherwise has a right to appeal by law.
  4. The appellate body shall consider the application based on the established record, within 60 days of a filed appeal. It shall give deference to the previous review body, but may take any action authorized by the decision-making body under this code if it determines that a clear error was made.
  5. The procedure and required notice shall be the same as required of the original application.
- J. **Technical Studies.** The Director, on behalf of any public official, department, or agency, the Planning and Zoning Commission, or the Town Council, may require applicants to submit technical studies necessary to evaluate the application. Technical review by outside entities with expertise or jurisdiction over some aspects of the application may be required in place of, in addition to, or in association with any studies. Examples of technical studies that may be required include traffic studies, infrastructure capacity and impact analysis, geologic, geotechnical or hydrologic studies, environmental impact and biological assessments, noise studies, market studies, or fiscal and economic impacts. The persons or firms preparing the studies may be subject to the approval of the Director. The costs of all studies shall be borne by the applicant. Any application that is determined to require technical studies or review from entities outside of the Town may require special schedules based on the reasonable time frames to conduct those studies or additional reviews.
- K. **Permits.** Upon final approval and completion of any conditions as specified for each application in this section, applicants may apply for all permits necessary to construct buildings, infrastructure, and site improvements. Permits necessary to show full compliance with the standards of this code, other applicable Town codes, or other agency requirements or laws may be required.



- L. **Successive Applications.** When the review body takes final action to deny an application, the same or a similar application shall not be refiled for one year from date of denial. The Director may permit a refiled of the application sooner than 1 year when it is determined that significant physical, economic or land use changes have taken place within the immediate vicinity, or where a significant text amendment to this code has been adopted that may affect the outcome of the action on the application. There shall be no time limitation on an application that the Director determines is substantially different from a previously denied application, when considering the proposed use, scale or intensity of development, and potential impacts on adjacent property.

**17-2-2 Platting**

- A. **Applicability.** Plat applications are required to design and coordinate streets, open spaces and other civic places with developable lots and buildings; to create lots and establish or alter the legal boundaries of a property; and to account for public facilities and services, infrastructure, development patterns, or other long-range growth and development considerations prior to potential fracturing of ownership. Plat applications shall be initiated by the property owner. Specifically, plat applications shall apply to:

1. Any division of land into more than one lot or parcel;
2. Any adjustment of previously platted lots that alter the legal boundaries or potential ownership patterns, other than those by operation of law, acquisition by a public entity, or by court order such as partition or quite title action; and
3. Any development on previously unplatted property.

- B. **Types of Plats and Applications.** Plat applications are classified and processed as one of two types:

1. *Minor Plats.* Minor plats are routine applications such as lot adjustments or land divisions that change legal boundaries but do not significantly alter overall development patterns or impact public services.
2. *Major Subdivisions.* Major subdivisions are all other land divisions or development impacting development patterns and intensity, rights-of-way, or infrastructure, which require a comprehensive review through preliminary plat and final plat procedures.

- C. **Minor Plat.** Minor plats shall be processed according to the following criteria and procedures.

1. *Eligibility.* The following situations are specifically eligible for minor plat processes:
  - a. The adjustment to legal boundaries of previously platted lots.
  - b. The consolidation of up to 4 previously platted lots into fewer lots.
  - c. The division of a previously platted lots into no more than 2 additional lots.
  - d. The division of previously unplatted land or of a platted tract into 4 or fewer lots.
  - e. A survey or other legal instrument to correct an error in the legal description, certification, or other element of an approved plat; to dedicate, vacate, or alter easements; or to confirm legal boundaries of lots in an approved plat that could only be determined post-construction.
2. *Review Criteria.* An application may be approved by the Director if the Director determines that all of the following are met.
  - a. No significant increase in service requirements (utilities, schools, traffic control, streets, etc.) or impact on the ability to maintain existing service levels will result.
  - b. The application does not alter any zoning district boundaries due to adjustments to any lots.



- c. All resulting lots meet the legal standards of the subdivision regulations and applicable zoning districts.
- d. The lot patterns are compatible with the surrounding area and any previously approved final plat for the subject property. In determining compatibility, the size and dimension of lots, the layout and design of existing subdivisions and rights of way, and the degree of deviation from previous development and the potential impact of this deviation on surrounding property shall be considered.
- e. Any dedication of right-of-way included in the plat is part of a planned street or required expansion of an existing street and is subject to acceptance by the Town Manager or may be further referred to the Town Council for acceptance of that right-of-way.
- f. No other significant issues exist with potential development enabled by the plat that could affect planning policies, undermine the application of other development regulations, or impact adjacent property owners.
- g. No prior administrative plat process created the lots being resubdivided, such that the proposed administrative plat and lots appear to circumvent the major subdivision process.

Any application not classified as an administrative plat or not meeting these criteria shall be processed as a major subdivision with a preliminary plat and final plat.

3. *Review Procedures.* In addition to the general requirements in Table 2-1 and Section 17-2-1, the requirements in this sub-section apply to administrative plat applications.
    - a. If the Director determines at any point in the process that the application is not eligible or appropriate for an administrative plat the Director may require that the application be processed as a major subdivision.
    - b. Any administrative plat that includes right-of-way or other public dedication shall be accepted by Town Manager or the Town Council by certification on the plat.
  4. *Effect of Decision.*
    - a. The applicant shall submit the approved administrative plat and all other required documents and certificates to the Town for execution.
    - b. The Town shall record the administrative plat and executed documents with the applicable county clerk and recorder.
    - c. The administrative plat shall become effective after recording.
- D. **Major Subdivision – Preliminary Plat.** Any subdivision not eligible as an administrative plat is a major subdivision that shall require approval of a preliminary plat. A preliminary plat shall be processed according to the following specific procedures.
1. *Applicability.* The preliminary plat provides detailed planning review of development patterns, street networks, block and lot layout, and the ability to meet public facility and utility requirements for future development, prior to preparation of detailed construction and engineering plans. The Director may allow a preliminary plat and final plat to be processed simultaneously, provided the submittal requirements and criteria for both applications can be met. For any application that is particularly complex, the Director may require the applicant to first submit a concept plan as discussed in Sec. 17-2-4 B.1 for public review by the Planning and Zoning Commission and Town Council prior to official submittal. Review of a concept plan shall not require any approval, but merely provides feedback and general consensus and provides the applicant direction for preparing a formal preliminary plat.
  2. *Review Criteria.* A preliminary plat shall be reviewed according to the following criteria.
    - a. The application is in accordance with the Comprehensive Plan, and in particular, the physical development patterns and concepts of the plan.





- b. The development and infrastructure are arranged in a manner to minimize impacts on geologic hazards, environmentally sensitive areas, wildlife habitat, or other natural features of the land.
  - c. The arrangement and proposed design of streets, open spaces, and blocks meet the development and design standards this Chapter and are coordinated with existing or potential development on adjacent property.
  - d. The proposed blocks and lots are capable of meeting all development and site design standards of the applicable zoning district.
  - e. The application demonstrates a preliminary feasibility of being able to meet the design, construction, performance, and maintenance requirements for all required improvements.
  - f. Any phasing is clearly indicated and demonstrates a logical and coordinated approach to development, and the timing, location, and construction of amenities is consistent throughout phases.
  - g. Any impacts identified by specific studies or technical reports, including a review of storm water, are mitigated with generally accepted and sound planning, engineering, and urban design solutions that reflect long-term solutions and sound fiscal investments.
  - h. The design does not impede the construction of anticipated or planned future public infrastructure or other development within the area.
  - i. The plat has addressed issues of professional staff or any other public entity or review agencies asked to officially review the preliminary plat and received positive recommendations.
3. *Review Procedure.* In addition to the general requirements in Table 2-1 and Section 17-2-1, the requirements in this sub-section apply to preliminary plat applications.
- a. At the pre-application meeting, and based on the size, scope and impact of any future development anticipated or pending with the request, the applicant shall propose how to coordinate the Neighborhood Meeting according to Section 17-2-1.D.
  - b. Any application that is particularly complex or involves significant planning and design issues, may be coordinated with a Rezoning in Section 17-2-3 or a Planned Development in Section 17-2-4 prior to or concurrent with an official submittal of a preliminary plat.
  - c. After review by staff, receipt of any comments from referral agencies, and any necessary resubmittal, the Director shall schedule review by the Planning and Zoning Commission.
  - d. The Planning and Zoning Commission shall hold a public hearing and make a recommendation to the Town Council on the preliminary plat.
  - e. After a recommendation by the Planning and Zoning Commission, the preliminary plat shall be scheduled for a public hearing at the Town Council for approval of the design concepts in the plat and acceptance of all public lands or proposed facilities.
4. *Effect of Decision.*
- a. The approval of the preliminary plat does not constitute an acceptance of the subdivision but authorizes preparation of the final plat.
  - b. An approved preliminary plat shall be effective for two years, except that any complete submittal of final plat for any phases indicated on a preliminary plat shall renew remaining portions of the preliminary plat. If a final plat is not submitted in that timeframe, the preliminary plat shall expire.
  - c. The Director may grant a one-year extension, if the applicant demonstrates substantial progress towards the design and engineering requirements necessary to submit a final plat



- E. **Final Plat.** After approval of the preliminary plat, the applicant may submit a final plat for all or for portions of the preliminary plat area subject to a phasing plan approved with the preliminary plat. A final plat shall be processed according to the following specific procedures.
1. **Review Criteria.** A final plat shall be reviewed according to the following criteria, as well as all criteria applicable to the preliminary plat review.
    - a. The layout and design of the final plat is substantially consistent with the approved preliminary plat considering the number and size of lots and outlots; the block layout, street designs and access; the open space systems and civic design elements; the infrastructure systems; or other elements of coordinated developments. Deviations made necessary due to the further detail in planning, design and engineering, and which meet the standards of this code, are generally considered “substantially consistent” with the preliminary plat.
    - b. The construction plans for any utilities, infrastructure, and public or common facilities meet all technical specifications.
    - c. All required improvements, dedications, fees, financial guarantees, and maintenance guarantees are provided.
    - d. The phasing and timing of required improvements ensures construction and performance guarantees. Any phasing that meets an approved preliminary plat is presumed acceptable. Any deviations of the final plats from an approved phasing plan shall not alter the timing or coordination of required improvements or amenities in the approved preliminary plat.
    - e. Deviations in the final plat from the approved preliminary plat may be considered where the change:
      - (1) Complies with all applicable zoning standards, subdivision design standards, and meets the intent and design objectives of those standards.
      - (2) Does not increase the impact of any development on required improvements beyond the capacity for required improvements identified in the preliminary plat;
      - (3) Does not impact any condition of the Planning and Zoning Commission or Town Council associated with the approval of the preliminary plat;
      - (4) Is generally consistent with development concepts in the preliminary plat in terms of land uses, scale, and intensity of development, and in no case changes the number of lots, dwelling units, buildings, or sizes of blocks and open spaces by more than 10 percent; and
      - (5) If technical studies were required with the preliminary plat, the author of the study shall submit an amendment noting that the change does not impact any findings of the study.
    - f. Any other changes to the preliminary plat, including significant changes in the phasing or dedication of public lands and rights-of-way, may require resubmittal of a revised preliminary plat.
  2. **Review Procedure.** In addition to the general requirements in Table 2-1 and Section 17-2-1, the requirements in this section apply to final plat applications.
    - a. The applicant shall identify all improvements to be constructed, either according to the required improvements listed in this code or by a specific agreement for the project. The applicant shall submit final plans and specifications for these improvements, and ensure construction of these improvements of financial guarantees as provided in Section 17-3-4.
    - b. Staff shall review the final plat for conformance with the planning and design elements, and the engineering specifications, and a final plat that meets these criteria shall be presented to the Town Council for acceptance.



- c. A final plat that does not meet these review criteria may require reprocessing as a revised preliminary plat.
  - d. The Town Council shall make a final decision on final plats based on these criteria, and may accept the dedication of any easements, rights-of-way, or other public lands on behalf of the Town.
3. *Effect of Decision.*
- a. The applicant shall submit the approved final plat and all other required documents and certificates to the Town for execution. Approval may be conditioned upon payment of all other applicable fees and execution of all applicable agreements prior to recording.
  - b. Once approved and all conditions are satisfied, the Town shall record the final plat and executed documents with the applicable county clerk and recorder.
  - c. The plat shall become effective after recording, and recording shall complete the Town’s acceptance of the dedication of land for public purposes indicated in the approved final plat.
  - d. A recorded plat may be modified through the same procedure used to approve the final plat unless it qualifies as a minor subdivision, or unless the changes are significant enough to require a new preliminary plat.
  - e. No substantial site construction may begin until all final plat documents are executed and recorded, applicable fees paid, and plans and agreements for required improvements are in place according to Section 17-3-4. A building permit shall not be issued until the completion, inspection, and acceptance of all required improvements, unless otherwise agreed to in writing with the Town.

17-2-3 Rezone

- A. **Applicability.** The rezone process provides review of changes to the boundary of zoning districts (rezoning) that may be necessary to implement the Comprehensive Plan, to account for changed conditions in the general area, or to reflect a change in policies with respect to future development. A minor modification to a zoning district to better align with final development configuration of lots and streets is also eligible for a rezone and may be initiated by the Town. Applications for a rezone may be filed by the property owner, the Town Council, or the Planning and Zoning Commission, or by Staff on behalf of these Town entities.
- B. **Review Criteria.** Review, recommendations, and decisions for a proposed rezone shall be based on the following criteria.
  - 1. The rezone furthers one or more of the purposes of these regulations in Section 17-1-3, and on balance any purposes that may be undermined are outweighed by the benefits of those purposes it furthers.
  - 2. The proposal is consistent with the goals and objectives of the Comprehensive Plan and any other plan, policy or guidance adopted pursuant to that plan.
  - 3. The change is consistent with the intent of the proposed zoning district, specifically considering:
    - a. the design of streets, civic spaces and other open space;
    - b. the pattern, scale, and format of buildings and sites; and
    - c. the compatibility and transition with other complementary uses and development in the vicinity.
  - 4. The change is necessary for at least one of the following reasons:
    - a. There has been a material change in the character of the area or in the Town generally, such that the proposed rezone is in the public interest.







17-2-4 Planned Development

A. Applicability. The Planned Development process is intended for innovative development concepts that require a higher degree of specific master planning due to the scale, novelty, or complexity of the project. It is a type of rezone, but is based on a specific and integrated development plan. This process affords flexibility in the standards to improve the relationship of the project to the context; to deliver greater community benefits; and to better meet the purpose, intent, and objectives of this code. Application for a Planned Development may be filed by the property owner, the Town Council or by staff on behalf of these Town entities.

- 1. Planning Thresholds. A development plan shall include sufficient area to implement planning concepts that generate broader public benefits only gained from flexible application of the standards, and not simply be used to justify deviations for single projects or on a site-specific basis. Typical applications include:
a. Large-scale planned communities that involve transitions in land uses, development patterns or intensity, or public and civic spaces;
b. Additions to previously approved PUDs if the flexible application of standards is used to integrate projects with previous plans;
c. Projects with a mix of uses that are not otherwise accounted for by one or a combination of the base zoning districts of the code;
d. Projects that need deviations to facilitate appropriate infill development or redevelopment of a site; or
e. Other similar public or community benefits determined by the Director.
2. Eligible Adjustments. Design and site elements that may be stipulated in a Planned Development, and vary from other sections of this Code include:
a. Modifications of building types and development standards, including lot sizes, setbacks, or heights.
b. Enhanced design specifications for buildings, open and civic space, streetscapes, or landscape that provide higher standards to execute a specific theme;
c. List of permitted or prohibited land uses and accessory uses;
d. Modifications to public streets and transportation-related infrastructure to specifically accommodate a transit-oriented development within 1/4 mile of a highway, interstate or transit corridor, or support more walkable and multi-modal patterns.
e. Any changes that can positively impact housing affordability based on a financial impact analysis and based on federal, state, or local guidelines relative to Area Median Income (AMI).

B. Development Plan. A Planned Development zoning application requires a specific plan for coordinated development of the entire area within the planned zoning boundary, and shall include the following:

- 1. Concept Plan. A Concept Plan is a plan the presents the overall vision for the project, and development strategies for applying the Comprehensive Plan and Future Land Use Map policies and principles to a specific area. A Concept Plan shall demonstrate:
a. Statements on the intent and objectives for the project, and how they meet the review criteria for PUD rezones;
b. Maps designating general land use categories and distinct areas of the plan;
c. Diagrams and maps identifying a general arrangement and character of streets and open spaces;
d. Graphics illustrating anticipated scale, intensity and character of development;
e. A comparative description of how the plan and proposed standards differ from implementation of strict standards of the development code.



- f. A list of commitments to planned amenities or design strategies that will deliver public or community benefits beyond what the base zoning district requires.
- 2. **Framework Plan.** A Framework Plan is a design plan for the development pattern, streets, and civic spaces that serve as organizing elements of the area and development projects. A Framework Plan shall demonstrate the following, and may serve as a preliminary plat to the extent it includes all elements in Section 17-2-2.D:
  - a. Outline any proposed streets, internal streetscapes, and access, and how they coordinate with the adjacent development patterns, street networks, and blocks;
  - b. Specify dimensions and design cross sections for streets and internal circulation, or identify types and classifications for all routes.
  - c. Indicate the location, function, size, type and other design characteristics of open and civic spaces – whether public, common, or private.
  - d. Propose any phasing or implementation strategy for projects that will be designed or permitted in stages, including the estimated timing and any other details of implementing the project through future final plats and site development plans.
- 3. **Regulating Plan.** A Regulating Plan becomes the zoning map for the specific project. It shall be based on the most comparable base zoning district(s), but specifically identify where development standards or uses may differ from those that would otherwise be applicable through the zoning district(s) and general development requirements of this code. It indicates the following:
  - a. The block and lot patterns, and where transitions in use or development intensity occur;
  - b. Specific land uses and their density/intensity. Including additions, subtractions, or other limitations from uses otherwise permitted in the base district;
  - c. The building and site design standards applicable for each distinct area; and
  - d. Any detailed plans, prototypes, renderings, elevations or other urban design and architectural specifications that can help expedite future development proposals through the site development plan process.

**C. Review Criteria**

- 1. **New Planned Developments.** Review, recommendations, and decisions for newly proposed planned development shall be based on the following criteria:
  - a. The plan implements the Comprehensive Plan to a demonstrated higher design and development standard than could be accomplished under application of general zoning districts and development standards.
  - b. Unique benefits to the community result from the flexibility in the proposed plan which elevate the general public health, safety and welfare of the community and surrounding areas, rather than flexibility to strictly to benefit the applicant or a single project.
  - c. The flexibility in the proposed plan allows the project to better meet or exceed the intent statements of the base zoning district(s).
  - d. The proposed adjustments to the standards do not undermine the intent or design objectives of those standards when applied to the specific project or site.
  - e. The plan reflects generally accepted and sound planning and urban design principles with respect to applying the goals and objectives of the Comprehensive Plan and the purposes of this code.
  - f. The plan meets the review criteria for a rezone in Section 17-2-3.B.
- 2. **Minor Amendment to PDs & PUDs.** Minor amendments to PDs under this code or PUDs approved under a prior code, may be approved by the Director, provided it meets all criteria or conditions for the initial approval, and is limited to the following:



- a. Any change in the number of housing units, change in lot sizes or dimensions, or increase the extent of non-residential uses is less than 5%.
  - b. There is no decrease in the amount of open space or other reduction of amenities from the approved plan.
  - c. Any change in the height or square footage of buildings is no more than 10% of the approved measurements.
  - d. Any change in a design standard meets the criteria for alternative compliance in Section 17-2-6.
  - e. Changes to the boundaries of any planning areas do not change the boundaries of the PUD, do not alter the mix of uses by more than 10% in land area or square footage, and otherwise reflect a similar land use plan.
  - f. The proposed change is consistent with concept plans in the previously approved planned unit development.
  - g. The plan otherwise meets all of the review criteria for site development plans in Section 17-2-5.
3. **Major Amendment to PDs & PUDs & Conversions.** Changes to previously approved PDs that exceed allowances for minor amendments, or conversions of PUDs approved under a prior code to the provisions of this code, may be proposed for a portion of the area under the following criteria:
- a. The plan proposes the most closely applicable base zoning district(s) for in terms of land use, development intensity, and building form and scale.
  - b. The proposed change is consistent with concepts or plans in the previously approved PUD or planned development.
  - c. The plan does not increase development beyond any capacity constraints or impact limits of the previous plan.
  - d. The proposed plan either meets the standards provided in this code and the conversion is to a base zoning district according to general standards, or where deviations from the base zoning districts or other standards of this code are requested, they are in closer compliance than is allowed under the prior PUD or planned development.
  - e. The plan meets all other applicable criteria and review process for a site development plan.
  - f. Any other changes that do not meet these criteria may only occur through the same process and criteria for a new planned development.
- D. **Review Procedure.** The following specific procedures supplement the general procedures in Section 17-2-1 and Table 2-1 applicable to planned developments:
- 1. The Planned Development process involves at least two steps:
    - a. The development plan establishing the zoning and any necessary deviations; and
    - b. Platting and site development plans for specific components of the development plan.

However, based on the complexity of projects and degree of advanced planning and urban design necessary for a project, the Director may require, or the applicant may elect, breaking the review of the elements of a development plan in sub-section B. into two or more steps to review Concept Plans and preliminary designs, Framework Plans and larger-scale planning and design, or the full development plan.
  - 2. The Planned Development application is a rezoning and shall follow the procedures in Section 17-2-3.C.
  - 3. In most cases, land will need to be subdivided in order to carry out a development plan. The platting process is a separate process but may run concurrently with the planned development process, as specified in Section 17-2-1.B.



- E. **Effect of Decision.** Approval of a planned development shall constitute acceptance of the overall planning concepts and development parameters, and may constitute additional rights as specified below.
1. **Concept Plan.** Approval of the Concept Plan reflects the approved land uses and density / intensity, and a commitment to planned amenities and design strategies. Independent of any corresponding approval of a Framework Plan or Regulating Plan, it serves as a more specific application of the Comprehensive Plan and Future Land Use Map policies and principles to the specific area, and reflects consensus that future development plans in accordance with the concepts should be approved.
  2. **Framework Plan.** Approval of a Framework Plan indicates that the basic development patterns and infrastructure concepts are agreed to in principle as conforming to the intent of the Comprehensive Plan and any other plans or policies created under the guidance of that plan. Approval of a Framework Plan may have the same effect as approval of a preliminary plat as specified in Section 17-2-2.D, provided it includes or is accompanied by information required for preliminary plats.
  3. **Regulating Plan.** Approval of a Regulating Plan shall have the same effect as a rezoning specified in Section 17-2-3.D. Sites governed by an approved Regulating Plan shall be designated on the Official Zoning Map with the letters of the proposed base zoning district plus “PD” (planned development). (For example, where a portion of the development plan uses the R-1, R-3 and the MU-NC base zoning districts, the zoning of each area of an approved regulating plan shall be R-1-PD, R-3-PD, and MU-NC PD respectively.)
  4. **Final Development.** Prior to applying for permits for final development, any project included as part of a Planned Development shall first require approval of a final plat and a site development plan as provided in these regulations. In addition to all other information and criteria required for those applications, submittals under an approved Planned Development shall demonstrate that all applicable standards, requirements, and conditions of the development plan have been met.
  5. **Duration of Plan.** A Planned Development shall lapse and be of no further force and effect if a final plan (all of applicable final plats or site development plans) for specified phases has not been approved within three years of the date of approval of the development plan. Approval of final plans for a portion of the plan shall renew this period. The Town Council may approve an extension of a development plan for up to three additional years. The Town and applicant through a development agreement or approved phasing plan may establish timelines different from this section.

### 17-2-5 Site Development Plan

- A. **Applicability.** The site development plan process ensures that development projects meet the development and design standards of this code, and all other standards applicable to the property. It coordinates development projects with the public realm design and with adjacent sites, including streetscape design, compatible arrangement of buildings, pedestrian and vehicle access, site design, lighting, and landscaping. Site development plans may be initiated by the property owner.

The site development plan process specifically applies to any of the following:

1. All new non-residential development, mixed-use development, or residential development with multi-unit building types.





2. Any development or site improvements in a PD zoning district or a PUD approved under a prior development code.
3. New detached houses or multi-unit houses where 3 or more buildings are proposed.
4. Expansion or alterations to an existing multi-family or non-residential building that alter the footprint, massing or facade design
5. A change of use that is potentially more intense than the existing use, or that could otherwise trigger associated site development activity, such as parking, access, landscape, or screening.
6. Any site development activity that expands the existing impervious surface.
7. Any changes to the site access and circulation, or other development requirements that significantly impact streetscape design or existing traffic conditions near the site.
8. The Director may require abbreviated site development plans or other improvement plans for any other development necessary to demonstrate zoning compliance prior to permitting.

A pre-application meeting is recommended to clarify the scope of the project or changes to a site, and thereby best determine the needed submittal materials.

- B. **Review Criteria.** In general, any site development plan in compliance with all applicable standards of this code shall be approved. In making a determination of compliance with the standards applied to a particular project and site, the following criteria shall be considered:

1. *Generally.*
  - a. The plan meets all applicable standards or the criteria for any discretionary approvals.
  - b. The plan does not substantially undermine any goals or objectives of the Comprehensive Plan that are applicable to the area or specific project.
  - c. The plan does not present any other apparent risks to the public health, safety or welfare of the community.
  - d. The application is consistent with or meets the intent of all prior approvals and conditions associated with the project.
  - e. The plan does not directly conflict with the intent or design objectives of any applicable standard in this code.
  - f. The application can reasonably be assumed to meet the criteria for all subsequent permits and reviews needed to build the project as proposed.
2. *Site Design and Engineering.*
  - a. The plan provides safe access and internal circulation considering the site, the block and other surrounding connections, and appropriately balances vehicle, bicycle and pedestrian needs for the context.
  - b. The plan provides or has existing capacity for utilities and other required improvements to serve the proposed development.
  - c. The plan provides adequate management of storm water runoff.
  - d. The plan provides proper grading considering prevailing grades and the relationship to adjacent sites.
3. *Landscape and Open Space Design.*
  - a. The plan creates an attractive aesthetic environment and improves relationships to the streetscape or other nearby public, civic or common spaces.
  - b. The plan enhances the environmental and ecological functions of un-built portions of the site and makes effective use and conservation of water resources.
  - c. The plan reduces the exposure and adverse impact of more intense activities or components of the site or building on the streetscape and on adjacent properties.



4. **Building Design.**
    - a. The location, orientation, scale and massing of the building creates appropriate relationships to the streetscape and to adjacent properties.
    - b. The selection and application of materials will promote proper maintenance and quality appearances over time.
    - c. The building reinforces the character of the area and reflects a compatible architectural relationship to adjacent buildings. Specifically, if there is any consistency or commonality in the scale, proportion, forms and features, and materials of adjacent buildings, they inform choices on the proposed building.
- C. **Review Procedure.** In addition to the general requirements in Section 17-2-1 and Table 2-1, the following requirements are specific to site development plan applications:
1. The Director shall review the application and determine if the review of any other department or agency is required.
  2. At the applicant's discretion, and as part of the pre-application steps, the applicant may present a preliminary sketch or Concept Plan for review by staff or the Planning and Zoning Commission and Town Council. This may be used to confirm interpretations, test basic concepts and standards, or review options for a proposed project.
  3. For any application that presents significant interpretation issues regarding the standards and criteria, proposes substantial land use change, or is of a scale and intensity that may impact surrounding properties in a manner different than existing development in the area, the Director may require a Concept Plan or that the site development plan be reviewed and approved by Planning and Zoning Commission, and may require notice or meetings with potentially impacted property owners and residents.
  4. Applications associated with another application may be approved with a condition on final approval of the associated application. The site development plan shall be noted in the associated application and either affirmed or denied by the review body according to the criteria of the associated application.
  5. The Director shall make the final decision on site development plans, and the decision may be appealed to the Planning and Zoning Commission. For development plans that include a substantial impact to public infrastructure, traffic patterns and the transportation networks, or other impacts that may require additional review and consideration, the Director may refer this project for Full Review with the Planning & Zoning Commission and Town Council for final determination.
- D. **Effect of Decision.**
1. Approval of a site development plan shall authorize the applicant to apply for a building permit and other applicable permits.
  2. Approval of a site development plan shall be valid for one year unless some other period is stated on the approval or any other associated application. The Director may grant a 1-year extension provided no conditions, standards, or policies affecting the application have changed.
  3. The Director may approve minor amendments to any site development plan, provided the changes do not:
    - a. Increase the proposed residential density by more than 5%, or the non-residential floor area by more than 10%.
    - b. Increase the building footprint by more than 5%.
    - c. Increase the building height by more than 10%.
    - d. Increase the impervious surface by more than 10%.
    - e. Change the design of the plan to substantially and negatively alter:
      - (1) pedestrian or vehicle access;
      - (2) relationships of constructed elements to adjacent property;
      - (3) landscape and open space designs; or



- (4) the architectural appearance of buildings.
- f. In all cases the change meets all applicable development standards for the site and does not negatively impact any criteria or conditions of the original approval.
- 4. Any site development plan where permits are not issued prior to a lapse, or any other changes are proposed, shall require a new application.

### 17-2-6 Alternative Compliance

A. **Applicability.** The alternative compliance process provides limited flexibility to design standards so that the best design solution may be applied to a particular context or site. It ensures that projects meet the intent and design objectives of the standards of this code and allows for relief from strict application of the standards where an equal or better design solution is possible. Alternative compliance shall not undermine requirements of this code, but provides equivalent alternative designs or standards applied in a site-specific or creative way. Alternative compliance applications may be initiated by the property owner.

Specifically alternative compliance shall be applicable for any of the following:

- 1. Street design standards in Section 17-3-1.
- 2. Open space design standards in Section 17-3-2.
- 3. Residential development and design standards in Sections 17-5-2 and 17-5-3;
- 4. Non-residential design standards in Sections 17-6-2 and 17-6-3;
- 5. Access and parking standards in Article 7;
- 6. Landscape & site design standards in Article 8; and

B. **Review Criteria.** The following criteria apply to any application that is proposing alternative compliance to any of the eligible standards.

- 1. Specific conditions, configurations, or context of the site make strict compliance with the standard impractical, or meeting the standards would clearly not advance the intent or design objective of the standard.
- 2. The proposed alternative equally or better meets the intent or design objective of the standards and is not used to avoid appropriate application of the code standards.
- 3. The alternative does not undermine any other standards or create additional negative impacts on adjacent sites.
- 4. The alternative shall not alter any standard in a manner that permits a use that would otherwise be prohibited.
- 5. The alternative is not strictly for the convenience of a specific project, but is justified under any of the following broader community benefits:
  - a. Aesthetic considerations that permit better coordination of the lot and building with the established character of the specific area;
  - b. Improved environmental performance;
  - c. Enhanced pedestrian or bicycle accommodations, or better civic space design;
  - d. Adaptive reuse of an existing building, additions to an existing building, or infill on an existing lot that accommodates development comparable to that on adjacent property;
  - e. Better serves public health and safety considerations.
- 6. The deviation is the minimum necessary to address the circumstance or context.

C. **Review Procedures.** In addition to the general requirements in Section 17-2-1 and Table 2-1, the following requirements are specific to alternative compliance applications:

- 1. Applications shall be submitted with a written narrative explaining the rationale for the request and an accompanying site development plan demonstrating the request. Collectively these shall demonstrate:



- a. Required standard;
  - b. Why the required standard is not practical;
  - c. The proposed standard or alternative solution; and
  - d. How the proposed standard or alternative is an improvement.
2. Alternative compliance associated with an application that requires approval of another review body may be approved by the Director conditioned on final approval of the associated application. The alternative compliance shall be noted in the associated application and either affirmed or denied by the review body according to the criteria of the associated application.

**D. Effect of Decision.**

1. Approval of alternative compliance shall be indicated by a written statement of the Director, which shall be submitted with and clearly noted on any subsequent submitted plans or permit applications. It shall authorize deviation from the standards only to the extent demonstrated on the approved plans.
2. The approval shall only be valid for one year from the written statement, or for the time period of any associated or subsequent approved plans or permits.
3. Denial of an alternative compliance request may be appealed as provided in Section 17-2-9, Appeals of Administrative Decisions.

### 17-2-7 Use by Special Review

- A. **Applicability.** A use by special review provides flexibility for different uses within a zoning district and allows the potential for additional uses subject to specific conditions. These uses are not generally appropriate throughout the district, but due to the design and operational characteristics of particular application of the use, or due to conditions in the area where the use is proposed, may be appropriate based on a case-specific review. Uses by special review may be initiated by the property owner for those uses as indicated by the Use Table in Section 17-4-2.
- B. **Review Criteria.** A use by special review shall be reviewed according to the following criteria:
1. All criteria for site development plan review in Section 17-2-5.B. are met, including any conditions or additional requirements identified in this code for the particular use.
  2. The application furthers the intent of the proposed zoning district and is otherwise determined to be consistent with the Comprehensive Plan.
  3. Compatibility with the area and other allowed uses in terms of operating characteristics such as hours of operation, visible and audible impacts, traffic patterns and parking demands, intensity of buildings and activity on the site, and other potential impacts on adjacent property.
  4. The long-range plans applicable to the site and surrounding area are not negatively impacted considering the permanence of the proposed use, the permanence other uses in the area, potential future uses, and any changes in character occurring in the area.
  5. Whether a limited time period for the permit is reasonably necessary to either limit the duration of the use, assess the use against changing conditions in the area, or require periodic reporting or review of the permit.
  6. The recommendations of professional staff or other technical reviews associated with the application.
  7. Whether any additional site- or use-specific conditions are necessary to meet these criteria.
- C. **Review Procedure.** In addition to the general requirements in Section 17-2-1 and Table 2-1, the following requirements are specific to use by special review applications.





1. Applications may be accompanied by site development plan where it is necessary to review conformance with standards of this code and any performance criteria for the particular use.
2. The Planning and Zoning Commission shall hold a public hearing and shall make a recommendation to the Town Council. Upon a recommendation from the Planning and Zoning Commission, the Town Council shall review the application and make the final decision on the use by special review.

**D. Effect of Decision.**

1. All approved plans and conditions associated with a use by special review shall be recorded with the applicable county clerk and recorder.
2. Approval and recording of a use by special review shall authorize the applicant to apply for a building permit and other applicable development or construction permits.
3. Approval of a use by special review shall be valid for one year, and the Director may grant a one-year extension, provided no applicable standards or conditions have changed. Any application not acted upon according to the approval and conditions within this period shall be void. (This period requiring action on an approved use by special review is distinct from any condition limiting the duration of the permit.)
4. A use by special review may be revoked or modified with additional conditions by the Town through the same procedures approving the permit, upon a finding that the conditions of approval have not been met, or that the use has otherwise violated the provisions of this code.
5. Minor changes to an approved use by special review may be approved by the Director limited to the following:
  - a. A change of ownership provided all conditions and criteria of the permit are met, and provided the new owner demonstrates the likelihood to continue to comply with all standards.
  - b. Any change to any associated site development plan provided it meets the minor amendment criteria, and does not violate any required conditions of the approval.
  - c. A change in operations that is otherwise determined by the Director to not have a significant impact on any adjacent property and is otherwise consistent with the criteria and conditions for approval of the original use by special review.
  - d. Any other change shall require an amendment to the use by special review through the same process as the original approval

### 17-2-8 Variance

- A. Applicability.** A variance is a process to provide relief from a strict interpretation of the zoning and site design and development standards of this code, which when applied to a particular property and in a specific context would create practical difficulties or unnecessary hardship on all reasonable use of the property. This application shall only apply to the design, dimensions and other site development standards of this code and shall not be used to authorize a use that is prohibited by the applicable zoning district. Variances may be initiated by the property owner.
- B. Review Criteria.** A variance shall be reviewed and approved only on the finding that all of the following conditions are met:
1. Unique physical conditions not ordinarily found in the same zoning district, and that are not created by the property owner deprive the owner of privileges enjoyed by other property in the vicinity and in the same zoning district;
  2. The strict application of the regulations constitutes an unnecessary hardship upon the property owner, hindering reasonable uses of the property. Economic considerations



- alone shall not constitute an unnecessary hardship if a reasonable use for the property exists under the standards of this code;
3. The granting of the variance will not adversely affect the rights of adjacent property owners or residents;
  4. The variance desired will not adversely affect the public health, safety, or general welfare;
  5. Granting the variance would not alter the essential character of the surrounding neighborhood, and the general spirit of the ordinance and intent of the standards will be maintained; and
  6. The requested variance is the minimum necessary to relieve the conditions and permit reasonable use of the property.
- C. **Review Procedures.** In addition to the general requirements in Section 17-2-1 and Table 2-1, the following requirements are specific to variance applications:
1. The concurring vote of a majority of the membership of the Board of Adjustment shall be necessary to grant a variance.
  2. In granting a variance, the Board of Adjustment may impose conditions and requirements that best assure the criteria for approval are in place and maintained, and any violation of these conditions shall be considered a violation of the ordinance.
  3. The Board shall issue all decisions in writing, including the grounds for its decision based on findings of fact regarding each criterion, within 30 days after the decision has been made at a public hearing.
- D. **Effect of Decision.**
1. An approved variance shall become effective when recorded with the applicable county clerk and recorder. Upon recording the applicant may proceed with any necessary approvals or permits authorized in the variance.
  2. A variance shall run with the land to extent the zoning of the subject property remains in place.
  3. Any decision not acted on within one year of the decision by the Board shall expire.
  4. Any person aggrieved by a final decision of the Board of Adjustment may appeal the decision to the district court within 30 days of the Board's vote on the final decision.

### 17-2-9 Appeal of Administrative Decision

- A. **Applicability.** The appeal process is to determine if there was an error in a final decision made under this code. There are two types of appeals:
1. *Applications.* An appeal of a final decision on a development application in Table 2-1 which shall be made according to the appeal process specified for that application.
  2. *Administrative Decisions.* An appeal of a final administrative decision made under the authority of this code, which shall require the filing of an Administrative Appeal application according to Table 2-1 and this section.
- All appeals shall follow the standards and criteria in Section 17-2-1.I.
- B. **Criteria.** An administrative appeal shall be reviewed according to the following criteria:
1. The Board of Adjustment shall grant the administrative official's decision a presumption of correctness, placing the burden of persuasion of error on the appellant.
  2. An appeal shall be sustained only upon findings, supported by the record, that the official was in error.
  3. In deciding on an appeal, the Board shall have all powers of the official from whom the appeal is taken, and the Board may reverse, affirm wholly or partly, remanded the



decision back to the administrative official with instructions, or modify the decision being appealed.

- C. **Review Procedures.** In addition to the general requirements in Section 17-2-1 and Table 2-1, the following requirements are specific to administrative appeal applications:
1. Notice of the administrative appeal shall be served upon the person whose decision is being appealed by providing a copy of the appeal. The administrative official whose decision is being appealed shall transmit all plans, applications and other files directly impacting the decision to the Board within 30 days of filing.
  2. An administrative appeal stays all proceedings in furtherance of the action appealed from unless the official from whom the appeal is taken certifies to the Board after the notice of appeal that a stay could cause imminent peril to life or property. In such case, proceedings shall not be stayed other than by a restraining order which may be granted by the Board or by a court of record on application, on notice to the officer from whom the appeal is taken and on due cause shown.
  3. The concurring vote of a majority of the membership of the Board of Adjustment shall be necessary to overturn or modify an administrative decision.
  4. In deciding on an appeal, the Board of Adjustment may impose conditions and requirements that best assure the criteria for approval are in place and maintained, and any violation of these conditions shall be considered a violation of the ordinance.
  5. The Board shall issue all decisions in writing within 30 days of the hearing, including the grounds for its decision based on findings of fact.
- D. **Effect of Decision.**
1. An approved appeal shall become effective when decided upon and issued in writing.
  2. An approved appeal shall be kept on file with the Town and guide all future decisions on the same issue, and in the same or similar situations, unless limited by the terms of approval or unless modified by an ordinance amendment.
  3. Any person aggrieved by a final decision of the Board of Adjustment may appeal the decision to the district court within 30 days of the Board's vote on the final decision.

### 17-2-10 Text Amendments

- A. **Applicability.** Text amendments to these regulations may be initiated by the Town Council or the Planning and Zoning Commission, or by Staff on behalf of these entities.
- B. **Review Criteria.** A text amendment shall be reviewed according to the following criteria:
1. The amendment furthers the purposes of these regulations.
  2. The amendment is in accordance with the Comprehensive Plan and has been considered for both its long-range affects as well as immediate impacts.
  3. The amendment promotes the public safety, health and general welfare of the community in the Town of Johnstown.
  4. The amendment improves the effectiveness and efficiency of administering the Development Code.
- C. **Review Procedures.** In addition to the general requirements in Section 17-2-1 and Table 2-1, the following requirements are specific to text amendment applications:
1. Applications may be accompanied by a related Comprehensive Plan amendment, or more specific plan, provided that amendment or plan has met all of the legal and policy requirements for plan approvals independent of the proposed text amendment.



2. The Town Council may recommend the application be returned to Planning and Zoning Commission for further study or additional information at its next regular meeting. Failure by the Planning and Zoning Commission to consider or revise its recommendation shall be considered a resubmission of its original recommendation.
  3. The Planning and Zoning Commission may recommend or Town Council may approve a lesser change than was proposed in the notice, when considering the proposed change relative to the currently applicable standards.
- D. **Effect of Decision.** Amendments to the text of these regulations shall be approved by the Town Council in the form of an ordinance and be effective after the date specified in the ordinance. The Director shall incorporate approved amendments into this code by reference to the specific amending ordinance, indicating the newly applicable provisions and any replaced provisions, or by recodification of the official code that incorporates the approved amendment.

### 17-2-11 Vested Property Rights

- A. **Applicability.** The following applications may be considered “site-specific development plans” which establish a vested property right upon any approval or conditional approval according to the procedures and criteria of this code. establishes the right to undertake and complete development according to a “site specific development plan” as defined by this code to meet the requirements of C.R.S. Article 68 of Title 24. A “site-specific development plan” shall mean final approval and the applicant’s acceptance of conditions of any of the following types of applications:
1. Site Development Plan
  2. Administrative Plat
  3. Final Plat
  4. Other elective applications at the request of a property owner and subject to the discretion of the Town Council.
- B. **Review Criteria.** The review criteria for a vested property right shall be the same criteria as the associated application. In addition, when the Town Council is considering a request to vest any other property right or development approval, it shall consider the following additional criteria:
1. The level of planning, urban design, or engineering investment that was necessary for the applicant to reach this point in the application.
  2. The extent of details included in the proposal, the certainty associated with future development, and the extent of future reviews that may be necessary to advance the project to construction.
  3. The context of the property and the likelihood of future changes in the surrounding area that could impact the project.
  4. Any other aspect of public health, safety, and welfare.
- C. **Specific Procedures.** In addition to the general requirements in Section 17-2-1 and Table 2-1, the following requirements are specific to vested right applications.
1. **Notice & Hearings.** The statutory notice and hearing requirements shall be satisfied as follows:
    - a. **Final Plats.** For final plats, the notice and public hearing to consider the preliminary plat before the Planning and Zoning Commission provided the Commission shall indicate that such vested right shall only be created upon approval of the required final plat by the Town.





- b. *Site Development Plans.* For site development plans, which are approved by the Director or Planning & Zoning Commission, a separate hearing before the Town Council following the decision. The applicant shall request a vested right hearing within 30 days following the approval of the site development plan, or the right to request such a hearing shall be waived.
        2. *Plat or Plan Language.* Each site-specific development plan shall contain the following language: "Approval of this plan [or plat] creates a vested property right subject to all conditions of approval pursuant to C.R.S. Section 24-68-103 et. seq., as amended. The effective date of vesting is [insert date]."
        3. *Publication.* Approval of a vested right shall be published in a newspaper of general circulation within Johnstown within 14 days of the Town Council decision advising the public of the site-specific development plan and approval of a vested right.
- D. **Effect of Decision.**
  1. Final approval of a site-specific development plan shall create a vested right to undertake and complete development and use of real property pursuant to Colorado Statutes, but only as to those terms and conditions contained in the approved site-specific development plan.
  2. The review and approval of a vested property right in a site-specific development plan shall not prevent the Town, in subsequent actions, from applying any of the following to the subject property:
    - a. New ordinances, rules, regulations, standards, and policies that do not conflict with those in effect as of the site-specific development plan's effective date of approval;
    - b. New ordinances, rules, regulations, standards, and policies that are specifically anticipated and provided for in the terms or conditions of the approved site-specific development plan;
    - c. New ordinances, rules, regulations, standards, and policies that are necessary for the immediate preservation of the public health and safety, whether adopted while a complete application is pending or after the decision; or
    - d. New ordinances, rules, regulations, standards, and policies when the Town finds that the site-specific development plan is based on substantially inaccurate information supplied by the applicant.
  3. A vested property right shall remain vested for 3 years from the publication date of the decision unless a longer term is agreed to by the Town in a development agreement. An amendment to any site-specific development plan shall not extend the period of vested rights, unless otherwise authorized by agreement approved by the Town.
  4. A landowner may waive a vested property right by separate agreement, which shall be recorded in the office of applicable county clerk and recorder. Unless otherwise agreed to by the Town, any landowner requesting annexation to the Town shall waive in writing any pre-existing vested property rights as a condition of annexation.
  5. Any violations of the approved plan, or any failure to comply with conditions of approval shall result in forfeiture of the vested property right.
  6. The Town Council may revoke the vested property right through the same procedures as the original plan approval, and after providing at least 14 days written notice to the property owner and original applicant.

## 17-2-12 Annexation & Establishment of Zone District(s)

- A. **Applicability.** The annexation process is to add unincorporated areas to the Town. The process considers logical extensions of the boundaries, sets the conditions for well-ordered development,



and provides efficient and effective extension of municipal services and facilities. Annexation applications may be by petition of the landowners or at the initiation of the Town Council.

**B. Review Criteria.**

1. **General Eligibility.** The Town Council may consider an annexation petition for land that satisfies the eligibility requirements of the statutes of the state as follows:
  - a. The area proposed for annexation has not less than one-sixth of its perimeter contiguous with the municipal boundaries.
  - b. A community of interest exists between the area proposed for annexation and the Town; the area is urban or will be urbanized in the near future; and the area is integrated with or is capable of being integrated with the Town.
  - c. The full width of all public rights-of-way adjacent to a proposed annexation shall be included in the annexation.
  - d. Any land in single ownership that would be divided by the proposed Town boundary shall require consent of the landowner.
  - e. The responsibility to apply for exclusion from any applicable special districts or school districts shall be upon the applicant of the annexation.
  - f. All other state statute requirements are satisfied.
2. **Specific Criteria.** The Planning Commission and Town Council shall evaluate annexations according to the following criteria:
  - a. The proposed annexation is in conformance with the Town's Comprehensive Plan in terms of future growth, development patterns and intensity, and proposed or anticipated land uses.
  - b. Adequate services are or will be available to support the development expected to result from the proposed annexation, in accordance with Section 17-3-4.
  - c. The proposed annexation provides for a continual and rational boundary Town.
  - d. The proposed annexation accommodates reasonable anticipated growth and future land use needs.

**C. Review Procedures.** In addition to any specific procedure required by the laws of the state at the time of annexation, and in accordance with the general procedures applicable by Section 17-2-1 and Table 2-1, the following specific procedures apply to annexations:

1. **Petition for Annexation.** The petition shall be signed by persons comprising more than 50% of the landowners in the area and owning more than 50% of the land area.
2. **Annexation Elections.** As an alternative to an annexation petition, the qualified electors of the area being proposed for annexation may petition the Town Council to hold an annexation election.
  - a. The petition for annexation election shall be signed by at least 75 qualified electors or 10% of the electors, whichever is less, or as otherwise required by state statutes.
  - b. The petition shall be filed with the Town Clerk and shall comply with the provisions of the state statutes.
  - c. If the petition for annexation election is in substantial compliance with state statutes, the Town Council shall call for an election to be held. Notice of such election shall be given by the Town Clerk.
  - d. If a majority of the votes cast are against annexation, or the vote is tied, the annexation proceedings to date will be voided and considered of no effect and the Town Council shall proceed no further with the annexation proceedings.
  - e. If a majority of the votes cast at the election are for annexation, the Town Council may thereafter annex the area.



3. **Town Annexation.** As an alternative to an annexation petition or election, the Town may initiate annexation of any property that is entirely surrounded by Town boundaries for more than three years, or which is owned by the Town.
4. **Application.** Application form and related application fees, including all additional plans and details required on the forms shall be provided by the applicant.
5. **Request for Zoning.** The applicant shall submit a request for zoning in accordance with this section and Section 17-2-3, Rezoning or Section 17-2-4, Planned Development. The Director shall conduct an analysis of existing land uses on the subject property to ascertain zoning and lawfully established nonconforming uses. Nonconforming uses shall be permitted to continue as provided in Section 17-1-7.
6. **Staff and Agency Review.** The Director shall coordinate review of an application with all necessary reviewing agencies, and allow them two weeks from the date of distribution of the annexation plat and supporting documents to make any objections or comments to the Director. This time period may be extended to the minimum period needed to complete the review.
7. **Resolution to Consider Annexation.** The Town Council shall determine eligibility and whether to proceed with annexation of property by resolution. The resolution shall include the dates of any required public hearings, any other corresponding review procedures, and determine if an annexation agreement will be required.
8. **Annexation Impact Report.** For annexations of areas larger than ten acres, the Town shall prepare an impact report concerning the proposed annexation. The report shall be prepared at least 25 days prior to the date of the Town Council's hearing on the proposed annexation, and a copy of the report shall be filed with the Board of County Commissioners governing the area proposed to be annexed within five days after preparation of the report. The annexation impact report shall contain the following information at a minimum:
  - a. A map or maps of the municipality and adjacent territory to show the following:
    - (1) The present and proposed boundaries of the Town in the vicinity of the proposed annexation;
    - (2) The present streets, major trunk water mains, sewer interceptors and outfalls, other utility lines and ditches and the proposed extension of such streets and utility lines in the vicinity of the proposed annexation; and
    - (3) The existing and proposed land uses in the areas to be annexed.
  - b. A copy of any draft or final annexation agreement, if available;
  - c. A statement on plans of the Town for extending and providing municipal services at the time of annexation;
  - d. A statement on the method to finance the extension of the municipal services into the area to be annexed;
  - e. A statement identifying existing districts within the area to be annexed; and
  - f. A statement on the effect of annexation upon local public school district systems, including the estimated number of students generated and the capital construction required to educate students.
9. **Planning & Zoning Commission Hearing.** The Planning and Zoning Commission shall hold a public hearing and make a recommendation to the Town Council based on the criteria in this section. Annexation of property owned by the Town does not require a hearing and may be approved by the Town Council by ordinance.



- 
10. **Town Council Hearing.** The Town Council shall hold a public hearing and make any decision authorized by this code or the Colorado Statutes. The Town Council may approve the annexation by ordinance subject to the criteria in this section. Annexation of property owned by the Town does not require a hearing and may be approved by the Town Council by ordinance.
- D. **Effect of Decision.** If the annexation is approved, the Director shall cause a copy of the signed annexation plat to be recorded in the appropriate county clerk and recorder's office.
1. **Effective Date.** The annexation shall be effective upon filing of the annexation ordinance and map with the county.
  2. **Development Plans.** The Town may approve a Development Plan per Section 17-2-4 or other land use or development concept plan per Section 17-2-3, in association with annexation and prior to the effective date of the annexation and zoning.
  3. **Zoning.** Annexed areas shall be included in the Town's zoning ordinance and map within 90 days after the approval of an annexation ordinance. The Town shall consider zoning such newly annexed areas under the appropriate zoning category as follows:
    - a. If land use approval or development of areas being considered for annexation is not pending upon completion of annexation, if the subject property is in a transitional state regarding development, or if it is in the best interest of the Town, the Town Council shall place the newly annexed property into the H-A Holding Agriculture Zoning District.
    - b. Requests for zoning districts other than the H-A Holding Agriculture District may be considered by the Town Council in conjunction with the annexation and based on the submittal of all applicable requirements for a rezoning application. The Town Council shall place the newly annexed property into the most appropriate zoning district, considering the goals and objectives of the Town's Comprehensive Plan and the applicant's future development plans.
    - c. During the time in which zoning of newly annexed areas takes place, the Town may refuse to issue any building or occupancy permit for any portion or all the newly annexed area.
  4. **Annexation Agreements.** The Town may otherwise coordinate the effective date of annexation, future development plans, required improvements and capital planning, and application of zoning through a specific annexation agreement.





---

## Article 3. Subdivision, Development, & Community Design

- 17-3-1 Streets
  - 17-3-2 Open & Civic Space
  - 17-3-3 Blocks & Lots
  - 17-3-4 Required Improvements & Dedications
  - 17-3-5 Community Facilities & Fees
- 

### 17-3-1 Streets

- A. **Intent.** The intent of the street design standards is to:
1. Emphasize street design as a key determinant of Johnstown’s community image and unique identity.
  2. Ensure the proper arrangements of blocks and lots that coordinate with long-term growth and development of the community.
  3. Plan street networks to connect to adjacent development and future development areas at regular intervals and avoid overloading traffic on regional or arterial streets that become barriers.
  4. Build complete and multi-modal networks of small, well-connected streets, trails and paths to improve the access, capacity, safety and efficiency of transportation systems.
  5. Use street design to call attention to differing contexts within the Town, and to better support development patterns and uses abutting the streets.
  6. Design streets to account for all potential users of the streets, including pedestrians, bicycles, automobiles, trucks, and transit.
  7. Integrate open and civic spaces with street networks and designs to establish a valuable public realm.
  8. Coordinate and integrate individual sites into the design of the community, including existing and planned future development in the area.
- B. **Street Network.** Arterial, collector, neighborhood connector, and local streets shall be laid out according to the Town’s planning and Development Standards for development, streets, and open spaces. In the absence of more specific or updated guidance in these plans or for a specific area, the following standards shall apply to street networks:
1. *Blocks and Connectivity.* Streets shall be laid out to provide a network of streets and blocks based on the planning context and development pattern as identified in Table 3-1:



Planning Context	Block Size	Closed-End Street Limits
<b>Downtown, Walkable Commercial. &amp; Mixed-Density Neighborhoods</b> <i>Downtown, near downtown areas, walkable commercial areas, primarily in the Activity Centers, High Density/Intensity areas or other commercial nodes, mixed-use, or mixed density neighborhood transitions to these areas. where walkable patterns and multi-modal routes are planned.</i>	150' min. 500' max. 4 ac. max.	Per Exceptions in B.2 only
<b>General Neighborhoods &amp; Non-residential</b> <i>Walkable mixed-density and suburban neighborhoods and other areas supporting commercial corridors or employment areas outside walkable centers, primarily in the Moderate and Low Intensity / Density areas.</i>	250' min. 800' max 7 ac. max	Per Exceptions in B.2 only.
<b>Campus, Rural, or Remote Areas</b> <i>Limited to areas where large-scale uses with internal circulation or low intensity / density uses with limited circulation needs, where disrupting the development patterns and street network is justified, typically in the Very Low Density / Intensity or Greenway areas.</i>	250' min. 1,320' max. 10 ac. max.	600' max.



**Figure 3-1 Connectivity & Block Sizes.** Street networks shall be based on maximum block sizes (length between centerlines of perimeter streets and area) and stub to adjacent property at a frequency sufficient to create connected networks unless exceptions justify not connecting.

2. **Exceptions.** Blocks may only exceed the acre or block length maximums in Table 3-1, or provide alternative designs and connectivity, based on the following are exceptions:
  - a. **Natural Features, Open Spaces or other Civic Spaces.** Blocks or parcels abutting or containing important natural features, topographical constraints, or open



- b. *Regional Transportation Routes.* Blocks or parcels abutting significant regional transportation routes that impede local network connectivity, such as highways or rail rights-of-way, may be modified provided the street layouts and development patterns achieve local connectivity in all other ways possible.
- c. *Rural Parcels.* Tracts divided into lots of at least one acre for rural, agriculture, or very low-intensity development may exceed the block limits, provided they are designed to allow future streets in compliance with these regulations and permit a logical pattern of re-subdivision with minimal disruption of existing or planned buildings, utilities, and other structures.
- d. *Oversized Parcels.* Where oversized parcels are platted for special land uses or development patterns that accommodate large-scale buildings, such as campuses, industrial uses, employment centers, or regional commercial areas, platted blocks may be larger provided private streetscapes matching the block structure of Table 3-1. Private streetscapes shall mimic streetscape and design amenity of this section and create logical extensions and connections to the public street network beyond the project.
- e. *Closed-end Streets.* In any case where streets are not required to connect by these standards or are justified by these exceptions, alternative designs such as loops, courtyard layouts, or closes are preferred over dead ends and cul-de-sacs.
- f. *Specific Plan.* A specific street network plan approved by the Town through the planned development process in 17-2-4 or similar planning initiative for a connected local network for a significant area beyond individual projects may provide different connectivity provided there are sufficient external connections to the surrounding transportation system and the design meets the intent and design objectives of this section.



Figure 3-2 Private streetscapes. Private streetscapes shall be used to mimic public street networks and streetscapes for over-sized parcels and large scape development (17-3-1.B.2.d).




Figure 3-3 Disconnected Street Options. Where streets will not connect, blocks and lots should be laid out to limit the need for cul-de-sacs and maximize other options such as loops, closes, eyebrows and courtyard patterns. (Section 17-3-1.B.2.)

- 3. **Walkways and Bicycle Routes.** In any case where exceptions for larger blocks apply, or any other area where pedestrian and bicycle connections are important, such as adjacent to schools, parks, trail systems or community centers, the Town may require pedestrian walkways or bicycle routes through blocks or at the end of any closed-end street. Connections shall meet the open space design standards in Section 17-3-2.



3-4 Walkways and Bicycle Routes. Where streets will not connect or where larger blocks are platted, connections for pedestrians or bikes may be required through blocks or at the ends of disconnected streets. (17-3-1.B.3).



- 4. **External Connections.** Streets shall be planned to provide continuation to adjacent areas at intervals where all resulting blocks meet the standards in Table 3-1, unless justified by an exception in 17-3-1.B.2.
  - a. The Town may require dedication of right-of-way and construction of streets extended to the boundary line of the property to be subdivided or approve alternative arrangements for location and timing of construction to coordinate with anticipated future development of adjacent areas.
  - b. Areas of future development or smaller subdivision may require a conceptual street network associated with a preliminary plat and applied to adjacent property and connection to other planned major streets to demonstrate compliance with this section and the practicality of external connections.
  
- 5. **Intersections and Offsets.** Subject to adopted Design Standards, streets shall be laid out to intersect to include the following:
  - a. Intersection angles should be as near as possible to right angles.
  - b. Oblique streets shall be curved to approach an intersection at right angles, for a minimum distance prior to the intersection.
  - c. Intersections shall be aligned with existing intersections on the opposite side of the street, and offsets of the centerlines are not acceptable.
  - d. Intersections of more than two streets at one point are not acceptable.
  - e. Deviations and different intersection configurations may be approved through a design modification process, if required or utilized to emphasize unique natural features, better correspond to topography, implement traffic calming, or create gateways or focal points within the street network.
  
- C. **Street Types & Design.** The street types in this section implement variations for context-based street design, enhancement of multi-modal transportation options, and support the intent of this section to accommodate a variety of contexts. Design Standards shall be followed in all circumstances; however these type classifications provide alternative design variations that may be more appropriate for a development’s context; provided it meets all engineering and safety standards.
  - 1. **Street Design Standards.** Typical cross section standards are shown for each street type in Table 3-2: Street Types and Cross-sections with examples following the table. Application of these standards may be further refined with adjustments for a particular context or application, using the Complete Street Design Guide in Section C.3, Table 3-2.
  - 2. **Context & Type.** The street design variations are grouped with the following design types for application to apply to more specific contexts:
    - a. **Neighborhood Streets.** A neighborhood-oriented street type is appropriate where a higher level of neighborhood design amenity and walkability is desired. It is characterized by large street trees, sidewalks, slow speeds, and occasional on-street parking.
    - b. **Pedestrian Streets.** A pedestrian-oriented street type is appropriate for all areas where walkability is a goal. It is characterized by narrow lanes, slower speeds, on-street parking, and large, well-designed pedestrian amenity zones that support businesses and economic activity along these streets. Ideal for a downtown or high-pedestrian activity area.
    - c. **Parkway and/or Bikeway.** A high-amenity street type that emphasizes landscape and/or bicycle facilities. It is characterized by balanced approach to bicycles, pedestrians, and vehicles, and uses enhanced landscape to create welcoming environments. This street type is usually reserved for signature streets or important bicycle connections, and may be coordinated with Open and Civic Space Systems in Section 17-3-2.





- c. *Standard Streets.* The basic street type appropriate generally where no particular development characteristics or urban design context warrant application of other street types, or where moving traffic is the sole priority. Based on the Design Standards, with no variation.



**Table 3-2: Street Types & Cross-sections**

Street Type	ROW Width	Street Width [1]	Travel Lanes	Parking	Bicycle Facility	Landscape Amenity	Detached Sidewalk
<b>Major Arterial – 120' / 78'</b>							
Pedestrian Focus	120'	78'	4 @ 11'	8'	N/A – slow speed	9' amenity zone 18' center median	12'
Parkway / Bikeway	120'	78'	4 @ 11-12"	n/a	8-10' protected lane	10-12' tree strip 20' center median	8'-10'
Standard Street	120'	78'	4 @ 12' w/ center turn lane	n/a	n/a	10' tree strip	10'
<b>Minor Arterial – 110'/74'</b>							
Pedestrian Focus	110'	74'	4 @ 11'	8'	n/a – slow speed	5-10" amenity zone 10'-18' center median	10'
Parkway / Bikeway	110'	74'	4 @ 11-12"	n/a	8'-10' protected lane	8'-12' tree strip 10'-18' center median	6'-10'
Standard Street	110'	74'	4 @ 12' 2' outside shoulder	n/a	n/a	10' tree strip	5'
<b>Collector – 80' / 52'</b>							
Pedestrian / Bikeway	80'	52'	2 @ 11'	8'	7' protected lane	4' amenity zone	10'
Pedestrian Mixed-use Focus	80'	52'	2 @ 11'	8' (1 side) 22' angled (1 side)	n/a – slow speed	4' amenity zone	10'
Parkway / Bikeway	80'	52'	2 @ 11'	n/a	7' protected lane	8' tree strip 16' center median	6'
Standard Street	80'	52'	2 @ 12' 12' center turn lane	n/a	4' lane	8' tree strip 14' center median	6'
<b>Local – 60' / 32-36'</b>							
Neighborhood Connector	60'	32'	2 @ 9'	7'	n/a – slow/low volume	8' tree strip	6'
Pedestrian Street	60'	32'	2 @ 11' 2' shoulder (1 side)	8' (1 side)	n/a – slow speed	4' amenity zone	10'
Pedestrian Mixed-use Street	60'	36'	2 @ 10'	8'	n/a – slow speed	4' amenity zone	8'
Bikeway	60'	32'	2 @ 10'	n/a	6' lane	8' tree strip	6'
Standard Street	60'	36'	2 @ 12'	4'	n/a	6' tree strip	5'
<b>Lane 60' / 24'</b>							
Rural Local	60'	24'	2 @ 10' 2' outside shoulder	n/a	n/a	rural buffer with drainage	n/a
<b>Access Alley 30' / 20'</b>							
Residential Alley	30'	20'	16' yield lane	n/a	n/a	2' buffer	n/a
Non-residential Alley	30'	20'	2 @ 9'	n/a	n/a	1' buffer	n/a

- [1] Street width is front-of-curb measurement, with curb and gutter included street width where it is on-street parking or a travel lane; or to the edge of paving if alternative edge and drainage is approved.
- [2] Access alleys may be located in public access easements at the Town's discretion and provided a property owner's association or other entity with financial and administrative capacity for maintenance is established.




3. *Complete Streets Design Guide*. When proposing a design modification to adjust the typical cross-sections for specific contexts or constraints, the guidelines in Table 3-3: Complete Street Design Guide should apply:

Table 3-3: Complete Street Design Guide		
Street Element	Size	Context & Application
<b>Travel Lanes</b>	12' +	High-speed / high-volume; generally avoid on city streets.
	11'	Applicable on major streets or routes where frequent truck or transit vehicles are expected.
	10'	Generally applicable on all city streets with through traffic.
	9'	Limited to low-volume streets, slow-speed streets, or where ROW is constrained.
	12' -17' yield lanes	Limited to slow, low-volume streets in well-connected networks, where intermittent parking and occasional queuing areas allow two cars to pass.
<b>Bicycle Lanes</b>	n/a	Slow or low-volume streets where bicycles can mix with travel lanes.
	4' – 6' lane	Low-speed streets or constrained ROW (typically < 35mph)
	7'-10' protected lane	Important bike routes or higher speed streets (typically 35+ mph); 2' – 4' protected buffer; 4' – 8' bicycle travel way
	Off street facilities	High-speed / high-volume (typically 45+mph); or portions of trails system.
<b>Parking</b>	6'-7'	Limited to low-volume residential streets.
	7' 8'	Generally applicable to all residential and commercial areas where parking is necessary.
	14'-22' angled	Limited to high-activity streets to maximize parking; depth depends on angle of parking, availability of backing area or cueing lane, and other traffic circumstances.
<b>Landscape Area</b>	2' – 8' amenity zone	Walkable areas (typically paired with adjacent on-street parking) where hardscape, landscape, and street furniture extend sidewalks as social space.
	8'+ amenity zoned	Used for high-activity streets that prioritize social space in streetscapes (i.e., sidewalk dining, mini-courtyards); can accompany Open & Civic Space system credits
	1' – 4' landscape area	Avoid –difficult to grow and maintain plants or trees.
	5' – 6' tree strip	Limited to constrained ROW; small or ornamental trees only.
	7' – 8' tree strip	Generally applicable, sufficient for large shade trees.
	8' – 12' tree strip	Use on busy streets or where no on-street parking exists to provide greater pedestrian buffer.
	13'+ tree strip	Used on signature streets for enhanced landscape amenities; space can be shared with or shifted to medians' and may meet Open & Civic Space system credits (See 17-3-2.C. & D.).
	10' – 20' Median	Used on signature streets for enhanced landscape; can be accompanied with turn lanes and/or mid-street pedestrian refuge at intersections
<b>Sidewalks</b>	20'+ Median	Used on higher-order signature streets; may meet Open & Civic Space system credits (See 17-3-2.C. & D.).
	5'	Minimum, generally applicable standard (typical neighborhood streets)
	6' – 8'	Minimum for non-residential streets (if combined with amenity zone), and priority routes in neighborhoods (i.e. routes to schools, parks, or other destinations).
	8' – 10'	Used for non-residential streets, walkable areas (if combined with amenity zone); or higher density neighborhoods.
	10' +	Used for signature streets in walkable areas, where social spaces are desired in streetscapes, or as a multi-use bicycle / pedestrian path in other contexts.
	Detached	All sidewalks are “detached” to provide a buffer between pedestrians and the street or moving traffic; unless (a) on-street parking is prevalent and the amenity zone provides and expansion of the sidewalk; or (b) right-of-way constraints prevent a more complete street design.



D. Intersection Design.

1. **Corner Radii.** Curb radii shall be designed according to the Design Standards. However, to balance the competing interest of vehicle turning movements and the distance and safety of pedestrians crossing the street, the Public Works Director may recommend, and the Town Engineer may approve, decreases in the specified corner radii based on the following considerations:
  - a. The context of a particular development, and particularly whether walkable development patterns are a priority and whether neighborhood or mixed-use street types in Table 3-2 are used.
  - b. The impact that the specified radius has on increasing the distance that pedestrians must cross.
  - c. The desired speeds of vehicles on the roadway and the desired speeds and volume of turning vehicles.
  - d. The connectivity of the street network and whether vehicles have multiple alternative routes that minimize frequent turning movements.
  - e. The effective turning radius of vehicles considering other features of the specific cross section, including bicycle lanes, on-street parking or other configurations that impact the actual path of turning movements.
  - f. The likelihood that large vehicles will make frequent turning movements at a particular location, compared with the ability of over-sized vehicles or unusual turning movements to safely encroach into other areas of the street.
  
2. **Sight Distances.** Proper lines of sight shall be maintained at all intersections. The proper line of sight shall be an unobstructed view from the stopping point on the approaching street to all points between 2.5 and 8 feet above the roadway along the centerline of the intersecting street or as otherwise indicated in the Design Standards.



**Figure 3-4 Clear Sight Distance.** Sight distance is measured from the stopping point of the approaching vehicle to the center of the lane in oncoming traffic, based on the speeds of oncoming traffic. Clearances may be affected by the types of objects in the sight triangle and the control factors of the intersection. See Design Standards for appropriate distance based on speed.

- a. No building or other type of physical obstruction shall be placed or maintained within the triangle created by the centerline of the street intersection or access, the stopping point on the approaching street, and the sight distance specified.



- b. Street trees, light poles or other limited narrow obstructions are allowed within the sight triangle provided they do not have any foliage, limbs, or other obstructions in the clearance area and are no closer than 15 feet to the intersecting street edge.
  - c. Landscape, plants, and groundcover may be planted in the triangle, provided they do not exceed 30 inches from the elevation of the adjacent street surface.
  - d. Fully controlled intersections where signalization establishes and prioritizes safe turning movements may deviate from the above sight triangle standards if site conditions warrant and based upon a recommendation of the Public Works Director.
3. **Crosswalks.** All intersections and crosswalks shall be designed to address conditions at each specific location. In general, sidewalks intersecting with public streets or other vehicle access shall have crossings meeting the Design Standards, as well as the following:
- a. All intersections of collector streets or higher classification shall be considered for enhanced crossings including pavement markings, bulb outs, refuge islands or other traffic-calming measures that are appropriate to the context of the intersection.
  - b. Where blocks exceed more than 600 feet between intersections or at other locations of high pedestrian activity, mid-block crossings shall be considered with appropriate pavement markings and pedestrian signals. Mid-block crossing designs and locations are subject to a specific recommendation and approval of the Public Works Director.
  - c. Any crosswalk over 80 feet, or any other significant pedestrian crossing, may require a pedestrian refuge in the median at the discretion of the Public Works Director.
4. **Turn Lanes.** Turn lanes for left or right turn movements may be required for specific intersections by Public Works Director, based on an approved traffic study. Requirements for turn lanes should be based on careful consideration of the context balancing the impact of crossing distances for pedestrians, vehicle turning speeds, and prioritization of other planning, urban design, and traffic engineering issues. Wherever possible, this space should come from reconfiguration of the space within the roadway width near the intersection (i.e. within median space, narrowing lanes, or limiting on-street parking) rather than claiming space from the pedestrian area or streetscape, or rather than widening the road and right-of-way.
- E. **Traffic Calming.** In order to meet the desired speeds throughout the street network, to manage volumes in association with the street network, and to meet the intent of this section, traffic-calming strategies may be required in street plans. Traffic calming may include bulb outs and curb extensions, medians and islands, neck downs, vertical diverters, enhanced or raised crossings, and other speed management techniques as provided in the Design Standards or other industry guides addressing multi-modal transportation and urban design issues.
- F. **Engineering & Construction Specifications.** All other engineering specifications, horizontal and vertical alignment, design details, and technical or construction specifications for constructing streets, utilities, stormwater, irrigation, and other public improvements shall meet the Design Standards.





17-3-2 Open & Civic Space

- A. **Intent.** The intent of this section is to:
  1. Emphasize open and civic spaces as a key determinant of Johnstown’s community image and unique identity.
  2. Coordinate open and civic spaces with street networks to maximize the civic design and establish valuable development patterns.
  3. Value the design, function, and appropriate location of different types of open space, rather than solely the quantity of space, including distinctions for passive and active spaces.
  4. Consider the context and multiple functions that open spaces can serve to support development including ecological, recreation, aesthetic, and urban design functions.
  5. Promote good civic design and create focal points for the community and development projects.
  6. Integrate natural systems into the design of common or public open spaces to improve stormwater management, protect water resources, preserve natural features, and enhance ecosystems.

B. **Required Open Space.** Subdivision applications and development plans shall provide public or common open space as provided in this section.

- 1. *Required Open Space.* All plat applications shall provide open space according to Table 3-5: Required Open Space.

Table 3-5: Required Open Space		
Context	Public Open Space	Common Open Space
Residential Zoning or Residential uses in non-residential districts	15%	<ul style="list-style-type: none"> <li>▪ &lt; 3 acres – no requirement</li> <li>▪ 3 - 20 acres –10%</li> <li>▪ 20+ acres - 15%</li> <li>▪</li> </ul>
Commercial & Mixed-uses	15%	<ul style="list-style-type: none"> <li>▪ &lt; 3 acre – no requirement</li> <li>▪ 1 - 5 acres – 3%</li> <li>▪ 3+ acres - 5%</li> <li>▪</li> </ul>
Industrial Uses	15%	n/a

\* Amount is based on net area excluding streets, alleys and easements. Any excess dedicated public open space accepted by the Town may contribute to the common open space requirement. Common open space may only count to the public open space requirement per Section 17-3-2.B.3.

- 2. *Fee In Lieu of Dedication.* When a subdivision or development plan cannot dedicate land acceptable to meet the public open space requirements of Section 17-3-2 due to circumstances beyond their control, the Town may evaluate the option for the applicant to pay a fee in lieu of dedication. This option shall be at the sole discretion of the Town.
  - a. The fee shall equal the fair market value of the land area required to be dedicated.
  - b. The fair market value shall be established by an appraisal commissioned by the Town at the applicant’s expense, or otherwise agreed to by the two parties.
  - c. The fee shall be due prior to recording of the final plat.
  - d. All fees shall be placed into a park fund to be utilized for the acquisition of land for park, trails and open space purposes, and shall not replace, reduce, or be used as the park fee, required by Section 17-3-5.C.



3. **Common Open Space Credit.** Common open space in excess of the amount required in Table 3-5, may be credited to the public open space requirement only upon a finding of all of the following, and approved by the Town Council at final plat:
  - a. There are no spaces within the proposed project that meet public open space standards acceptable to the Town for dedication;
  - b. There is no available open space within the vicinity that will serve the needs of the proposed project, which could be acquired with funds supplied by the fee;
  - c. The common open space amount is sufficient to meet both public and common open space requirements in Table 3-5; and
  - d. The common open space will otherwise remain open and accessible to all property for which the credit is being granted.
  
4. **Ownership and Management.** Open and civic space platted or reserved as part of a development shall require specific designation on the final plat or development as a separate tract or outlot. Ownership of the open space tract shall be in one of the following, subject to all other provisions of this section:
  - a. Dedication to a public entity as part of the rights-of-way, parks, or other community facilities element of the plat according to Section 17-3-5.B.
  - b. Creation of or dedication to a non-profit entity capable of carrying out the ownership and management.
  - c. Creation of a homeowners', leaseholders' and/or property owners' association that owns the space in common and is capable of carrying out the ownership and management.

All open and civic space shall require documentation that outlines the ongoing maintenance plans, and demonstrates the capacity for administrative and financial management of the space according to these standards. Documents such as covenants for a homeowners' association, bylaws or charter for a non-profit entity, or similar agreements and guarantees, shall be filed with the clerk and recorder's office and recorded with the plat designating the open space, prior to any building permits.

- C. **Open & Civic Space System.** The proper arrangement of open and civic spaces shall coordinate with street networks, block and lot layouts, and the landscape and site amenities of individual lots. Such spaces shall be integrated into the design of developments and subdivisions, and provide an appropriate level of service based on service areas noted.
  1. **Types.** Table 3-6 specifies the type, size, and service areas of different open and civic spaces that may meet the open space requirement.



Type	Size [1]	Service Area	Bonus Multiplier [2]	Application	
				Public	Common
<b>Natural Open Space / Agriculture Preservation</b>	5-acre min.; 200' min. width; 40+ acre optimal or significant continuity with adjacent areas	n/a	1.0x to 2.0x – Determined by Director based on the community benefit and significance of the space	■	■
<b>Park - Regional</b>	40+ acres	w/in 1.5 miles		■	
<b>Park - Community</b>	10 – 40 acres	w/in 1 mile		■	
<b>Park - Neighborhood</b>	3 – 10 acres	w/in 0.5 mile		■ [3]	■
<b>Park – Small</b>	0.5 – 3 acres	w/in 0.25 mile			■
<b>Trail</b>	20' wide, min. easement; 8' – 12' min. trail	w/in 1000'		■ [3]	■
<b>Civic Space - Green</b>	1 – 3 acres	w/in 0.25 miles	1.5x		■
<b>Civic Space - Square</b>	5K s.f. – 1 acre	w/in 1,000'	1.5x		■
<b>Civic Space – Plaza / Courtyard</b>	1K – 5K s.f.	abutting lots or on the same block	1.25x		■
<b>Enhanced Streetscape</b>	[see Section 17-3-2.D.]	abutting lots on the same block	1.25x	■ [3].	■

- [1] See Section 17-3.2.D Open Space Design Guidelines for more specifics on the size and design, and service areas of different open space types.
- [2] Areas marked with a bonus multiplier (i.e. 1.5x) can count towards the open space requirement based on the actual area times the multiplier, provided the space is designed according to the Design Guidelines in 17-3-2.D. For example, an 8,000 s.f. Green designed according to 17-3-2.E can count to as 12,000 s.f. (8,000 x 1.5) for the open space requirement for all lots within 0.25 miles.
- [3] Eligibility of Neighborhood Parks, Trails, and Enhanced Streetscape designs as part of the Public open space requirement is at the discretion of the Town, considering parks, trails, and streetscape plans, and subject to acceptance on a final plat.

2. **Location Criteria.** To coordinate open and civic spaces into a system that integrates the public realm with surrounding development, subdivision and development design shall consider the following location criteria for open spaces:
  - a. Connect and integrate open spaces with public streetscapes and other civic destinations, such as schools, to improve visibility and access;
  - b. Provide access for residents, employees, and visitors to recreation opportunities for active living, and ensure that all dwellings are within the service area of at least two types of opens spaces indicated in Table 3-6.
  - c. The opportunity to preserve and integrate natural features (particularly for Natural Open Spaces, Parks or Trails), including protection of groves of trees, prairie, streams, unusual and attractive topography and other desirable natural landscape features and views;
  - d. The opportunity for formal Civic Spaces (Green, Square, Plaza / Courtyard) to serve as gathering places and be a focal point for compact, walkable places, located as an extension of the streetscapes at highly traveled and visible locations;
  - e. The types of spaces that reinforce character of the area or create gateways and transitions to distinct places; and
  - f. Playgrounds, sport courts, and spaces for community gatherings shall be designed to ensure the area is located outside the required setbacks for oil and gas wells and facilities, per Table 5-1 and Table 6-1. These areas may be included in the open space calculations or for trails to traverse, assuming they meet all applicable criteria.




- 3. **Stormwater Facilities.** In addition to stormwater management purposes, such facilities shall be designed and integrated into the street network or open and civic space system in order to avoid redundant and inefficient facilities on individual lots. Any area used for stormwater may be counted towards the open space requirement provided:
  - a. It is integrated into the design of the space in a manner that it is an aesthetic amenity and is consistent with the design character of the space. Examples include:
    - (1) Stream channels for conveyance and filtration;
    - (2) Playing fields, with appropriate size and slopes, within intermittent detention basins;
    - (3) Formal areas when designed with detention as civic art or focal points of the space.
  - b. The design does not impact the utility of the space for either purpose (i.e., stormwater functions do not compromise the use and value of the space as intended open space, and open space designs do not compromise maintenance, management, and performance for stormwater functions).
  - c. The maintenance and management of the portion of the facility serving stormwater functions is clearly identified, whether that is a public dedication or whether it is an obligation of the owner or property owners' association.
- D. **Open & Civic Space Design Guidelines.** Open and civic spaces, as discussed in Table 3-6, shall be designed according to the following guidelines for each specific type:

**Natural Open Space / Agriculture Preservation**

The size, location and design of a Natural Open Space is dependent on the inherent characteristics of the land and the presence of valuable agricultural, natural amenities, or ecological resources worthy of protection. The ability to provide contiguity with similar features on adjacent sites may be important to the design and location of development and preserved areas.

**Size:** 5 contiguous acres (min.); 200' wide minimum; ideally, ability to connect 40 + acres of contiguous natural lands or agricultural lands.

**Service Area:**  
1 mile



**Design Elements & Guidelines**

- ❑ Natural Open Space includes any area of existing or restored open lands such as riparian corridors and wetlands, unique geological formations, important habitats, or substantial groupings of important plant and tree types. The goal is to protect the edges and to maximize intact and undisturbed spaces that provide valuable ecosystem services for the community, support preservation goals, or enhance the aesthetics and amenities of the area. Active recreation such as trails and paths can be a part of these areas provided, they do not disrupt the essential natural character and ecological functions.
- ❑ In the Agriculture Overlay area indicated in the Comprehensive Plan this type of open space may also include preservation of productive agricultural lands, particularly if they are integrated as a focal point of future development.



**Park**

**Size / Service Area**

- Regional – >40 acres / 1.5 miles +
- Community – >10 – 40 acres / 1 miles
- Neighborhood – >3 – 10 acres / ½ mile
- Mini – 0.5 – 3 acres / ¼ mile



**Design Elements & Guidelines**

- Any park planned for public dedication shall be designed according to official plans, policies, and Design Standards of the Town.
- Parks should be at least 200’ wide in all directions (100’ for Mini Park).
- Fronts on 1 or more public streets for 400’ or more (100’ Mini Park); exception to street frontage if designed abutting part of a public trail system.
- One shade tree for every 30’ of street frontage; one shade tree per 50’ of internal trails or paths; 20 shade trees per acre for all other areas beyond 30’ from streets or trails; plus other landscape to support the overall park design.
- Ornamental plantings, concentrations of trees, and other enhanced landscape at gateways, entrances, and prominent corners.
- Between 15% and 50% of the area, depending on context and scale of the park, and at the discretion of the Town, shall be designed for active, programmed or structured recreation such as ball fields, playgrounds or sport courts. The remainder of the area shall be allocated to ground cover, tree areas, gardens, or other natural or formal landscape for passive recreation.

**Trail**

**Size**

20’ min. width; 30’ if includes multi-purpose trail  
 May be dependent on topography and natural features.  
 Requires sufficient continuity to connect with existing and planned pedestrian and bicycle systems outside of project and/or connect meaningful walking and biking destinations (schools, parks, neighborhood centers, etc.)



**Service Area**

- Internal to development – ¼ mile
- Community trail – 1 mile

**Design Elements & Guidelines**

- Any trail planned for public dedication shall be designed according to official plans and policies of the Town.
- Trails corridors should include a paved or otherwise dust-free stabilized surface at least 8’ wide, and 10 to 12’ wide if a shared bike / pedestrian trail.
- The landscape area on each side of the trail should be at least 6’, and wider in places that incorporate natural features or significant vegetation.
- One shade tree for every 50’ of trail length; and one ornamental tree or small evergreen tree for every 25’ of trail length.
- Trails corridors located along rights-of-way may be integrated into the streetscape design to create the optimal multi-modal design for the street and trail, particularly along major and minor arterial streets.






**Civic Space**

**Size / Service Area**

Green – 1 – 3 acres / ¼ mile  
Square – 5K s.f. – 1 acre / 1,000’  
Plaza / Courtyard– 1K - 5K s.f. / abutting lots or on same block.





**Design Elements & Guidelines**

- ❑ Civic space shall have frontage on a public street (or internal access street) with direct pedestrian access to the streetscape and sidewalk, subject to the following;
  - Greens along at least 3 sides and at least 75% of the perimeter,
  - Squares along at least 2 sides and 60% of the perimeter.
  - Plazas along at least 1 side and at least 30% of the perimeter.
  - Courtyards along at least 20% of the perimeter, or an entrance from a gateway and passage along the street.
- ❑ Buildings shall front on and frame the civic space, and be designed with frequent entrances, transparency, and outdoor seating areas to create activity in the space and make physical and visual connections between the buildings and the space.
- ❑ Civic spaces shall have a balance of formal gathering places (hardscape, seating, public art, etc.) and landscape (gardens, lawns, planting beds, etc.). generally, within the following:
  - Green: formal = 15% - 50%; landscape = 85% - 50%
  - Square: formal = 50% - 75%; landscape = 25% - 50%
  - Plaza: formal = 75% - 85% landscape = 15% - 25%
  - Courtyard: formal = 25% - 50%; landscape = 50% - 75%
- ❑ One shade tree for every 25’ of street frontage; and one ornamental or evergreen tree for every 2,000 square feet, located within the space and along the streetscape.

**Enhanced Streetscape**

**Size**

Gateway features: 100 s.f. – 1K s.f.  
Pedestrian / Landscape Amenity: at least 50% more than required for streets by Section 3.01  
Boulevard Median: 12’ collector; 16’ arterial



**Service Area**

Abutting lots along same block

**Design Elements & Guidelines**

- ❑ Gateways concentrate landscape and ornamental structures at important intersections or at entrances to distinct neighborhoods or districts. Gateways may be located more frequently throughout a neighborhood or district with smaller, subtle treatments at multiple intersections, creating a hierarchy of streetscape elements that define the character of the area.
- ❑ Gateways landscape: 1 canopy tree per 35’ of street frontage; 1 ornamental tree or evergreen tree per 250 s.f.; 3 shrubs per 100 s.f.
- ❑ Pedestrian and landscape amenity areas at least 50% greater than required by the streetscape design in Section 17-3-1.C. or landscape median of at least 12’ on collector streets or 14’ on arterial streets; may count to common open space.
- ❑ Pedestrian and landscape amenities shall include planting that is at least 50% above the rate required for the street.
- ❑ Streetscape enhancements shall generally be located in separate tracts designated on a plat or require additional right-of-way



### 17-3-3 Blocks & Lots

A. **Intent.** The intent of the blocks and lots standards is to:

1. Ensure the proper arrangement of blocks and lots in relation to the street network and open and civic spaces.
2. Design subdivisions to be coordinated with adjacent development patterns or future development in terms of street networks, open and civic spaces, and block patterns.
3. Arrange blocks and lots in a manner that is least disruptive to existing topography and capitalizes on inherent natural characteristics of the land as defining features.
4. Coordinate access and utilities for each lot in association with larger systems of streets and infrastructure.
5. Promote appropriate site, building, and frontage designs in relation to streetscapes and open spaces.
6. Ensure that all lots are buildable according to this code and that all non-developed tracts or other parcels serve community functions in relation to the overall development pattern

B. **Block & Lot Arrangement**

1. **General Layout.** All blocks shall be laid out to have two tiers of lots fronting streets on opposite sides, unless dictated by existing development patterns outside of the control of the project or by access management on regional transportation routes. In these cases, streetscape standards and open or civic spaces should be used to create buffers and transitions at the rear of lots.
2. **Block Size & Patterns.** The maximum block length shall be based on the street connectivity standards and specific context as identified in Section 17-3-1.B.
3. **Lot Patterns.**
  - a. Lot size, width, depth, and shape shall meet the applicable zoning district standards and accommodate appropriate building location, orientation, and site design. Corner lots or irregular shaped lots may need additional space.
  - b. All lots shall front on a public street, or on an alternative access or common open space where specifically allowed by these regulations.
  - c. All side lot lines shall be as close as practical to perpendicular to front lot lines, or radial to any curves along the front lot lines. Irregular lot patterns shall only be permitted where they are used to integrate patterns of buildable lots into the overall block structure and to provide consistent relationships of lots and buildings to the streetscape.
  - d. Lots shall be designed to ensure the buildable area of any lot shall not be encumbered by the required setbacks for oil and gas wells and facilities, per Table 5-1 and Table 6-1.
4. **Easements.** All blocks shall include easements for all utilities, required improvements, access, drainage, and open spaces necessary to serve each lot. Easements shall be granted by the owner to the appropriate entity. Easements shall be determined based on the specific needs of a development through development review and granted prior to construction. Unless otherwise specified through the development review process, utility easements shall be as specified in Table 3-7: Easements.



Table 3-7: Minimum Utility Easements	
Common rear lot lines	16', 8' on each lot
Rear lots along an alley	None, provided the alley is at least 20' wide and can accept utilities
Perimeter rear lot lines w/o common boundary	10'
Side easements, where necessary	5'
Front easements (if necessary due to other site / ROW constraints)	10'

5. **Drainage.** Where a subdivision is traversed by a natural watercourse, drainageway or stream, blocks shall be laid out in coordination with these features, and they shall be integrated into the open and civic space systems.
  - a. Drainage areas shall be left in a natural state, and no encroachments shall be made on a significant natural drainage channel that impairs its stormwater and ecological function wherever practical.
  - b. A pedestrian or bikeway easement may be required where the block structure is interrupted more than permitted in Section 17-3-1.B, or where the Planning and Zoning Commission or Town Council determines the area is appropriate for active recreation or transportation uses.
  - c. All necessary rights-of-way and easements shall be dedicated to the Town or other public entity to preserve the hydrologic, environmental, or stormwater function of the watercourse, drainageway or stream.

### 17-3-4 Required Improvements & Dedications

- A. **Intent.** The intent of this section is to:
  1. Ensure that all improvements necessary to serve lots and buildings are constructed, inspected, or otherwise assured of completion prior to the issuance of building permits and other final approvals.
  2. Integrate the design and construction of public, common, and private improvements in the most effective and efficient manner.
  3. Prevent undue burden on public utility systems and community facilities serving other areas from the improper location or design of subdivisions or development projects.
  4. Provide appropriate apportionment of construction and maintenance costs for public facilities serving development.
  5. Protect against subdivisions or development projects where soil, subsoil, or flooding conditions would create potential dangers to property, infrastructure investments, or public health and safety.
  6. Coordinate construction of required improvements with other anticipated improvements and with future growth.
- B. **Applicability.** The standards and procedures of this section are coordinated with other development applications affecting the planning, design, and construction of public or common improvements. Specifically, they apply to:
  1. Preliminary feasibility plans for all required improvements associated with a preliminary plat in Section 17-2-2.D.
  2. Construction plans for all required improvements associated with a final plat in Section 17-2-2.E, a Planned Unit Development and Framework Plan in Section 17-2-4.B.2, or similar development plan.



3. Site plans that are required to provide improvements for any capacity or facility deficiencies are identified in Section 17-2-6.B.2.
  4. Any other common or site improvements that serve beyond a single project or building, or where the Director determines that the procedures and guarantees of this section should apply to specific improvements.
- C. **Subdivision Improvement and Development Agreement.** The Town and the applicant shall enter into a subdivision improvement and development agreement more specifically defines the type, timing, and guarantees for all required improvements. The Director may waive this requirement for any application where the improvements are routine or minor relative to the extent of development.
1. Applicants shall be responsible for the entire cost and installation of improvements necessary to serve the proposed development.
  2. The applicant may contribute its proportionate share to any established participation agreement or for any existing facilities with the capacity to serve the project.
  3. The Town may require oversizing of facilities and establish cost sharing strategies for any improvements where it is determined to serve property in the vicinity or potential future development more efficiently.
  4. The agreement shall be recorded in association with an approved plat or development plan.
- D. **Improvements & Dedications.** The following improvements and dedications are required to be constructed, installed, or dedicated with subdivisions or development projects, except where sufficient facilities exist or will be constructed through other means.
1. **Rights-of-way.** Rights-of-way shall be dedicated meeting the widths specified in Section 17-3-1.C, or any other widths required by the Public Works Director to meet the ultimate planned street classification.
    - a. Additional rights-of-way may be required based on traffic study, long-range transportation plans, or other Town-accepted transportation policy or analysis.
    - b. The dedication of half-streets on the perimeter of a project shall not be accepted unless:
      - (1) The applicant coordinates the dedication of the corresponding half outside the project;
      - (2) The applicant provides sufficient guarantees for the cost of improvements and construction on the corresponding half street; and
      - (3) The applicant establishes acceptable plans for the timing and construction of the full street.Failure to meet perimeter conditions shall not justify an exception to the connectivity or external connection standards of Section 17-3-1.B., or otherwise enable large non-street perimeters of projects.
  2. **Streets.** Streets shall be constructed according to the street types in Section 17-3-1, including travel lanes, parking, bicycle lanes, sidewalks, landscape amenities, and street trees. This shall include all streets internal to the project, and any new streets or street upgrades external to and necessary to serve the project. Additional streetscape elements including streetlights, street name signs, traffic signal lights and signs, and crosswalk designations shall be provided according to Town Design Standards
  3. **Access.** Access shall be provided to all lots. This shall include access and alleys, driveway approaches, and other required vehicle circulation and parking components, and easements where shared or cross-access is proposed or required.



4. **Open & Civic Spaces.** Open and civic spaces, whether public, common, or shared, shall be provided according to Section 17-3-2. In addition, dedication or reservation of areas to serve public or community facility needs according to Section 17-3-5 shall be provided.
  5. **Drainage.** Easements and drainage systems shall be provided to serve the project at the largest practical scale including storm sewer lines, natural and constructed conveyances, retention/detention ponds, and similar facilities. Drainage systems may be incorporated into street and open space systems where they meet the standards and design requirements for each facility.
  6. **Water & Sanitary Sewer.** Easements and utility services shall be provided to serve each lot and principal structure with sanitary sewer and potable water, connecting each lot and principal building to an existing public system.
    - a. An agreement with the Town for service of the subdivision or development defining dedication requirements per the Johnstown Municipal Code, and committing to serve the property with water and sanitary sewer service.
    - b. Raw water dedication and payment of fees is required prior to recordation of a residential plat or prior to issuance of a commercial or multi-family building permit, unless otherwise agreed to in writing with the Town.
  7. **Electric and Communication.**
    - a. Electric power and communication connections and wire shall be placed underground in raceways or conduits.
    - b. Transformers, switching bases, terminal boxes, meters cabinets, pedestal ducts, and other facilities shall be placed underground, or may be placed on the surface provided they are located and adequately screened for safety and concealment.
    - c. Electrical transmission and distribution feeder lines and communication trunk and feeder lines may be placed above ground, if determined to be appropriate by the Public Works Director.
  8. **Fire Hydrants.** Fire hydrants shall be provided at each street intersection, line terminus, and other necessary points to meet Town Design Standards Fire Code, and Fire District requirements.
  9. **Reference Monuments.**
    - a. Permanent reference monuments of stone or concrete, at least 36 inches deep and 6 inches square or round, with a suitable center point shall be located as required by the Town.
    - b. Iron pin monuments at least 24 inches long and flush with the surface shall be placed at all points on boundary lines where there is a change in direction, at all lot and block corners, and at other points required by the Town.
- E. **Timing of Obligations & Improvements.** All required improvements shall be provided through the following steps unless otherwise agreed to in a subdivision improvement and development agreement:
1. **Plan Submittals.** Engineering and construction plans for the entire plat or development plan shall be submitted and approved at one time for improvements in Section 17-3-4.D
    - a. The size, type, and general location of each improvement, and estimated cost shall be included as part of the final plat submittal and review.
    - b. Plans may propose phasing for construction of improvements according to phases approved with an associated plat or development plan. Construction acceptance, financial security, and permits may be approved or released according to an approved phasing plan.





- c. The Johnstown Review Committee may require verification or updates of any technical study required according to Section 17-2-1.J, or other report that verifies adequacy of the required improvements.
- 2. **Financial Guarantee.** The applicant shall provide a financial guarantee for 110% of the total cost of improvements, based on approved design and construction plans.
  - a. The guarantee shall be in a form approved by the Town Manager and Town Attorney.
  - b. The guarantee is due prior to commencement of construction of any improvement, except that the Public Works Director may authorize limited grading permits where there is no threat to preservation of natural areas and vegetation, adjacent properties, or other elements of the plan that may be subject to change prior to final approval.
- 3. **Construction & Installation.** Required improvements shall be constructed in accordance the planning and design standards of this code, the engineering and construction requirements of the Town Design Standards, and with plans approved by the Town.
  - a. A preconstruction meeting shall be scheduled to review approved plans, Town Design Standards, required permits, and timing of construction and inspections.
  - b. Construction of improvements shall not commence until notice to proceed, or other authorized permits are issued by the Town.
- 4. **Inspection & Construction Acceptance.** The applicant shall request inspection and construction acceptance for any completed improvements for a specific phase.
  - a. The Town shall inspect and may issue a letter of construction acceptance for any phase of improvements that comply with the approved plans.
  - b. Certified record drawings of improvements as built shall be submitted to the Town and certified by the contractor, project surveyor, and project engineer.
  - c. The Town may release the financial guarantee for any required improvements that have been accepted and where record drawings are submitted, but shall retain 15% of the cost of improvements as a maintenance and repair warrant.
- 5. **Maintenance & Repair Warranty.** The applicant shall provide a warranty for maintenance and repair of all improvements at the time of construction acceptance through either a new obligation, or through a limited release and retention of the financial guarantee.
  - a. The maintenance and repair warranty shall be at least 15% of the cost of improvements.
  - b. The warranty shall be for at least 2 years, or until the Town issues final acceptance, whichever is later.
  - c. The applicant shall be responsible for the repair, replacement, and maintenance of any required improvement which fails to function or meet the standards of the Town, prior to final acceptance.
  - d. In the instance of repair or reconstruction of any improvement and prior to final acceptance, the Town may require the extension of the 2-year warranty period.
- 6. **Permits.** The Town shall not issue building permits until construction acceptance has been issued for all public improvements for the development or applicable phase, except for the following:
  - a. **Detached Houses.** Building permits may be issued for detached houses prior to construction acceptance if limited to the following:
    - (1) No more than 50% of building permits for a particular phase may be issued prior to construction acceptance.



- (2) Required improvements shall be eligible for acceptance other than public landscaping, which may be delayed due to weather or seasonal planting considerations.
    - (3) No certificate of occupancy shall be issued until construction acceptance of all required improvements for the development or phase.
  - b. *Other Limited Permits.* The Director may approve other limited building permits on a case-by-case basis, in consultation with the Public Works Director, Fire Marshal, and other appropriate Town Departments when considering the following:
    - (1) Better phasing or coordination for the timing of construction of public improvements and buildings or other site improvements is proposed;
    - (2) Fire safety and emergency access is sufficiently addressed considering the type of construction; and
    - (3) Any other factors related to public health, safety, and welfare are addressed generally, no certificate of occupancy shall be issued for any part of a phase prior to construction acceptance.
  - c. *Revocation of Permits.* The Town may revoke, withhold, or stop any permits or certificates of occupancy during any period where the improvements are not constructed or maintained as required by this code or a subdivision improvements and development agreement.
- 7. *Final Acceptance.* The Town shall inspect the public improvements at the end of the warranty period, following a written request from the developer, submitted to the Town.
  - a. The applicant shall bring any improvements not meeting approved plans or design standards into compliance.
  - b. If identified deficiencies are not corrected and accepted within 120 days of the end of the warranty period or inspection, the Town may withhold further building permits or certificates of occupancy for the development or applicable phase.
  - c. The applicant shall provide the Town with record drawings for landscaping and irrigation that include designer and contractor certification statements of open and civic spaces. The applicant shall provide a copy of the record drawings to the property owners' association.
  - d. Upon final acceptance the Town may release the 15% maintenance and repair warranty. If final acceptance is not granted, all future maintenance and repair shall remain the responsibility of the applicant until the Town grants final acceptance of the improvements.
- 8. *Use of Guarantee.* With authorization by the Town Manager, the Town may execute and use any financial guarantee or maintenance and repair warranty to provide required improvements where:
  - a. The improvements were not provided as required by this code or a subdivision improvement and development agreement.
  - b. The improvements did not pass inspection and were not corrected within 120 days of notice of failure to pass inspection.
  - c. The improvements fail to be maintained according to standards during the warranty period, and the applicant failed to address or propose an acceptable plan to address the deficiency within 120 days of notice.
  - d. In the case of executing and use of any guarantee, the Towns shall keep all funds. If the actual cost to install or correct the improvements is greater than the amount retained in warranty, the Town may assess all costs against the property.



17-3-5 Community Facilities & Fees

- A. **Intent.** The intent of this section is to:
  1. Anticipate and evaluate the incremental and long-term impact of development on broader public and community facility needs.
  2. Identify opportunities to integrate plans for public and community facilities into the planning and design of proposed land divisions.
  3. Ensure that the most appropriate locations of public and community facilities are identified and considered prior to the premature commitment of these areas to conflicting development patterns.
  4. Locate and design public and community facilities in association with the areas they serve, and create gateways and focal points through public investment.
  5. Provide the opportunity to negotiate a fair price for land needed to develop public or community facilities beyond the impact of the particular project, or alternatively to provide an incentive to dedicate land where the lack of facilities may otherwise constrain potential future development.
  6. Ensure that land benefited by public capital investments share in obligations for construction, operation, maintenance, and replacement of these facilities proportionate to their impacts.
  7. Promote fiscal responsibility for all public entities by coordinating the planning, design, and financing of public facilities concurrent with impact the generated from proposed development.
  
- B. **Dedication and Reservation of Land.** The Planning and Zoning Commission or Town Council may request the dedication or require the reservation of land to the Town or other government entity with jurisdiction over public and community facilities, to facilitate the appropriate location for parks, open space, public safety, schools, utilities, or other public or community infrastructure and facilities.
  1. **Dedication.** A request for dedication of land may be initiated by the Town, or on behalf of another public entity having jurisdiction over public and community facilities.
    - a. The dedication may be included on a plat, by deed of dedication, or through a separate agreement with the entity having jurisdiction.
    - b. Inclusion of the dedication on the plat shall be at the discretion of the applicant, except for the following land dedication or fee in lieu specifically required by this code:
      - (1) Open space dedications;
      - (2) School site dedications; and
      - (3) Dedications required for other public entities, such as library, recreation district, fire districts, and similar entities.
    - c. Dedication, or fee in lieu, shall be subject to approval and acceptance by the Town Council, and any other appropriate agency having jurisdiction of the public or community facility.
  
  2. **Reservation.** As an alternative to dedication, the Town may require that the land be reserved to permit negotiation for acquisition by a public entity, according to the following:
    - a. A requirement for reservation shall be based on plans of the entity having jurisdiction over the facility that identify the general location and extent of the facility, or some other documented need for the facility.
    - b. The reservation shall be for a set period of time established by the Planning and Zoning Commission or Town Council but not more than 5 years, unless agreed to by the applicant.
    - c. The reservation may be accompanied by a contingency plat, demonstrating how land will otherwise be developed. The contingency plat may serve as a



- d. preliminary plat should the property not be acquired by the public entity during the reservation period.  
 The property shall not be developed until the reservation period expires or the property is acquired, and future development shall follow the applicable procedures in Article 2 of this code.

3. **Development Agreements.** Nothing in this section shall limit the Town’s authority to enter into development agreements with developers and provide dedication of land, fees, or construction of actual public and community facilities on terms different than specified in this Section.

C. **Impact Fees Established.** The following development fees have been established by the Town by specific impact fee ordinances. Fees are payable at the time of building permit issuance, subject to an exemptions, exceptions, or appeal provisions of this section.

Table 3-8: Impact Fees						
Use		Development Fees [1]				
		2023	2024	2025	2026+	
Transportation Facilities Development Fee [2]	<i>Detached House</i>	\$ 3,062	\$ 3,215	\$ 3,375	\$ 3,544	
	<i>Attached House</i>	\$ 2,605	\$ 2,735	\$ 2,872	\$ 3,016	
	<i>Retail</i>	\$ 5.42	\$ 5.70	\$ 5.98	\$ 6.28	
	<i>Office</i>	\$ 3.29	\$ 3.45	\$ 3.62	\$ 3.80	
	<i>Industrial / Other</i>	\$ 2.12	\$ 2.22	\$ 2.33	\$ 2.45	
Parks & Recreation Facilities Development Fee	<i>Detached House</i>	\$ 1,316	\$ 1,382	\$ 1,451	\$ 1,524	
	<i>Attached House</i>	\$ 1,120	\$ 1,176	\$ 1,235	\$ 1,297	
Public Facilities Development Fee	<i>Detached House</i>	\$ 1,752	\$ 1,839	\$ 1,931	\$ 2,028	
	<i>Attached House</i>	\$ 1,491	\$ 1,565	\$ 1,643	\$ 1,726	
	<i>Retail</i>	\$ 0.82	\$ 0.86	\$ 0.90	\$ 0.94	
	<i>Office</i>	\$ 0.82	\$ 0.86	\$ 0.90	\$ 0.94	
	<i>Industrial / Other</i>	\$ 0.82	\$ 0.86	\$ 0.90	\$ 0.94	
Library and Cultural Facilities Development Fee	<i>Detached House</i>	\$ 1,266	\$ 1,329	\$ 1,395	\$ 1,465	
	<i>Attached House</i>	\$ 1,077	\$ 1,131	\$ 1,188	\$ 1,247	
Police Facilities Development Fee	<i>Detached House</i>	\$ 797	\$ 837	\$ 879	\$ 922	
	<i>Attached House</i>	\$ 679	\$ 713	\$ 748	\$ 786	
	<i>Retail</i>	\$ 0.75	\$ 0.79	\$ 0.83	\$ 0.87	
	<i>Office</i>	\$ 0.28	\$ 0.29	\$ 0.30	\$ 0.32	
	<i>Industrial / Other</i>	\$ 0.28	\$ 0.29	\$ 0.30	\$ 0.32	
Loveland Fire and Rescue Authority Fee [2]	<i>Single Family</i>		\$1,000			
	<i>Multi-family</i>		\$ 692			
	<i>Commercial</i>		\$ 0.60			
	<i>Industrial</i>		\$ 0.12			
Front Range Fire Rescue Fire Protection District [3]	<i>Single-family / Two-family</i>		\$ 1,087			
	<i>Multi-family</i>		\$ 692			
	<i>Any Non-residential</i>		\$ 0.60			

[1] Residential Fees are on a per unit basis and apply to any net increase in dwelling units; non-residential fees are on a per square foot basis and apply to any net increase in the square footage of a use or the increment for any change of use.



- [2] The fire and rescue fees are applicable only in the jurisdictional boundaries of the respective fire districts – Loveland Fire and Rescue Authority and Front Range Fire Rescue Fire Protection District.
1. **Annual Inflation Adjustments.** The impact fee shall be automatically adjusted to account for inflationary increases in the cost of provided public facilities on January 1 of each year. The adjustment shall be based on the most recent data from the Engineering News Record Construction Cost Index for the Denver Metropolitan Area. Alternatively, The Town Council may determine appropriate inflation adjustments through the annual review process in Section 17-3-5.G.
  2. **Exemptions.** An applicant may request an exemption from specific impact fees on forms provided by the Town.
    - a. The Town Council shall evaluate the request and may grant an exemption in whole or in part.
    - b. The Town shall deposit funds in the amount of the exemption into the appropriate impact fee account from non-impact fee funds within a time period that is consistent with the Town capital improvements program.
  3. **Development Agreements.** Nothing in this section shall limit the Town’s authority to enter into development agreements with applicants and provide dedication of land, fees, or construction of actual infrastructure improvements.
  4. **Fire and Emergency Services Providers, School District and Special Districts.** The applicant shall confer with the appropriate fire and emergency service provider, school district and any special district to determine whether an impact fee is owed and the amount of the impact fee. The Town shall confer with the provider and may withhold Town permits or approvals until any required fees have been satisfied.
  6. **Appeals.** Appeals of any decision on impact fees by an administrative official may be appealed to the Town Manager by filing a written appeal with the Town Clerk. Appeals of the Town Manager’s decision shall be appealed to the Town Council following the same procedure:
    - a. Appeals shall be on forms provided by the Town and detail the specific grounds for the appeal.
    - b. The applicant shall have the burden of proving the decision was in error.
    - c. Filing and appeal shall not stay the imposition or collection of the impact fee unless a letter of credit or surety for the amount of the fee has been provided to the Town.
    - d. The Town Manager and/or Town Council shall make a decision within 30 days of filing an appeal.
    - e. No building permits or approvals shall be issued until the appeal is resolved and the appropriate fees paid. However, if a letter of credit or other surety for the amount of the fee is provided the Town may choose to issue a permit or approval with an agreement that the appropriate fee shall be paid through subsequent resolution of the appeal and surety.

**D. Establishment of Accounts and Funds.**

1. **Impact Fee Accounts.** An impact fee account shall be established by the Town for each category of capital improvements for which impact fees are imposed.
  - a. Accounts shall clearly identify the category, account, or fund for which the impact fee has been imposed. Subaccounts may be established for individual impact fee districts.





- b. All impact fees shall be deposited into the appropriate impact fee account or subaccount. Accounts shall be interest-bearing with interest earned credited to and considered funds of the account.
  - c. The funds of each account shall at all times be capable of being accounted for separately from all other Town funds.
  - d. The Town shall establish and implement necessary accounting controls to ensure that the impact fee funds are properly deposited, accounted for, and appropriated in accordance with these provisions and any other applicable legal requirements.
2. **Appropriation of Impact Fee Funds.** Impact fee funds may be appropriated for capital improvements and for the payment of principal, interest, and other financing costs on contracts, bonds, notes, or other obligations issued by the Town or on behalf of other applicable local governmental entities.
- a. All appropriations from impact fee accounts shall be detailed on appropriate forms and filed with the Town Treasurer.
  - b. Impact fees shall be appropriated only:
    - (1) For the particular category of capital improvements for which they were imposed, calculated, and collected; and
    - (2) Within the impact fee district where collected, except as provided in subsection 2.d.
  - c. Impact fees shall not be appropriated for funding maintenance or for operational or personnel expenses associated with the provision of the capital improvements.
  - d. Impact fee funds may be appropriated for a capital improvement located outside of the district of the new land development where collected only if the demand for the capital improvement is generated in whole or in part by the new land development or if the capital improvement will actually serve the new land development.
3. **Procedure for Appropriation of Impact Fee Funds.**
- a. The Town Manager shall annually identify capital improvement projects anticipated to be funded in whole or in part with impact fees. The capital improvement recommendations shall be based upon the annual review in Section 17-3-5.E. and other relevant information, and may be part of the Town's annual budget and capital improvements programming process.
  - b. The recommendations shall be consistent with the intent and standards of this section, the particular impact fee ordinances, other applicable legal requirements, and any guidelines adopted by the Town Council
  - c. Impact fee-funded capital improvements in the Town's annual budget and capital improvements program shall include description, nature, location, capacity to be added, service area, need/demand for, and the anticipated timing of completion of the capital improvement.
  - d. The Town Council may authorize impact fee-funded capital improvements at other times the Town Council determines necessary and appropriate.
  - e. The Town Council shall verify that adequate impact fee funds are or will be available from the appropriate impact fee account for the particular category of capital improvements.
4. **Refunds.**
- a. **Eligibility.** An applicant who has paid an impact fee may be eligible for a refund where:
    - (1) A building permit has expired or has been revoked prior to construction; or



- (2) If construction has been started and abandoned prior to a certificate of occupancy, only if the uncompleted building is completely demolished.
- b. **Applications.** Applications for a refund shall be made in writing to the Town within 60 days of expiration or revocation of a permit. The application shall include:
  - (1) Evidence that the applicant is the property owner or the duly designated agent of the property owner;
  - (2) The amount of the impact fees paid by capital improvements category and receipts for the payments; and
  - (3) Evidence of the expiration or revocation of the building permit or approval of demolition of the structure pursuant to a valid Town-issued demolition permit.

Failure to apply for a refund within 60 days following expiration or revocation of the building permit or demolition of the structure shall constitute a waiver of entitlement to a refund.
- c. **Decision.** The Town shall review the application and supporting relevant evidence and determine whether a refund is due.
  - (1) The Town may, at its discretion, make refunds of impact fees by direct payment, by offsetting refunds against other impact fees due for the same category of capital improvements for new land development on the same property, or by other means subject to agreement with the property owner.
  - (2) A ten-percent administrative fee, not to exceed \$500, shall be deducted from any refund and retained in the appropriate impact fee account to defray the administrative and processing expenses.
  - (3) No interest shall be paid in calculating the amount of the refunds.
- d. **Fire, Emergency and School Services.** Any requests for refunds of the fire, emergency or school service fees shall be made to the service providers, who are solely responsible for deciding and providing refunds.

- E. **Annual Report.** At least once every year, not later than October 15 and beginning October 15, 2001, and prior to the Town Council’s adoption of the annual budget and capital improvements program, the Town Manager shall prepare and submit annual impact fee report to the Board.
  - 1. The annual report may include evaluation of capital improvements planning, analysis of annual development activity and permit statistics, assessment of funds and capital improvements expenditures, recommended updates to the fee schedules and calculation, recommended amendments to the fee ordinances and impact areas, and any other information relevant to or required by specific impact fee ordinances.
  - 2. The Town Council shall receive the annual report and may take any action it deems appropriate based on the information.

- F. **402 Interchange Fee.** Pursuant to the Town’s authority to enact fees to recover costs of providing, maintaining, and improving infrastructure for properties within its jurisdiction, the 402 Interchange Fee is established as a special fee to recover a portion of the costs of the reconstructed interchange at Interstate 25 and State Highway 402, accomplished between approximately 2017 and 2022.
  - 1. **Applicability.** The 402 Interchange Fee shall apply to any request for a building permit on property within the area designated on a map maintained by the Town and publicly available, except:
    - a. Alterations or expansions of existing buildings where no dwelling units are created or no nonresidential square footage added;
    - b. The construction of accessory buildings or structures that do not add dwelling units or square footage to the principal building or use of land; or



- c. The replacement of a destroyed or partially destroyed building or structure with a new building or structure of the same square footage.
- 2. *Establishment of Fee.* The 402 Interchange fee shall be levied and assessed as indicated in the current Town Fee Schedule.
- 3. *Use of Funds.* The revenues from the 402 Interchange Fee shall be remitted to the Street and Alley Fund.
  - a. The funds shall be used solely to reimburse the Town for the cost of improvements to and reconstruction of the Interstate 25 and State Highway 402 interchange.
  - b. The Town shall keep an accurate accounting of the cost of the improvements and revenues collected.
  - c. In the event that the total amount of the fee revenues paid to the Town equal the sum of \$ 2,500,000.00, plus interest from the effective date of the fee at a rate of 2.75% per annum, all property owners in the designated fee area shall be relieved of any further obligation to pay the 402 Interchange Fee.
- 4. *Not An Impact Fee or Development Charge.* The Town Council does not intend that the 402 Interchange Fee be construed as an impact fee or development charge within the meaning of Section 29-20-104.5, C.R.S., as amended, but that the 402 Interchange Fee be a special fee within the home rule authority of the Town. To the extent that the provisions of Section 29-20-104.5, C.R.S., as amended, conflict with the provisions of this section, this section shall control.



Article 4. Districts & Uses

- 17-4-1 Establishment of Zoning Districts
17-4-2 Permitted Uses / Use Table
17-4-3 Specific Use standards
17-4-4 Accessory Uses
17-4-5 District Performance Standards

17-4-1 Establishment of Zoning Districts

A. Intent. To carry out the purposes of this code, the following districts are established, with the intent given for the character of specific areas, the development patterns and context, and the types or intensity of uses and buildings.

Table 4-1: Zoning Districts & Intent. Table with 2 columns: District & Intent, Relationship to Comprehensive Plan. Rows include H-A - Holding / Agriculture, R-E - Rural Estate, R-1 - Single-Family Neighborhood, and R-2 - Mixed-Density Neighborhood.



**Table 4-1: Zoning Districts & Intent**

District & Intent	Relationship to Comprehensive Plan
<p><b>R-3 – High Density Neighborhood</b> The R-3 district provides residential living (small- or large-scale residential building types) in a moderate-to high-density pattern in suburban areas or walkable neighborhoods. This district should be located as a transition between lower-density neighborhoods or more intense non-residential uses, and where a high level of accessibility, public amenity and support services are immediately available.</p>	<p>General application in high-intensity areas, or limited applicability at strategic points and transitions to and within Activity Centers</p>
<p><b>MU-DT – Downtown.</b> The MU-DT district provides an integrated mix of retail, service, entertainment and civic uses, and supporting office and residential uses, in a compact and walkable format. This district preserves the historic “main street” scale and small-town character of Johnstown. It is the vibrant heart of the community with a high level of civic design, walkable urban patterns, and a concentration of diverse, small-scale uses.</p>	<p>General application for Downtown Activity Center.</p>
<p><b>MU-NC – Neighborhood Commercial.</b> The MU-NC Neighborhood Commercial District provides for small-scale and low-intensity uses that complement, support, and are integrated into surrounding neighborhoods and other higher-intensity commercial areas. It may exist in compact, walkable formats in close proximity to neighborhoods, or alternatively if automobile oriented the impacts of access and operations on adjacent areas are limited and mitigated by the small-scale format and lower intensity of the uses.</p>	<p>Limited application for nodes within the Low Intensity area to provided walkable destinations and supporting services for neighborhoods; General application within Activity Centers or commercial areas in the Moderate Intensity Area.</p>
<p><b>MU-RC – Regional Commercial.</b> The MU-RC is intended to provide regional commercial, entertainment, and/or employment destinations. While compact, walkable, or transit-served locations and formats are preferred – particularly in areas designated as activity centers, this district may accommodate some higher-intensity and larger format commercial uses – particularly if they are removed from or on the periphery of activity centers or otherwise located to not disrupt walkable patterns.</p>	<p>Limited application within Activity Centers in the Moderate Intensity areas; General application for commercial areas in the High Intensity Area</p>
<p><b>I-1 –Industrial Light.</b> The I-1 district provides primarily service, employment, manufacturing and distribution uses at a scale, intensity and format that will not have significant impact on adjacent uses, and which can mix with supporting and compatible service and retail uses characteristics of mixed and flex business areas.</p>	<p>General application adjacent to heavier industrial areas, as a transition to less intense uses, and limited application as an employment component of mixed-use or commercial areas in the High Intensity Area.</p>
<p><b>I-2 Industrial – Heavy.</b> The I-2 district provides primarily manufacturing uses at a scale, intensity and format that could impact adjacent uses or where specific land resources, distribution facilities or other supporting infrastructure is needed. It may include limited applications of support service, employment or distribution uses.</p>	<p>Limited application in the industrial areas for more intense uses that need special siting or other infrastructure support.</p>
<p><b>PD and PUD</b> – See Section 17-2-4 for the intent and applicability of planned zoning districts.</p>	<p>General application for innovative design concepts applied to a master planned area.</p>

- B. **Official Zoning Map.** The boundaries of the districts are shown on the official Zoning Districts Map on file with the Planning and Development Department. Electronic copies and files of this map shall reference the “Official Copy” on file with the Planning and Development Department, but any copy should be verified with the Department before materially relying on any electronic or other representative copy of the map.
- C. **Transition of Previous Districts.** The zoning districts under the previous code correspond to the zoning districts in this code as specified in Table 4-2. The Official Map under the previous code shall transition and be interpreted according to the corresponding zoning districts in this table, and all further zoning changes shall follow the districts in this code.





<b>Table 4-2: Zoning Districts Transitions</b>	
<i>Prior Code</i>	<i>This Code</i>
<i>H-A Holding Agriculture</i>	<i>H-A Holding Agriculture</i>
<i>SF-1 Single-Family Residential</i>	<i>R-1 Single-family Neighborhood</i>
<i>SF-2 Single-Family Attached Residential</i>	<i>R-2 Mixed-density Neighborhood</i>
<i>MF-1 Multi-Family Residential</i>	<i>R-3 Multi-family Neighborhood</i>
<i>NC – Neighborhood Commercial</i>	<i>MU-NC Mixed-use Neighborhood Center</i>
<i>CB – Central Business District</i>	<i>MU-DT Mixed-use Downtown</i>
<i>Gateway Commercial District</i>	<i>MU-RC Mixed-use Regional Center</i>
<i>Gateway District</i>	<i>I-1 – Industrial - Light</i>
<i>I - Industrial District</i>	<i>I-1 – Industrial - Light</i>
<i>n/a</i>	<i>I -2 Industrial - Heavy</i>
<i>Recreation and Open Space</i>	<i>n/a – integrated into all districts</i>
<i>PUDs</i>	<i>PDs - see Section 17-2-4</i>

### 17-4-2 Permitted Uses

- A. **Use Table.** To implement the intent of each zoning district, facilitate complementary transitions between districts, and to regulate a variety of compatible uses within zoning districts each district is permitted the uses indicated in Table 4-3. The table identifies uses as:
1. Permitted uses (P) subject to general district development and buildings standards and review procedures.
  2. Uses allowed by special review (S) subject to the review process and criteria for a Use by Special Review in Section 17-2-7.
  3. All uses listed in the table (whether P or S), or more specific types of uses generally enabled in the table, may be subject to specific standards or limits in Section 17-4-3, Specific Use Standards
  4. Other accessory or temporary uses not listed in the table may be permitted according to the standards of Section 17-4-4, Accessory Uses.
  5. Uses in the table are more specifically described in Section 17-11-1, Description of Uses. Where a proposed use is not generally listed or appears to meet the description of more than one use type, the Director shall make an interpretation on the most equivalent described use considering:
    - a. The similarity of the use in terms of scale, impact, and operations to other described uses;
    - b. The typical building format and site design associated with the use based on existing relevant examples; and
    - c. The potential contribution of the use to the intent of the zoning district, and the ability to complement and be compatible with other permitted uses, based on typical formats and site designs.
- Any use that may not be interpreted as equivalent to a use in Table 4-3 is not anticipated by these regulations and may only be allowed by an amendment to the development code.



ARTICLE 4 – DISTRICTS & USES

Item #14.

17-4-2 PERMITTED USES

**Table 4-2: Permitted Uses**

P = Permitted, subject to general district standards S = Permitted, only by special review and discretionary process = Blank means the use is not permitted		H-A	R-E	R-1	R-2	R-3	MU-NC	MU-DT	MU-RC	I-1	I-2	Specific Conditions
		<b>Residential Uses</b>										
Household Living	One-unit Dwelling	P	P	P	P	P						
	Multi-unit Dwelling				P	P						
	Live / Work Dwelling				S	S	P	P	P			17-4-3.A
	Dwelling – Mixed-use					S	P	P	P			17-4-3.B
	Mfgd. / Small Format Home Community				PD	PD	PD	PD	PD			17-5-6
<b>Group Living</b>												
Group Living	Established Residential (all building types)						P	P	P	P	P	
	Group Home – Small	P	P	P	P	P	P	S	S			17-4-3.C
	Residential Care – Limited	S	S	S	S	S	P	S	P			17-4-3.D
	Residential Care – General					S		S	P			17-4-3.D
<b>Public / Institutional Uses</b>												
Assembly	Limited (< 400 capacity / < 2 ac.)	P	P	P	P	P	P	P	P	P		
	General (400–800 capacity / 2 – 5 ac.)					P	P	P	P	P		
	Large (800+ capacity / 5+ acre)								P	P		
Civic & Institutional Buildings	Government and Town	P	P	P	P	P	P	P	P	P		
	Library, public				P	P	P	P	P			
	Museum, cultural						P	P	P			
	School			P	P	P	P	P	P			
Park and Open Space	Athletic Field			S	S	S	S	S	P	P	P	
	Recreation Center or Grounds			S	S	S	S	S	P	P	P	
	Park, Trail, Civic Space (See 17-3-2)	P	P	P	P	P	P	P	P	P	P	
Utilities	Utility Major									S	P	
	Utility – Minor (principal use)			S	S	S	S	S	S	S	S	
<b>Agriculture Uses</b>												
Agri-tourism	Roadside Stands	P	S	S	S	S	S	S	S	P		
	Farmers Market	P	S			S	P	P	P	P		
	Community Farm	P	S	S								
Farming	Farming - Limited	P	S	S								
	Farming - General	P										
	Farming - Industrial	S									S	
	Agriculture Industrial Services									P	P	
<b>Commercial Uses</b>												
Animal Care / Sales	Limited - <3K – no boarding						P	P	P	P	P	
	Small - 3K – 8K or limited boarding	S							P	P	P	
	General -8K – 30K or boarding	S								P	P	
	Large – Outdoor or > 30K)	P								S	P	
Dependent Care	Dependent Care – Limited (< 3K)	S	S	S	S	S	P	P	P	S		
	Dependent Care – General (3K – 8K)				S	P	P	P	P	S		
	Dependent Care – Large (> 8K )						S	S	P	S		
Entertainment & Recreation	Indoor / Limited (< 8K)						S	P	P	P	S	
	Indoor / General (8-30K+)							S	P	P	S	



ARTICLE 4 – DISTRICTS & USES

Item #14.

17-4-2 PERMITTED USES

Table 4-2: Permitted Uses												
P = Permitted, subject to general district standards S = Permitted, only by special review and discretionary process = Blank means the use is not permitted		H-A	R-E	R-1	R-2	R-3	MU-NC	MU-DT	MU-RC	I-1	I-2	Specific Conditions
Food & Beverage Service	Indoor / Large (30K+)							S	P	P	S	
	Outdoor							S	S	S	S	
	Restaurant – Limited (< 3K)						P	P	P	P		
	Restaurant – Small (3K – 8K)						S	P	P	P		
	Restaurant – General (> 8K)							S	P	P		
Lodging	Bed & Breakfast (up to 5 rooms)	S	S			S	P	P	P			17-4-3.E
	Inn (6 to 40 rooms)						P	P	P			
	Hotel / Motel (40+ Rooms)							S	P	S		
Medical Service	Limited - < 8K s.f.					S	P	P	P	P	S	
	General – 8K – 30K s.f.								P	P	S	
	Large – Hospital Complex –30K+ s.f.								P	P	P	
Office	Limited (<8K or < 33% of MU project)					S	P	P	P	P	P	
	General (8K – 30K)							P	P	P	P	
	Large (30K+)								P	P	P	
Personal Service	Limited (<3K or < 33% of MU project)					S	P	P	P	P	S	
	Small (3K – 8K)							P	P	P	S	
	Large (>8K)								P	P	S	
Retail	Limited (<3K or <33% of MU projects)					S	P	P	P	S		
	Small (3K-8K)						P	P	P	S		
	General (8K-30K)							S	P	S		
	Large (> 30K)								P	S		
	Retail – Outdoor & Equipment Sales								S	S		
Retail -Grocery Store	Small (< 8K)					S	P	P	P	P		
	General (8K – 30K)							P	P	P		
	Large (30K +)								P	P		
Vehicle & Equipment Uses	Gas Station – Limited (1-8 Pumps)						S	S	P	P	P	17-4-3.G
	Gas Station – General (9-16 pumps)								S	P	P	17-4-3.G
	Gas Station – Large (17+ pumps)								S	P	P	17-4-3.G
	Automobile Repair - Limited						S	S	P	P	P	17-4-3.H
	Automobile Repair - Body Shop									P	P	
	Automobile, RV, Equip. Sales / Rental								S	S		
	Car Wash and Automobile Detailing						S		S	P		
Manufacturing / Industrial Uses												
Industrial Service	Contractors Office & Fleet Services								S	P	P	
	Industrial Service, Light									P	P	
	Industrial Service, Heavy										S	
	Vehicle / Fleet Maintenance Facility									S	P	
Manufacturing	Limited / Artisan						P	P	P	P	P	17-4-3.I
	Brewery, Distillery, or Winery						S	S	S	P	P	17-4-3.J
	Manufacturing - Light								P	P	P	
	Manufacturing - Heavy										S	
Warehouse / Storage	Wholesale & Distribution									P	P	
	Indoor Storage									S	S	17-4-3.K



Table 4-2: Permitted Uses												
P = Permitted, subject to general district standards S = Permitted, only by special review and discretionary process = Blank means the use is not permitted	H-A	R-E	R-1	R-2	R-3	MU-NC	MU-DT	MU-RC	I-1	I-2	Specific Conditions	
	Outdoor storage									S	S	17-4-3.K
Fuel Storage (principal use)									S	S		
Automobile Wrecking / Salvage Yard										S		
Hazardous Waste Handling										S		
Waste / Salvage									S	S		
Recycling Operation, Enclosed									S	S		
Recycling Operation, Unenclosed									S	S		
Waste transfer Station										S		

17-4-3 Specific Use Standards

The following uses may have impacts different than those generally enabled in the zoning districts, and have standards specific to the uses. These standards shall be met whether the use is a generally permitted use, accessory use, or a Use by Special Review according to Table 4-3. The uses in this section may include more specific types or formats of the uses generally enabled in Table 4-3.

- A. **Live-Work Dwelling.** In districts where Live / Work Dwellings are permitted, they shall meet the following standards and conditions to be compatible with the context.
  - 1. Commercial uses shall be limited to those uses that are otherwise permitted in the district, or uses allowable through the Use by Special Review process in Section 17-2-7.
  - 2. Any commercial activity shall occur on the ground floor and be directly accessible from the adjacent public street, sidewalk, or other public space or publicly accessible common area.
  - 3. Commercial activity, and any accessory assembly, production of fabrication shall be scaled and operated in a way that is compatible with other residential uses in the area.
  - 4. The commercial occupancy shall not be considered accessory to the residential dwelling, and therefore not subject to the accessory home occupation standards. However, the resident and the principal occupant of the commercial area shall be the same and the commercial occupancy shall be limited to no more than 50% of the building. Any greater percentage shall be treated as a mixed use or multi-unit building.
  
- B. **Mixed-use Dwelling.** In districts where mixed-use dwellings are allowed uses, the following standards shall apply:
  - 1. In the mixed-use districts, at least 50 percent of the ground floor of a mixed-use building shall be in a non-residential land use. In the R-3 Zoning District, no more than 50 percent of the total gross floor area of a structure containing a mixed-use, including basement area, shall be devoted to non-residential uses.
  - 2. In the R-3 zone, the use shall be located on a collector street or higher, or otherwise located as a transition between residential and non-residential uses.
  - 3. In the R-3 zone, only commercial uses permitted in the MU-NC district are allowed, and they may be further conditioned, limited, or prohibited through the Use by Special Review process in Section 17-2-7.
  - 4. Mixed-use dwellings in commercial and mixed-use zones may include any commercial use permitted within that zoning district.



- 
- 5 The design and character of all buildings and sites shall be compatible with the predominant character of the surrounding neighborhood. The operating characteristics of a non-residential land use in a predominantly residential neighborhood shall be compatible with the residential uses. For the purposes of this section, operating characteristics shall include, but not be limited to, hours of operation, number of employees and visitors, lighting, noise and traffic.
- C. **Group Home - Small.** In districts where group homes are enabled, they shall meet the following standards and conditions to ensure they are integrated into neighborhoods, have a non-institutional nature, and maintain the residential character of neighborhoods.
1. Group homes shall meet all of the residential design standards applicable in the particular district, and any alterations to support the group living shall be done in a discrete way in accordance with those standards.
  2. In the R-1 districts, no group home shall be located less than 750 from another existing group home, except that the Director may waive the is requirement if separated streets, parks, civic spaces or other transitions that establish different neighborhoods
  3. Group homes shall be supervised at all times, and may include up to 2 resident care givers.
  4. Group homes shall be licensed by, operated by, or owned by a governmental agency or non-profit qualified to provide care and supervision.
  5. Group homes shall not include alcoholism or drug treatment centers, work release facilities or other housing facilities qualifying as residential care – institutional.
- D. **Residential Care – Limited and General.** When Residential Care – Limited or General uses are located in residential districts, they shall meet the following:
- 1 The use shall be located on a collector street or higher, or otherwise located as a transition between the neighborhoods and non-residential uses.
  2. The building and site shall meet all residential design standards so that the use, building, and site is compatible with the neighborhood in terms of scale and intensity of activity.
  3. Any facilities necessary to serve the residents, guests, or to support the staff, which are non-residential in nature shall be located on the most discrete portions of the site and building, and otherwise designed and screened to mitigate impacts on adjacent property.
- E. **Lodging – Bed & Breakfast.** In districts where lodging – bed & breakfast is allowed; it shall meet the following standards.
1. Except when located in the H-A district or non-residential districts, the use is in or within ¼ mile of a mixed-use center, such that guests may experience the convenience of nearby retail, office, entertainment, and recreation amenities;
  2. The applicant shall occupy a residence on the site and must demonstrate a sufficient ability for site maintenance and property management; If the resident occupant is not the homeowner, the homeowner shall provide a notarized authorization with the permit application.
  3. There shall be no more than 5 guest rooms.
  4. Meals or food served in the bed and breakfast shall be prepared in a central kitchen on-site and served solely for bed and breakfast occupants. Cooking facilities, other than convenient in-room appliances and fixtures shall not be permitted in guest rooms.
  5. One off-street parking space shall be provided per guest room on site, although this provision may be waived by the Director if the context and circumstances of each





dwelling unit prove the space unnecessary. However, all parking and access shall be sited to meet all frontage design and site design standards applicable in the district.

#### F. Marijuana Uses.

1. *Intent & Findings.* It is the intent of this Section to prohibit certain uses related to medical marijuana, and, in furtherance of its intent, the Town Council makes the following findings:
  - a. The Colorado Medical Marijuana Code, Section 12-43.3-101, et seq., C.R.S., clarifies Colorado law regarding the scope and extent of Article XVIII, Section 14, of the Colorado Constitution.
  - b. The Colorado Medical Marijuana Code specifically authorizes the governing body of a municipality to "vote to prohibit the operation of medical marijuana centers, optional premises cultivation operations, and medical marijuana-infused products manufacturers' licenses."
  - c. The Colorado Medical Marijuana Code specifically authorizes a municipality "to prohibit the operation of medical marijuana centers, optional premises cultivation operations, and medical marijuana-infused products manufacturers' licenses...based on local government zoning, health, safety, and public welfare laws for the distribution of medical marijuana."
  - d. Based on careful consideration of the Colorado Medical Marijuana Code, Article XVIII, Section 14, of the Colorado Constitution, and the potential secondary effects of the cultivation and dispensing of medical marijuana, and the retail sale, distribution and manufacturing of medical marijuana-infused products, such land uses have an adverse effect on the health, safety and welfare of the Town and its inhabitants.
  - e. As a matter of the Town's local land use and zoning authority, and consistent with the authorization provided by the Colorado Medical Marijuana Code, no suitable location exists within the Town for the operation of medical marijuana centers, medical marijuana cultivation operations or medical marijuana-infused products manufacturing.
  - f. Patients and primary caregivers should otherwise be afforded the protections of Article XVIII, Section 14, of the Colorado Constitution, and Section 25-1.5-106, C.R.S., as further clarified under House Bill 10-1284 adopted by the Colorado Legislature in its 2010 Session and known as the Colorado Medical Marijuana Code.
2. *Authority.* The Town's authority to adopt this Section is found in: the Colorado Medical Marijuana Code, Section 12-43.3-101, et seq., C.R.S.; the Local Government Land Use Control Enabling Act, C.R.S., Section 29-20-101, et seq., C.R.S.; Section 31-23-101, et seq., C.R.S. (municipal zoning powers); and Section 31-15-501, C.R.S., (municipal authority to regulate businesses). The Town Council has authority to prohibit business uses related to recreational marijuana in the Town, deriving from, among other sources, Article XX, Section 6, of the Colorado Constitution, State statutes, including but not limited to C.R.S. § 31-15-401, and Article XVIII, Section 16, of the Colorado Constitution.
3. *Uses Prohibited.* It is unlawful for any person to operate, cause to be operated or permit to be operated any of the following uses:
  - a. Medical marijuana centers, an optional premises cultivation operation or a medical marijuana-infused products manufacturing facility.
  - b. Recreational marijuana establishments
  - c. Marijuana consumption establishments.



4. **Patients and Primary Caregivers.** Nothing in this Section shall be construed to prohibit, regulate or otherwise impair the protections of the use of medical marijuana by patients as provided in Article XVIII, Section 14, of the Colorado Constitution, or the provision of medical marijuana by a primary caregiver to a patient in accordance with Article XVIII, Section 14, of the Colorado Constitution, the Colorado Medical Marijuana Code, and rules promulgated thereunder.
- G. **Gas Stations.** In districts where gas stations are allowed uses, the following standards shall apply:
1. No displays, storage of merchandise, service areas, or other equipment and facilities shall be located closer than 20 feet from the street right-of-way line
  2. If on-site convenience store or other retail or service component is provided, the design, location and operation of these facilities shall meet all applicable non-residential design standards based on the zoning district, building type, and frontage type.
  3. Vehicle circulation shall avoid potential pedestrian/vehicle conflicts on the site and along the streetscape.
    - a. Adequate stacking spaces for automobiles shall be provided on site and outside of setbacks to eliminate any impact on public streets.
    - b. Circulation, stacking and other access issues shall be designed in a manner that has the least impact on pedestrians entering the principal building from public streets and from internal pedestrian or parking areas.
    - c. No access or queuing area or service area shall be provided between the building and the street on any pedestrian oriented streetscape. (Pedestrian Street types in Section 17-3-1 or A Frontages in Section 17-6-3). Use of alleys, internal access streets, and vehicle service areas to the rear of buildings for service areas is required to preserve the streetscape design and development patterns of these areas.
  4. The site shall comply with all landscape and screening standards in Article 8 and the following specific requirements:
    - a. A 6 feet masonry wall shall be installed along property lines where the use abuts residential districts or uses.
    - b. A Type 1 buffer shall be applied along all non-building street edges.
    - c. Any accessory vehicle service areas or entrances shall be setback at least 80 feet from the right-of-way, or screened according to Section 17-8-3.
  5. The maximum height of a canopy shall be 20 feet for flat roofs and 24 feet for pitched roofs.
    - a. Canopies shall be architecturally compatible with the principal building and all other accessory structures on the site with the same or complementary materials, architectural style and colors.
    - b. The material used on the underside of the canopy shall not be highly reflective.
    - c. Setbacks for the canopy shall be measured from the outside edge of the canopy.
    - d. All light sources, including canopy, perimeter and flood lights and lenses, shall be shielded or fully recessed within the roof canopy so that light is contained on-site.
- H. **Automobile Repair – Limited.** In districts where automobile repair – limited is allowed, it shall comply with the following:
1. Motor vehicles being serviced or stored while waiting to be parked in legal parking spaces for that purpose, and shall not be parked on streets, alleys, public sidewalks, or other areas not specifically intended for parking on the approved site plan.



2. All work shall be performed within an enclosed structure.
  3. No equipment, scrap, materials or parts may be deposited or stored on the premises outside of an enclosed structure.
  4. Any area subject to wheeled traffic or storage shall be screened from adjacent or adjoining residential districts by a solid wall or fence, or other buffer that completely screens this area according to Section 17-8-3.
- I. **Manufacturing – Limited / Artisan.** In districts where limited / artisan manufacturing uses are allowed, it shall comply with the following:
1. A retail or service use, such as a display room, sales area, or other sampling is permitted as an accessory use to the manufacturing use.
  2. The total area of the facility shall be less than 10,000 square feet.
  3. No byproducts such as smell, waste, smoke or noise result from the manufacturing that is distinctly different or of greater intensity than other principal commercial uses in the area.
  4. Traffic, customer, and shipping patterns and activities from the manufacturing use are not distinctly different from the principal commercial use in terms of intensity and hours of activity.
- J. **Manufacturing - Breweries, Distilleries, and Wineries.** In districts where breweries, distilleries, and wineries are permitted, they shall comply with the following:
1. In the MU-NC, MU-DT and MU-RC districts these uses shall be permitted only in conjunction with a restaurant, tavern, retails sales, or sales room located on the same premises as the manufacturing of the beverage.
  2. Additional conditions of the site improvement plan or Use by Special Review process may be applied to ensure the use is designed and operated in a manner that does not create nuisance impacts on surrounding uses and is appropriate to the scale, intensity, and character of the district.
- K. **Storage.** In districts where indoor or outdoor storage is permitted by special review, they shall be subject to the following additional conditions:
1. Uses shall be evaluated for whether they are a short-term or interim use of land based on the extent of changes occurring in the area; the type, extent, and character of planned future growth; and the level of investment in the proposed used.
  2. Uses shall be separated from any other indoor or outdoor storage area in the growth management area by at least 3 miles.
  3. Outdoor storage shall be fully screened from adjacent properties.
  4. Security measures are taken to ensure controlled access and 24/7 monitoring of the site, which may require an on-site caretaker residence.

#### 17-4-4 Accessory Uses

- A. **Accessory Uses, Generally.** All principal uses may include accessory uses. All accessory uses, and any accessory use not specifically mentioned in this section, shall be subject to the following general standards:
1. The use and any structure are clearly incidental and subordinate to a principal use and customarily associated with the principal use.
  2. The use is on the same lot as an active principal use.
  3. The use is operated and maintained under the same ownership, or by the same lessee, as the principal use.



4. The use and any structures or other site design elements meet the generally applicable dimension, development, and design standards applicable to the lot.
  5. The use is compatible with the general character of the area and comparable in scale and intensity to other uses in the vicinity.
  6. Any structures or site design elements to support the use are not significantly different from what is typical for other allowed uses in the district, or where different can be screened or located to minimize impact on adjacent property.
  7. No unusual traffic patterns or increases in activity that impact the use and design of streets and public spaces differently than other allowed uses will result.
  8. All uses are conducted, and structures are maintained in a way that is conform with the intent and objectives of all other design and development standards applicable to the property, are consistent with the intent of the zoning district, and do not adversely affect adjacent property in a manner different from other permitted principal uses.
- B. **Accessory Dwelling.** In addition to the standards applicable to all accessory uses in Section 17-4-4.A, the following additional standards apply to accessory dwellings:
1. Accessory dwelling units may be permitted when associated with a detached house, as indicated in Table 5-1, Residential Building & Lot Standards.
  2. Accessory dwelling units may be located in a detached accessory building or located within the principal building (such as an attic, basement, or rear apartment).
  3. The floor area of the accessory dwelling shall not be more than 1,000 square feet or 50% of the principal dwelling unit, whichever is less.
  4. One additional parking space per unit shall be provided on site. The Director may waive this requirement if the context and circumstances prove the space unnecessary due to access to transit, availability of on-street parking on the block, or the configuration of parking available for the principal dwelling having additional options.
  5. Accessory dwelling units shall meet the development and design standards for the lot in Article 5.
  6. The accessory dwelling shall be compatible with principal building, and whether within the principal building or in a detached structure in the following ways:
    - a. The dwelling shall be clearly subordinate to the principal dwelling through the location of access, building entrances, parking, and other design features that accommodate the dwelling.
    - b. Entrances and exterior stairs shall be located towards the interior of the lot or alley, and away from the side lot line of adjacent property.
    - c. Attached accessory structures shall be to the side or rear of the principal structure, or otherwise integrated into the principal dwelling structure.
  7. Prior to occupancy of the unit all building and occupancy permits shall be approved, and inspections conducted demonstrating compliance with applicable building and fire safety codes. These approvals may be conditioned on correcting any deficiencies in the primary dwelling and/or accessory dwelling.
  8. The applicant shall provide a signed and notarized affidavit to be recorded with the applicable county clerk and recorder, attesting to the following occupancy and use standards.
    - a. An individual holding an ownership interest in at least 50% of the property shall occupy either the principal dwelling or the accessory dwelling as their permanent address demonstrated by two forms of proof of residency
    - b. Occupancy of each unit shall comply with all other rules and standards, though each dwelling may be considered as an independent dwelling unit.
    - c. The owner shall verify compliance with these conditions with the Town on an annual basis.
  9. All permitting and impact fees applicable to new construction shall apply to an accessory dwellings, including the provision of additional raw water, per municipal code.



- 
10. Accessory dwellings shall connect to water and sewer lines of the principal dwelling, subject to the requirements of the Town.
- C. **Home Occupation.** In addition to the standards applicable to all accessory uses in Section 17-4-4.A, the following additional standards apply to home occupations:
1. Home occupations are permitted on any property where the principal use is residential dwellings.
  2. The building and site shall retain all appearances as a residence, and no alterations to entrances, storage, window or merchandise displays, parking or other facilities that alter the residential character or clearly indicate non-residential uses shall be permitted.
  3. Employment shall be limited to residents of the principal dwelling and 1 additional non-resident.
  4. The activity shall be operated entirely within the dwelling or accessory buildings, and limited to occupy no more than 50% of the combined floor area of all structures on the property, except permitted home care accessory uses may use the entire space.
  5. No traffic, services, or deliveries shall be generated by the home occupation that is abnormal to a residential neighborhood.
    - a. Activity from deliveries, customer, or patron visits shall generally be limited to between the hours of 7 a.m. and 9 p.m.
    - b. Except for permitted home care accessory uses, customer visits shall be limited to no more than 8 per day and no more than 2 customers at a time.
    - c. All parking necessary for the use shall be confined to the garage, driveway, or street directly in front of the dwelling meeting the applicable Residential Building and Site Design standards in Section 17-5-3.
  6. Sale of any merchandise shall be limited to items that have been made, grown, or prepared on site, or to remote or mail-order sales, where storage and exchange do not happen on site.
  7. No equipment, machinery or operation shall be used in such activities that are perceptible off the premises because of noise, smoke, odor, dust, glare, radiation, electrical interference, or vibration.
  8. In-home dependent care (distinct from commercial buildings and uses), may be permitted subject to all required state licensing and operation provisions.
  9. Home occupations shall not be permitted for the following businesses:
    - a. Animal care or medical services.
    - b. Automobile service, detailing, and repair.
    - c. Food or beverage services.
    - d. Any use involving storage, operation, or parking of equipment and large vehicles such as towing, landscape maintenance, or construction businesses.
    - e. Any use involving the dispensing, use, storage, or processing of hazardous materials.
    - f. Funeral home or mortuary.
    - g. Manufacture or sale of wine, distilled spirits, malt beverages, or similar.
- D. **Outdoor Storage, Residential.** Accessory outdoor storage may be permitted in the residential zoning districts subject to the following standards:
1. *Portable Storage Containers.* Portable storage containers may be permitted subject to the following limitations.
    - a. On lots less than 10 acres, no more than one 40-foot in length container, or two 20-foot in length storage containers, limited to a maximum of 320 square feet and 2,700 cubic feet is allowed
    - b. On lots greater than 10 acres, for each 10-acre increment, one 40-foot in length container, or two 20-foot in length storage containers is allowed.





- c. Containers shall be placed on a paved surface and not over any easement or right-of-way, or otherwise create any sight obstruction.
      - d. Placement is limited to a period reasonably necessary to complete the associated project or task, not to exceed 30 days in one calendar year on the site.
    2. **Recreational Vehicles.** Outdoor storage or parking of recreational vehicles shall be subject to the standards of the Johnstown Municipal Code. Recreational Vehicles do not meet the standards for a dwelling unit, and therefore may not offer long term residential use.
    3. **Other Storage.** All other accessory outdoor storage, other than ordinary and incidental residential accessories, shall either be:
      - a. Completely screened from adjacent property and public streets; or
      - b. Be limited to no more than 72 hours in any 30-day period; or
      - c. Be associated with an active building permit and in which case the storage may extend for the duration of the permit and subject to all other permit conditions.
- E. **Outdoor Storage, Non-residential.** Accessory outdoor storage may be permitted in the non-residential districts subject to the following standards:
  1. In the MU-NC, MU-DT, and MU-RC districts, the storage area shall be located behind the front building line of the principal building.
  2. The storage area shall be fully screened from adjacent properties and public spaces according to the standards and design requirement of Section 17-8-3 and Section 17-8-5, and no materials shall be stacked higher than the screening.
  3. The storage area shall be located in the most remote section of the site or building as possible, but no closer than 20 feet to any street or right-of-way in any in all cases.
  4. Storage areas shall be limited to:
    - a. No more than 200 square feet in the MU-NC district.
    - b. No more than 500 square feet in the MU-DT districts.
    - c. No more than 25% of the building footprint in the MU-RC district.
    - d. No more than 100% of the building footprint in the I-1 district.
  5. The storage area shall be paved per the requirements for parking lots, except a stabilized dust-free and all-weather surface may be used in the I-1 district.
  6. All other outdoor storage shall only be permitted through a Use by Special Review process subject to Section 17-2-7, or where outdoor storage is permitted as a principal use.
- F. **Drive-Through Service Facilities.** In addition to the standards applicable to all accessory uses in Section 17-4-4.A, the following additional standards apply to drive-through service facilities:
  1. Drive-through service facilities may be permitted on any property where the principal use is commercial or service uses.
  2. The service area shall not substantially expand the traffic or vehicle circulation otherwise necessary for the site. In general, the service area shall use the same entrance and exit from the site as the principal use, unless a more remote or discrete service off an alley or secondary street better meets the criteria in this section.
  3. Vehicle circulation shall avoid potential pedestrian/vehicle conflicts on the site and along the streetscape.
    - a. Adequate stacking spaces for automobiles shall be provided on site and outside of setbacks to eliminate any impact on public streets.
    - b. Stacking areas shall generally accommodate at least 3 vehicles for non-food service uses and 8 vehicles for food-service uses, but may be modified for greater or lesser stacking dependent on the use and the context of the site.



- c. Circulation, stacking and other access issues shall be designed in a manner that has the least impact on pedestrians entering the principal building from public streets and from internal pedestrian or parking areas.
        - d. No access or queuing area shall be provided between the building and the street on any pedestrian oriented streetscape. (Pedestrian or Parkway / Bikeway street types in Section 17-3-1 or A Frontages in Section 17-6-3). Use of alleys, internal access streets, and the rear of buildings for drive-through services is required to preserve the streetscape design and development patterns of these areas.
  - 4. Service areas and windows shall be located in the most remote location possible, considering adjacencies to public streetscapes, residential property, or other sensitive adjacencies.
    - a. Signs, speakers, or service facilities shall not be visible or audible from the residential property. Operational limitations and additional screening or buffers may be required beyond the standards of Section 17-8-3 to ensure compatibility.
    - b. Signs, speakers, or service facilities shall be located on the side or rear of buildings to minimize impact on streetscapes.
    - c. To the maximum extent practicable, drive-through lanes shall not be located between the principal building and street or other public gathering places. Where this is not possible, they shall be setback at least 20 feet for the right-of-way to permit additional landscape design and impact mitigation.
    - d. Any stacking area, drive-through circulation lanes or drive-through facilities visible from the streetscape shall require enhanced landscape and frontage design elements beyond the standards of Section 17-8-2 and 17-6-3.
  - 5. The Director may require any drive-through service facility that does not clearly meet these standards and criteria to be reviewed subject to the procedures for Use by Special Review in Section 17-2-7.
- G. **Outdoor Display and Service Areas.** In addition to the standards applicable to all accessory uses in Section 17-4-4.A, the following additional standards apply to outdoor display and service areas, such as sidewalk seating and dining or sidewalk sales:
- 1. Outdoor display and service areas may be permitted on any property where the principal use is commercial or service uses.
  - 2. Outdoor display and areas shall be located on the same lot as the principal use or along the street frontage immediately abutting the use in the case of buildings along streets designed to the Pedestrian standards in Section 17-3-1 or A Frontages in Section 17-6-3.
  - 3. The area shall be limited to no more than 50% of the ground floor area of the principal use, or may be subject to special use review for larger areas..
  - 4. Display and service areas shall not be arranged where they interfere with pedestrian movements or building access, or with clear vision areas. At least 5 feet clear or at least 50% of the width any sidewalk, whichever is greater, shall remain clear and unobstructed by any display or service areas located on a sidewalk.
  - 5. The area may be located in parking areas, provided it does not interfere with adequate parking and circulation of the entire site. The permanence of any structures shall be considered in evaluating the impact on adequate parking needs for the site.
  - 6. The display and service area may be excluded from required parking for that retail square footage, up to 40 spaces.
  - 7. The area shall be at least 100 feet from any residential zoning district and screened from view along any property line abutting a residential use.
  - 8. The hours of operation shall be between 7 a.m. and 10 p.m., except where the use is more than 500 feet from any residential district.
  - 9. Any outdoor display or service area beyond these requirements may only be permitted as an allowed outdoor sales principal use or subject to the general accessory use provisions in 17-4-4.A.



H. **Small Renewable Energy Equipment.** Consumer-scale renewable energy equipment may be an accessory use to another permitted use subject to the following additional standards, and provided it meets all other requirements for a building permit. Any renewable energy facility that does not meet the limits of this section shall be considered a public utility service use and only allowed as permitted in Table 4-4 as a principal use of land.

Table 4-4: Accessory Renewable Energy Equipment		
	Accessory Use by Building Permit	Accessory Use through Use by Special Review
<b>Solar</b>		
<i>Building Mounted</i>	<ul style="list-style-type: none"> <li>▪ 8" max. off and parallel with pitched roof</li> <li>▪ 5' max. off a flat roof</li> <li>▪ Any installation projecting more than 3' off a flat roof shall be screened from ground level or adjacent property by a parapet, or other architectural screen integral to the design of the building.</li> </ul>	<ul style="list-style-type: none"> <li>▪ 8' max. off a roof or building wall</li> </ul>
<i>Ground Mounted</i>	<ul style="list-style-type: none"> <li>▪ 6' high max</li> <li>▪ 10' setback min.                             <ul style="list-style-type: none"> <li>▪ Screened from adjacent property and the ROW in the same manner as all other mechanical equipment.</li> </ul> </li> </ul>	<ul style="list-style-type: none"> <li>▪ 10' max high</li> </ul>
<b>Wind</b>		
<i>Building Mounted</i>	<ul style="list-style-type: none"> <li>▪ 4' max. above roof (residential buildings)</li> <li>▪ 8' max. above roof (non-residential buildings)</li> </ul>	<ul style="list-style-type: none"> <li>▪ 12' max. above roof (residential buildings)</li> <li>▪ 20' max. above roof (non-residential buildings)</li> </ul>
<i>Ground Mounted</i>	<ul style="list-style-type: none"> <li>▪ 30' max. height (residential districts)</li> <li>▪ 45' max. height (non-residential districts)</li> </ul>	<ul style="list-style-type: none"> <li>▪ 45' max. height (residential districts)</li> <li>▪ 60' max. height (non-residential districts)</li> </ul>

I. **Craft Food & Beverage Manufacturing.** Production, retail sale, and distribution of food and beverages, such as micro-brewery, bakery, or other on-site manufacturing, is allowed accessory to an otherwise permitted restaurant or customer service use, provided:

1. That all manufacturing areas, or any warehousing, shipping and distribution facilities are clearly subordinate to the principal use as a restaurant.
2. No byproducts are generated such as offensive smell, waste, smoke or noise resulting from the manufacturing that is distinctly different or of greater intensity than the principal use or similar permitted principal uses in the district.
3. Traffic, customer, and shipping operations and activities from the manufacturing use are not distinctly different than the principal use, both in terms of intensity and hours of activity.

Otherwise such uses are only permitted as a principal manufacturing use.

J. **Recycling Collection Point.** Small recycling collection areas or similar drop-off kiosks may be accessory use to an existing commercial or industrial land use, limited to the following:

1. Facilities shall not be located within 250 feet of any residential zoning district.
2. Permeant or temporary structures are limited to no more than 300 square feet and shall be setback at least 20 feet from any public right-of-way.
3. Facilities shall permit adequate circulation and access for drop off of materials, and for the periodic removal of materials by larger vehicles.
4. The facility shall be placed on asphalt or concrete and shall not impact any landscaping or landscaped areas.
5. Facilities shall be placed on a more remote portion of the site, appropriately screened from adjacent property or rights-of-ways, and otherwise located in a manner to limit adverse impacts on adjacent property and the public streetscape.
6. The facility shall accept only non-perishable recyclable waste, or may be a collection point for donation of reusable, non-perishable household items such as books or clothing.
7. No processing or other power-driven mechanical devices or facilities are permitted.



8. Containers shall be constructed and maintained with durable waterproof and rustproof material, covered when the site is not attended, and shall have sufficient capacity according to a collection schedule. All material shall be stored in the unit and shall not be left outside of the unit when unattended.
9. The facility shall be maintained in a clean and sanitary manner, free of litter and any other undesirable materials.
10. Containers shall be clearly marked to identify the type of material that may be deposited. The facility shall be clearly marked to identify the name and telephone number of the facility operator and the hours of operation and display a notice stating that no material shall be left outside the containers.

**17-4-5 District Performance Standards**

A. **General Operation & Performance Standards.** All principal and accessory uses in mixed-use and non-residential districts shall be operated in a manner that meets the performance standards in Table 4-5.

<b>Table 4-5: Non-residential District Performance Standards</b>				
	<i>MU - NC</i>	<i>MU-DT &amp; MU-GC</i>	<i>I-1</i>	<i>I-2</i>
<b>Daytime Noise.</b> Noise levels during business hours (7AM-10PM) [1]	60db	60db	70db	80db
<b>Nighttime Noise.</b> Noise levels during quiet hours (10PM – 7AM) [1]	50db	55db	65db	75db
<b>Impacts Outside the Building.</b> No heat, odor, dust, glare, radiation, vibration, smoke, or fumes shall be produced that is perceptible outside a building and could become a nuisance to adjacent uses shall be produced. [2]	☑	☑		
<b>Impacts Beyond the Property Line.</b> No heat, odor, dust, glare, radiation, vibration, smoke, or fumes shall be produced that is perceptible beyond the property line and could become a nuisance to adjacent uses shall be produced. [2]	☑	☑	☑	
<b>Impacts to Health or Property.</b> No heat, odor, dust, glare, radiation, vibration, smoke, or fumes shall be produced that be damaging to humans or property beyond the property line.[2]	☑	☑	☑	☑
<b>Lighting &amp; Right-of-way.</b> Lighting measured at the property line adjacent to right-of-way	1.0 FC	1.5 FC	1.0 FC	1.0 FC
<b>Lighting &amp; Residential Uses.</b> Lighting measured at the property line adjacent to residential uses	0.1 FC	0.5 FC	0.1 FC	0.1 FC
<b>Lighting &amp; Same or More intense Uses.</b> Lighting measured at the property line adjacent to the same or more intense zoning districts	1.5 FC	2.0 FC	2.0 FC	2.0 FC

[1] Noise standards shall be enforced consistent with the Town noise control standards in the Johnstown Municipal Code. In the hours between 7:00 a.m. and the next 7:00 p.m. the noise levels may be increased by ten dB for a period not to exceed fifteen minutes in any one-hour period.

[2] Pollution and general nuisance standards shall be enforced in accordance all other health, sanitation, and nuisance standards of the Johnstown Municipal Code

B. **Conditions & Compatibility.** The Town may impose conditions upon the approval of any development application or any permit to ensure that it is compatible with adjacent uses and compliant with the district performance standards. Conditions may include:

1. Hours of operation and deliveries.
2. Location, design, and screening of outdoor activity areas or other site activities that generate potential adverse impacts to adjacent uses.



3. Placement of facilities that require regular service of large or utility vehicles, such as trash receptacles or loading areas.
4. Location of outdoor speakers, communication, or other amplification systems.
5. Light height, intensity, shield and design, and hours of partial and full illumination.





## Article 5. Residential Development & Design

- 17-5-1 Intent & Applicability
- 17-5-2 Residential Building Types
- 17-5-3 Neighborhood Design
- 17-5-4 Courtyard Pattern
- 17-5-5 Conservation Pattern
- 17-5-6 Manufactured & Small Format Housing District

### 17-5-1 Intent & Applicability

A. **Intent.** The Residential Development Standards have the following intent.

1. Provide housing variety within neighborhoods and among different neighborhoods, and ensure compatible transitions between different residential building types.
2. Improve the appearance and livability of neighborhoods with good civic design.
3. Design and locate parks, trails and other open spaces as focal points that shape neighborhood character.
4. Design neighborhoods with slow-speed streetscapes, well-connected sidewalks and trails, and shade, and enclosure provided by street trees
5. Reinforce the distinct character of different neighborhoods based on their context:
  - a. Prioritize housing and walkable neighborhoods with convenient access to services, amenities, and destinations.
  - b. Promote lower-density rural neighborhoods with access to large, contiguous open spaces and natural areas.
6. Orient all buildings and lots to the public street or to common open spaces, and locate active social spaces along the streetscape
7. Design buildings with human-scale details such as entry features, windows and doors, massing elements, and ornamental features, particularly where these features create compatibility among a mix of building types.
8. Promote lasting and sustained investment in neighborhoods with quality design.

B. **Applicability**

1. The standards in this Article shall generally apply to all residential development, except where stated that sections only apply to specific building types, specific districts, or specific scales of projects.
2. Modification or additions to buildings or sites shall meet these standards to the extent of the modification or addition, except that the Director may waive any requirement that conflicts with the consistent design of an existing building or conflicts with the prevailing character on the block or immediate vicinity of the project.
3. The standards shall not apply to ordinary maintenance of existing buildings, except that maintenance to any building may not occur in a manner that moves the building further from compliance with these standards.



17-5-2 Residential Building Types

A. Building Types & Development Standards. The development standards for residential zone districts shall be based on the different building types permitted in each zone district, specified in Table 5-1, Residential District Building & Lot Standards. The design standards in other sections of this article, or any other adopted design guidelines, may further affect the design and location of each building type in a specific application.




Figure 5-1 Building Types Building types in Table 5-1 are distinguished based on lot sizes, unit configuration, building footprints, building massing, building placement, and frontage designs. This diagram illustrates these key standards in Table 5-1 applied to a typical lot.



Table 5-1: Residential Building & Lot Standards

Zoning Districts								# of Units		Development Standards							
A	RE	R-1	R-2	R-3	MU	PD-M	Building / Lot Types	Principal	Accessory	Minimum Lot Standards			Minimum Setbacks [4]				Building Height
										Size	Width [1]	Lot Open Space	Front [2]	Interior Side	Corner Side [1]	Rear	
■	■						Detached House – Farmstead	1	1	40 ac.	200' +	n/a	35'	25'	35'	50'	35' / 2.5 stories
	■	■					Detached House – Estate Lot	1	1	40K s.f.	80' +	n/a	35'	25'	35'	50'	35' / 2.5 stories
		■	■				Detached House – Large Lot	1	1	12K s.f.	65'	50%	25'	7'	15'	20'	35' / 2.5 stories
		■	■	■			Detached House – Standard Lot	1	1	6K s.f.	50'	30%	25'	5'	10'	20'	35' / 2.5 stories
		◇	■	■			Detached House – Small Lot	1	n/a	4K s.f.	35'	20%	15'	4'	10'	8'	35' / 2.5 stories
			◇	◇		■	Detached House – Compact Lot	1	n/a	1.5K s.f.	28'	n/a	15'	4'	10'	8'	24' / 2 stories
			■	■			Duplex / Multi-unit House	2 - 6	n/a	6K s.f.; 2.5K s.f. per unit	50'	25%	25'	5'	10'	20'	35' / 2.5 stories
			■	■	■		Row House	3 - 8	n/a	1.5K s.f. per unit	18' per unit	15%	15'	5' [3]	10'	8	40' / 3 stories
			□	■	■		Apartment – Small Lot	3 - 12	n/a	5K – 14K s.f.	50' – 100'	Per Table 3-5	15'	5' [3]	10'	20'	40' / 3 stories
				■	■		Apartment – Medium Lot	13 - 24	n/a	14K – 30K s.f.	100' – 200'	Per Table 3-5	25'	5' [3]	10'	20'	50' / 4 stories
				□	□		Apartment – Large Lot / Complex	25 +	n/a	30K + s.f. +	100' +	Per Table 3-5	25'	5' [3]	20'	20'	65' / 6 stories
■	■	■	■	■			Accessory Buildings	see 17-4-3.B		See Residential Accessory Buildings in Section 17-5-2.C							
						■	Small Format Housing Project			See Small Format & Manufactured Housing Projects in section 17-5-6.							

■ Permitted

◇ Limited to Courtyard Pattern only per Section 17-5-4 or to meet the housing diversity requirements of Section 17-5-2.D

□ Limited to locations along Collector or Arterial streets, or otherwise incorporated into lots or blocks that are part of the civic and open space system in Section 17-3-2.

[1] Corner lots shall add at least 5' to the required lot width. Otherwise, all lots shall meet both the minimum width and size specified in the table, and width is determinative of the building / lot type.

[2] Front setbacks may be modified based on context and the Frontage Design standards in Section 17-5-3.A.

[3] Row Houses and Apartments shall have a minimum 10' side setback when abutting lots with a detached house, and at least 6" for every 1' of building height.

[4] Buildings and structures shall be setback from plugged and abandoned wells at least 50 feet; and from oil and gas facilities at least 250 feet.

**B. Dimension Exceptions.** The following are exceptions to setback and building dimensions standards established in Table 5-1: Residential Building Type & Development Standards.

1. **Lot and Building Configurations.**
  - a. Row houses and side-by-side duplexes may have individual units platted on separate lots, provided the building meets the standards in Table 5-1 and each unit meets any per-unit or proportional standards for each lot.
  - b. Side lot easements between abutting lots may be granted in association with a plat to have the effect of “zero lot line” patterns. Easements for exclusive use of the side yard may be granted to the abutting owner to meet the lot open space requirements and design standards in Section 17-5-3.C for the grantee yet maintain the required setbacks from the platted lot line for each building in Table 5-1 for the grantor. Easements shall be identified on a recorded plat or in an agreement, and account for all access and maintenance scenarios for the lots, open space, and buildings.
  - c. The front setbacks for each building may be modified according to the frontage types and Frontage Design Standards in Section 17-5-3.A.
  - d. Lots may be configured in a Courtyard Pattern as provided in Section 17-5-4.
  - e. Lots may be configured in a Conservation Pattern as provided in Section 17-5-5.



**Figure 5-2 Side Lot Easements**

Side lot easements may be used to provide more contiguous areas to meet the lot open space requirements and have the effect of a zero-lot line configuration. (17-5-2.B.1.b.).

2. **Setback Encroachments.** The following encroachments into the required setback are permitted, except in no case shall this authorize structures that violate the provisions of any easement.
  - a. Primary entrance features such as an open sided front porch may encroach beyond the required front building line, as specified in Section 17-5-3.A.3.
  - b. Structural projections such as bay windows, balconies, canopies, chimneys, eaves, cornices, awnings, open fire escapes, egress wells, or other non-foundational overhangs or projections may extend up to 4 feet from the foundation and encroach into the setback, but no closer than 2 feet from any lot line. This exception shall be limited to no more than 20% of the total area of a building elevation.
  - c. Unenclosed and un-roofed decks or patios at or below the first-floor elevation may extend into the rear or side setback but no closer than 3 feet to any lot line.
  - d. Ground-mounted mechanical equipment, condensers, meters, and utility boxes accessory to the building may be located in the side or rear setback provided that



it extends no more than 6 feet from the principal building, no closer than 3 feet to the lot line, and is screened from public right-of-way by structures or landscape. These limitations do not apply to any utility structures otherwise authorized to be located according to easements or in the right-of-way, which shall follow the location and design standards of those specific authorizations.

- 3. **Height Exceptions.** The following are exceptions to the height limits in Table 5-1:
  - a. Building elements integral to the design and construction of the building, such as parapet walls, false mansards, or other elements essential to a quality appearance may extend up to 6 feet above the roof deck of a flat roof.
  - b. Architectural features such as chimneys, ornamental towers and spires, and similar accessory elements may extend up to 50% above the actual building height, provided they are integral to the specific architectural style of the building and are less than 15% of the building footprint.
  - c. Functional and mechanical equipment such as elevator bulkheads, cooling towers, smokestacks, roof vents, or other equipment may be built up to their necessary height in accordance with building codes provided they are screened according to the standards of this code.

C. **Accessory Buildings - Residential.** Accessory buildings shall be permitted in association with and on the same lot as a principal building or use and are subject to the following additional limitations.

- 1. **Accessory Building Standards.** Accessory buildings shall be permitted based on the lot size and type of structure, subject to the standards in Table 5-2: Residential Accessory Structures:

Table 5-2: Residential Accessory Structures				
Type	Quantity	Size	Height	Setbacks
Minor Structure (small shed, and similar structures)	<ul style="list-style-type: none"> <li>▪ 1 / lot;</li> <li>▪ + 1 / each 10k s.f.;</li> <li>▪ Maximum of 3</li> </ul>	<ul style="list-style-type: none"> <li>▪ 200 s.f. max each structure</li> </ul>	<ul style="list-style-type: none"> <li>▪ 12' max</li> </ul>	<ul style="list-style-type: none"> <li>▪ 5' side or rear</li> <li>▪ Behind the rear building line of the principal structure</li> </ul>
Secondary Building (detached accessory building, garage, etc.)	<ul style="list-style-type: none"> <li>▪ 1 / lot</li> <li>▪ 2 / lot, over 40K s.f.</li> <li>▪ Apartments: Min. Needed to provide parking or storage for units</li> </ul>	<ul style="list-style-type: none"> <li>▪ 50% of principal building footprint up to 1,000 s.f. max. each structure</li> </ul>	<ul style="list-style-type: none"> <li>▪ 16' max,</li> <li>▪ 25' if an ADU or living space is over a functional garage;</li> </ul>	<ul style="list-style-type: none"> <li>▪ At least 10' behind the front building line of the principal structure</li> <li>▪ Per Table 5-1</li> </ul>
Any building over 10' high or more than 120 square feet shall meet the design standards in Section 17-5-2.C.3.				
Out-building (large storage building, barns, etc.)	<ul style="list-style-type: none"> <li>▪ 1 / lot over 40K s.f.</li> <li>▪ + 1 / each 3 ac.</li> <li>▪ Maximum of 5</li> </ul>	<ul style="list-style-type: none"> <li>▪ 2,500 s.f. max</li> <li>▪ No size or height limit in H-A district, provided structure is accessory to agriculture use.</li> </ul>	<ul style="list-style-type: none"> <li>▪ 25' max</li> </ul>	<ul style="list-style-type: none"> <li>▪ 10' from side and rear;</li> <li>▪ 35' from any street side; and</li> <li>▪ Behind the rear building line of the principal structure</li> </ul>

- 2. **General Standards.**
  - a. All accessory buildings shall be clearly incidental and subordinate to the principal building and use, in terms of scale, location, and orientation.
  - b. Minor accessory structures 200 square feet or less, less than 10 feet high, and not on a foundation or slab should be movable and are subject to meeting all easement conditions.





3. **Secondary Building Standards.** In any residential zone district, secondary buildings over 200 square feet or over 10 feet high shall meet the following massing and design standards to ensure compatibility with the principal structure:
  - a. The wall height shall be no more than 9 feet above each finished floor, except that gables, dormers, or other subordinate walls may support a pitched roof.
  - b. The roof peak or other top of structure shall not exceed 20 feet above finished floor for pitched roofs with a 6:12 pitch or greater, and no more than 16 feet for shed roofs or pitched roofs below a 6:12 pitch.
  - c. The design shall be compatible with the principal building considering materials, architectural details and style, window and door details, and roof pitch and form.
  - d. Secondary buildings with vehicle access directly from an alley or shared easement shall be situated to avoid parking that encroaches in the alley or easement. They may be built with the access 3 feet from the alley or shared easement, or with the access at least 20 feet from the alley or shared easement.


D. **Housing Diversity.** Residential projects shall meet the following housing diversity guidelines based on the scale and context of an overall development. Diversity shall be based on the categories and building types indicated in Table 5-3 and be applied according to Table 5-4.

Table 5-3: Housing Categories & Building Types		
Category I: Detached Houses	Category II: Mixed & Multi-unit Housing	Category III: Multi-family and Mixed Use
<ul style="list-style-type: none"> <li>▪ Detached House -Large Lot</li> <li>▪ Detached House -Standard Lot</li> </ul>	<ul style="list-style-type: none"> <li>▪ Detached House – Small Lot</li> <li>▪ Detached House – Compact Lot</li> <li>▪ Duplex / Multi-unit House</li> <li>▪ Row house</li> <li>▪ Apartment - Small</li> </ul>	<ul style="list-style-type: none"> <li>▪ Apartment – Medium</li> <li>▪ Apartment – Large / Complex</li> <li>▪ Apartment – Mixed-use Building</li> </ul>

Table 5-4: Housing Diversity	
Project Scale	Required Mix
< 40 Units	no requirement
40 – 80 Units	<ul style="list-style-type: none"> <li>▪ At least 2 building types</li> <li>▪ No more than 70% of one type</li> </ul>
81 - 200 Units	<ul style="list-style-type: none"> <li>▪ At least 3 building types</li> <li>▪ No more than 50% of one type</li> <li>▪ At least 25% Category II</li> </ul>
201+ Units	<ul style="list-style-type: none"> <li>▪ At least 4 building types</li> <li>▪ No more than 50% of one type</li> <li>▪ At least 50% from Category II</li> </ul>

### 17-5-3 Neighborhood Design

- A. **Frontage Design.** The design of lot frontages establishes the relationship of buildings and lots to the streetscape. Frontage design includes building placement, lot access, garage extent and location, and entry features. Frontage Types designed according to the standards and design objectives of this sub-section may be used to modify the front setback established in Table 5-1.
1. *Design Objectives.* Frontage types shall be applied to meet the following design objectives:
    - a. Enhance the image of neighborhoods by coordinating streetscape investment with private lot and building investment.
    - b. Design frontages to the context of the neighborhood, block, and street.
    - c. Coordinate development across several lots, considering the cumulative impacts on streetscapes from access, parking, and landscape design.
    - d. Orient all buildings and lot frontages to the streetscape, while still promoting effective transitions from public spaces to private spaces on the lot.
    - e. Limit the impact on the neighborhood streetscape from frontages designed for car access, particularly on narrower lots or walkable streets and neighborhoods.
    - f. Provide outdoor social spaces that activate the streetscape.
    - g. Use front entry features to reinforce neighborhood character, promote unique design, create subtle variation in building patterns, and create a consistent, human-scale connections to the streetscape.
  2. *Frontage Design Standards.* Frontage types shall be designed according to the standards in Table 5-5, Residential Frontage Types & Design Standards. Sub-sections following the table provide specific design strategies and techniques to be used to meet these standards. Where multiple frontage types are permitted, the applied frontages should be similar for all lots on the same block face or gradually transition to different building placement and frontage types on adjacent lots. In general, the front building line (FBL) of adjacent buildings shall not differ by more than 5 feet.



**Figure 5-3 Frontage Design Standards**

This diagram illustrates the key elements of frontage design in Table 5-5: (A) front building line; (B) front entry features, (C) driveway widths (applies to the first 30' of frontage depth or up to the front building line); (D) garage extent and location, and (E) landscape areas. These elements determine the relationship between the building, the lot, and the streetscape, and affect the character of the area when applied across multiple lots on a block.



**Table 5-5: Residential Frontage Types & Design Standards**

Frontage Element	Terrace Frontage	Neighborhood Frontage	Suburban Frontage	Buffer Frontage
Illustrative Concept				
Application	A RE R-1 R-2 R-3	■ ■ ■	■ ■	■ Any permitted non-residential building in all residential districts Limited to Apartments – Large/Complex on lots wider than 200'
Front Building Line	10' – 25'	25' – 60'	25' +	35'+
Front Entry Feature	Required, Section 17-5-3	Required, Section 17-5-3	Required, Section 17-5-3	Optional
Driveway Width	15% of lot width, up to 20' maximum	20% of lot width, up to 20' maximum	40% of lot width, up to 27' maximum	25% of lot width, up to 36' maximum
Garage Limitations	<ul style="list-style-type: none"> <li>20% of front facade;</li> <li>Flush or behind FBL;</li> <li>up to 35% if 12'+ behind FBL</li> </ul>	<ul style="list-style-type: none"> <li>35% of front facade;</li> <li>Flush or behind FBL;</li> <li>up to 45% if 12'+ behind FBL</li> </ul>	<ul style="list-style-type: none"> <li>50% of front facade;</li> <li>12' in front of FBL, max</li> <li>Up to 60% of facade if behind FBL</li> </ul>	<ul style="list-style-type: none"> <li>45% of front facade; and</li> <li>12' in front of FBL, max; or</li> <li>No requirement if set back more than 60' from front lot line and behind FBL.</li> </ul>
Frontage & Front Yard Landscape [1]	<ul style="list-style-type: none"> <li>60% minimum landscape; and</li> <li>40% maximum hardscape.</li> </ul>	<ul style="list-style-type: none"> <li>75% minimum landscape; and</li> <li>25% maximum hardscape.</li> </ul>	<ul style="list-style-type: none"> <li>50% minimum landscape; and</li> <li>50% maximum hardscape</li> </ul>	<ul style="list-style-type: none"> <li>Type I: 6' + buffer on constrained sites or minor streets.</li> <li>Type II: 15' + buffer generally.</li> <li>Type III: 30' + buffer on sites over 2 acres or major streets.</li> </ul>


■ Permitted

[1] Landscape refers to allocation of space between front lot line and front building line. See Section 17-8-2 Landscape Design for planting requirements, standards, and specifications.




- 3. **Front Entry Features.** Front entry features create human-scale massing elements that relate buildings to the frontages and streetscape, and provide outdoor social spaces that activate the streetscape. The entry feature standards and design techniques in Table 5-6 shall be used where entry features are required by frontage types in Table 5-5, and are otherwise recommended to meet the standards of Table 5-7, Building Design Standards and achieve the design objectives of this Section.

Table 5-6: Front Entry Features			
Design Element	Minimum Width	Minimum Depth	Details & Ornamentation
Porch	10'	7'	<ul style="list-style-type: none"> <li>Decorative railing or wall 2.5' to 4' high along at least 50% of the perimeter.</li> <li>Covered by a roof, canopy, pediment, or similar structure.</li> </ul>
Stoop	8'	6'	<ul style="list-style-type: none"> <li>Decorative railing or walls along steps and side of stoop.</li> <li>Ornamental features accent the front entrance, such as a canopy, pediment, transom windows, enlarged trim and molding, or other similar accents that emphasize the door over other facade features.</li> </ul>
Entry Court	12', but not >50% of front facade	8'	<ul style="list-style-type: none"> <li>Recessed entry within the building footprint.</li> <li>Ornamental pillars, posts, or landscape accent the pedestrian entrance and create a gateway into the entry court.</li> </ul>
General Design			<ul style="list-style-type: none"> <li>Entry features shall have a sidewalk or path at least 4 feet wide directly connecting the entry feature to the public sidewalk or street or internal civic space. For Suburban or Buffer Frontages this can connect via the driveway.</li> <li>Entry features shall be integrated into the overall building design including compatible materials, roof pitch and forms, and architectural style and details.</li> <li>Entry features shall be single-story, so that any roof structure and any ornamentation occur between 8' and 14' above the floor-level of the entry feature.</li> <li>Entry features meeting these standards may encroach up to 10 feet in front of the front building line, but not closer than 5 feet to a public or common property line, provided they are unenclosed on all sides that project into the setback.</li> <li>Any building with more than 150 feet of front facade, or any side greater than 200 feet and permitted within 20 feet of the street, shall have 1 entry feature for every 100 linear feet of building frontage on the street.</li> </ul>



**Figure 5-4 Front Entry Features - Types**

The porch, stoop, and entry court are three distinct types of entry features that create active, social spaces and human-scale details on the residential frontages. Spaces with a minimum width (A) and depth (B) specified in Table 5-6 provide usable social spaces, activate the streetscape and frontage, and contribute to the massing and modulation required by the building design standards.



**Figure 5-5 Primary Entry Feature - Encroachments**

Front entry features meeting the standards of this section create social spaces that help activate streetscapes, and create a variety of human-scale details along blocks. These features may encroach into the front setback to improve the frontages along blocks. (Table 5-6)






Figure 5-6 Primary Entry Feature - Large Buildings  
Front entry features should be more frequently located on larger buildings with wall planes in close proximity to the street. This breaks up the building massing and activates the streetscape. (Table 5-6)

4. **Driveway Limits.** The following driveway standards apply to the driveway limits in Table 5-5: Residential Frontage Types & Design Standards:
  - a. Front driveway access is prohibited for any lot served by an alley. The Director may waive this prohibition in cases where the alley does not provide adequate access and according to alternative compliance criteria in Section 17-5-3.A.6
  - b. Driveway width limits apply to the first 30' of the lot depth, or up to the Front Building Line, whichever is less.
  - c. Any garage meeting the location and design standards may have a driveway expanded to the width of the entry in front of the garage entry, but no closer than 10 feet to the front lot line.
  - d. In cases where standards prohibit front-loaded driveways and garages and on a particular lot, a range of options with different access patterns and garage locations may be used, including detached garages, single-line or shared drives, and internal common lanes or alleys.
  - e. All required parking shall be sited outside of the frontage area.
  - f. Driveways and parking areas are subject to Design Standards for width and access connections to any public right of way or alley.




Figure 5-7 Application of Driveway Limits

Driveway limits shall apply to the first 30' or up to the Front Building line, whichever is less; except any front-loaded garage meeting these standards may have a driveway expanded to the width, provided the expanded area is no closer than 10' from the front lot line.



- 5. **Front-Loaded Garage Design.** The following garage design standards apply to the garage limits in Table 5-5: Residential Frontage Types & Design Standards:
  - a. Garage limits apply to front-loaded garages. Alternatives such as detached garages, side- or rear-loaded garages, or attached garages that are accessed from the front but located on the rear of buildings are not subject to the limits.
  - b. Garage limits shall be measured by the exterior walls of the floor plan or other clearly distinguished massing element on the front façade, not including trim.
  - c. Any front-loaded garage permitted to project in front of the main mass of the house shall:
    - (1) Have a front entry feature associated with the non-garage mass of the building that projects in front of or is no more than 4 feet behind the garage entry and is at least 10 feet wide; and
    - (2) Be limited to wall planes of no more than 200 square feet with garage entries, using step-backs of a bay by at least 4 feet and/or ornamental features such as canopies, eyebrows, or cantilevers to break up the wall plane.
  
- 6. **Alternative Compliance.** Alternative compliance to the frontage design standards established in Section 17-5-3.A, Frontage Design may be authorized according to the process and criteria in Section 17-2-6, Alternative Compliance, and any of the following additional applicable criteria:
  - a. The context presents a clear pattern of existing buildings and lots on the same block and opposite block face with a different arrangement in terms of the front building line, driveway access patterns, and extent and placement of garages.
  - b. An alternative design allows the building, garage, and access to be sited in a way that preserves significant or unique topography or other natural features on the site.
  - c. The specific standard is not practical due to the context and location of the lot or other physical conditions beyond the specific building and site not created by the landowner; and
  - d. In all cases the deviation is the minimum necessary to address the circumstance, the alternative equally or better meets the design objectives of this Section, and there are no negative impacts to other design standards applicable to the building or site.
  
- B. **Building Design.** Building design refines the scale and form of buildings beyond basic height, setback, and lot coverage standards.
  - 1. **Design Objectives.** The following design objectives shall be used in applying the building design standards in this section.
    - a. Relate buildings to public realm and streetscape in a consistent manner and create compatible massing along the block face.
    - b. Arrange buildings in a way that creates meaningful outdoor spaces on the site, with building designs that define and activate these spaces.
    - c. Blend a variety of building sizes and types and create compatible transitions between adjacent buildings of different scales by mimicking similar massing and proportions nearest to adjacent development.
    - d. Use materials and human-scale architectural features to create depth, texture, variation, and visual interest, particularly on larger facades, along streetscapes, near active open spaces, or near adjacent lots and buildings.
    - e. Encourage unique architectural expression and promote the use of key details and design characteristics inherent in the chosen style for the building.
    - f. Promote enduring investments with the application of durable, quality materials.




2. **Residential Building Design Standards.** Table 5-7, Building Design Standards provides standards for massing and facade design to meet the design objectives. Sub-sections following the table provide specific design strategies and techniques to be used to meet these standards.

Table 5-7: Residential Building Design Standards			
Design Detail	Building Type	Detached House (all), and Multi-Unit House	Row House, Apartment (all)
<p><b>Wall Plane Limits.</b> Maximum wall plane without a massing variation of 4'+ on at least 25% of elevation.</p>		800 s.f. or 45 linear feet	1,200 s.f. or 70 linear feet
<p><b>Blank Wall Limits.</b> Maximum wall plane without modulation on at least 20% of the wall plane.</p>		500 s.f. or 30 linear feet	800 square feet or 45 linear feet
<p><b>Roof Plane Limits.</b> Maximum roof plane without offset of at least 2', complex planes, dormers or gables.</p>		600 s.f. or 35 linear feet	1,000 s.f. or 50 linear feet
<p><b>Transparency.</b> Minimum window and door openings per elevation</p>		<p>Front – 20% Side – 8% Street-side - 15% Rear - 8%</p>	<p>Front – 20% Side – 8% Street-side - 15% Rear - 8%</p>
<p>Materials</p>		<p>Exterior walls of garages may be excluded from this requirement, provided the wall is not street-facing, and other architectural details and materials are used to meet any applicable blank wall limits.</p> <ul style="list-style-type: none"> <li>▪ Primary Material – 55% - 75%</li> <li>▪ Secondary Material -20% - 30% (limit 2, one of which must be masonry)</li> <li>▪ Accent Material - 5% - 15% (limit 2, which may include architectural decorative metals)</li> <li>▪ Limit – 4 materials total</li> </ul>	

3. **Wall & Roof Plane Limits.** Massing techniques use changes in the building footprint, height, or significant shifts in wall and roof planes to break down the volume of larger buildings. Wall planes that exceed the wall and roof plane limits in Table 5-7 shall have at least 25% of the elevation differentiated by one or more of the following massing techniques:

- a. Break the building into distinct masses (primary mass, secondary mass, and wings), where portions of the building are offset from the main mass by at least 8 feet or are otherwise noticeably smaller and subordinate to the main mass.
- b. Step back portions of the building footprint or upper stories by at least 4 feet in association with meaningful outside space, such as a balcony, deck, patio, or entry court.

- c. Use cantilevers on upper stories that provide at least a 2 feet overhang of other portions of the wall plane.
- d. Provide single-story entry feature that project at least 6 feet from the wall plane.
- e. Articulate rooflines by stepping the roof, using gables and dormers, dropping eaves, and using prominent overhangs to create offsets and projections of at least 2 feet.
- f. Where larger buildings are next to smaller buildings, or are along a block with smaller buildings, step the height of the building or offset secondary masses to create compatible massing nearest to adjacent structures.



**Figure 5-10 Wall Plane Limits**

Wall planes over the size specified in Table 5-7 shall be broken up with a range of techniques so that at least 25% of the elevation is differentiated with distinct wall planes. (17-5-3.B.3.).

- 4. **Blank Wall Limits.** Modulation uses materials, ornamental details, and subtle variations in the wall plane to break up blank wall planes. Street-facing wall planes that exceed the blank wall limits in Table 5-7 shall use three or more of the following techniques so that at least 20% of the facade is distinguished by modulation:
  - a. Create projections in the wall planes with bay windows, balconies, awnings, or canopies that project at least 4 feet from the wall plane.
  - b. Create voids in the wall plane with step-backs of upper stories or balconies that recess at least 4 feet from the wall plane.
  - c. Differentiate stories, roofs, or other masses with prominent trim materials and/or incorporate material changes on different modules of the building. Significant trim or ornamentation used to break up blank walls or wall planes shall project between 2 inches and 2 feet from the wall and be at least 8 inches wide.
  - d. Use color changes and accent materials to emphasize distinct components of the facade. Material and color changes should wrap corners and occur at the inside corner of a massing element or occur in association with a significant trim or ornamentation to give a finished and unified appearance to the element.
  - e. Break up remaining large expanses of blank walls with facade composition that considers the location and grouping of windows, doors, or architectural details.




5. **Transparency.** Windows and doors provide transparency, detail, and visual rhythm on the facade, and they break up blank walls with the location, pattern, and proportions of these openings. The following techniques should be used to achieve the design objectives of this sub-section and to meet the windows and doors requirements of Table 5-7, Building Design Standards:
- a. Create relationships to outdoor spaces near buildings with the location, pattern, and proportions of windows and doors
  - b. Incorporate distinct and visually significant windows and doors (size, orientation, and ornamentation) to emphasize key locations on the facade or to relate to important social spaces.
  - c. Locate windows doors to create a coordinated facade composition considering the entire facade as a whole, and to break up large expanses into different components with the grouping of windows and doors.
  - d. Locate and design windows strategically in relation to privacy concerns in adjacent spaces and buildings but maintain consistent exterior patterns and façade composition. High-bank windows, transom windows, opaque windows, and window treatments that are adaptable and user-controlled are better may be used to deliver privacy as opposed to omitting windows.
  - e. Use windows and doors with projecting trim and ornamentation to create depth, texture, and shadows on the facade; to emphasize openings; or to gang groups of openings. Openings that have projecting trim and casements (at least 1 inch off the facade and 4 inches wide) or that group widows with significant details may count these additional features for up to 25% of the window and door requirement.
  - f. The window requirement may be waived on sides of buildings that are closer than 3 feet to the property line, if necessary to meet applicable building code requirements.
6. **Materials.** Building materials with texture and patterns create visual interest and signify quality construction and detailing. The following techniques should be used to meet the material standards of Table 5-7, Building Design Standards and achieve the design objectives of this section:
- a. Primary materials shall be natural materials, such as painted or natural finish wood siding (horizontal lap, tongue-and-groove, board and batten or vertical), brick, stone, stucco, ceramic or terra cotta tile. Synthetic alternates to these natural materials may be used if manufacturer specifications and/or precedents for application demonstrate that it will perform equally or better than the principal materials in terms of maintenance, design, and aesthetic goals.
  - b. At least 20% of all materials, whether primary or secondary, shall be masonry, brick, or stone.
  - c. Coordinate changes in color and materials in association with changes in massing and modulation of the building.
  - d. Use changes in color or materials to differentiate the ground floor from upper floors and the main body of the building from the top or roof-structure, particularly on buildings 3 stories or more.
  - e. In multi-building projects, use subtle variations in building materials and colors on different buildings, to create variety among buildings within a consistent palette of materials and colors for the project.
  - f. Percentage coverage shall apply to the façade and any street-facing wall, and shall be measured from the first-floor elevation to the tope eave, not counting the doors and windows or interim roof features, but does include garage doors.
7. **Variations of Buildings.** All projects involving three or more buildings shall provide variations in the elevations from the two buildings on each adjacent side, and the three nearest buildings on the opposite side of a facing block, with at least two of the following:





- a. Variations in the front entry features as indicated in Section 17-5-3.A.3. Variations should include combinations of at least two of the following changes:
  - (1) Different types of entry features: such as porch, stoop, or entry court;
  - (2) Different roof styles associated with the entry feature: such as gable, hip, shed, flat, arched, or no roof;
  - (3) Different locations and extent of the same entry feature: such as centered, shifted left or right, or wrapped; projecting or embedded; and half or full lengths; and/or
  - (4) Different ornamentation or architectural styles that lead to distinct qualities within a similar scale or pattern.
- b. Variations in the facade composition, including massing, modulation, window types and placement, materials, and details and ornamentation, to the extent that the buildings have a distinct appearance;
- c. Variations of the roof forms considering the type of roof, orientation of gables, or use and placement of dormers; or
- d. Variations of the building type or models of the same type with distinctively different floor plans that lead to different massing. Mirror images of the same model and floor plan shall not be used to meet the variation requirement.
- e. In the case of multi-unit buildings:
  - (1) For duplexes / multi-unit houses that are intended to mimic the scale and form of detached houses, a hierarchy of doors and entrances shall be used to create the appearance of a single building, and the variation shall apply between buildings.
  - (2) For row houses and similar buildings that are clearly designed for multiple units, subtle variations in the materials and entry features shall apply to emphasize different units, and the variation shall apply between units in the building.



**Figure 5-13 Front Entry Features - Variety**

*Using a wide variety of entry feature types, styles and designs is a way to create subtle distinctions between the same or similar building types and can add common human-scale patterns among different types or scales of buildings. (17-5-3.A.3 and B.7.a)*



- 8. **Alternative Compliance.** Alternative compliance to the building design standards established in Section 17-5-3.B, Building Design may be authorized according to the process and criteria in Section 17-2-6, Alternative Compliance, and any of the following additional applicable criteria:
  - a. The requirement is not consistent with the particular architectural style selected for the building based on reputable resources documenting the style.
  - b. The requirement would make the building less compatible with designs or characteristics of other buildings or sites adjacent to the project or that are prevalent throughout the area.
  - c. Deviations from material standards and any simulated products demonstrate a proven performance in terms of maintenance and quality appearance.
  - d. In all cases the deviation is the minimum necessary to address the circumstance, the alternative equally or better meets the design objectives of this Section, and there is no negative impact on other design standards applicable to the building or site.
  
- C. **Block & Lot Open Space Design.** A system of different types of open spaces shapes the neighborhood character and creates unique identities for different neighborhoods. Block and lot open spaces complement the overall civic and open space system and provide active gathering places and aesthetic enhancements to the buildings and lots.
  - 1. **Design Objective.** The following design objectives shall be used to apply the open space standards Section 17-3-2, Open & Civic Spaces and in Table 5-1, Residential Building & Lot Standards.
    - a. Promote the arrangement of neighborhoods, blocks and lots in a way that responds to the existing natural features.
    - b. Ensure access to a variety of different types of open spaces including natural areas, park and recreation amenities, and formal gathering spaces.
    - c. Use open spaces to create gateways, focal points, connections, and transitions in coordination with the street network, block structure, and lot arrangement.
    - d. Design all unbuilt areas to serve as valuable neighborhood features, considering the aesthetic, ecological, recreation, or community-serving potential of these spaces.
    - e. Require all lots and buildings have access and proximity to usable open space, whether public, common, or private, and whether neighborhood-scale, block-scale, or building- and lot-scale spaces.
  
  - 2. **Required Site Open Space.** Each building type shall provide the open space specified in Table 5-1, (Residential Building & Lot standards; Lot Open Space) within the lot or project. With the exception of Detached Houses, lots platted through a final plat with common open space may credit the common open space towards the lot open space requirement, provided it meets the following standards:
    - a. The space is public or remains accessible to the public; or
    - b. If private or common space, the lot applying the credit has access to the space through ownership or other agreement, and the space is otherwise dedicated and reserved from future development.
    - c. The space shall be on the same lot, or on the same block within 1,000 feet of the lot, and meet the design standards for one of the open and civic space types in Section 17-3-2.
  
  - 3. **Lot Open Space Design.** Lot and building open space required for each building type shall create a common or private amenity for the site and building. Buildings and open spaces on a lot shall be arranged to create usable outdoor spaces that meet one or more of the following types:



- a. Public or Common open space designed and platted according to the standards in Section 17-3-2, Open & Civic Space, subject to the limitations in subsection C.2 above;
  - b. Private yards and spaces, including:
    - (1) Frontage areas designed according to Section 17-5-3.A., excluding any driveways, parking areas or other automobile space;
    - (2) Courtyards, meeting the standards of Section 17-5-4;
    - (3) Rear yards provided they are part of an open area of at least 375 square feet and at least 15 feet in all directions; and
    - (4) Private uncovered decks or patios provided they are part of an open area at least 120 square feet and at least 10 feet in all directions. This space is limited to no more than 25% of the requirement for lot and building.
  - c. For apartment or mixed-use buildings, rooftop decks provided they are at least 300 square feet, and at least 15 feet in all directions – this space is limited to no more than 25% of the requirement for the lot and building; or
  - d. For apartment or mixed-use buildings, private balconies or patios, provided they are at 80 square feet, and at least 6 feet in all directions – this space is limited to no more than 25% of the requirement for the lot and building.
4. *Alternative Compliance.* Alternative compliance to the open space design standards established in this Section 17-5-3.C. may be authorized according to the process and criteria in Section 17-2-6, Alternative Compliance, and any of the following additional applicable criteria:
- a. The specific standard is not practical due to the context and location of the lot and meeting the requirement would otherwise result in improper arrangement of the building or site.
  - b. In instances of infill development or a context where a clear pattern of existing buildings and lots on the same block and opposite block face present a different arrangement in terms of buildings and lot open spaces.
  - c. The lot and building have access to at least two different active open spaces within 1,000 feet which meet the design and service area standards in Section 17-3-2, Open & Civic Space.
  - d. In all cases the deviation is the minimum necessary to address the circumstance, the alternative equally or better meets the design objectives of this Section, and there are no negative impacts on other design standards applicable to the building or site.

### 17-5-4 Courtyard Pattern

- A. **Design Objective.** A courtyard pattern can integrate multi-building projects into the neighborhood pattern by connecting formal open space to the street frontage and using that space as an organizing element for buildings and lots. It is an effective infill strategy or is appropriate on deeper lots and blocks. Residential buildings and lots may be designed to front on a courtyard based on the design standards in this section.
- B. **Applicability.** The courtyard pattern is appropriate where:
  - 1. Courtyards are arranged within the block structure and designed as an extension of the public streetscape and open and civic space system for the neighborhood;
  - 2. Blocks and surrounding lots are deep, allowing a different configuration of buildable lots; or
  - 3. Other developed areas where existing lot patterns in the vicinity warrant use of this pattern to facilitate infill development and compatible building types.



- C. **Eligible Building Types.** The following building types are eligible for this pattern, subject to the limitations stated:
  1. Small Apartments, up to 5 buildings or 36 units, whichever is less.
  2. Row Houses, up to 4 buildings or 24 units, whichever is less.
  3. Duplex/Multi-unit Houses and Detached Houses, up to 10 buildings or 24 units, whichever is less.
  
- D. **Design Standards & Exceptions.**
  1. The minimum lot size per building may be reduced up to 20%, provided the courtyard is owned in common by all lots or otherwise established as a shared-space amenity.
  2. The courtyard shall be designed according to the standards in Section 17-3-2 and have frontage on a public street or be accessible from the streetscape by a pedestrian passage.
  3. Lots may front on the courtyard, rather than along a street. Building frontage standards shall apply on the courtyard and on the public street frontage.
  4. The front setback may be reduced to 5 feet from the courtyard boundary.
  5. Any buildings fronting on the street, or the sides of any buildings adjacent to the street shall still meet requirements for public frontages and orientation standards in this section.
  6. Vehicle access and parking for each lot shall be coordinated for all lots and buildings, be designed in a way that minimizes the impact the courtyard and lot frontages, and meet all frontage standards along the public street.







Figure 5-14 Courtyard Pattern

The courtyard pattern allows for a different configuration of buildings in specific contexts. The pattern arranges buildings on smaller lots with a common frontage on the courtyard. The courtyard and the front buildings provide to the streetscape, while other buildings may relate direction to the courtyard. Vehicle access is shared and limited to more remote or discrete portions of the project.

17-5-5 Conservation Pattern

- A. Design Objective. Residential lots and buildings may be arranged around an open space system that will preserve greater amounts of intact open and natural spaces or agricultural uses that are designed as a focal point and community amenity.
B. Applicability. The conservation pattern is appropriate in more remote areas, and specifically is eligible in the A or RE zoning districts. It requires a planned development application as outlined in Section 17-2-4.
C. Density Bonus. The base density and open space required shall be based on a typical and practical layout according to the underlying zoning district (A or RE). The following density bonus may be granted based on the amount of additional intact open space to be preserved in the plan. The "bonus" units shall not require additional open space, other than the space specified in Table 5-8.

Table 5-8: Conservation Design Density Bonus. Table with 6 columns: Preserved Area [1], Bonus Units Above Base Density, Project Size, Base Density Yield, Additional Units, Developed area. Rows show percentages from 20% to >60% with corresponding unit yields and developed areas.

[1] Total percentage of the project area preserved as open space meeting the Natural Open Space, Trail, or preservation of productive agriculture lands criteria in Section 17-3-2.

- D. Lot Sizes & Building Types. The resulting density based on the plan after the density bonus is applied may be allocated in the developed portion of the project with the following building types. No combination of these building types may be used to allow more units than authorized by the density bonus. All other standards applicable to each building type in Table 5-1 shall apply within the developed portion of the plan.
1. Detached house – farmstead, estate lot, large lot, standard lot, small lot, or compact lot
2. Duplex / multi-unit house
3. Row house
E. Open Space. Open space shall meet the design criteria of Section 17-3-2 for Natural Open Space, Trail, or include prime farmland or other existing and productive agriculture lands designed to be a focal point and community amenity. All lots shall have access to the public or





common open space preserved as part of the plan within 1,000 feet, measured along pedestrian or trail routes.



**Figure 5-15 Conservation Pattern**  
 The conservation pattern allows both a greater number of units and a greater concentration of those units in exchange for greater quantities and more coordination of larger open spaces.

**17-5-6 Manufactured & Small Format Housing District**

- A. **Intent.** The intent of this section is to provide manufactured or other small-format homes in a neighborhood or community that includes common neighborhood amenities, and with site designs that limit impacts on adjacent property and promotes development patterns that are compatible with the surrounding areas.
- B. **Applicability.** Small format home communities are permitted in the Manufactured and Small Format Housing District – PD-M, and implemented as a planned development project according to Section 17-2-4 These standards shall not apply to: (1) mobile homes, trailers or similar temporary buildings used as an interim structure associated with an ongoing construction project under valid permits; (2) interim or temporary housing strategies to address emergencies; or (3) detached houses that are assembled off site and “manufactured,” provided they meet all other design standards of the applicable zoning district.
- C. **Development Standards.** Except as otherwise modified through a development plan according to the approval procedures and criteria in 17-2-4, the general development standards for manufactured and other small format home projects are included in Table 5-9.

Table 5-9: PD-M Development Standards	
Project	Amount of Bonus Units Above Base Density
Project Size:	3 acre minimum, 200' minimum frontage an arterial or collector  <i>Exception:</i> The Director may recommend a plan for as small as 2 acres and 100 feet of public street frontage if the plan demonstrates exceptional community design and layout for the common areas within the community, a high-quality and well-designed housing concept, and special attention to integrating and relating the project to surrounding areas.
Project Intensity:	7 units per acre, maximum



<b>Table 5-9: PD-M Development Standards</b>	
	<i>Exception:</i> Up to 15 units per acre for any project with more than 30% of the project area designed as useable open space meeting Open Space types in Section 17-3-2.
Perimeter Setbacks	25' minimum from any street boundary; 15' from any property boundary (See Article 8 – Type III Buffer; or Neighborhood Frontage Type.)
<b>Home Sites</b>	
Lot Size	3,000 s.f. minimum,  <i>Exception:</i> 1,500 s.f. minimum for any project with more than 30% of the project areas designed as useable open space meeting the types in Section 17-3-2.
Lot Width	30' minimum, <i>Exception:</i> 24' for projects meeting the open space bonuses above. Frontage shall be on a public street, common internal street, or common open space with street access at the rear of the site.
Setbacks	Front: 10' from the lot/home site line, or 15' from the edge of the internal street, whichever is greater Side: 5', or 3' minimum with 10' between buildings Rear: 10' All buildings shall meet the project perimeter setback.
Height	30' maximum
Site Design	Each home site shall have a private patio, courtyard or similar outdoor amenity of at least 120 square feet. Any structure associated with this outside amenity may be located within 5 feet of the lot or home site boundary. Each home site may have an accessory storage building up to 160 square feet, up to 8 feet tall. The accessory storage building shall be set back at least 50 feet from any public or internal street, or behind the dwelling unit. Accessory buildings shall be separated by at least 5 feet from any other structure.
Parking	Each home site shall have at least one on-site parking space, and at least one excess or guest space within 200 feet of the unit. The excess or guest space may be "on-street" where streets are designed for parking or in a common area.

D **Uses.** In addition to any uses enabled for the PD-M district in Table 4-2, projects may include the following specific uses:

1. Dwelling units consisting of modular homes, mobile homes, or other similar small, detached dwellings.
2. Accessory buildings and uses incidental to those listed above and which support the residential community, including offices, recreation buildings, storage areas, maintenance and utility facilities, or other community services.

E. **Common Areas.** All common areas not dedicated as home sites according to the development standards in subsection C shall be designed as part of the Development Plan (See Section 17-2-4.B, Planned Development procedures). This space shall be allocated to:

1. Internal vehicle circulation for the community, laid out to provide connectivity and continuity through the community and organize the project into blocks and lots so that all home sites and lots are served by streets. There shall be at least two entrance points from public streets for each project. Internal roadways shall be 20' where no parking is permitted, 24' wide where parking is permitted on one side, and 28' wide where parking is permitted on both sides.
2. Open and Civic Space meeting one of the design types specified in Section 17-3-2 at a rate of at least 300 square feet per dwelling or 20% of the overall project, whichever is greater. Projects with more than 30% dedicated to usable open space (non-street, circulation or parking space) may be eligible for exceptions to the standards noted in



Table 5-8. All open and civic spaces shall be designed and located in a manner that ensures adequate accessibility for all units in the community.

3. At least one of these spaces shall include a community building, which is centrally located, for recreation and meeting functions, laundry facilities, or other common amenities. The community building shall be at 1,500 square feet, or 15 square feet per dwelling unit, whichever is greater.
4. Other internal circulation or open space such as walkways, landscape buffers or other site design amenities that improve the quality of the community and its relationship to surrounding areas. Pedestrian connections shall be accounted for on all streets or at greater intervals through a trail or path system.
5. A storm shelter shall be provided which may be included with the clubhouse.
6. A common storage and utility area shall be provided within the plan including at least 100 square feet per unit. This area may be used for storage of large equipment, recreational vehicles, maintenance or other utility functions for the community. This area shall be screened from the project and from surrounding property according to the buffer standards in Article 8.

**F. Building Design.**

1. All dwellings shall have a front entry feature, such as a porch, stoop, or outside patio relating the home site to the lot frontage or other common open space upon which the dwelling is located.
2. Parking spaces on a home site shall be located to the side or rear of the dwelling. Home sites may include a carport or garage, is no larger than 440 square feet, but in no case larger than the dwelling unit.
3. Any structure shall meet all applicable building and fire codes, and be situated on a permanent foundation.

**G. Landscape & Parking Design.** The standards of Articles 7 and 8 are generally applicable to PD-M district development plans, except as modified through a development plan based on the approval procedures and criteria in Section 17-2-4.

**H. Subdivisions.** Each home site may be individually platted if:

1. All lots shall have public utility access as provided in Article 3, including public easements for access to each home site and all other standards and criteria of the subdivision standards are met;
2. There are covenants and restrictions and associations assuring that these provisions for the Development Standards, Common Areas, Building Design and Utilities and Services, as demonstrated on an approved plan, will be maintained through a management entity or common association.



---

## Article 6. Non-residential Development & Design

- 17-6-1 Intent & Applicability
- 17-6-2 Non-residential Development Standards
- 17-6-3 Frontage Design
- 17-6-4 Building Design
- 17-6-5 Open Space Design
- 17-6-6 Specific Frontage & Design Plans

---

### 17-6-1 Intent & Applicability

- A. **Intent.** The intent of the Non-residential Development & Design standards is to:
1. Enable a range of compatible buildings and sites that meet the intent of each zoning district.
  2. Improve the appearance and vibrancy of mixed-use, commercial, and employment centers with good civic design.
  3. Promote quality architectural and site design, and use the visual priority of buildings to shape streetscapes and open spaces.
  4. Reinforce the distinct character of different corridors, centers and districts with development patterns and building and landscape design appropriate to the context, and specifically the high intensity, moderate intensity, low intensity, and very low intensity areas of the Comprehensive Plan.
  5. Strengthen the accessibility of places by coordinating site access and internal circulation systems with multi-modal street networks.
  6. Promote lasting and sustained investment in corridors, centers, and districts with quality design.
- B. **Applicability.**
1. The standards in this Chapter shall apply to all non-residential and mixed-use development in the MU-NC, MU-DT, MU-RC, and I districts, except where stated that sections only apply to specific districts or specific situations.
  2. All new structures and development shall comply with these standards.
  3. Modification or additions to existing structures or sites shall meet these standards to the extent of the modification or addition, except that the Director may waive any design standards applied to modifications or additions that:
    - a. Conflict with the consistent design of an existing building;
    - b. Conflict with a desired and prevailing character on the block or immediate vicinity of the project; or
    - c. To otherwise facilitate infill development or adaptive reuse of an existing building.
  4. The standards shall not apply to ordinary maintenance of existing buildings or sites, except that maintenance shall not occur in a manner that brings the building or site to a greater degree of non-conformance with these standards.



**17-6-2 Non-residential Development Standards**

A. **Non-residential Lot and Building Standards.** The lot and building standards for non-residential uses in the following districts are specified in Table 6-1.

Table 6-1: Non-residential Lot & Building Standards								
Zoning District	Minimum Lot Standards			Minimum Setbacks [5]				Building Height (max)
	Area		Lot Coverage (max.)	Front [1]	Interior Side [2]	Corner Side	Rear [3]	
MU-NC	2K – 40K s.f.		80%	10' – 25'	5'	20'	10'	40' / 3 stories
MU-DT	2K – 30K s.f.		100%	0' – 10'	5'	10' [4]	10'	40' / 3 stories
MU-RC	2.5K s.f.		20%	25'	5'	10' [4]	10'	60' / 5 stories
I-1 & I-2	10K s.f. min.		10%	25'	10'	25'	10'	40' / 3 stories

- [1] Front setback requirements may be modified for a particular street or block, based on the frontage types and design standards in Section 17-6-3.B.
- [2] The interior side setback for buildings which share a party wall is 0'. For any side lot line that abuts a residential use or a district that has a greater side setback requirement, the greater side setback of the abutting district shall apply;
- [3] For any lot where a rear lot line abuts a residential district, a setback of at least 25' shall apply.
- [4] The side setback for corner buildings may be 0' in the MU-NC, MU-DT, or MU-RC districts, provided they meet the Frontage A standards on the lot and building for at least the first 30' from the front corner. [Section 17-6-3].
- [5] Buildings and structures shall be setback from plugged and abandoned wells at least 50 feet; and from oil and gas facilities at least 250 feet.





**B. Dimension Standards & Exceptions.** The following applies to the lot and building standards established in Table 6-1: Non-residential Lot & Building Standards.

**1. Setbacks**

- a. In no case shall any setback exception or modification violate the provisions of a recorded easement.
- b. Any structural projections over public rights of way, or any similar area designed for pedestrian circulation, shall be at least 9 feet above the grade, and in no case within 5 feet of any curb for a street, access drive, or other area for vehicles.
- c. Structural projections such as bay windows, balconies, chimneys, eaves, cornices, awnings, open fire escapes, egress wells, or other non-foundational overhangs or projections may extend up to 4 feet from the foundation and encroach into the setback, but no closer than 2 feet from any lot line. This exception shall be limited to no more than 20% of the total area of any single facade.
- d. Ground-mounted mechanical equipment, meters, and utility boxes accessory to the building may be located in the side or rear setback provided that it extends no more than 6 feet from the principal building, no closer than 3 feet to the lot line, and is screened from public right-of-way by structures or landscape. These limitations do not apply to any utility structures otherwise authorized to be located according to easements or in the right-of-way, which shall follow the location and design standards of those specific authorizations.
- e. A lot may have more than one principal building, provided any accessory, secondary, or additional principal building shall be located at least 10 feet from any other building on the same or adjacent lots, or be joined by a party wall meeting all aspects of the building code. All buildings shall cumulatively meet the lot and building requirements in Table 6-1.

**2. Height.**

- a. Architectural features such as chimneys, ornamental towers and spires, and similar accessory elements may extend up to 50% above the actual building height, provided they are integral to the specific architectural style of the building and encompass less than 15% of the building footprint.
- b. Accessory building elements integral to the design and construction of the building, such as parapet walls, false mansards, or other design elements essential to quality building appearance may extend up to 6 feet above the roof deck on a flat roof.
- c. Functional and mechanical equipment such as elevator bulkheads, cooling towers, smokestacks, roof vents, or other equipment may be built up to their necessary height in accordance with building codes, provided the features are non-reflective and screened by parapet walls, or other design elements according to Section 17-8-3, or otherwise designed in a manner consistent with and integral to the specific architectural style of the building.

**C. Accessory Buildings – Non-residential.** Accessory buildings shall be permitted in association with and on the same lot as a principal building, subject to the same standards in Table 6-1, Non-residential Lot & Building Standards, and to the following additional limitations.

- 1. Accessory buildings are not subject to the design standards in Sections 17-6-3 and 17-6-4 provided they area under 200 square feet, are setback more than 80 feet from any public right of way or public space, or otherwise not visible due to the location and



- orientation of the principal structure. All accessory buildings shall be at least 10 feet from the principal building, or other distance specified by applicable building codes.
- 2. Any portion of the building or structure over 200 square feet or over 10 feet high, and potentially visible from the street or other public areas shall use materials, colors, and details that are compatible with the principal structure, or otherwise be screened according to Section 17-8-3.
- 3. Any building other building or structure shall be treated as a second principal building and meets all lot and building design standards for a principal building.

**17-6-3 Frontage Design**

A. **Design Objectives.** Frontage design determines the relationship between private development and the streetscape and affects the character of different streets, blocks, and districts. Application of frontage types is based upon a combination of the character of the district, the streetscape design, and the relationship to adjacent lots The frontage design standards have the following design objectives:

- 1. Enhance the image of the Town by coordinating streetscape investment with private lot and building investment.
- 2. Use buildings to shape streetscapes and public spaces, and orient buildings to these spaces.
- 3. Design frontages based on the scale and context of the area, block, and street, particularly emphasizing landscape areas to buffer sites from higher-volume / higher speed streets and emphasizing social spaces and human-scale features on walkable and multi-modal streets.
- 4. Coordinate development across multiple lots with compatible frontages along block faces, considering building placement, access, parking, landscape, and open space design.
- 5. Strengthen the identity and economic value of distinct places by reinforcing consistent patterns of streetscape, frontage design, and building materials, placement, and form.

B. **Frontage Design Standards.** The frontage types and design standards may modify the front setback established in Table 6-1. Subsections following this table provide specific design strategies and techniques to meet the design objectives and standards.

<b>Table 6-2: Non-residential Frontage Design</b>				
	<i>Frontage A</i>	<i>Frontage B</i>	<i>Frontage C</i>	<i>Frontage D</i>
<i>Front Building Line (build-to range)</i>	0' – 10'	0' – 25'	25' – 80'	80' +
<i>Required Front Building Line (min. % of frontage width)</i>	75%	60%	35%	35%
<i>Parking Setback (min.)</i>	Behind rear of building	Behind front building line	25' min. See Sec.17-7-4	25' min. See Sec.17-7-4
<i>Extent of Parking Frontage (max.)</i>	0%	40%	65%	65%
<i>Landscape</i>	See Sections 17-3-2, 17-7-4, and 17-8-3			



<i>Applicability</i>	<i>MU-DT</i>	■	□	□	-
	<i>MU-NC</i>	■	■	□	□
	<i>MU-RC</i>	■	■	■	□
	<i>I-1 &amp; I-2</i>	□	□	■	■

\* Unless otherwise specified in the Johnstown Standards and Specifications manual.  
 ■ Permitted by right.  
 □ Permitted subject to Alternative Compliance procedures and criteria in this Article and in Section 17-2-6.

C. **Front Building Line.** All buildings shall establish a front building line within the range specified in Table 6-2, Non-residential Frontage Design, based on the appropriate frontage type for the specific street and block. All buildings shall occupy the minimum percentage specified for required front building line with either of the following:

1. Front building facades meeting the design standards in Table 6-3, Non-residential Building Design; or
2. Open spaces meeting the requirements of Section 17-6-5, Open Space Design, provided:
  - a. It is limited to no more than 50 linear feet or 50% of the lot frontage, whichever is greater;
  - b. There are defining vertical features at the extension of the required front building line, such as decorative walls, fences, or landscape features; and
  - c. All building facades fronting the open space meet the building design standards otherwise applicable to the building frontage.
3. Corner lots shall meet the frontage requirement along the side street for at least 30' or 30% of the side street frontage, whichever is greater.

D. **Landscape.** The remainder of the frontage between the streetscape and front building line shall include landscape and open space designs.

1. For frontages with buildings built between 0 and 10 feet from the front lot line, the streetscape design standards in Section 17-3-1, Street Design and Article 8, Landscape Design may satisfy this requirement, or extensions of the streetscape and landscape elements in easements or the private frontage.
2. In all other cases the landscape design shall be according to the requirements of Chapter 7, Access & Parking and Article 8, Landscape Design.
3. On all frontage types, lot open space meeting the standards of Section 17-6-5 may be included in the frontage area.

E. **Alternative Compliance.** Alternative Compliance to the frontage design standards in this Section may be authorized according to the process and criteria in Section 17-2-6, Alternative Compliance and any of the following additional applicable criteria:

1. The context presents a clear pattern of existing buildings and lots on the same block and opposite block face that are different from the requirements and are desirable to maintain.
  - a. Frontages should be similar for all lots on the same block face or gradually transition to different frontage types in situations that enable multiple types.
  - b. Front building lines on adjacent lots should generally not differ by more than 10 feet, unless substantial space exists between the buildings.



- c. Blocks with pedestrian amenities, on-street parking, or designed according to the Pedestrian and Parkway / Bikeway street type standards in Section 17-3-1 are generally appropriate for the Frontage Types A and B standards.
- d. Blocks with higher traffic speeds or volumes, which lack pedestrian amenities, or lack on-street parking are generally appropriate for Frontage Types C and D standards.
- 2. Parking and access that serves a greater area beyond the site and block may deviate from these standards, provided it does not negatively impact development on adjacent lots and it is designed to minimize impacts on streetscapes.
- 3. Civic uses or landmark buildings may deviate from frontage designs provided they are in a location that serves as a focal point for the surrounding area, and the exception is used for improved social space or aesthetic features on the frontage.
- 4. In all cases where a non-building frontage area is permitted with alternative compliance, a strong development edge shall be created along the required frontage by a combination of an ornamental wall or fence that compliments the building design and additional landscape elements that create defined vertical elements.

### 17-6-4 Building Design

- A. **Design Objectives.** Building design refines the scale and form of buildings beyond the basic setback, height, and lot coverage standards and improves the relationship of buildings to public and active spaces. The building design standards of this Section have the following design objectives:
  - 1. Refine the scale, massing, and design details of buildings to a greater degree of interest and aesthetics the closer they are to the streetscapes and other publicly used spaces.
  - 2. Relate buildings to adjacent development by mimicking similar scale, massing, and proportions through step-backs and secondary masses that break up larger masses.
  - 3. Locate doors and windows in a way that activates space, creates connections to important exterior spaces, and promotes economic activity at the interface of buildings and public spaces.
  - 4. Use materials and human-scale architectural features to create depth, texture, variation, and visual interest, particularly on larger facades, along streetscapes, or near active open spaces or adjacent lots.
  - 5. Emphasize the quality and longevity of investments with materials and colors that are attractive, durable, and have low maintenance requirements.
  - 6. Concentrate architectural and design features on facades that are public-facing.
- B. **Building Design Standards.** The building design standards in Table 6-3 are based on the placement of the building and proximity to the streetscape. Subsections following the table provide specific design strategies and techniques to meet the design objectives and standards.

Table 6-3: Non-residential Building Design			
Front building line	0' – 10'	11' – 25'	26' +
<i>Massing &amp; Modulation</i>	50' l.f. / 500 s.f.	75' l.f. / 1,000 s.f.	100' l.f. / 2,000 s.f.
<i>Entry Feature Spacing</i>	50' max.	100' max	1 per building
<i>First Story Transparency</i>	60% min.	40% min.	40% min. w/in 50' of entry



Table 6-3: Non-residential Building Design			
Front building line	0' – 10'	11' – 25'	26' +
Upper Story Transparency	15% min.	15% min.	15% min. n/a for industrial buildings
Materials	See Section 17-6-4.F / Table 6-4		

- C. **Massing & Modulation.** Wall planes that exceed the linear feet or square footage limits in Table 6-3, Non-residential Building Design shall be interrupted by one or a combination of the following techniques:
1. Emphasize structural bays and vertical breaks of the building exterior at regular intervals, with visible features such as columns, pillars, pilasters, or other details and accents along at least 25% of any public facing façade, and project at least 2 feet from the primary plane of the facade.
  2. Define horizontal elements with projections at least 4 feet from the wall associated with entrance features or differentiating stories, such as balconies, awnings, cantilevers, or similar horizontal elements.
  3. Break the volume of the building into distinct components with:
    - a. Step-backs of upper stories of at least 8 feet;
    - b. Recesses of the building footprint greater than 4 feet; or
    - c. Deviations shall encompass at least 20% wall planes of the entire public-facing elevation.
  4. Horizontal differentiation of a base, body and top of buildings with materials and architectural details.
    - a. For buildings less than 3 stories, this can be a distinct foundation, a facade, and an articulated roof structure, such as eaves and fascia for pitched roofs, or cornices and parapets for flat roofs.
    - b. For buildings 3 stories or more, the first floor should be clearly differentiated from upper stories to establish the base and an embellished roof structure.
    - c. Any belt course or trim band establishing the break in base, body and top shall use a material or pattern distinct from the primary material, 6 to 36 inches wide, off-set from the wall plane 4 to 24 inches; or may be a lessor trim associated with a material change.
  5. Use patterns of windows and doors, meeting the transparency requirements in subsections D. or E., to create a rhythm and balance with vertical and horizontal elements on the elevation.
  6. Use ornamental architectural details, and material and color changes associated with trim or massing elements along areas where there are no windows or doors.
  7. Use varied elevation types to create distinct patterns within and between buildings in a multiple-building complex or development comprised of similar structures.
- D. **Entry Features.** Primary public entrances shall be clearly defined on all front facades with at least two of the following elements and be located at intervals specified in Table 6-3, Non-residential Building Design:
1. An architectural emphasis such as raised parapets, gables, canopies, porticos, overhangs, pediments, arches, or projections or recessions within the wall plane of at least 3 feet.
  2. Transom or sidelight windows that frame and emphasize the entry.





3. Architectural details such as tile work and moldings, columns, pilasters, or other similar material changes.
  4. Integral planters, seating, or wing walls associated with an entry court or plaza that integrates landscape and hardscape designs.
  5. For corner buildings, any entrance feature located on the street corner may count to both sides, and may be considered located at 25' from each corner for the purpose of the required primary entry feature intervals.
- E. **Transparency.** The window and door transparency requirements of Table 6-3, Non-residential Building Design shall be met with one or more of the following techniques:
1. Where expressed as a first story requirement the percentage shall be measured between 2 feet and 8 feet above the sidewalk grade, or within 10 feet above the first-floor elevation if the building is set back more than 10 feet from the street.
  2. Where expressed as an upper story requirement, the percentage shall be measured between the floor level and ceiling of each story.
  3. All first story windows required shall provide direct views to the building's interior or to a lit display area extending a minimum of 3 feet behind the window.
  4. For industrial and civic buildings setback more than 25 feet from the street, clerestory windows may meet the first or upper story window requirements.
- F. **Materials.** Use exterior building materials with a texture and pattern that creates visual interest and signifies quality construction and detailing.
1. The predominant surfaces on building walls shall be one of the primary materials listed in Table 6-4, Non-residential Building Materials.
  2. No more than 4 materials should be used, including the use of secondary and accent materials.
  3. Material changes shall emphasize different elements of the building, in association with the massing and modulation standards in subsection C.
    - a. Where material changes are vertical with different materials stacked one above another, the transition between materials should include a belt course, trim band, sill, cap, frame, roof (if at ceiling height), or similar element to separate the two materials. Heavier and larger materials should be below lighter or smaller materials.
    - b. Where material changes are horizontal with different materials side-by-side, the transition between materials should occur at interior corners or at the trim line, architectural column or pilaster where the change is emphasizing different structural or massing components for a building.
  4. Material colors shall be low reflectance, subtle, classical, neutral or earth tone colors. Primary, secondary, and accent materials shall establish distinct but compatible color palettes. The use of high-intensity colors, metallic colors, black or fluorescent colors is limited to accent areas.
  5. For industrial-style buildings in the I-1 and I-2 districts, only the street-facing facades must meet these requirements.



Table 6-4: Non-residential Building Materials

Primary Materials (40% to 80%)	Secondary Materials (15% to 40%)	Accent Materials (5% to 20%)
<ul style="list-style-type: none"> <li>▪ Brick</li> <li>▪ Stone</li> <li>▪ Slate</li> <li>▪ Stucco</li> <li>▪ Exterior Insulation and Finish System (Water-managed EIFS only)</li> <li>▪ Fluted or split-faced block.</li> </ul>	<ul style="list-style-type: none"> <li>▪ Any of the primary materials</li> <li>▪ Wood siding</li> <li>▪ Architectural tiles</li> <li>▪ Concrete Masonry Units (CMU - colored and textured only)</li> <li>▪ Tilt-up concrete panels with brick or stone facing.</li> <li>▪ Architectural metals (prefinished non-corrugated)</li> <li>▪ Transparent or tinted glass</li> <li>▪ Corrugated metal</li> </ul>	<ul style="list-style-type: none"> <li>▪ Any of the primary or secondary materials</li> <li>▪ Precast stone</li> <li>▪ Wood trim or simulated wood</li> <li>▪ Translucent glass (not on first story)</li> <li>▪ Canvas or similar durable cloth (awnings only)</li> </ul>

\* Prohibited materials include: Vinyl siding, concrete block or tilt-up (smooth-faced), barrier-type EIFS, and reflective metal or glass.

G. **Alternative Compliance.** Alternative Compliance to the building design standards in this Section may be authorized according to the process and criteria in Section 17-2-6, Alternative Compliance, and any of the following additional applicable criteria:

1. The requirement is not consistent with the specific architectural style selected for the building based on reputable industry resources documenting the style.
2. The requirement would make the building less compatible with designs or characteristics of other buildings or sites adjacent to the project or that are prevalent throughout the area, and that are desirable to reinforce.
3. The requirement is inconsistent with the principal function of the building when applied to industrial buildings in the I-1 and I-2 districts.
4. Deviations from material standards and any simulated products demonstrate a proven performance in terms of maintenance and quality appearance. Manufacturer specifications and/or precedents for application may be required demonstrate that it will perform equally or better than the allowed material.

### 17-6-5 Open Space Design

A. **Design Objectives.** The design of open space can reinforce the character of unique districts and distinct places. Design of open space on a lot integrates the unbuilt areas of the site with the public realm design and can mitigate undesirable development impacts. The required lot open space, resulting from the remainder of the maximum lot coverage in Table 6-1, and any other open and unbuilt spaces or uncovered surfaces, shall be designed and located to meet the following design objectives:

1. Coordinate site design with the open space system and public realm design of the area.
2. Use open space as an organizing element for development, creating focal points for buildings or groups of buildings, and create transitions between distinct building sites.
3. Design a hierarchy of gateways, gathering places, parks, and natural features, and integrate these spaces with the system of streets, through drives, trails, and pedestrian passages.
4. Select open space types based on the context, function, and natural amenities of the site; in general, more compact and formal gathering spaces are most appropriate in walkable



- commercial and mixed-use areas, and more spacious and natural areas are most appropriate in large commercial or industrial areas.
5. Use landscape, furnishings, fixtures, art, planters, and other elements of open spaces to complement buildings, coordinate buildings and sites, and distinguish the unique character of different places.
  6. Preserve natural features that can serve as amenities, maintain views to and from important outside spaces, perform ecological functions, or provide important connecting corridors.
  7. Promote active gathering spaces in appropriate locations.
- B. **Lot Open Space Design.** Lot open space required for each building and lot in Table 6-1 shall create an amenity for the site and building. Buildings and open spaces on a lot shall be arranged to create usable outdoor spaces that meet one or more of the following types:
1. Private frontage landscape areas designed according to the frontage design standards in Section 17-6-3., excluding any driveways, parking areas, or other automobile space;
  2. Open space meeting the requirements for public or common open space in Section 17-3-2.
  3. Common rooftop decks provided they are at least 200 square feet, and at least 12 feet in all directions – this space shall be eligible for credit up to 25% of the open space requirement for the lot and building;
  4. Private balconies or patios, provided they are at least 100 square feet, and at least 8 feet in all directions– this space shall be eligible for credit up to 25% of the open space requirement for the lot and building; or
  5. Landscape areas and buffers designed according to the standards of Article 8, which shall only be counted towards the following percent of the open space requirement, even where greater landscape or buffers are required by other sections:
    - a. No more than 25% of the requirement for lot open space in the MU-DT and MU-NC district.
    - b. No more than 50% of the requirement for lot open space in MU-RC ; and
    - c. No limit in the I-1 and I-2 districts.
- C. **Alternative Compliance.** Alternative compliance to the lot open space design standards established in this section may be authorized according to the process and criteria in Section 17-2-6, Alternative Compliance, and any of the following additional applicable criteria:
1. The lot and building have access to at least two different active open spaces on the same block or abutting blocks, each meeting the design and service area standards in Section 17-3-2.
  2. Other designs that promote infill development or rehabilitation of existing buildings and sites in a compact, and walkable context.
  3. Recreation and social spaces are otherwise adequately met appropriate for the building and use by public spaces such as streetscapes, parks and open space, recreation centers, or other common and accessible amenities.
  4. Any screening, buffering, or other non-useable open space needs for the use, site, or building meet the standards of Section 17-8-3.

### 17-6-6 Specific Frontage & Design Plans

The frontage design, building design, and open space design standards are in this Article. may be refined and further specified based on a specific area plan for multiple properties and owners. The plan shall use the standards in 17-6-3, 17-6-4, and 17-6-5. but specifically apply them on a block-by-block basis. The



plan shall be approved by the Town as a supplement to the comprehensive plan. Alternatively, specific application of frontage types may be based on a plan approved in association with a development proposal, provided it: (1) is at least 10 acres; (2) includes at least 20% of Frontage A frontages; (3) includes at least 60% Frontage A or B standards; and (4) includes no more than 30% Frontage D standards. All plans approved shall be included or cross-referenced in the subsections below.

A. **[Reserved]**

*[This section can be used to document and catalogue specific frontage and design plans either as the Town undertakes more specific plans using this concept, or as development proposals meeting these thresholds are proposed.]*



---

## Article 7. Access & Parking

- 17-7-1 Intent & Applicability
- 17-7-2 Access & Circulation
- 17-7-3 Required Parking
- 17-7-4 Parking Design

---

### 17-7-1 Intent & Applicability

- A. **Intent.** The intent of the Access and Parking standards is to:
1. Emphasize the importance of site access for multiple modes of transportation.
  2. Preserve streetscape design and street functions by coordinating access along block faces and internal to blocks.
  3. Create access and parking standards appropriate to the context of the site, considering surrounding development patterns and street design.
  4. Provide the optimal amount of vehicle parking for individual sites, recognizing that too much and too little parking each have negative impacts.
  5. Ensure appropriate site design features that mitigate the physical and aesthetic impact of parking on streetscapes and surrounding sites.
  6. Maximize opportunities for on-street parking, shared parking, and other strategies to reduce the inefficiency from underutilized and redundant surface parking on adjacent sites.
  7. Promote parking designs that minimize runoff, decrease heat island effects, incorporate low impact design features, and infiltrate storm water into the ground.
- B. **Applicability.** Access and parking shall be shown on site plans, according to the application requirements in Article 17-2. Specifically the standards in this article apply to:
1. All new development, buildings or uses on a site.
  2. A change of use, or additions to existing building, except that
    - a. Additional parking requirements shall only apply to the expanded portions of buildings;
    - b. Additional parking shall only apply to non-residential uses that would require 20% or more additional required parking than the previous condition; and
  3. The parking design standards shall only apply to the newly constructed parking, except when more than 50% of an existing parking area is reconstructed, all parking and access shall comply with this section.
  4. The access standards shall not limit the location of any existing access, except:
    - a. In conjunction with a public streetscape project;
    - b. Where an entire site is redeveloped or when more than 50% of a parking area is added, reconstructed, or similarly impacted by development; or
    - c. Where the existing access is determined by the Town to be a danger to public safety.
    - d. Where an existing access conflicts with an adopted access control plan.





17-7-2 Access & Circulation

A. Design Objectives. The design of access to and internal circulation for sites shall achieve the following design objectives:

- 1. Reduce impacts of driveways and curb cuts on streetscape designs and reduce or eliminate conflicts with pedestrians, bicycles, and vehicles.
2. Promote shared, common, or other vehicle access and loading internal to blocks, particularly on busier streets or where the standards otherwise limit or prohibit access.
3. Coordinate reasonable vehicle access with frontage designs for lots and buildings based on context and according to Sections 17-5-3.A and 17-6-3.
4. Provide safe and convenient bicycle and pedestrian access to buildings and sites at an equal or greater level than vehicles, and in the most direct and safe way possible.

B. Vehicle Access. Vehicle access shall be designed according to the following standards.

- 1. Driveway Location. Except for where shared or common access is permitted and executed through easements, driveways shall be set back from side or rear lot lines as stated in Table 7-1 Minimum Driveway Setbacks.

Table 7-1: Minimum Driveway Setbacks. Table with 4 columns: Access, Setback from side or rear lot line, Setback from street side corner, Separation from other driveways. Rows include Residential access < 6 units, Residential access 7 - 40 units, Nonresidential access and residential access to 41+ units, Shared access, and Alley access.

[1] Driveway spacing may be averaged along a block for residential lots or on local streets to allow the best arrangement considering grades, streetscapes, and building and lot layouts. This may result in two adjacent lots having access near the same lot line on one side (2' side setback on each), while greater separation between driveways is provided between lots on the opposite sides.

- 2. Private Streetscapes. Any single project, lot, or site greater than 5 acres, or lots where access is constrained by driveway standards, shall provide a system of private streetscapes that establish access and circulation within the site. (See Figure 3-2 in Section 17-3-1). Private streetscapes:
a. Shall be laid out to organize the site into smaller internal blocks.
b. Shall be designed to mimic public street cross sections in Table 3-2, including sidewalks, landscape amenities, on-street parking and travel lanes.
c. May be treated as public streets for determining the proper location, orientation and design of sites, buildings, and utilities within the project.
d. Trail, greenway, or pedestrian passages meeting the standards of Section 17-3-2 may account for a portion of this internal circulation network, provided it connects buildings, open spaces, and internal streets with similar networks external to the site and presents a logical connection point for pedestrians and bicycles.



- 3. **General Design Standards.** All accesses shall meet the following design standards.
  - a. Sufficient on-site storage for queued vehicles waiting to park, drive-through, or exit without interfering with street traffic.
  - b. Circulation between adjacent parcels in non-residential areas shall be provided by private streetscapes, cross access easements, and other shared access provisions to protect the function, design, and character of public streets.
  - c. Landscape, buildings, and other site elements at access points shall meet the sight distance requirements of Section 17-3-1.D.2, Sight Distances.

**B. Internal Sidewalks.**

- 1. **Sidewalk Standards.** Development sites shall include direct sidewalk connections and circulation at the same or greater frequency as provided for vehicles. Sidewalks shall connect public entrances of buildings and sites to the following, in the safest and most direct manner possible:
  - a. Sidewalks in the public streetscape and along private streetscapes.
  - b. Parking areas and perimeter sidewalks, internal walkways, or crosswalks associated with the parking areas.
  - c. Civic or open space, or other common areas designed for active use.
  - d. Transit stops, ride-share, and park and ride location – existing or planned.
  - e. Where the above connections are not practical or would exceed 300 feet, the best alternative pedestrian connection shall be determined in coordination with the staff review.
- 2. **Sidewalk Width.** Internal sidewalks shall meet the requirements of Table 7-2: Internal Sidewalk Widths.

Table 7-2: Internal Sidewalk Widths	
Location	Minimum Width
Residential property < 10 units	5'
Residential property 10 + units	6'
Nonresidential property, site circulation	6'
Nonresidential property, along the front facade or to primary entrance < 10,000 square feet	8'
Other primary pedestrian routes on a site.	
Nonresidential property, along the front façade or to the primary entrance 10,000 + square feet	10'
Along any parking area with vehicle overhangs.	+ 2' to other required width

- 3. **Pedestrian Amenities.** Sidewalks and internal pedestrian circulation shall be separated from moving vehicles with vertical curbs, landscape buffers, curbside parking, or similar elements of the circulation and open space system; except crosswalks or other similar limited segments, which may be distinguished paint, brick, or colored or scored concrete and similar design features that signify pedestrian priority.

**C. Bicycle Connections.** Nonresidential and multi-unit dwelling projects with 10 or more units shall provide connections between the on-site bicycle parking and the public street or nearest bicycle route, trail or greenway. These connections may be provided by:

- 1. An internal sidewalk meeting Section 17-7-3.E. Sidewalks, where the distance is less than 200 feet and people may be expected to dismount and walk their bicycles;
- 2. A shared use path at least 10 feet wide;
- 3. An internal bicycle trail meeting standards in Section 17-3-2.C; or



4. Private streetscapes utilizing the most applicable public on-street bicycle accommodations in Section 17-3-1.C.
- D. **Alternative Compliance.** Alternative compliance to the access and circulation standards in this Section may be authorized according to the process and criteria in Section 17-2-6, Alternative Compliance, based on the intent and design objectives of this section, and with the following additional applicable criteria:
1. The standards, when applied to a particular project or street, will adversely impact the function of the transportation network in the vicinity of the site.
  2. A specific access management study or plan has altered the application of these standards for the particular street segment, or the guidance for traffic control in the Standards and Specifications manual lead to a different result.
  3. The project warrants a different access design when considering the functional class of the street, the streetscape design on the particular block, and the existing and anticipated adjacent land uses.
  4. In all cases, the alternatives shall be evaluated balancing the streetscape design objectives of the specific street type, traffic conditions of a particular street segment, and bicycle and pedestrian needs.

### 17-7-3 Required Parking

- A. **Vehicle Parking Rates.** Table 7-3: Required Parking provides minimum parking requirements and general categories apply to all similar uses not specifically listed. The following criteria shall be used in interpreting the table:
1. Employee rates shall consider maximum number of employees likely to be on-site at one time.
  2. Square footage rates shall consider leasable floor area or active area dedicated to the particular use. Where this number is not easily or readily determined, 85% of gross floor area may be used.
  3. A seating or capacity rate shall consider total number of seats based on industry standards for typical layouts of buildings or building codes.
  4. Where uses or sites have components of different uses (i.e. hotel with a restaurant), each component shall be calculated under most applicable rate.
  5. Where a use is not similar to a general use in the table or could meet more than one category, the Director shall determine the appropriate classification based on industry guides and the most similar use in terms of scale, format and operation.



<b>Table 7-3: Required Parking</b>	
<b>Use Category / Specific Use</b>	<b>Minimum Parking Rate</b>
<b>Residential</b>	
<i>Accessory Dwelling</i>	1 / unit
<i>Dwellings (detached, manufactured)</i>	2 / unit
<i>Dwellings (attached, multiple, or mixed)</i>	1 / unit (Studio / 1 bedroom)
	1.5 / unit (2 bedroom)
	1.75 / unit (3 bedroom)
	2 / unit (4 + bedroom) Director may administratively approve 0.5 / unit for micro units (> 400 s.f.)
<i>Senior Living (independent)</i>	0.5 – 0.75 / unit
<i>Senior Living (assisted or nursing)</i>	1 / 4 beds + 1 per employee
<i>Group Home (assisted)</i>	1 / 4 beds + 1 per employee
<i>Group Home (protective or rehabilitative)</i>	1 / 2 bed + 1 per employee
<i>Group Home (emergency shelter)</i>	1 / 8 beds + 1 per employee
<b>Public / Civic</b>	
<i>Assembly</i>	1 / 3 seats
<i>Public Safety / Services</i>	1 / 400 s.f.
<i>Library</i>	1 / 600 s.f.
<i>Museum</i>	1 / 1,000 s.f.
<i>School</i>	2 / class (elementary or junior)
	1 / 4 students + 1 / employee (senior or higher education) OR 1 / 4 seats of all auditorium or even space, whichever is greater
<b>Commercial</b>	
<i>Retail – Small (under 3K)</i>	1 / 500 s.f.
<i>Retail – General (3K+)</i>	1 / 250 s.f.
<i>Lodging - B&amp;B</i>	1 / guest room + 1
<i>Lodging - Hotel / Motel</i>	1 / guest room + 1 / 200 s.f. of restaurant + 1 / 8 seats of meeting space
<i>Medical Care</i>	1 / 200 for all general office and service areas + 1 / bed (admittance permitted)
<i>Office</i>	1 / 300 s.f.
<i>Services ( i.e. medical / personal services, day care, bank, vehicle repair, or similar uses with frequent customer service)</i>	1 / 250 s.f.
<i>Restaurant, bar or night club</i>	1 / 100 s.f.
<i>Health and Fitness Center</i>	1 / 150 s.f.
<i>Recreation and Entertainment</i>	1 / 300 s.f. generally
	1 / 4 seats of fixed seating areas
	1 / active patron station (i.e. 4 per lane bowling; 4 per hole golf course; etc.) 1 / 100 s.f. for food and beverage service areas
<b>Industrial</b>	
<i>Manufacturing</i>	1 / 500 s.f. (artisan/limited or light)
	1 / 750 (all others) Director may administratively approve 1 / 1000 s.f. or 1 / employee for any large format manufacturing operations where the s.f. of building or site does not reflect the scale of operations or parking needs
<b>Agricultural</b>	
<i>.All uses</i>	Use combination of residential, public/civic commercial and industrial rates based on type and general nature of agriculture activities.



- B. Maximum Parking.** Development shall not provide more than 140% of the minimum required parking without documented evidence of actual parking demand based on studies of similar uses in similar contexts. In addition, any parking permitted over 120% of the minimum shall require mitigation of the potential impacts of additional parking through one or more of the following strategies:
1. Utilize eligible parking reductions permitted in Section 17-7-3.C., Parking Reductions.
  2. Provide shared parking for other uses on the block or adjacent blocks according to this Section 17-7-3.D.
  3. Use alternative surfaces designed to infiltrate stormwater, and approved by the Public Works Director.
  4. Provide additional buffers and site open spaces to screen parking with at least a 10% increase in the open space or buffers required for the parking, and at least a 20% increase in the amount of landscape material required for the parking.
  5. Design parking areas over the 120% minimum as dual-purpose space, such as plazas, playgrounds, or similar event areas for regular and active use of the space during non-peak parking times.
  6. Increase the lot open space required for the building and site in Section 17-5-3.C or Section 17-6-5 by an amount equal to the area of parking over the 120% minimum and locate this open space to limit the impact and visibility of parking.
- C. Parking Reductions.** The parking required by Table 7-3: Required Parking may be reduced depending on context and according to the following strategies:
1. *MU-DT Zone District Exemption.*
    - a. No parking is required in the MU-DT zoning district for nonresidential uses,
    - b. Any permitted residential uses shall meet the requirements in Table 7-3, except residential uses in mixed use buildings which shall meet 50% of the requirement in Table 7-3.
    - c. The Director or Town Council may require parking for any nonresidential use over 10,000 square feet provided the location, accessibility, and design of the parking is consistent with the overall planning and urban design objectives of the downtown area, or for any residential uses where the location, density, and residential building types are likely to have an impact on public or business parking in the vicinity.
  2. *On-street Parking Credit.* On-street parking within 300 feet of any lot frontage shall count towards the parking requirement at a rate of 0.5 spaces for every on-street space.
  3. *Alternative Transportation Credit.* Provision of creative and alternative modes of transportation for a development may be eligible for up to 50% reduction of the required vehicle parking. To be eligible for this credit, the applicant must demonstrate that it is practical to expect significant bicycle access to the site based on: the location and proximity to the broader bicycle transportation network; the design of the site; and the nature of the use and anticipated patrons.
  4. *Administrative Adjustment.* The Director may reduce the required parking for any use by up to 3 spaces or 10% of the required spaces, whichever is greater, due to the nature of a particular use or any unique circumstances on the site.
- D. Shared Parking.** Required parking may be reduced for any site containing multiple uses, or for adjacent sites with different uses according to Table 7-4, Shared Parking.





1. Any approved shared parking arrangement shall require an agreement and easement among all landowners participating to ensure access, joint use, maintenance, and other operational issues.
2. The agreement shall be recorded with the county clerk and recorder and shall state that it cannot be changed or modified without the approval and signature of the Director.
3. A shared agreement that differs from this table may also be approved based on a joint parking study for the sites and uses demonstrating adequate parking during peak hours for all parties to the agreement.
4. Using Table 7-4, properties shall provide adequate parking for all uses during provided peak hours such that the demand is appropriately accommodated throughout the day.

<b>Table 7-4: Shared Parking</b>					
<b>Use</b>	<b>Percentage of Required Parking by Time Period</b>				
	<b>Weekday</b>		<b>Weekend</b>		<b>All</b>
	<b>6 AM to 5 PM</b>	<b>5 PM to 1 AM</b>	<b>6 AM to 5 PM</b>	<b>5 PM to 1 AM</b>	
<i>Employment</i>	100 %	10 %	5 %	5 %	5 %
<i>Retail or Service</i>	75 %	75 %	100 %	90 %	5 %
<i>Restaurant</i>	50 %	100 %	75 %	100 %	25 %
<i>Entertainment &amp; Recreation</i>	30%	100 %	75 %	100 %	5 %
<i>Place of Worship</i>	5 %	25 %	100 %	50 %	5 %
<i>School</i>	100 %	10 %	10 %	10 %	5 %
<i>Dwellings</i>	25 %	90 %	50 %	90 %	100 %
<i>Lodging</i>	50 %	90 %	75 %	100 %	100 %

- E. **Bicycle Parking.** All nonresidential or multifamily shall provide bicycle parking spaces according to Table 7-5, Bicycle Parking.

<b>Table 7-5 Bicycle Parking</b>	
<b>Activity</b>	<b>Required Spaces</b>
<i>Retail or office uses</i>	10% of the required vehicle spaces.
<i>Recreation and community facilities</i>	15% of the required vehicle spaces
<i>Other institutional, employment, industrial or entertainment uses</i>	5% of the required vehicle spaces.
<i>Multi-unit Residential Buildings</i>	1 per dwelling unit; 2 per dwelling unit with 3 or more bedrooms

Bicycle parking shall be designed according to the following standards:

1. A structure shall be securely anchored to the ground and usable for both U-locks and cable locks, support a bike at two points of contact to prevent damage to wheels or frames.
2. Bicycle parking for nonresidential uses shall be located within 100 feet of the primary entrance unless the Director approves an alternative location.



3. In the MU-DT district, bicycle parking facilities may be located in the right-of-way, in an amenity zone, subject to streetscape design plans and the Town approval. Structures shall be designed with artistic or ornamentation enhancements compatible with the streetscape character at the specific location.
  4. On-site structures that serve another primary function, such as light poles or bollards, but are designed to meet these standards, may count to the bicycle parking requirement.
  5. Alternative standards and specifications based on recognized industry guidance or best practices for bicycle parking may be approved by the Director through development review.
- F. **EV requirements.** Electric vehicle charging stations and readiness are required to be provided on all new parking areas with more than 20 spaces required as the minimum parking requirement. This ratio shall not apply to parking spaces provided above the minimum. The Town supports additional spaces made ready or capable with conduit installed on additional spaces.
1. Residential multifamily developments shall provide a minimum of 5% of the required spaces with installed charging stations, and ensure another 5% of spaces are ready for installation, meaning full circuits are installed at construction for future station additions.
  2. Nonresidential and mixed uses shall provide a minimum of 10% installed; 10% ready.
  3. Existing parking areas that redevelop or expand the area shall apply these rates to the new spaces only.
- G. **Accessible Parking.** Accessible vehicle parking spaces shall be provided in accordance with the applicable building codes and the Americans with Disabilities Act (ADA) guidelines for quantity, design, and location.

#### 17-7-4 Parking Design

- A. **Design Objectives.** The layout, location and design of parking areas shall meet the following design objectives.
1. Locate parking and circulation in ways that minimize negative impacts on public streetscapes or adjacent sites.
  2. Use landscape, building design, and other site design strategies to improve the appearance of parking areas.
  3. Incorporate sustainable practices into parking design to minimize runoff, decrease heat island effects, incorporate low impact design features, and otherwise reduce environmental impacts.
  4. Encourage smaller and more compact parking areas to reduce impacts.
- B. **Landscape Areas.** The landscape area standards in Table 7-6 Parking Lot Landscape are based on the number of spaces and location of the parking area relative to the principal building (front, side, or rear).



Spaces per Parking Block	Front [1]	Side & Rear
151 or more	<ul style="list-style-type: none"> <li>Prohibited – must be broken into smaller parking blocks</li> </ul>	<ul style="list-style-type: none"> <li>10' perimeter buffer; and</li> <li>10 spaces per internal island</li> </ul>
51 or 150	<ul style="list-style-type: none"> <li>25' front setback buffer</li> <li>10' perimeter buffer</li> <li>10 spaces per internal island</li> </ul>	<ul style="list-style-type: none"> <li>6' perimeter buffer</li> <li>15 spaces per internal island</li> </ul>
20-50	<ul style="list-style-type: none"> <li>10' front setback buffer</li> <li>6' perimeter buffer</li> <li>15 spaces per internal island</li> </ul>	<ul style="list-style-type: none"> <li>6' perimeter buffer</li> </ul>
Under 20	<ul style="list-style-type: none"> <li>6' front setback buffer</li> <li>6' perimeter buffer</li> </ul>	<ul style="list-style-type: none"> <li>6' perimeter buffer, except where abutting an alley</li> </ul>

[1] Any surface parking lot in residential districts shall be behind the front building line or setback at least 30' from the front lot line, whichever is less.

The landscape areas required by Table 7-6 shall be allocated as follows:


1. The perimeter landscape areas shall be continuous, except for perpendicular driveways or sidewalks accessing the parking area.
2. Interior landscape islands shall be either:
  - a. A peninsula extending from the perimeter landscape area at the required intervals, at least 9 feet wide and the depth of adjacent parking spaces.
  - b. An end cap island at the required intervals that is at least 9 feet wide and at least 150 square feet for 1 stall and at least 300 square feet for two stalls; or
  - c. A continuous "center strip" between two opposing stalls along the entire parking bank that is at least 6 feet wide.
3. Perimeter area and center strip that includes a sidewalk shall meet both the sidewalk width and perimeter landscape area width independently, with no landscape area being less than 6 feet wide.
4. Perimeter and internal landscape areas shall include plant materials meeting the requirements of Section 17-8-2.

**C Sidewalks.** In meeting the standards of Sections 17-7-2.B and 17-7-4.B, a sidewalk connection shall be provided from the perimeter of the parking lot to the building entrance or building frontage. For a site or parking area with over 200 spaces, a sidewalk connection shall be provided through the parking areas and to the building frontage at least every 400 linear feet. Sidewalks meeting this standard may be located internal to the parking lot if separated from the surface parking, in perimeter landscape area or landscape median, or along a through access drive.

**D. Parking Dimensions.** Parking areas shall be designed to meet the dimension specifications in Table 7-7: Parking Dimensions.

Parking Angle Width (A)	Width (B)	Length (C)	Depth to Curb (D)	Curb Width (E)	Aisle Width – One-way (F)	Aisle Width – Two-way (G)	Bumper Overhang*
0°	7.0'	22'	7.0'	22'	12'	20'	n/a
30°	8.5'	20'	18'	17'	15'	20'	1.5'
45°	8.5'	20'	20'	12'	15'	20'	1.5'
60°	9.0'	20'	21'	10.5'	18'	24'	2.0'
90°	9.0'	20'	18'	9.0'	20'	24'	2.0'

- \* Amount of Depth to Curb dimension that may overhang landscape area or sidewalk other wheel stop block. If overhanging sidewalk, this amount shall be added to the required minimum sidewalk width.



**Figure 7-1 Parking Dimensions**  
Dimensions standards of Table 7-7, applied to typical parking layouts.

**E. General Design Standards.**

1. All required parking shall be on-site except as specifically provided in this Article for credits or shared parking sections. Additionally, the Director may allow for a portion of required parking off site through a site plan review subject to the following specific considerations:



- a. It is within 300 feet of the subject site;
  - b. It is in the same or comparable zoning district;
  - c. The presence of the off-site lot does not negatively impact potential development on that lot or in the vicinity.
  - d. There are no pedestrian barriers or other access constraints between the parking and use, and safe connections are provided between each.
  - e. An agreement demonstrating rights and control of the off-site property is provided.
2. No parking space shall be located where it backs into a street or through access drive except:
    - a. Residential parking in driveways, which for driveways accessing buildings and lots with 6 units or less; or
    - b. On-street parking on public streets or private streetscapes according to the standards in Section 17-3-1.C.
  3. Required parking areas shall be used solely for the parking of vehicles in operating condition for patrons, occupants or employees of the use, unless specifically authorized otherwise by provisions in this code.
  4. Up to 25% of the required spaces on a site may be permitted to be designed and signed for compact cars, with no space less than 16’ deep with a 2’ overhang, at 90°. These spaces may not be located along a required emergency access route.
  5. Parking and access areas shall be designed to adequately address drainage and runoff, including curb, gutters and inlets, or other drainage strategy approved by the Public Works Director to support best management practices to minimize runoff and encourage infiltration of storm water.
  6. Off-street parking areas and driveways shall be graded and paved with an all-weather material meeting the Design Standards.

- F. **Loading Requirements.** In mixed-use, commercial, or industrial districts, off-street loading shall be required as indicated in Table 7-8, Loading Areas.
1. The number and size of spaces may be revised based on the operating characteristics of the particular use and determined through site plan review.
  2. Loading areas shall be located on a remote portion of the building and site or internal to the block and buffered by other buildings wherever possible.
  3. Loading areas and activities shall not interfere with the use of walkways, drive aisles, stacking areas, internal access streets or public streets.
  4. Loading shall be screened from public streets or adjacent properties and other public-facing areas in a manner that best limits visibility and mitigates noise, according to the buffer types and design standards in Section 17-8-3.
  5. In areas, projects or zoning districts designed to promote pedestrian activity, or for buildings and sites where more compact building and site design is required, alternate loading standards shall be permitted by the Director. Alternate loading standards may include sharing of loading spaces among multiple smaller tenants, using side streets, on-street parking, or alleys – particularly where there are sufficient spaces during off hours for loading or deliveries per Table 7-8, or other similar strategies that avoid designing sites for large vehicle access.





Table 7-8: Loading Areas	
Gross Floor Area	Required Loading Area and Size
Under 10,000 s.f	N/A, or may be shared per 17-7-4.F.5
10,001 – 25,000 s.f	1 space; 10' x 25'
25,001 – 40,000 s.f.	2 spaces; at least one of which is increased to 10' x 50'
40,001 or more s.f.	3 spaces, plus 1 for every 50,000 s.f. over 100,000; at least every third space shall be increased to 10' x 50'

- G. **Alternative Compliance.** Alternative compliance to the parking design standards in this section may be authorized according to the process and criteria in Section 17-2-6, Alternative Compliance, based on the intent and design objectives of this section, and with any of the following additional applicable criteria:
1. To facilitate infill development or where site constraints hinder the ability to meet the dimensional standards.
  2. To integrate more sustainable practices considering the water quality, air quality, energy efficiency, or other similar environmental impacts.
  3. To better accommodate any non-vehicle or other alternative modes of transportation.
  4. Any exception shall be based on documentation that the proposed dimensions and arrangements will not require unsafe or impractical vehicle maneuvering.



## Article 8. Landscape & Site Design

- 17-8-1 Intent & Applicability
  - 17-8-2 Plant Requirements
  - 17-8-3 Buffer & Screens
  - 17-8-4 Plant Specifications
  - 17-8-5 Fences & Walls
- 

### 17-8-1 Intent & Applicability

A. **Intent.** The intent of the landscape and site design standards is to:

1. Improve and maintain the image of the Town and build value with a well-designed public realm, coordinating streetscapes, open spaces, and lot frontages.
2. Emphasize distinct areas throughout the Town with the location and design of landscape areas
3. Coordinate landscape and design amenities across multiple sites with special attention to the consistent relationship of public and private frontages.
4. Strengthen the character, quality, and value of development with landscape design that serves multiple aesthetic, environmental, and social functions.
5. Enhance the ecological function of un-built portions of sites, and protect and integrate established natural amenities into development projects.
6. Screen and mitigate the visual, noise, or other impacts of sites and buildings.
7. Conserve water and shift to water-conscious landscape design that is regionally appropriate and specific to the arid Front Range climate.

B. **Applicability.** The standards of this Section shall apply to all development except:

1. Additions to existing buildings or sites that do not result in an increase in building footprint or impervious surfaces by more than 10%; or
2. Changes in use that do not result in an increase in land use intensity, considering hours of operation, types of activity, or other functional impacts of the use.
3. In cases where the landscape standards apply to existing sites that may redevelop or change use, the intent is to bring the site into full compliance with these standards. For infill and rehabilitation of existing sites the Director may prorate the requirements to the extent of the site work where full compliance is not possible or practical, and only apply the standards to portions of the site subject to development.
4. For existing development with approved landscape plans, continued adherence to and maintenance of those plans is required until such time as it may redevelop or proceed with an amendment.

### 17-8-2 Plant Requirements

A. **Design Objectives.** Landscape plans shall meet the following design objectives:

1. Frame important streets and emphasize gateways with street trees, landscape massing, and other vertical elements.
  2. Provide comfort, spatial definition and visual interest to active outdoor spaces including walkways, civic spaces, parks, trails or other similar outdoor gathering places
-



3. Improve resource and energy efficiency with landscape arrangements that consider wind blocks, heat gain, water usage, solar access, and other elements inherent to the site.
4. Promote storm water management and prevent erosion through natural landscape elements that intercept, infiltrate, store, or convey precipitation and runoff.
5. Locate plants, landscape features, and site design elements sensitive to seasonal solar and shading conditions, particularly maximizing summer shade and winter sun on active portions of sites.
6. Encourage the protection and preservation of healthy plants and landscape features that can meet current and future needs of the site through development, rather than plant and design new ones.

B. **Landscape Requirements.** The required landscape shall be based on different elements of the site according to Table 8-1, and in accordance with the Design Standards.

Table 8-1: Landscape Requirements			
Site Element	Deciduous Trees	Evergreen Trees	Shrubs
<b>Streetscape:</b> The landscape area in the ROW or along the lot line immediately abutting the right of way.	1 canopy tree per 35' of lot frontage, every 25' to 45' on center. (See Design Standards for use of tree grates in walks)	n/a	n/a
<b>Front Yard &amp; Foundation.</b> The area between the building line and ROW along a street, including street sides of corner lots.	1 ornamental tree per 40' of lot frontage for buildings set back more than 10' from the front lot line; AND 1 canopy tree per 35' of lot frontage for buildings set back more than 40'.	Evergreen trees may be substituted for ornamental trees at a rate of 1 for 1, and for canopy trees at a rate of 2 for 1, for up to 50% of the requirement.	1 shrub per 5' of building frontage. 3 ornamental grasses may be substituted for each shrub up to 50% of the requirement. Seasonal planting beds or pots associated with the entrance may substitute for any building located closer than 10' to the front lot line.
<b>Parking.</b> Areas on the perimeter, or interior of parking.	1 canopy tree per 5 parking spaces	Evergreen trees may be substituted for canopy trees at a rate of 2 for 1, for up to 50% of the requirement	1 shrub per 8' of perimeter. 1 shrub per 5' for any parking area within 25' of any right of way or sidewalk.
	Ornamental trees may be substituted for canopy trees at a rate of 2 for 1 up to 50% of the requirement		3 ornamental grasses may be substituted for each shrub up to 50% of the requirement.
<b>Buffers.</b> Areas of a site that require additional landscape to mitigate potential impacts on streetscape or adjacent property.	See Section 17-8-3.		
<b>Civic and Open Spaces.</b> Areas of the site designed as part of a broader system of formal and natural open spaces.	See Section 17-3-2		
<b>Other Areas</b>	<ul style="list-style-type: none"> <li>▪ 1 canopy tree; or</li> <li>▪ 2 ornamental trees; or</li> <li>▪ 2 evergreen trees and 5 shrubs</li> </ul> per 1000 SF of interior lot areas or per 3000 SF of open space/outlot areas All other unbuilt or unpaved areas require ground cover, decorative rock, mulch or other natural and permeable surfaces resulting in 75% coverage of all areas within 3 years of planting.		



- C. **Credits for Existing Vegetation.** Preservation of existing landscape material that is healthy and desirable species may count for landscape requirements provided measures are taken to ensure the survival through construction and all other location and design standards are met.
1. Landscape plans shall provide an inventory of all existing trees or significant woody vegetation including size, health, species, and any proposed for removal.
  2. Existing landscape credits shall only count towards the portion of the site where it is located, according to the site elements in Table 8-1. For example, an existing tree may only count towards the required planting for parking lot perimeters if it remains in the parking perimeter in the final design.
  3. Credits shall be on a 1 for 1 basis provided it meets the minimum specifications for new plants. The Director may approve landscape material that is larger or otherwise established and valuable on a 2 for 1 basis, or may approve plants of exceptional quality due to species, location, maturity, and health on a 3 for 1 basis.
  4. Trees or other existing landscape that contributes to the standard shall be identified on a landscape plan and the critical root zone shall be protected for the entirety of construction by a construction fence. Tree protection measures shall be based on applicable industry standards and best practices to ensure survival of the landscape.
- D. **Design & Location.** The landscape required by Table 8-1 shall be arranged and designed in a way that best achieves the intent of this Article and design objectives of this Section, considering the context and adjacencies proposed on the site. Required plantings shall be planted in the following specific locations on the lot.
1. **Streetscape Trees.** Streetscape and frontage trees shall be located in line with other trees along the block to create a rhythm along the streetscape and promote enclosure of the tree canopy. In the absence of a clearly established line along the block, trees may be planted in the following locations in order of priority.
    - a. Centered between the sidewalk and curb;
    - b. Planted within wider walks on pedestrian-oriented or mixed-use streets located in tree wells with grates meeting the Design Standards;
    - c. 5 to 10 feet from the back of a curb where no sidewalk exists or from the sidewalk in other situations where the sidewalk is attached;
    - d. Within the first 10 feet of the adjacent lot line where significant constraints in the right-of-way would prevent other preferred locations;
    - e. Ornamental trees may be substituted for canopy street trees only in situations where no other alternative is available due to constraints of the site or right-of-way conditions. Ornamental trees may be used where trees are to be located within 10 feet of any overhead wires.
    - f. Shrubs or perennials planted in the streetscape (parkway, medians) shall be placed outside or sized appropriately to avoid impact to any site distance limits in the Design Standards.
  2. **Front Yard & Foundation Trees & Shrubs.** Front yard and foundation plantings shall be located in open spaces near the building and in planting beds along the building frontage.
    - a. Ornamental and evergreen trees shall be located within 25 feet of the building.
    - b. Shrubs and smaller plantings shall be located within 10 feet of the foundation.
    - c. Where planting beds are used within hardscape around a foundation, they should be at least 4 feet wide, at least 60 square feet, and concentrated along at least 50% of the building frontage.
    - d. Foundation plantings are not required in service and loading areas



- 
- e. Utilize larger and vertical landscape elements to frame entries, anchor the corners of buildings, and break up the visual impact of large or long building facades.
3. **Parking Lot Landscape.** Parking lot landscape requirements shall be planted in perimeter buffers and landscape islands planned and designed according to Section 17-7-4, Parking Lot Design.
    - a. There shall be at least one canopy tree per 35 feet of parking lot perimeter, or one ornamental or evergreen tree per 20 feet of perimeter.
    - b. There shall be at least one tree per parking lot island, or one canopy tree or two evergreen or ornamental trees per 300 feet of other internal landscape area.
    - c. Shrubs shall be located to define parking lot edges, screen parking from adjacent sites, or create low barriers along sidewalks and streetscapes.
    - d. Any parking within 25 feet of the right-of-way shall have a Type 1 buffer per Section 17-8-3.
  4. **Interior Lot & Common Open Space / Outlot Landscape.** The remaining unpaved, unbuilt area of a lot or any outlot shall be landscaped at the rate indicated in Table 8-1. Plants shall be designed and located to meet the design objectives, unless otherwise approved under subsection E. Alternative Compliance. Stormwater facilities shall not have plantings within the required capacity area of the facility, and landscape required for those areas shall be integrated throughout the site in other appropriate areas.
  5. **Sight Distance.** Screens, buffers and landscape shall be located and designed to maintain proper lines of sight at all intersections of streets, alleys, driveways, and internal access streets as provided in the Design Standards.
  6. **Specific Applicability.** Where landscape standards for different conditions or elements of a site overlap, effective site and landscape design may enable the space and plants to count toward more than one requirement, based on the greater plant requirement applicable to that area. For example, a buffer area required by Section 17-8-3 may also be along a parking area perimeter, or a parking area perimeter may also be along a streetscape, and the greater planting requirement between these areas can satisfy both requirements. Approval shall be subject to the Director determining that the intent and design objectives of this section are achieved.
- E. **Alternative Compliance.** Alternative compliance to the landscape design standards established in Section 17-8-2, may be authorized according to the process and criteria in Section 17-2-6, Alternative Compliance, and any of the following additional applicable criteria:
1. The alternative results in better design of common or civic space on the site;
  2. The alternative results in a better allocation of plants in relation to adjacent streetscapes or other public spaces; or
  3. The alternative is necessary to improve the longevity or survival of plant materials
  4. The alternative protects areas of environmental significance, including habitat, floodplains, and river or riparian corridors.
  5. In all cases the deviation is the minimum necessary to address the circumstance, the alternative equally or better meets the design objectives of this Section, and there are no negative impacts on other design standards applicable to the building or site.





17-8-3 Buffers & Screens

- A. **Design Objectives.** Intense land uses or site elements shall be buffered and screened from streetscapes and adjacent property according to the following design objectives. These objectives shall be used in applying the buffer requirements in Table 8-2, Buffer Planting Designs.
  - 1. Mitigate impacts of parking lots or vehicle circulation near streets or property lines with landscape barriers and low-level headlight screening.
  - 2. Use berms, vertical landscape, dense plantings, or other grade or spatial changes to alter views, subdue sound, and change the sense of proximity of incompatible uses, buildings, or site conditions.
  - 3. Soften transitions where changes in development patterns, intensity of land uses, or building scale occur.
  - 4. Screen service and utility areas of buildings and sites from adjacent property or streetscapes with architectural features, fences, or landscape that limit visibility or noise.
  - 5. Utilize three layers of landscape buffers and screens, including: canopy trees (high-level – 30'+); evergreen or ornamental trees (mid-level – 6' to 30'); and shrubs, annuals, perennials, and ground cover (low-level – under 6'), to directly and most effectively mitigate potential impacts and adjacencies.
- B. **Buffer Planting.** The planting requirements in Table 8-2: Buffer Requirements shall be used to buffer and screen more intense uses or elements of sites according to the design objectives of this section. The buffer width is independent of and may include any setback, parking perimeter buffer, or other open space requirement so that the larger requirement controls.

Site Element	Minimum Width [1]	Trees [2]	Screen [2]
<b>Type 1:</b> A low screen used to define the edges of areas, particularly along streets, alleys or walkways.	5'	1 canopy tree per 30' May substitute evergreens or ornamental tree at 2 for 1 for up to 50% of the trees	3' high shrubs at 3' on center; OR 3' high solid decorative wall or fence with shrubs, grasses and perennials along 50%
<b>Type 2:</b> A buffer designed to soften the transition between different uses, scales of buildings, or intensity of uses	10'	1 canopy tree per 30' May substitute evergreens or ornamental tree at 2 for 1 for up to 50% of the trees	6' high shrubs planted 6' on center.
<b>Type 3:</b> A buffer design to create a special and visibility barrier between incompatible situations	15'	1 canopy tree per 30' AND 1 ornamental or evergreen tree per 30'	6' high solid fence or wall with 3' – 6' shrubs and perennials along 50% the exterior fence

[1] The width of a required buffer may be narrower to account for infill situations, or more compact and urban conditions; or may be wider when combined with additional landscape or setback standards. In these cases, a combination of additional plants or structural separation may be required.

[2] Linear dimensions refers to the outside perimeter or linear feet of a use or area requiring the screen or buffer.

Buffer types in Table 8-2 shall be required in the following circumstances.

- 1. **Type 1 Buffers.** Type 1 buffers shall be required:
  - a. Except for driveways of detached houses and multi-unit houses, along the boundaries of any parking located within 25 feet of the public right of way. Parking lots with 50 or more spaces in one area require the use of a decorative wall and plantings.



- 
- b. Where parking is located within 100 feet of any pedestrian area, internal sidewalk, or public or common gathering space, with no other screen or visual separation
  - c. Along parking areas located less than 20 feet from an adjacent property unless a shared parking easement exists for the area to be readily interpreted as a single parking area.
2. **Type 2 Buffers.** Type 2 buffers shall be required:
- a. Between multi-unit projects with 10 or more units and detached houses
  - b. Between commercial and residential uses.
  - c. Between industrial and commercial uses.
  - d. In a common open space along any residential lots that back to a collector or arterial street.
  - e. Along any side or rear boundary of a commercial or industrial use that directly faces a highway or interstate.
3. **Type 3 Buffers.** Type 3 buffers shall be required.
- a. Any transition between industrial and residential uses.
  - b. Buffer and screening of any specific high-intensity uses or high-intensity portions of a site abutting or visible for public spaces or active portions of commercial and mixed-use property, as determined necessary through development review.
  - c. Any permitted outdoor storage areas or contractor yard areas.
  - d. Along any residential boundary that directly faces a state highway or interstate.
4. **Generally.** Any buffer may be required where necessary to meet the design objectives of this section or to achieve the general screening standards of Section 17-8-3.
- C. **General Screening.** All of the following shall be screened from streets or adjacent property by placement of buildings, open space, dense evergreen vegetation, a decorative and durable opaque fence or wall complementing the architectural details and materials of the building, or a combination of these screening strategies. Where design of the building, frontages, open space, buffers and other site requirements do not adequately screen these elements, the Director may require additional planting to achieve the design objectives of this Section.
1. Plantings and other screening features may suffice for:
- a. Electrical and mechanical equipment such as transformers, air conditioners, or communication equipment and antennas whether ground-, wall- or roof-mounted.
  - b. Large or long blank walls visible from public streets, public or common areas or other sensitive boundaries in association with the buffer standards.
  - c. Utility stations or fixtures.
2. Solid screening wall or fencing required for:
- a. Permanent or temporary outdoor storage and transit hub parking areas
  - b. Trash and recycling enclosures.
  - c. Delivery and vehicle service bays.
  - d. Overhead doors and loading docks.
- D. **Alternative Compliance.** Alternative compliance to the buffer and screening standards established in Section 17-8-3, may be authorized according to the process and criteria in Section 17-2-6, Alternative Compliance.



17-8-4 Plant Specifications

- A. **Design Objectives.** The plant specifications have the following design objectives:
  1. Ensure the longevity and survival of landscape investments with proper species, location, installation and maintenance of plants.
  2. Promote regionally appropriate strategies, including limiting risk of disease or infestation through diversity of urban forest on an area- or town-wide basis.
  3. Establish minimum standards that balance immediate conditions with reasonable long-term growth and performance of landscape plans.
  4. Require water efficient strategies in terms of the water needs of landscape plans, and the continued operations and maintenance of sites.
  
- B. **Species.** All trees, shrubs, and seed mixes shall be selected and planted according to the Johnstown Recommended Plant Materials and other specifications in the Streetscape, Parks, Open Space section of the Design Standards. In addition to any species on these lists, alternatives may be proposed and approved as part of the development review provided they:
  1. Are documented by a landscape architect or other credible information comparable in type and performance to any species on this list;
  2. Are adaptable to the climate of the Front Range region and the specific conditions in which they are proposed; and
  3. Are not invasive or otherwise problematic to the overall health of the landscape.
  
- C. **Plant Specifications.** All landscape materials shall meet the American Standards for Nursery Stock standards, and be selected for its native characteristics or survival in the climate for the Front Range region. Plants shall meet the following specifications at planting:

Table 8-3: Plant Specifications	
Type	Specification
Canopy Tree	2" DBH; Mature height of at least 30'
Ornamental Tree	2" DBH ; 8' to 10' minimum planting height for multi-stemmed; Mature height of 15' – 30'
Evergreen Tree	6' minimum planting height; Mature height of at least 10'. Evergreens with mature heights of 30' or more may be classified as large trees.
Shrub	24" or 5-gallon minimum container
Perennials	1-gallon container
Ground Cover	Areas designed for vegetative cover shall have 50% ground cover at the time of planting and full coverage within 2 growing seasons
General	Plants used for screening and buffers shall achieve the required opacity and function in its winter seasonal conditions within 2 years following planting.

DBH – Diameter at breast height



D. **Tree Diversity.** The required trees planted shall promote diversity with the following species selection criteria.

Table 8-4: Tree Diversity	
Required Trees	Diversity
1 - 9	No specific requirement, but trees should be diversified from those existing trees in the vicinity.
10 - 39	At least 2 genus; AND At least 3 species No more than 50% of any one species
40+	At least 3 genus; AND At least 4 species No more than 33% of any one species

\* Any streetscape master plan or public realm plan may achieve street tree diversity on a broader or block-scale basis while planting the same species on individual segments for the urban design effect.

E. **Water Conservation Guidelines.** All landscape plans shall conserve water with landscape materials and design techniques using the following principles.

1. Incorporate a “zoned planting scheme” to reduce water demand by grouping plants with similar water requirements together in the same hydrozone.
2. Limit high-irrigation turf and plantings to appropriate high-use areas with high visibility and functional needs, and use water-conserving grasses such as fescue sods. Turf and spray-irrigated areas shall be limited to:
  - a. Residential rear yard areas maximum of 50%, up to 2,000 SF for single family homes, except for lots platted prior to January 1, 2024;
  - b. Areas designed for play, sports fields, and similar common or public park areas;
  - c. Achieving specific aesthetic and design objectives at significant gateways, corridors, or entryways to neighborhoods or activity centers, at the discretion of the Town.
3. Use drought tolerant plants, suitable to the region, with low watering and pruning requirements. Water conservation and xeric species may be found and referenced on the plantselect.org website, or similar reputable source acceptable to the Town.
4. Incorporate soil amendments and use of organic mulches that reduce water loss and limit erosion. All planting areas shall receive soil amendments of at least 3 cubic yards per 1,000 square feet. Certification of and proof of amendment may be required.
5. Install efficient automatic irrigation systems that incorporate water conservation measures, including spray heads for ground cover and drip irrigation for shrubs and trees, weather/rain gauges, and high-efficiency or precision nozzles.
6. Native grasses may be used in low-traffic areas and require irrigation to establish. Raw water dedication, per the Johnstown Municipal Code - required with a review for credit at the sole discretion of the Town upon confirmation of the removal or effective disablement of the irrigation system. Seed mix shall be per the Design Standards.
7. Alternative non-potable sources and systems of irrigation water for all common landscape areas is encouraged and shall be required if available in sufficient quantity

F. **Stormwater Treatment.** Landscape amenities that incorporate stormwater treatment are recommended, provided they can meet both the landscape design standards and the stormwater management performance standards. Techniques such as bioswales, water quality ponds, and rain gardens should be used to infiltrate runoff from parking lots, streets, civic spaces, and other impervious surfaces wherever possible.



- G. **Planting & Maintenance.** All landscape plans shall include installation specifications meeting the Design Standards method of maintenance including a watering system and statement of maintenance methods.
  - 1. All plantings shall be properly maintained. Plant materials which fail to grow within a 2-year period or which exhibit evidence of insect pests, disease, and/or damage shall be appropriately treated, and any plant in danger of dying or already dead shall be removed and replaced.
  - 2. All elements of an approved landscape plan including plant materials shall be considered material elements of the project in the same manner as parking, buildings, or other details. Deficiencies of any approved landscape plan at any point may be enforced as a violation of the provisions of this ordinance.
  
- H. **Alternative Compliance.** Alternative compliance to the plant specification standards established in Section 17-8-4, may be authorized by the Director according to the process and criteria in Section 17-2-6, Alternative Compliance, and any of the following additional applicable criteria:
  - 1. The alternative is necessary to improve the longevity or survival of plant materials.
  - 2. The alternative improves the health or general species mix specific to the context and vicinity of the site.
  - 3. In all cases the deviation is the minimum necessary to address the circumstance, the alternative equally or better meets the design objectives of this Section, and there are no negative impacts on other design standards applicable to the building or site.

### 17-8-5 Fences & Walls

- A. **Design Objectives.** Fences and walls provide safety and security, screening, and architectural enhancements to sites and buildings and shall meet the following design objectives:
  - 1. Fence and wall designs shall consider the context of the area, the location on the site, and the desired functions.
  - 2. Fences and walls with prominent publicly visible locations require higher design standards, accompaniment of landscape to soften the expanse, or a combination of both.
  - 3. Fences and walls in walkable contexts or nearest pedestrian facilities require a lower profile, more open design, or both.
  - 4. Fences and walls in prominent public places should complement the design of the site and the architecture of the associated building.
  - 5. Fences and walls shall be designed and located sensitive to the massing and design relationship, and other impacts to adjacent property.
  
- B. **Fence & Wall Standards.** All fences and walls shall meet the following standards.
  - 1. *Height & Location.* Fences shall be located according to Table 8-5: Fence Height and Location.

Table 8-5: Maximum Fence Height and Location		
	Residential	Commercial & Industrial
Front	<ul style="list-style-type: none"> <li>▪ 3' high if solid</li> <li>▪ 4' high if at least 50% open</li> </ul>	<ul style="list-style-type: none"> <li>▪ 3' high if solid</li> <li>▪ 4' high if at least 50% open</li> </ul>
Side & Rear	<ul style="list-style-type: none"> <li>▪ 6' if behind the front building line</li> </ul>	<ul style="list-style-type: none"> <li>▪ 8' if behind the front building line</li> </ul>





**Table 8-5: Maximum Fence Height and Location**

<i>Location</i>	<ul style="list-style-type: none"> <li>▪ All fences or walls shall be located on private property.</li> <li>▪ Where a property line is not known, installation shall be at least 2 feet from any public or common space sidewalk or trail.</li> <li>▪ If inadvertently located in any public right of way are subject to removal without replacement, if the area is required for public use or maintenance, repair, or replacement.</li> </ul>
<i>Generally</i>	<ul style="list-style-type: none"> <li>▪ Ornamental enhancements associated with an entry or gateway may be up to 8' high.</li> <li>▪ All fences or walls located along adjacent lot lines shall be constructed so that either:             <ul style="list-style-type: none"> <li>○ The face of the fence is on the property line, with the finished side facing outward; or</li> <li>○ The face of the fence is at least 3 feet from the property line. Any areas set back 3 feet or more from the property line, which could become enclosed by other similarly located fences or walls, shall provide at least one gate for access and maintenance equipment.</li> </ul> </li> <li>▪ Fences or walls outside of required setbacks (i.e. in the buildable envelope), and behind front building line can exceed height limits, but may be limited by building codes or other public health and safety standards.</li> <li>▪ Height includes any retaining wall or berm the fence is built on; however, the Director may grant exceptions where for fences in conjunction with a berm or wall where they equally or better serve the intent and design objectives of this Article.</li> </ul>

2. **Permitting and Maintenance.** All fences and walls shall be built to applicable codes, be engineered and permitted where required, and be maintained in good condition regarding both structure and appearance.
3. **Perimeter Fences.** Any fence designed as part of a perimeter fence for multiple properties, as part of a landscape buffer, or any expanse longer than 100 feet and within 30' of a collector or arterial, shall meet the following standards:
  - a. All fencing shall be softened with landscape materials on the street side of fences meeting the buffer standards of Section 17-8-3.
  - b. Expanses of over 300' shall be broken up by either:
    - (1) Offsets to solid fencing required of at least 3 feet on 1/3 of the length for every 300-foot span; or
    - (2) Ornamental designs on at least 1/2 of every 300-foot span that is at least 75% open (i.e. wrought iron); and
    - (3) Masonry columns are required at least every 100 feet.
4. **Sports and Recreation Fences.** Fences for sports and recreation facilities, or for any other similar public facility, may be up to 10 feet generally; or up to 14 feet for tennis, pickleball, or similar sport courts if at least 50% open above 7 feet high; and taller to serve the functional need for backstops or golf course protection.
5. **Materials.** All fences and walls shall be made of the following durable materials:
  - a. Decorative iron;
  - b. Masonry;
  - c. Wood, commercially-available wood intended for fencing;
  - d. Vinyl;
  - e. Vinyl covered chain-link/woven wire may be used in commercial and industrial applications, except prohibited for any front fence or along a public street;



- 
- f. Barbed wire, limited to the top 12" of a fence placed on the side or rear of commercial and industrial uses, not immediately adjacent to a residential use. Fences and only if all portions of barbed wire are above 6 feet high. Razor and concertina wire is prohibited except in special and unique circumstances or in applications for federally-protected facilities.
  - g. Electrical fences are only allowed for permitted agriculture uses.
- 6. *Construction and Erosion Control Fences.* Temporary fences for construction may be up to 10 feet in height, or as otherwise specified in construction permits.
  - 7. *Drainage Easements.* No fence shall be constructed which could impede the flow of drainage waters. All fences must be installed in a manner that will not constrict the water flow planned for proper drainage of the lots in a subdivision.
  - 8. *Sight Distances.* All fences, walls or screening shall be located out of the sight distances in the Design Standards, or otherwise limited to no more than 3 feet high in these areas.
- C. **Alternative Compliance.** Alternative compliance to the fence and wall standards established in Section 17-8-5, may be authorized by the Director according to the process and criteria in Section 17-2-6, Alternative Compliance.



## Article 9. Signs

- 17-9-1 Intent & Applicability
  - 17-9-2 Exempt Signs
  - 17-9-3 Permitted Sign Types & Allowances
  - 17-9-4 Standards for Specific Signs
  - 17-9-5 General Standards – All Signs
  - 17-9-6 Planned Unit Development Signs
- 

### 17-9-1 Intent & Applicability

- A. **Intent.** The intent of the sign standards is to:
1. Create an attractive aesthetic environment in the town.
  2. Enhance the quality and civic design of the community through the visual priority of buildings, streetscapes, open spaces, landscapes, and other investments in the public realm.
  3. Ensure that signs preserve and contribute to the unique character and identity of distinct places and districts.
  4. Improve economic viability by assuring that the town is a visually pleasant place to visit, conduct business, and live.
  5. Provide effective identification and communication for businesses, institutions, and other community destinations without excessive competition for visual attention.
  6. Protect property values and investments by minimizing adverse effects from signs on adjacent property.
  7. Promote safety for pedestrians, bicyclists, motorists, or other users of the public rights-of-way with proper location, construction, operation, and maintenance of signs.
  8. Ensure that the constitutionally guaranteed right of free speech is protected through appropriate standards for signs as a way of public communication.
- B. **Applicability.**
1. **General Applicability.** The standards in this Article shall apply to all signs except:
    - a. Legal non-conforming signs, subject to the provisions in Section 17-1-7.F
    - b. Exempt signs, to the extent of the limitations and specifications in Section 17-9-2.
  2. **Permit Required.** All signs shall require a permit to demonstrate compliance with this Article, issued based on an application signed by the property owner or the owner's authorized agent, except the following signs:
    - a. Signs exempt from a sign permit, as specified in Section 17-9-2.
    - b. The change of copy or content, change of sign panels, or similar changes to an existing sign that conforms to these standards, provided there is no change in the size, sign structure, or other essential design characteristics of the sign.
    - c. Ordinary maintenance or repair of existing signs provided no structural changes are made.
    - d. Permits may be required for any sign work to demonstrate compliance with other public safety codes, such as electrical, fire, or building codes.



C. **Sign Measurements.** Sign dimensions shall be interpreted as follows:

1. **General Area Calculation.** All applicants for a sign permit shall provide the surface area of the sign in square feet, providing methods and measurements for the calculation. Signs mounted on or displayed as a standard geometrical shape shall be measured by the standard mathematical formula for that shape. Signs mounted on or displayed as an irregular shape shall be measured by the smallest area of up to two standard geometrical shapes that can encompass the entire sign mounting.
2. **Freestanding Signs.** The area of a sign shall be computed by the entire area of the face of the structure, cabinet, or module encompassing the sign. Bases or supporting structures that include no message may be excluded from the sign area calculation.
3. **Wall, Window or Other Building-mounted Signs.** Any building mounted sign mounted on a background shall be measured by the area of the background. If mounted directly on the wall, the area shall be computed by means of the smallest single and continuous perimeter of up to two standard geometric shapes that enclose the outer limits of the writing, emblem, or other display. Gaps which are greater than two times the height of the sign area, when using the continuous perimeter above, may be subtracted from the calculation of the sign area, but it shall be interpreted as two signs. The area of the wall or window area for the purposes of determining the sign allowance shall be the total surface of the wall or window visible in an elevation view.
4. **Decorative Elements.** Embellishments such as pole housing, framing, decorative roofing and support structures, such as architectural or masonry bases, shall not be included in the area of the measurement if they contain no writing, emblem, or other display.
5. **Double-faced Signs.** Where the sign faces of a double-faced sign are no more than three feet apart at any location, only one face will be measured in computing sign area. If the two faces of a double-faced sign are of unequal area, the area of the sign will be the area of the larger face.
6. **Three-dimensional Objects.** Three-dimensional sign area is measured by the profile surface area that encloses the entire object on each side. This is calculated by the largest two-dimensional elevation of the object, taken from a typical viewing angle.

## 17-9-2 Exempt Signs

The following signs are exempt from a sign permit provided the sign meets all other applicable requirements of this Article. Unless specifically noted, exempt signs do not count towards the sign allowance specified for each zoning district. Signs beyond the limits of the exemptions may only be permitted by permits meeting the sign standards and allowances of the zoning district.

A. **Property Identification Signs.** Signs that enhance the ability of public safety, emergency services personnel, and the general public to locate a property, and which are visible from the right-of-way or other publicly accessible common areas, are exempt from permits subject to the following limitations:

1. **Address Signs.** Two per address, including suite numbers, up to 2 square feet each, only one of which may be ground-mounted. Address signs on buildings shall be placed between 4 feet and 12 feet high. Ground-mounted address signs shall be no more than 36 inches high, or incorporated into other permitted signs.



- 
2. **Building Name Plate.** Each building or site may have one name plate sign per frontage on streets or common areas, up to 5 square feet. Building name plate signs shall be associated with the permanence or significance of the building or site, rather than a particular tenant, and include designs such as engraved stone, bronze plates, or similar ornamental detail integrated with the architecture of the building or the site landscape.
- B. **Public Safety, Traffic Control or Public Information.** Signs designed and located to control traffic movement and safety of vehicles and pedestrians according to uniform traffic control device standards; public wayfinding signs for community destinations; signs required by the Town's Building or Fire Code; or signs otherwise required to support any official action or legal obligation of a federal, state, or local government, may be designed and located to meet the public purposes or requirements of other codes.
- C. **Flags.** Flags shall be mounted a building below the building height or mounted on a permanent freestanding pole subject to the height limit of the zoning district and setback from the property line a distance equal to the actual height of the flagpole.
1. **Residential Uses.** Up to three non-commercial flags may be permitted per lot. Total flag area per property shall not exceed 80 square feet and no single flag may be more than 40 square feet. Residential uses may also display non-commercial flags in windows, which will be counted toward the total number and allowable area.
2. **Nonresidential Uses and Mixed-use Projects.** Up to five non-commercial flags may be permitted per lot. Total flag area per property shall not exceed 200 square feet and no single flag may be more than 100 square feet.
- D. **Window Signs.** Signs or window graphics may be mounted to the interior of any first-floor windows in nonresidential districts, provided signs shall not exceed more than 25 percent of the area of all first-floor windows, and at least 50 percent of the window the sign is mounted on remains clear of any visual obstructions.
- E. **Temporary Signs.** Temporary signs are exempt from the sign permit process, and are subject to the standards in Sections 17-9-2 and 17-9-2, and 17-9-4.D.
- F. **Incidental Signs.** Incidental signs for nonresidential uses or multi-family complexes, which are intended to convey messages to guests, patrons, or other users of the property, such as traffic or parking instructions, service or other internal directions, security warnings, or other similar minor accessory signs are limited to:
1. No single sign may be more than 4 square feet, or 12 square feet for lots more than 1 acre.
2. Signs that are over 1.5 square feet are limited to no more than 12 square feet total sign allowance per lot, or 40 square feet per acre, whichever is greater.
3. Signs shall be no more than 6 feet high if ground-mounted or 12 feet high if mounted on a building;
4. Signs shall be setback at least 10 feet from all property lines; and
5. Grouping or arranging incidental signs to have the effect of a larger permitted sign or and increase visibility from rights-of-way or other publicly accessible common area makes all signs in the grouping ineligible for this exemption.
- G. **Construction Signs.** Signs associated with active construction sites are limited to:
1. 80 square feet of total sign allowance per 600 linear feet of public street frontage, calculated on a pro-rata basis;
2. No more than 3 signs per street frontage;





- 3. Signs may be mounted on a building ground-mounted, and shall be limited to 12 feet in height;
- 4. Incidental contractor branding on vehicles, materials, fencing, work trailers, and similar shall be exempt, and not subject to this sign allowance limit; and
- 5. The signs shall only be posted for the duration of a valid permit associated with the project.

These signs are in addition to any other temporary sign allowances in Tables 9-2 and 9-3.

- H. **Special Event Signs.** Signs associated with a temporary special event may be approved through the permitting and approvals for the event. Signs shall generally follow the standards in this Section; however, the event approval process may authorize deviations that generally meet the intent of this Article, or are otherwise based on the short term and special circumstances of the event.
- I. **Interior Signs.** Any sign that is not visible from the right-of-way, from any point along the perimeter of the property or from adjacent property, or from publicly accessible common spaces are exempt from permits and the standards of this Chapter, but may be subject to electrical, fire, or building codes, or subject to other construction and public safety specifications.
- J. **Venue Signs.** Signs associated with a public or common gathering space for events, and which are oriented only towards patrons of the event, such as scoreboards, institutional logos, or similar experience branding are exempt from the permits and standards provided they are approved as part of a site plan for the facility.
- K. **Vehicle Signs.** Signs permanently and professionally affixed via paint, decal, sticker, wrap, or similar technology to the standard exterior of a licensed and functional vehicle, for the clear purpose of identifying the vehicle or service provider for commercial use, and parked in a typical vehicle or service area, or being driven, shall not be subject to this Code. All other signage affixed to a vehicle, trailer, or other mobile object that may be reasonably interpreted to be regularly, or permanently placed for the purposes of providing signage is subject to dimensional and locational elements in this Code.

### 17-9-3 Permitted Sign Types & Allowances

- A. **Permitted Sign Types.** The following sign types are distinguished for the purposes of determining the total sign allowance for permitted signs for each lot or building.

Table 9-1: Permitted Sign Types	
Sign Type	Description
<b>Building Signs</b>	A sign painted, printed, or attached to the exterior surface of a building, awning, canopy, or other fixed building surface in a permanent manner. Building signs are the principal signs for the building or site and generally have a scale and design legible to vehicles in the public right-of-way or otherwise legible distant from the building (distinguished from Pedestrian Signs below).
<b>Freestanding Signs</b>	A detached sign that is independent from any building. Freestanding signs are the principal signs for the building or site and generally have a scale and design legible to vehicles in the public right-of-way or adjacent drives. (Distinguished from Pedestrian Signs below).
<b>Pedestrian Signs</b>	A sign with a design and scale to be legible to pedestrians in front of or immediately adjacent to the building or site, or to be legible to individuals internal to a site containing multiple buildings. Pedestrian signs may be attached to buildings or mounted on the ground independent to a building in a permanent manner. Typical examples include signs hanging below a covered walk, canopy, or awning, mounted on or projecting from a wall, or freestanding signs associated with a pedestrian entrance or passage.



<b>Temporary Signs</b>	A portable sign which is not permanently embedded in the ground or permanently affixed to a building or structure, and designed or intended to be used for a brief period of time. Temporary signs do not include permanent signs with temporary or changeable messages.
------------------------	--

**B. Residential Districts.** The following sign types are permitted in residential zoning districts:

Table 9-2: Permitted Signs – Residential Districts		
Sign Type	Standards	
<b>Building Signs</b>	Quantity	<ul style="list-style-type: none"> <li>▪ Permitted for principal nonresidential or multi-unit residential buildings (i.e. schools, churches, community centers, apartments)</li> <li>▪ 2 per street-facing building elevation</li> <li>▪ No more than 1 on any single wall plane</li> </ul>
	Maximum Size	<ul style="list-style-type: none"> <li>▪ 5% of street-facing building elevation or 100 s.f , whichever is less (<i>per sign</i>)</li> </ul>
	Height	<ul style="list-style-type: none"> <li>▪ At least 1 foot below the top of the wall it is mounted on for flat roof buildings.</li> <li>▪ At least 1 foot below roof deck or eave line for pitched roof buildings.</li> </ul>
	Other Standards	See Section 17-9-4.A
<b>Freestanding Signs</b>	Quantity	<ul style="list-style-type: none"> <li>▪ Permitted for principal nonresidential or multi-unit buildings (i.e. schools, churches, community centers, apartments)</li> <li>▪ 1 per street frontage; but no more than 2 per lot.</li> </ul>
	Maximum Size	<ul style="list-style-type: none"> <li>▪ 32 s.f. (<i>per sign</i>)</li> </ul>
	Maximum Height	<ul style="list-style-type: none"> <li>▪ 6'</li> </ul>
	Other standards	<ul style="list-style-type: none"> <li>▪ Setback from property lines at least a distance equal to the height</li> </ul> See Section 17-9-4.B, Residential property may also be permitted Identity Signs as provided in Section 17-9-4.E
<b>Pedestrian Signs</b>	Quantity	<ul style="list-style-type: none"> <li>▪ Permitted for principal nonresidential or multi-unit buildings (i.e. schools, churches, community centers, apartments)</li> <li>▪ 1 per each public building entrance</li> </ul>
	Maximum Size ( <i>per sign</i> )	<ul style="list-style-type: none"> <li>▪ 6 s.f; or</li> <li>▪ 8 s.f. if associated with a primary building entrance</li> </ul>
	Maximum Height	<ul style="list-style-type: none"> <li>▪ 6' if ground-mounted</li> <li>▪ 12' if mounted on a building</li> </ul>
	Other Standards	See Section 17-9-4.C.
<b>Temporary Signs</b>	Total Allowance	<ul style="list-style-type: none"> <li>▪ 18 s.f., or 0.18 s.f. per 1' of street frontage whichever is greater, but no more than 48 square feet.</li> </ul>
	Quantity	<ul style="list-style-type: none"> <li>▪ N/A; subject to total allowance and duration limits; however the duration and period of multiple signs allowed is limited. See Section 17-9-4.D</li> </ul>
	Maximum Size ( <i>per sign</i> )	<ul style="list-style-type: none"> <li>▪ 8 square feet</li> <li>▪ 24 square feet per sign for lots with over 150' of street frontage.</li> </ul>
	Maximum Height	<ul style="list-style-type: none"> <li>▪ 6' if ground-mounted</li> <li>▪ 20' or 1' below top of wall plane, whichever is less, if mounted on a building</li> </ul>
	Other Standards	See Section 17-9-4.D



C. **Mixed-use & Industrial Districts.** The following sign types are permitted in mixed-use and industrial zoning districts:

Table 9-3: Permitted Signs – Mixed-use & Industrial Districts		
Sign Type	Standards	
<b>Building Signs</b>	Total Allowance	<ul style="list-style-type: none"> <li>2 s.f. for each 1 linear foot of building frontage for first 100' of building frontage; plus</li> <li>1 s.f. for each 1 linear of building frontage over 100' of building frontage</li> </ul>
	Quantity	<ul style="list-style-type: none"> <li>Single-tenant Buildings: 4 signs per street-facing elevation</li> <li>Multi-tenant Buildings: 1 primary sign per street-facing elevation, on a pro rata basis based upon the linear frontage of the building.</li> </ul>
	Maximum Size (per sign)	<ul style="list-style-type: none"> <li>200 s.f.</li> </ul>
	Maximum Height	<ul style="list-style-type: none"> <li>At least 1 foot below the top of the wall it is mounted on for flat roof buildings.</li> <li>At least 1 foot below roof deck or eave line for pitched roof buildings.</li> </ul>
	Other Standards	See Section 17-9-4.A
<b>Freestanding Signs</b>	Total Allowance	<ul style="list-style-type: none"> <li>1 s.f. for each 1 liner foot of building frontage for first 100' of building frontage; plus</li> <li>0.5 s.f. for each 1 linear of building frontage over 100' of building frontage</li> </ul>
	Quantity	<ul style="list-style-type: none"> <li>1 per 150' of street frontage (minimum 100' separation between signs)</li> <li>3 per lot or development maximum.</li> </ul>
	Maximum Size (per sign)	<ul style="list-style-type: none"> <li>N/A; limited to total allowance</li> </ul>
	Maximum Height	<ul style="list-style-type: none"> <li>Single user or 1-3 tenants- 12'</li> <li>Multi-tenants / Other - See Development Identity Signs in Section 17-9-4.E.</li> <li>Signs within 100' of the I-25 right-of-way 50' or 50' higher than adjacent interstate grade, whichever is higher.</li> <li>Signs within 50' of a state or U.S. highway right-of-way - 50'; not permitted in the MU-DT district.</li> </ul>
	Minimum Setbacks	<ul style="list-style-type: none"> <li>50% of the sign height and lot located in any easements</li> </ul>
	Other standards	See Section 17-9-4.B Projects over 5 acres may also be permitted Identity Signs as provided in Section 17-9-4.E
<b>Pedestrian Signs</b>	Quantity	<ul style="list-style-type: none"> <li>1 sign per each 50' of building frontage, or one for each tenant with a separate public entrance;</li> <li>Plus 1 for each building entrance</li> </ul>
	Maximum Size (Individual Signs)	<ul style="list-style-type: none"> <li>6 s.f.; or</li> <li>8 s.f. if associated with a primary building entrance</li> </ul>
	Height	<ul style="list-style-type: none"> <li>6' if ground-mounted</li> <li>12' if mounted on a building</li> </ul>
	Other Standards	See Section 17-9-4.C
<b>Temporary Signs</b>	Total Allowance	<ul style="list-style-type: none"> <li>32 s.f. total sign allowance, or 0.25 s.f. for every 1 linear foot of street frontage for lots over 100' of frontage, up to a maximum of 100 s.f.</li> </ul>
	Quantity	<ul style="list-style-type: none"> <li>N/A; subject to total allowance and duration limits; however the duration and period of multiple signs allowed is limited. See Section 17-9-4.D.</li> </ul>



Maximum Size (Individual Signs)	<ul style="list-style-type: none"> <li>▪ 12 s.f.</li> <li>▪ 24 s.f. for lots with 100' to 200' of street frontage</li> <li>▪ 48 s.f. per sign for lots with over 200' of street frontage.</li> </ul>
Height	<ul style="list-style-type: none"> <li>▪ 6' if ground-mounted</li> <li>▪ 20' or 1' below top of wall plane, whichever is less, if mounted on a building</li> </ul>
Other Standards	See Section 17-9-4.D

### 17-9-4 Supplemental Standards for Specific Sign Types

The standards in this section are supplemental standards, in addition to the general standards in Tables 9-2 and 9-3 applicable to specific sign types.

**A. Building Signs.** Buildings signs are subject to the following additional standards:

1. Building signs in the MU-DT district shall be limited to a sign band between the street level storefront and the first story cornice or frieze, or on a first-story awning, except buildings 3-stories or taller may allocate up to 50% of the building sign allowance to a sign located within 8 feet from the top of the facade.
2. No portion of a building wall or other structure may be built above the roofline, which serves no other structural or architectural purpose, other than to mount a sign or expand the sign area allowance. A parapet intended for rooftop mechanical screening or to provide articulation may be used to place building signs.
3. Building signs shall not project more than 15 inches off the wall surface, except projecting signs meeting the following additional limitations:
  - a. Projecting wall signs may extend from and be perpendicular to the wall up to 10 feet, but no closer than 5 feet to the back of the curb.
  - b. Projecting signs shall be at least 8 feet above grade.
  - c. Projecting signs shall be no larger than 2 square feet for every 1 foot of building height, to a maximum of 50 square feet.
  - d. Only one projecting sign is permitted per wall.

**B. Freestanding signs.** Freestanding signs are subject to the following additional standards:

1. Freestanding signs used in the MU-DT and MU-NC zoning district are permitted only in instances where the front entrance of the primary building is located in compliance with Section 17-6-3, Frontage Design, and is setback from the right of way at least 20 feet.
2. Support structures and bases shall be constructed with durable, high quality architectural materials (such as brick or stone) that complement the building or are integrated into the landscape and other site elements in terms of material, colors, and ornamentation.
3. Freestanding signs shall be accompanied by a landscape or civic space plan that integrates the sign area into the overall site, softens the visibility of the structural elements, and improves the appearance of the sign and property from the streetscape subject to the standards and criteria of Article 8.
4. Any lot or site that uses only building signs (no freestanding signs) may receive a 20% bonus in the permitted building sign allowance.

**C. Pedestrian Signs.** Pedestrian signs are subject to the following additional standards:

1. Pedestrian signs shall be placed along building frontages where there is direct pedestrian access and circulation



2. Signs may be mounted directly on the surface of the wall, awning, or canopy, or if hanging below, maintains at least 8 feet clearance from the sidewalk below
  3. Pedestrian signs associated with an entrance shall be located within 10 feet of a business entrance.
  4. Portable pedestrian signs (“A frame”, “sandwich board” or “T-frame”) have a limited license to be placed in the public right-of-way for any permitted retail or service use provided:
    - a. Signs are only permitted on Pedestrian Streets meeting the street design standards of Section 17-3-1, or other areas of a site associated with pedestrian circulation and access.
    - b. No more than one sign per public building entrance.
    - c. The sign shall be no more than 8 square and is limited to no wider than 3 feet and not taller than 4 feet.
    - d. The sign is placed within 20 feet of the main entrance of the building or service area of a business, and at least 2 feet from any curb.
    - e. The sign is placed on or near a sidewalk, and otherwise associated with pedestrian routes to and from the business.
    - f. The sign shall maintain at least six feet clear passage for pedestrians on the sidewalk, and is otherwise located to avoid visual obstructions or safety hazards for users of the right-of-way.
    - g. The sign shall be permitted only during business hours of the associated business.
    - h. The sign shall be weighted to remain upright and in place, and removed immediately in periods of high winds or otherwise at the request of the Town.
- D. **Temporary Signs.** Temporary signs are subject to the following additional standards:
1. No temporary sign shall be displayed for more than 120 consecutive days, without 120 days intervening. Relocation of a temporary sign, or removal and replacement with a substantially similar sign does not extend the time period for the temporary sign.
  2. The period when more than 1 temporary sign may be placed on a lot or site shall be limited to no more than 120 days.
  3. The total area allowance for temporary signs in Table 9-2 or 9-3 may be allocated to multiple signs, provided:
    - a. No single sign exceeds the maximum area per sign.
    - b. The limitation periods for a single sign or multiple signs is not exceeded.
    - c. Signs shall not be grouped or arranged to have the effect of a larger permitted sign or otherwise be coordinated as a single sign.
  4. Temporary signs shall not be illuminated or use any light reflecting materials or coating.
  5. Temporary signs shall be constructed of durable material, designed to resist quick deterioration from the elements, and securely anchored to not pose a distraction or hazard. Non-rigid materials (such as banners) shall be secured by a support or frame to avoid distraction or flapping.
  6. The Director may require the removal of any temporary sign that pertains to an expired event, or may refrain from enforcement of the duration or time limits for any temporary sign related to an event that has been extended beyond the control of the owner.
- E. **Identity Signs.** Larger commercial properties and residential neighborhoods may be permitted identity signs as provided in this section.
1. *Nonresidential, Mixed-use or Industrial Identity Signs.* Nonresidential or mixed-use projects over 20 acres and with multiple tenants or buildings are permitted identity signs in addition to the permitted freestanding sign allowances, subject to the following:





- a. Identity signs shall be incorporated into a significant architectural element that reflects the unique character and identity of the area.
  - b. Structures associated with identity features shall generally be subject to height limits of the district, however exceptions may be approved through the site development plan process and based on the context of the site. No exception shall be approved beyond the height limits in Table 9-3.
  - c. No more than two identity signs per entrance and one per corner at the intersection of two perimeter streets.
  - d. Maximum sign area shall be no more than 200 square feet per sign.
  - e. Identity signs shall be located at least 200 feet from any other freestanding sign, except for matching or complimentary identity signs on either side of an entrance.
  - f. Identity signs shall be located on the site of the nonresidential use, or in a common area owned and controlled by a property or business association, provided there is an owners association or similar entity to ensure on-going maintenance of the sign and landscape.
2. **Residential Identity Signs.** Residential projects with more than 20 lots or more than 5 acres are permitted identity signs in addition to the permitted freestanding sign allowances subject to the following standards:
- a. All residential gateway signs shall be monument signs, no higher than 8 feet, unless incorporated into an accessory structure that is an integral part of the landscape design.
  - b. Identity signs shall be limited to no more than 2 per entrance from a collector or arterial street, provided the entrances are separated by at least 300 feet.
  - c. Identity signs shall be limited to:
    - (1) 24 square feet for entrances on a collector street;
    - (2) 48 square feet for entrances on an arterial street.
  - d. Identity signs shall be set back from the lot or parcel line at least 6 feet.
  - e. Identity signs shall be located on the site of the residential use, or in a common area owned and controlled by a property or business association of the residential uses, provided there is a property manager, homeowners association, or other entity to ensure on-going maintenance of the sign and landscape.
3. **Site Development Plan Review.** All identity signs shall require a site development plan review according to the standards and criteria in Section 17-2-5, or may otherwise be incorporated into a broader site development plan in which the subject sign is located.
- F. **Multi-tenant Buildings & Sites.** Any nonresidential building or site with multiple tenants shall be subject to the following:
- 1. A sign plan shall demonstrate coordination of all signs on the building and site, allow sufficient flexibility for the replacement of signs or new tenants without the need for a new sign plan, unless a new sign design concept is proposed for the entire building or site.
  - 2. Building signs may be apportioned to any tenant with a separate exterior entrance and apportioned to their percentage of the street-facing elevation. In the case where all tenants share a common entrance the building signs may be apportioned to no more than two signs per street-facing elevation.
  - 3. Buildings that have multiple wall or freestanding signs, or multiple tenant components on a single sign shall coordinate all signs for the building or site. Coordination may be established by combinations of two or more of the following:
    - a. The same or similar fonts, in terms of color, scale, and style. However, a primary and secondary font may be incorporated into signs.
    - b. The same sign background in terms of material and color or coordinated colors.



- c. The same base or framing in terms of materials and style, provided it is prominent enough to be a visible coordinating element across multiple signs.
  - d. A consistent scale, orientation, shape or placement of signs. For example, all oval signs, or all signs located within a sign band across storefronts.
  - e. Pedestrian signs or portions of principal signs that are less than 33% of the sign areas, may deviate from coordinating elements to account for logos, icons, or branding unique to the tenants.
- G. **Drive-Through Service Facilities.** Drive-through service facilities may have two signs per service area, no more than 32 square feet per sign, and no more than 8 feet high. Drive through service signs may be further limited and located to the accessory use standards in Section 17-4-4, and the site development plan criteria in Section 17-2-5.
- H. **Electronic Message Displays.** Electronic message displays may be incorporated into permitted signs subject to the following additional limitations:
- 1. Only one display shall be permitted for each lot or development.
  - 2. Displays shall only be used for permitted non-residential uses, and shall be setback at least 100 feet from any property zoned for or used exclusively for residential uses.
  - 3. Portions of a sign use for electronic display shall be further limited in the following districts:
    - a. R-1, R-2, R-3, MU-NC and MU=DT districts – 24 square feet maximum.
    - b. All other nonresidential districts – 48 square feet maximum.
  - 4. Only static display is permitted with at least 8 seconds between changes in display and no more than 0.3 second for transitions.
  - 5. Changes may occur only by dissolve, fade or instantaneous change. Scrolling, flashing, rolling, window shading or other similar effects, or any other flashing or appearance of movement is prohibited.
  - 6. Displays shall be equipped with a sensor or other device that automatically determines the ambient illumination and programmed to dim according to ambient light conditions and keep the illumination to no more than 0.3 footcandles over ambient lighting conditions.
    - a. Lighting shall be measured perpendicular to the sign at a distance dependent on the overall sign area.
    - b. Unless standard industry practices dictate a different measure or method, the distance shall be the square root of 100 time the sign area. (i.e. a 50 square foot sign should be measured from 70.7 feet perpendicular to the sign.).
  - 7. Applications for sign permits containing an electronic display shall include the manufacturer's specifications and cd/m<sup>2</sup> rating.
  - 8. Signs shall not include any business message that is not on the same lot or premises as the sign, and shall not direct attention to a business, produce or service sold or offered off premises.
  - 9. Any sign that malfunctions causing flashing, motion, or other violations of this Chapter shall be turned off as soon as possible, but in no case longer than 24 hours. The sign shall not be turned on again until prepared to operate according to these standards.
  - 10. The Town shall have the right to enter the property and view the programmed specifications of the sign to determine compliance with these provisions in accordance with the sign permit issued for the sign.

17-9-5 General Standards – All Signs

A. Public Health, Safety, & Maintenance.



1. All signs shall be designed, constructed, located, and maintained in a manner that is compliant with all electrical, fire, and building codes, and any other industry standards for public safety of signs, so that the sign does not present any potential risk to public safety in the judgment of the Building Official or the Director.
2. No sign shall be designed and located in a way where it can imitate or be confused with an official government sign for traffic direction or any other public safety symbol.
3. Signs shall not obstruct visibility of pedestrians and vehicles with sight triangles, as defined by Section 17-3-2.D.2.
4. Any sign projecting over a walkway, active area in front of a building, or other area where people may pass shall maintain at least 7.5 feet vertical clearance.
5. No sign shall be located to obstruct any window, door, or other opening used for egress or required for light or ventilation.
6. No sign, sign structure, or associated grounds shall present any dilapidated state or condition that may impact the relationship to or appearance from the public right-of-way or adjacent property.
7. All signs and any surrounding grounds or landscape shall be maintained in good condition, free of any debris, weeds, disrepair, or other unsightly conditions.

**B. General Design.**

1. *Placement.* The location of all permanent building signs shall be incorporated into the architectural design of the building according to the following principles:
  - a. Placement of signs should be considered part of the overall facade design and composition.
  - b. Sign locations should align with major architectural features such as storefront sign bands, cornices and parapets, entrance features, marquees, windows, canopies, and other similar architectural features.
  - c. Signs shall not be placed where they obstruct any significant building design feature, including windows, architectural details, trim, and ornamentation.
2. *Durability & Appearance.* All permanent signs shall be designed to convey durability and a quality appearance according to the following principles:
  - a. Materials, particularly for the frames, casings or bases of signs, should be chosen to complement the architecture of the building, and coordinate with other accent materials or architectural details of the building and site.
  - b. Simple 2- and 3-color contrasting colors schemes should be used between the color of the background, letters, and accents to ensure legibility and quality appearances. Fluorescent colors should be limited to accents and typically less than 10% of the sign area.
  - c. Buildings and sites that have that have multiple building or freestanding signs should coordinate all signs using one or more consistent coordinating elements, such as similar fonts, colors, sign scale or shapes, backgrounds, or casing and framing material.

**C. Specific Designs Prohibited.**

1. No sign shall be attached to any public utility pole or installed within the public right-of-way, except:
  - a. Official government signs exempt from these standards according to Section 17-9-2.B;
  - b. Signs attached to and projecting from buildings and meeting all other standards of this Article;
  - c. Portable pedestrian signs meeting the limited license and exception in Section 17-9-4.C; or



- d. Signs otherwise licensed by the city through special events or management of the design and use of the right-of-way, apart from the Development Code.
- 2. No sign shall include balloons, streamers, pennants, or other air activated movements and animated elements such as flashing, blinking, or rotating, whether animated by mechanical, electrical, or environmental means.
  - a. This limitation shall not apply to pedestrian signs, provided any animated element of the sign or structure shall count to the limits of the pedestrian sign allowances.
  - b. This provision shall not apply to prohibit flags, temporary signs, or electronic message displays meeting the standards of this Article, or to signs approved in association with a special event permit.
  - c. This provision shall not apply to temporary holiday displays or works of art, provided there is no commercial message associated with them.
- 3. Materials and design which are prohibited include:
  - a. Vinyl fabric or other material that is not intended as a durable exterior building material.
  - b. Box signs consisting of metal or similar exterior framing, with replaceable translucent panels are not permitted as wall signs. Replaceable panels may be used in the context of a multitenant freestanding sign.
  - c. Exposed framing, wiring, or support posts or poles unless demonstrated to be an intentional and aesthetic part of the architectural design.
- 4. No sign shall be placed on any vehicle, bus, or trailer, or similar objects visible from the right-of-way, where the object is located specifically to function as a sign and to avoid the standards or criteria of this Article.
- 5. Any sign with a business message shall be located on the lot of the business activity and shall not direct attention to a business, produce or service sold or offered off premises, except signs for multi-tenant premises, which must be associated with the site and located in common areas controlled by the businesses or property owners' associations.

**D. Illumination.**

- 1. Any illumination of a sign shall be designed to eliminate glare or any other negative impacts on surrounding rights-of-way and property. In general, any direct source of light shall not be visible from the public street or adjacent property.
- 2. Light from an illuminated sign shall not spill onto adjacent properties. The light reading from sign lighting at any point within 10 feet from an adjacent property shall be less than one foot-candle. A photometric plan may be required.
- 3. External light sources shall be directed and shielded to conceal the light source and illuminate only the surface of the sign.
- 4. External illumination of a signs 10 feet high or more shall only occur from the top down.
- 5. No light source shall cause any glare, flashing, strobing, movement, or other similar impact off site, or that may be construed to mimic public safety distraction to traffic.
- 6. Exposed lighting where the light source is the sign, shall be limited to window signs mounted to the inside of the building, pedestrian signs, or used as an accent equaling less than 10% of the sign area.

**17-9-6 Planned Development Signs**

The provisions in this Article shall be used to guide signs within Planned Development (PD) application. Proposed planned developments may include a specific and coordinated sign plan with limited standards that address size, height, design, lighting, color, materials, location and method of construction of all signs planned within the PD. Absent a specific sign plan, the Town shall apply sign standards closest to the zoning district the PD land uses represent. The Town Council may impose alternate standards relating to



signs if it is determined that there are commensurate design trade-offs proposed for signs through the procedures and criteria in Section 17-2-4.





## Article 10. Supplemental Standards

- 17-10-1 Wireless Communication Facilities
  - 17-10-2 Floodplain Management & Flood Damage Prevention
  - 17-10-3 Natural Resource Extraction & Energy Development
- 

### 17-10-1 Wireless Communication Facilities

- A. **Intent.** In order to accommodate the communication needs of residents and businesses while protecting the public, health, safety and general welfare of the community, the Town Council finds that these regulations are necessary to:
1. Provide for the managed development and installation, maintenance modification and removal of wireless communications infrastructure in the Town with the fewest number of wireless communications facilities (WCFs) to complete a network without unreasonably discriminating against wireless communications providers of functionally equivalent services, including all of those who install, maintain, operate and remove wireless communication facilities;
  2. Minimize adverse visual effects of WCFs through thoughtful design and siting, including, but not limited to, camouflage design techniques, appropriate and effective screening and undergrounding whenever possible;
  3. Encourage the location of towers in areas that minimize the total number of towers needed throughout the Town;
  4. Require the co-siting of WCFs on new and existing sites wherever possible;
  5. Encourage the location of WCFs in areas where the impact to the Town and its residents is minimized;
  6. Enhance the ability of wireless communications service providers to provide wireless services to the community quickly, effectively and efficiently; and
  7. Effectively manage WCFs located in the public right-of-way.
- B. **Applicability.** The requirements set forth in this Section shall apply to all eligible facilities requests and WCF applications for base stations, alternative tower structures, towers, micro cells, small cells and all other wireless facilities, except the following:
1. *Amateur radio antennas.* Amateur radio antennas that are owned and operated by a federally licensed amateur radio station operator or are exclusively receive-only antennas, provided that the height is less than or equal to the distance from the base of the antenna to the property line and meets other applicable provisions of the Code are met.
  2. *Pre-existing WCFs.* Any WCF for which a permit has been properly issued prior to June 3, 2019, shall not be required to meet the requirements of this Section. Notwithstanding the foregoing, any modifications qualifying as an eligible facility request shall be evaluated under this Section.
  3. *Miscellaneous receiving antennas.* Antennas used for reception of television, multi-channel video programming and radio such as over-the-air receiving device (OTARD) antennas, television broadcast antennas, satellite antennas and broadcast radio antennas, provided such antennas are less than 1 meter in diameter, mounted on the ground with a total height less than 5 feet or attached to an existing building. The Director has the authority to approve modifications to the size and height restriction of OTARD



- antennas and OTARD antenna structures, if, in the reasonable discretion of the Director, modifications are necessary to comply with federal law.
4. *Emergency.* A WCF installed upon the declaration of a state of emergency by the federal or state government or by the Town pursuant to written determination, provided prior to the WCF installation or within 72 hours thereafter, that such action is necessary to protect the health, safety and welfare of the public.
  5. *Temporary WCF.* A cell on wheels, or similar temporary WCF, installed for the purpose of providing sufficient coverage for a special event for no more than 1) days, subject to administrative approval by the Town.

### C. Operational Standards

1. *Federal Requirements.* WCFs shall meet the standards and regulations of the Federal Aviation Administration, the FCC and any other federal government agency with the authority to regulate WCFs, as amended from time to time. If such standards and regulations are revised, then the owners of the WCF shall bring such facility into compliance with such revised standards and regulations within the time period mandated by the controlling federal agency. Unless preempted by federal law, failure to meet such revised standards and regulations within 30 days of the Town's determination of such failure shall constitute grounds for the removal of the WCF by the Town or by the owner of the WCF at the owner's expense.
2. *Permission to use public right-of-way or public property.*
  - a. *Public right-of-way.* Prior to, or concurrently with, the filing of an application seeking land use approval for the siting of WCF in the ROW, the applicant shall have an executed agreement with the Town, granting the applicant a non-exclusive license to use the ROW. WCFs attached to an existing pole or replacement pole or on a new traffic signal, street light pole or similar structure shall require written evidence of a license, or other legal right or approval, to use such structure by its owner. The applicant shall remain the owner of, and solely responsible for, any WCF installed in the ROW.
  - b. *Public property.* Prior to, or concurrently with, the filing of an application seeking land use approval for a WCF on public property, the applicant shall execute a lease agreement with the Town.
3. *Operation and maintenance.* To ensure the structural integrity of WCFs, the owner and operator of a WCF shall ensure that it is maintained in compliance with the standards contained in applicable local building and safety codes. If, upon inspection, the Town concludes that a WCF fails to comply with such codes and/or constitutes a danger to persons or property, then, upon written notice being provided to the owner of the WCF, the owner shall have 30 days from the date of notice to bring the WCF into compliance. Upon good cause shown by the owner and meeting reasonable safety considerations, the Director may extend such compliance period, not to exceed 90 days from the date of said notice. If the owner fails to bring the WCF into compliance within said time period, the Town may remove the WCF at the owner's expense.
4. *Abandonment and removal.* After the WCF is constructed, if a WCF has not been in use for a period of 3 months, the owner of the WCF shall notify the Town of the non-use and shall indicate whether re-use is expected within the ensuing three months. Any WCF that is constructed and is not operated for a continuous period of 6 months shall be considered abandoned. The Town, in its sole discretion, may require an abandoned WCF to be removed. The owner of such WCF, or the property owner who signed a removal affidavit,



shall remove the same within 30 days of receipt of written notice from the Town. If such WCF is not removed within said 30 days, the Town may remove it at the owner or the property owner's expense and any approved permits for the WCF shall be deemed to have expired. The Town may also, in its sole discretion, decline to approve any new WCF application until the applicant who is also the owner of any abandoned WCF has removed such WCF or provided payment for such removal to the Town.

5. *Hazardous materials.* No hazardous materials shall be permitted in association with WCFs, except those necessary for the operation of the WCF and only in accordance with all applicable laws governing such materials.
6. *Collocation and co-siting.* No WCF owner or operator shall unreasonably exclude a telecommunications competitor from using the same WCF facility or site. When an owner or operator seeks to exclude a telecommunications competitor, upon request from the Director, the owner or operator shall provide written evidence explaining why collocation or co-siting is not possible at the particular facility or site.

#### D. Review Procedures & Requirements

1. *Timeframe for review.* New WCFs shall be constructed, collocated or co-sited after a written request from an applicant is reviewed and approved by the Town, in accordance with this Section. The Town shall provide an application for WCF submittals, which shall require the provision of information necessary and adequate for the Town to appropriately make a determination with respect to the WCF development request. An application for a WCF that does not comply with the provisions and design standards of this Section may seek *Use by Special Review* approval pursuant to the procedure set forth in the Code.
  - a. *Facilities within public rights-of-way.* Applications for base stations, alternative tower structures, small cell facilities and alternative tower structures within public rights-of-way shall be reviewed by the Director for conformance with this Section, using the design standards in Subsection E. and those otherwise found in the Code. If the Director determines that WCFs in the rights-of-way are found to have a significant visual impact, are not compatible with the structure or surrounding area or do not meet the intent of this Section, the Director may refer such applications to the Planning and Zoning Commission for a *Use by Special Review* determination.
  - b. *WCFs, including towers.*
    1. Applications for towers, other than those defined or excepted in subsection D.1.a., must utilize the *Use by Special Review* procedure (conditional use approval) set forth in the Code, and meet the applicable submittal requirements site development plans in Article 2, unless otherwise directed by the Director.
    2. Applications for towers shall demonstrate that other alternative design options, such as using base stations or alternative tower structures, are not viable options.
    3. Subject to the tolling provisions in Subsection D.3, the Town shall render a decision within 150 days of the date on which an applicant submits a complete *Use by Special Review* application.
  - c. *Eligible facilities requests.*
    1. *Permitted use.* Eligible facilities requests shall be considered a permitted use in all zoning districts and shall be subject to administrative review.



The Town shall prepare an application form requiring submittal of the information necessary for the Town to consider whether a project constitutes an eligible facilities request, including, but not limited to, sufficient information to allow the Town to determine whether the request does not constitute a substantial change and whether it complies with applicable law. The application shall not require the applicant to demonstrate a need or business case for the request.

- 2. *Timeframe.* Subject to the tolling provisions in Subsection D.3, the Director shall render a decision within 60 days of the date on which an applicant submits a complete application.
- 3. *Ineligible requests.* If the Director determines that the applicant's request is not an eligible facilities, the presumptively reasonable timeframe in Section 332(c)(7) of the Telecommunication Act, as prescribed by the Shot Clock, shall begin to run from the issuance of the Town's decision that the application is not a covered request, assuming that the application is deemed to be complete at that time. The Town may request additional information from the applicant to evaluate whether the application is complete, during which time the timeframe for review of the application shall be tolled.

d. *Small cell facilities.*

- 1. *Application.* The Town shall prepare an application form requiring submittal of the information necessary for the Town to consider whether a project constitutes a small cell facility.
- 2. *Timeframe.*
  - (a) *Collocation on existing structure.* Subject to the tolling provisions in Subsection D.3, the Town shall render a decision within 60 days of the date on which an applicant submits a complete application.
  - (b) *New structure.* Subject to the tolling provisions of in Subsection D.3, the Town shall render a decision within 90 days of the date on which an applicant submits a complete application.
- 3. *Batched applications.* If a single application seeks authorization for multiple deployments, all of which may be categorized as either small cell facilities using an existing structure or small cell facilities using a new structure, then the timeframe for review shall be equal to that for a single deployment within that category. If a single application seeks authorization for multiple deployments, the components of which may be a mix of these aforementioned categories (small cell facilities using an existing structure or small cell facilities using a new structure), then the timeframe for review shall be equal to that with the longer review timeframe permitted for all components of that application.

2. *Additional submittal requirements.*

- a. In addition to the requirements contained in the Town-approved applications, the following supplemental items are required for all WCF applications:
  - (1) Applicable submittal requirements for site development plans in Article 2, unless otherwise waived by the Director;
  - (2) Signal non-interference letter;
  - (3) Radio frequency emissions letter;
  - (4) Photo simulations showing before and after conditions;
  - (5) Inventory of sites. Each applicant shall provide a narrative description and a map of the applicant's existing and currently proposed WCFs



within the Town and those within one half-mile of the Town's boundaries. The applicant shall inform the Town generally of the areas in which it believes WCFs may need to be located within the next 3 years. The inventory list shall identify the site name, address or location and a general description of the facility (i.e., rooftop antennas and ground-mounted equipment). This provision is not intended to be a requirement that the applicant submit its business plan, proprietary information or make commitments regarding locations of WCFs within the Town. This information will be used to assist in the Town's comprehensive planning and promote co-siting by identifying areas in which WCFs might be appropriately constructed for multiple users. The Town may share such information with other applicants seeking to locate WCFs within the Town, provided, however, that the Town shall not, by sharing such information, be making a representation that such sites are available or suitable. The inventory of sites shall be updated upon the submission of a new application filed more than 6 months subsequent to the prior application; and

- (6) *Abandonment and removal affidavit.* Affidavits shall be required from the owner of the property and from the applicant acknowledging that each is responsible for the removal of a WCF that is abandoned or is unused for a period of six (6) months.
- b. Applications must include all necessary information, materials, a business license and completed permit applications for the permits that are required for the construction and installation of the proposed WCF, including, but not limited to, building, electrical or right-of-way permits.
3. *Tolling and reset of the timeframe for review.* The review periods commence to run when a complete application is filed with the Town, and may be tolled by mutual agreement of the Town and the applicant. When the Town determines that an application is incomplete, the timeframe for review will be reset once a complete application is received in the manner set forth herein.
- a. *Tolling for small cell facility applications.* If an application is incomplete, the Town shall provide written notice to the applicant within 10 days of receipt of the application. The Town's timeframe for review shall be reset upon the Town's receipt of a complete amended application from the applicant. If the Town subsequently determines that the amended application is not complete, the Town shall provide a subsequent written notice to the applicant within 10 days of receipt of the amended application. The Town's timeframe for review shall toll until the applicant resubmits a subsequent amended application, and shall commence to run again on the business day following the day on which the applicant submits such subsequent amended application.
  - b. *Tolling for all other WCF applications.* If an application is incomplete, the Town shall provide written notice to the applicant within 30 days of receipt of the application. The Town's timeframe for review shall toll until the applicant submits an amended application, and shall commence to run again on the business day following the day on which the applicant submits such amended application. If the Town subsequently determines that the amended application is not complete, the Town shall provide a subsequent written notice to the applicant within 10 days of receipt of the amended application. The Town's timeframe for review shall toll until the applicant resubmits a subsequent amended application, and





shall commence to run again on the business day following the day on which the applicant submits such subsequent amended application.

- c. *Failure to act.* If an applicant fails to respond and resubmit the information requested by the Town within 14 days of the Town's written notice, the Town may make a determination of denial without prejudice. The applicant may thereafter submit a new application.
4. *Decision.* Any decision to approve, approve with conditions or deny an application shall be in writing and supported by evidence and shall be provided to the applicant. An applicant may appeal an administrative decision in accordance with the Code and may appeal a decision rendered by Town Council in accordance with state and federal law and regulations.
5. *Compliance with applicable law.* Notwithstanding the approval of a WCF application or eligible facilities request, all work must be completed in compliance with applicable building, structural, electrical and safety requirements as set forth in the Code and all other applicable laws and regulations. All applicants shall:
  - a. Comply with permits and licenses issued by a governmental authority with jurisdiction;
  - b. Comply with easements, covenants, conditions and restrictions on or applicable to the underlying real property;
  - c. Maintain the WCF in good working condition and to the standards established at the time of application approval; and
  - d. Ensure the WCF and the site is free from trash, debris, litter, graffiti and other forms of vandalism. Any damage shall be repaired as soon as practicable, and, in no instance, more than 10 days from the time of notification by the Town or after discovery by the owner or operator of the site. Notwithstanding the foregoing, any graffiti on WCFs located in the public rights-of-way or on public property may be removed by the Town, in its discretion, and the owner or operator of the WCF shall pay all costs of such removal within 30 days after receipt of an invoice from the Town.
6. *Fee.* The applicant shall pay a fee with the submission of the application. The fee shall be the maximum amount allowed by the FCC, if at all, or an amount set by Town Council by resolution. The fee shall constitute a reasonable approximation of the Town's costs and shall be imposed on a non-discriminatory basis. The Town may, in its discretion, retain professional consultants to review and assist in the processing of applications. If a professional consultant is retained by the Town, the applicant shall be required to pay the Town's actual costs for the consultant.

#### E. Design Standards

1. *Applicability.* WCFs shall be designed and located to minimize the impact on the surrounding neighborhood and to maintain the character and appearance of the Town. The design standards set forth herein shall apply to the location and design of all WCFs governed by this Section, unless otherwise exempted by the Town. While the Town anticipates and expects compliance with all the design standards set forth herein, the Town's primary objectives are to ensure that WCFs use camouflage and concealment design techniques to reduce visibility and be co-sited or collocated to minimize the number of facilities.
2. *General design standards for WCFs.*



- a. **Camouflage and concealment.** All WCFs and any transmission equipment shall, to the maximum extent possible, use camouflage and concealment design techniques including, but not limited to, the use of materials, colors, textures, screening, undergrounding, landscaping or other design options that blend the WCF into the surrounding natural setting and built environment.
- (1) Camouflage design may be of heightened importance where findings of particular sensitivity are made (e.g. proximity to historic, natural or aesthetically significant structures or areas, views or to community features or facilities). In instances where WCFs are located in areas of high visibility, they shall be designed (e.g., placed underground, depressed or located behind earth berms) to minimize their profile.
  - (2) Camouflage design may include the use of alternative tower structures should the Director determine that such design meets the intent of this Section and the community is better served thereby.
  - (3) WCFs shall be constructed out of non-reflective materials (visible exterior surfaces only).
- b. **Co-siting and collocation.**
- (1) **Co-siting.** WCFs shall be designed and constructed to permit the facility to accommodate WCFs from at least two wireless service providers on the same WCF, to the extent reasonably feasible based upon construction, engineering and design standards, except where such collocation would materially compromise the design intent of the WCF, particularly visually.
  - (2) **Collocation.** If existing eligible facilities are not available in the area to be served, WCFs shall be designed to utilize pre-existing structures, poles and buildings wherever possible.
- c. **Accessibility.** WCFs and associated equipment shall be designed and sited to comply with the Americans with Disabilities Act and all other local, state and federal laws and regulations. WCFs may not be located or maintained in a manner that causes unreasonable interference.
- d. **Height.** The maximum height of a WCF shall be 36 inches unless otherwise approved through a *Use by Special Review* procedure or the applicant provides compelling evidence that a majority of similar, nearby structures are taller and that a taller height is thus compatible. The Director shall determine whether a taller height is acceptable.
- e. **Setbacks.** The following minimum setback requirements shall apply to all WCFs, except for alternative tower structures and small cell facilities in the right-of-way, and shall be the greater of the following:
- (1) When attached to a structure, the setback for a principal building within the applicable zoning district;
  - (2) 25% of the facility height, including WCFs and related accessory equipment;
  - (3) For sites within 100 feet of residential uses, facilities over 30 feet from ground elevation measured within 5 feet of the base, a setback from all adjacent residential property lines of 1 foot for every foot in height; or
  - (4) 20 feet.
- f. **Lighting.** WCFs shall not be artificially lighted, unless required by the FAA or other applicable governmental authority or the WCF is mounted on a light pole or other similar structure primarily used for lighting purposes. All exterior lighting



within equipment yards shall be mounted on poles or on a building wall below the height of the screen wall or fence.

- g. **Noise.** Noise generated on a site must not be emitted at levels prohibited in the Code or otherwise prohibited by the Director, except that a WCF owner or operator shall be permitted to exceed such noise standards for a reasonable period of time during repairs, not to exceed 2 hours without the prior written authorization of the Director.
- h. **Landscaping.**
  - (1) All landscaping and screening shall adhere to the Town of Johnstown Landscape Standards and Specifications, as amended;
  - (2) WCFs shall be sited in a manner that ensures continued compliance with required landscaping and open areas for the principal uses on the parcel;
  - (3) WCFs, including small cell facilities, unless excepted by the Director for safety considerations, shall provide screening from rights-of-way and adjacent properties, which may, in the Director's discretion, include berms and plant materials; and
  - (4) Where landscaping is required, appropriate irrigation must be installed.
- i. **Screening.**
  - (1) All structures and improvements associated with a WCF shall incorporate adequate safety equipment and aesthetic treatments to be visually compatible with uses in the surrounding area;
  - (2) All equipment not located within the right-of-way and not otherwise addressed herein shall be fully screened within a walled yard or placed in an enclosed building except in cases where the Director determines that a better design alternative exists. The yard shall be enclosed by a solid fence or wall of sufficient height to screen all miscellaneous equipment from view from the right-of-way or adjacent properties and to provide security; and
  - (3) Cables, wires, boxes, transformers and other accessory equipment must be designed to be located internally or otherwise highly-integrated into any structure to the degree feasible to minimize visual clutter and screen.

3. **Additional design standards.**

- a. Building roof-mounted WCFs and equipment shall be set back from the edges of flat roofs, screened, painted, enclosed or otherwise effectively camouflaged and concealed to minimize the visual impact on surrounding properties and rights-of-way. No roof-mounting may occur on gabled or similar roofing structures that provide significant visibility from nearby rights-of-way and properties.
- b. Antennas may only be mounted to the side of a building if camouflage and concealment techniques are utilized to ensure maximum integration and minimal interference with the architectural features of that building. The equipment shall be mounted in a configuration as flush to the wall as technically possible, with a maximum protrusion of six (6) feet, and shall not project above the wall on which it is mounted.
- c. Equipment shall, to the maximum extent feasible, feature the smallest and most discreet components that the technology will allow so as to have the least possible impact on the architectural character and overall aesthetics of the building or structure.



- d. Roof-mounted WCF equipment shall be screened by parapet or screen walls in a manner compatible with the building's design, colors and materials.
  - e. If a replacement pole is being considered, the new pole must match, to the extent feasible, other street light and traffic poles within 528 feet of the site with regard to design, height, width and utility. A replacement pole accommodating internal wiring and cable may be up to 24 inches in diameter at the base.
4. *Design standards in relation to residential uses.*
- a. WCFs shall be sited and designed in a manner that is considerate of the proximity of the facility relative to residential structures, neighborhoods and planned residential areas in order to minimize the visual impacts of WCFs on existing and planned residential areas.
  - b. When placed on or adjacent to residential properties, a WCF shall be placed in close proximity to a common property line between adjoining residential properties, such that the WCF minimizes visual impacts equitably among adjacent and nearby properties.
  - c. For a corner lot, the WCF shall be placed adjacent to a common property line between adjoining residential properties or on the corner formed by two intersecting streets.
5. *Design requirements for specific types of WCFs.*
- a. Alternative tower structures not in the public right-of-way shall:
    - (1) Be designed and constructed to look like a building, facility, structure or other commonplace item typically found in the area;
    - (2) Be camouflaged or concealed consistent with other existing natural or manmade features in or near the proposed location;
    - (3) Be compatible with the surrounding area, including design considerations such as the context, scale, massing, height, articulation, topography and the landscaped environment;
    - (4) Be the minimum size needed to obtain coverage objectives. Height or size of the proposed alternative tower structure should be minimized as much as possible;
    - (5) Be sited in a manner that is sensitive to the proximity of the facility to structures, neighborhoods, special districts, natural areas and residential uses and zoning district boundaries; and
    - (6) Take into consideration the uses on adjacent and nearby properties and the compatibility of the facility to these uses.
  - b. Alternative tower structures and small cell facilities in the public right-of-way are subject to the alternative tower structures design standards in this Section and to the following additional design criteria:
    - (1) Alternative tower structures and associated small cell facilities or micro cell facilities may be deployed in the public right-of-way through the utilization of a street light pole, distribution lines, utility poles, traffic signal or similar structure;
    - (2) To the extent that an alternative tower structure is a vertical structure located in the public right-of-way, its pole-mounted components shall be



- located on or within an existing utility or street light pole serving another purpose whenever technically feasible;
- (3) If the applicant provides evidence that an existing structure is not available in the area where additional coverage is needed, a new pole or structure may be considered;
- (4) With respect to pole components, such components shall be located on or within a new utility pole where other utility distribution lines are aerial and there are no reasonable alternatives, if the applicant is authorized to construct the new utility poles;
- (5) Alternative tower structures shall be consistent with the size and shape of similar pole-mounted equipment installed by communications companies on utility poles in the right-of-way within reasonable proximity the proposed alternative tower structure;
- (6) Alternative tower structures shall be designed such that antenna installations on traffic signal standards are placed in a manner so that the size and appearance of the structure will not be considerably altered and the function of the signal will not be impacted;
- (7) Alternative tower structures shall be sized to minimize the negative aesthetic impacts to the right-of-way and adjacent properties;
- (8) Alternative tower structures shall not alter vehicular circulation or parking within the right-of-way or impede vehicular, bicycle or pedestrian access or visibility along the right-of-way;
- (9) Alternative tower structures may not be more than 5 feet taller (as measured from the ground to the top of the pole) than any existing utility or traffic signal pole within a radius of 528 feet of the pole or structure. A new or freestanding alternative tower structure may not be higher than 36 feet; and
- (10) Alternative tower structures in the right-of-way shall not exceed 24 inches in diameter.

c. Towers that are not alternative tower structures or small cell facilities are subject to the following:

- (1) No new towers, excepting small cell facilities in the right-of-way, shall be permitted unless the applicant demonstrates to the reasonable satisfaction of the Director that existing WCFs are not able to accommodate the needs that the applicant proposes to address with its tower application and sufficient separation of towers is achieved. Evidence may consist of the following:
  - (a) No existing WCFs with a suitable height are located within the geographic area required to meet the applicant's engineering requirements;
  - (b) Existing WCFs do not have sufficient structural strength to support applicant's proposed WCF;
  - (c) The applicant's proposed WCF would cause electromagnetic interference with the existing WCFs or the existing WCFs would cause interference with the applicant's proposed WCF; or
  - (d) The applicant demonstrates that there are other limiting factors that render existing WCFs unsuitable for collocation;
- (2) Towers shall either maintain a galvanized steel finish, or, subject to any applicable FAA standards and Town design approval processes, be painted a neutral color so as to reduce visual obtrusiveness;
- (3) Wherever possible, towers shall be located to utilize existing landforms, vegetation and structures to aid in screening the facility from view or to otherwise blend in with the surrounding built and natural environment;





- (4) Monopole support structures shall taper from the base to the tip;
- (5) All towers shall be enclosed by security fencing or wall and shall also be equipped with an appropriate anti-climbing device;
- (6) Where the proposed height exceeds that of the zoning district, towers over 90 feet in height shall not be located within one-quarter mile from any existing tower that is over 90 feet in height, unless the applicant has shown to the satisfaction of the Director that there are no reasonably suitable alternative sites in the required geographic area that meet the applicant's needs; and
- (7) Tower-related accessory equipment shall meet the following standards:
  - (a) All buildings, shelter, cabinets and other accessory components shall be grouped as closely together as technically possible;
  - (b) The total footprint coverage area of the WCF's accessory equipment shall not exceed 350 square feet;
  - (c) No related accessory equipment or accessory structure shall exceed 12 feet in height; and
  - (d) Related accessory equipment, including, but not limited to, remote radio units, shall be fully screened whenever feasible by being located behind parapet walls or within equipment enclosures.

6. *Design standards for ground mounted equipment.* Ground-mounted equipment shall be located in a manner necessary to address both public safety and aesthetic concerns. Wherever feasible, ground-mounted equipment that is otherwise visible from the right-of-way or adjacent properties shall be undergrounded to minimize the visual impact to the area and minimize impacts related to physical access on the site. Where appropriate and to the extent it is reasonably feasible based upon construction, engineering and design standards, the Director may require a flush-to-grade underground equipment vault.

7. *Deviation and interpretation.*

- a. *Deviation.* The Town anticipates and expects compliance with all the design standards set forth in this Section. If an applicant does not utilize the design standards, the applicant shall, in its application, identify the standards that are not utilized and the reason for the deviation.
- b. *Interpretation.* Where interpretation of the design standards is necessitated by the circumstances, the Director shall make such determination. The applicant may appeal the Director's determination to the Board of Adjustment.

F. **Definitions.** The following terms shall have the specific meaning given when used in this section. All other terms shall have their plain and ordinary meaning unless specifically defined for use throughout this Chapter in Article 11.

*Agreement.* An executed agreement, and any exhibits, supplements or amendments thereto, between the owner or operator of WCFs and the Town to utilize the public right-of-way or public property to install WCFs and associated equipment.

*Alternative tower structure.* Man-made trees, clock towers, bell steeples, light poles, buildings and similar alternative design mounting structures that are compatible with the natural setting and surrounding structures and camouflage or conceal the presence of the antennas or towers in a manner designed to make them architecturally compatible with the surrounding area. This term also includes any antenna or antenna array attached to an alternative tower structure. A stand-alone pole in the right-of-way, streetlight



or traffic signal that accommodates small cell facilities is considered an alternative tower structure to the extent it meets the camouflage and concealment standards of this Section.

**Antenna.** Any device used to transmit or receive radio or electromagnetic waves such as, but not limited to, panel antennas, reflecting discs, microwave dishes, whip antennas, directional and non-directional antennas consisting of one or more elements, multiple antenna configurations or other similar devices and configurations as well as exterior apparatus designed for telephone, radio or television communications through the sending or receiving of wireless communications signals.

**Base station.** A structure or equipment at a fixed location that enables Federal Communications Commission ("FCC") licensed or authorized wireless communications between user equipment and a communications network. The definition of base station does not include or encompass a tower as defined herein or any equipment associated with a tower. Base station includes, without limitation:

- (a) Equipment associated with wireless communications services such as private, broadcast and public safety services, as well as unlicensed wireless services and fixed wireless services such as microwave backhaul that, at the time the relevant application is filed with the Town under this Section, has been reviewed and approved under the applicable zoning or siting process or under another state or local regulatory review process, even if the structure was not built for the sole or primary purpose of providing such support; and
- (b) Radio transceivers, antennas, coaxial or fiber-optic cable, regular and backup power supplies, and comparable equipment, regardless of technological configuration (including distributed antenna systems and small-cell networks) that, at the time the relevant application is filed with the Town under this Section, has been reviewed and approved under the applicable zoning or siting process, or under another state or local regulatory review process, even if the structure was not built for the sole or primary purpose of providing such support.

The definition of base station does not include any structure that, at the time the relevant application is filed with the Town, does not support or house equipment described in paragraphs (a) and (b) above.

**Camouflage, concealment or camouflage design techniques.** Measures used in designing a WCF to alter or mask its appearance in such a manner as to substantially integrate it into surrounding building designs or natural settings to minimize the visual impacts of the facility on the surrounding uses and ensure the facility is compatible with the environment in which it is located. A WCF site utilizes camouflage design techniques when it:

- (a) is integrated as an architectural feature of an existing structure such as a cupola, spire, chimney, cornice or similar item;
- (b) is integrated in an outdoor fixture such as a utility tower; or
- (c) uses a design which mimics and is consistent with nearby natural features, architectural features (such as a clock tower), or is incorporated into (including without limitation, being attached to the exterior of such facilities and painted to match it) or replaces existing permitted facilities (including without limitation, stop signs or other traffic signs or freestanding light standards), such that the presence of the WCF is not readily apparent.

**Cell on wheels.** A mobile cell site that consists of an antenna tower and electronic radio transceiver equipment on a truck or trailer designed to boost reception as part of a larger cellular network and is temporary in nature.

**Collocation.**

- (a) the mounting or installation of transmission equipment on a pre-existing structure (i.e., tower, building, utility pole, street light pole); or
- (b) the modification of a structure for the purpose of mounting or installing an antenna facility on the structure to transmit or receive radio frequency signals for communications purposes, whether or not there is an existing antenna on the structure.



**Co-siting.** The sharing of a single structure, tower, designated area of land or other facility by more than one antennae or other WCF equipment.

**Eligible facilities request.** Any request for modification of an existing tower or base station that is not a substantial change.

**Eligible support structure.** Any tower or base station as defined in this Section, provided that it is existing at the time the relevant application is filed with the Town under this Section.

**Existing tower or base station.** A constructed tower or base station that was reviewed, approved and lawfully constructed in accordance with all requirements of applicable law as of the time it was built; for example, a tower that exists as a legal, non-conforming use and was lawfully constructed is existing for purposes of this definition.

**Micro cell facility.** A small wireless facility that is no larger than 24 inches in length, 15 inches in width, 12 inches in height, and that has an exterior antenna, if any, that is no more than 11 inches in length.

**Monopole.** A single, freestanding pole-type structure supporting one or more antennas.

**Over the air receiving device** shall mean an antenna used to receive video programming from direct broadcast satellites, broadband radio services and television broadcast stations, but shall not include antennas used for AM/FM radio, amateur ("ham") radio, CB radio, digital audio radio services or antennas used as part of a hub to relay signals among multiple locations.

**Pole-mounted small cell facility.** A small cell facility with an antenna that is mounted and supported on an alternative tower structure, which structure may be a replacement pole.

**Public property** shall mean real property owned or controlled by the Town, excluding the public right-of-way.

**Radio frequency emissions letter.** A letter from the applicant certifying that all WCFs that are the subject of the application shall comply with federal standards for radio frequency emissions.

**Replacement pole.** An alternative tower structure that is a newly constructed and permitted traffic signal, utility pole, street light, flagpole, electric distribution or other similar structure of proportions and of equal height or such other height that would not constitute a substantial change to a pre-existing pole or structure in order to support a WCF or small cell facility or micro cell facility or to accommodate collocation, and replaces a pre-existing pole or structure.

**Shot Clock.** The provisions of the Declaratory Ruling and Third Report and Order issued by the FCC on September 28, 2018, related to the timeframe for review and tolling, as may be amended by the FCC from time to time.

**Signal non-interference letter.** A letter from the applicant certifying that the WCFs that are the subject of the application will be designed, sited and operated in accordance with applicable federal regulations addressing radio frequency interference.

**Site for towers** (other than towers in the right-of-way and eligible support structures). The current boundaries of the leased or owned property surrounding the tower or eligible support structure and any access or utility easements currently related to the site. A site for other alternative tower structures, base stations, micro cell facilities and small cell facilities in the right-of-way is further restricted to that area comprising the base of the structure and other existing or proposed related accessory equipment deployed on the ground.

**Small cell facility or small wireless facility.** A WCF where each antenna is located inside an enclosure of no more than 3 cubic feet in volume or, in the case of an antenna that has exposed elements, the



antenna and all of its exposed elements could fit within an imaginary enclosure of no more than 3 cubic feet; and primary equipment enclosures are not larger than 28 cubic feet in volume; and all other wireless equipment associated with the structure, including the wireless equipment associated with the proposed antenna and any pre-existing associated equipment on the structure, is not more than 28 cubic feet in volume, cumulatively.

Small cell facilities are mounted to structures 50 feet or less in height, including their antennas, or are mounted on structures no more than 10% taller than other adjacent structures, or do not extend existing structures on which they are located to a height of more than 50 feet or by more than 10%, whichever is greater. Small cell facility shall also include a micro cell or micro cell facility.

**Substantial change.** A modification that substantially changes the physical dimensions of an eligible support structure if, after the modification, the structure meets any of the following criteria:

- (a) For towers, other than alternative tower structures or towers in the right-of-way, it increases the height of the tower by more than 10% or by the height of one additional antenna array, with separation from the nearest existing antenna not to exceed 20 feet, whichever is greater; for other eligible support structures, it increases the height of the structure by more than 10% or more than 10 feet, whichever is greater;
- (b) For towers, other than towers in the right-of-way, it involves adding an appurtenance to the body of the tower that would protrude from the tower more than 20 feet, or more than the width of the tower structure at the level of the appurtenance, whichever is greater; for eligible support structures, it involves adding an appurtenance to the body of the structure that would protrude from the side of the structure by more than 6 feet;
- (c) For any eligible support structure, it involves installation of more than the standard number of new equipment cabinets for the technology involved, but not to exceed 4 cabinets;
- (d) For towers in the right-of-way and base stations, it involves installation of any new equipment cabinets on the ground if there are no pre-existing ground cabinets associated with the structure, or else involves installation of ground cabinets that are more than 10% larger in height or overall volume than any other existing, individual ground cabinet associated with the structure;
- (e) For any eligible support structure, it entails any excavation or deployment outside the current site;
- (f) For any eligible support structure, it would defeat the concealment elements of the eligible support structure; for the purposes of this definition, a change that would undermine the concealment elements of this structure will be considered to defeat the concealment elements of the structure; or
- (g) For any eligible support structure, it does not comply with conditions associated with the siting approval of the construction or modification of the eligible support structure equipment, unless the non-compliance is due to an increase in height, increase in width, addition of cabinets or new excavation that would not exceed the thresholds identified in subsections (a), (b), (c) or (d) of this definition. For purposes of determining whether a substantial change exists, changes in height are measured from the original support structure in cases where deployments are or will be separated horizontally, such as on building rooftops; in other circumstances, changes in height are measured from the dimensions of the tower or base station, inclusive of originally approved appurtenances and any modifications that were approved prior to February 22, 2012.

**Telecommunications Act.** The Federal Telecommunications Act of 1996, 47 U.S.C. §§ 151-614 (1994 & Supp. 1998), as amended.

**Toll and tolling.** To delay, suspend or hold off on the imposition of a deadline, statute of limitations or time limit.

**Tower.** Any structure that is designed and constructed primarily built for the sole or primary purpose of supporting one or more FCC-licensed or authorized antennas and their associated facilities, including structures that are constructed for wireless communications services including, but not limited to, private, broadcast and public safety services, as well as unlicensed wireless services and fixed wireless services



such as microwave backhaul, and the associated site. The term includes self-supporting lattice towers, guyed towers, monopole towers, radio and television transmission towers, microwave towers, common carrier towers, cellular telephone towers, alternative tower structures and the like.

*Transmission equipment.* Equipment that facilitates transmission for any FCC licensed or authorized wireless communication service, including, but not limited to, radio transceivers, antennas, coaxial or fiber-optic cable and regular and backup power supply. The term includes equipment associated with wireless communications services including, but not limited to, private, broadcast and public safety services, as well as unlicensed wireless services and fixed wireless services such as microwave backhaul.

*Unreasonable interference.* Any use of the right-of-way that disrupts or interferes with the use by the Town, the general public or other person authorized to use or be present upon the right-of-way, when there exists an alternative that would result in less disruption or interference. Unreasonable interference includes any use of the right-of-way that disrupts vehicular or pedestrian traffic, any interference with public utilities and any other activity that will present a hazard to public health, safety or welfare.

*Wireless communications facility or WCF.* A facility used to provide personal wireless services as defined at 47 U.S.C. § 332 (c)(7)(C), as amended; or wireless information services provided to the public or to such classes of users as to be effectively available directly to the public via licensed or unlicensed frequencies; or wireless utility monitoring and control services. A WCF does not include a facility entirely enclosed within a permitted building where the installation does not require a modification of the exterior of the building; nor does it include a device attached to a building, used for serving that building only and that is otherwise permitted under other provisions of the Code. A WCF includes an antenna or antennas, including without limitation, directional, omni-directional and parabolic antennas, base stations, support equipment, alternative tower structures and towers. The term does not include mobile transmitting devices used by wireless service subscribers, such as vehicle or hand held radios/telephones and their associated transmitting antennas, nor does it include other facilities specifically excluded from the coverage of this Title.

## 17-10-2 Floodplain Management & Flood Damage Prevention

### A. Title & Purpose

1. *Statutory authorization.* The Legislature of the State has, in Article 20 of Title 29, C.R.S., delegated the responsibility of local governmental units to adopt regulations designed to minimize flood losses. The Town, as a home rule municipality, has the inherent authority to adopt land use regulations affecting the public health, safety, and welfare of the Town.
2. *Findings of fact.*
  - a. The flood hazard areas of the Town are subject to periodic inundation, which can result in loss of life and property, health and safety hazards, disruption of commerce and governmental services, and extraordinary public expenditures for flood protection and relief, all of which adversely affect the health, safety and general welfare of the public.
  - b. These flood losses are created by the cumulative effect of obstructions in areas of special flood hazard, which cause an increase in flood heights and velocities, and by the occupancy of flood hazard areas by uses vulnerable to floods, which are/may be hazardous to other lands because they are inadequately elevated, floodproofed, or otherwise protected from flood damage and therefore may further contribute to the flood loss.





3. *Statement of purpose.* It is the purpose of this Article to promote public health, safety and general welfare and to minimize public and private losses due to flood conditions in specific areas by provisions designed to:
  - a. Protect human life and health;
  - b. Minimize expenditure of public money for costly flood control projects;
  - c. Minimize the need for rescue and relief efforts associated with flooding and generally undertaken at the expense of the general public;
  - d. Minimize prolonged business interruptions;
  - e. Minimize damage to critical facilities, infrastructure and other public facilities, such as water, sewer and gas mains; electric and communications stations; and streets and bridges located in floodplains;
  - f. Help maintain a stable tax base by providing for the sound use and development of flood-prone areas in such a manner as to minimize future flood blight areas; and
  - g. Ensure that potential buyers are notified that property is located in a flood hazard area.
  - h. Ensure that those who occupy the floodplain assume the responsibility for their actions;
  - i. Protect the natural areas required to convey flood flows and retain flow characteristics; and
  - j. Obtain and maintain the benefits to the community of participating in the National Flood Insurance Program.
  
4. *Methods of reducing flood losses.* In order to accomplish its purposes, this Article uses the following methods:
  - a. Restrict or prohibit uses that are dangerous to health, safety or property in times of flood, or cause excessive increases in flood heights or velocities;
  - b. Require that uses vulnerable to floods, including facilities which serve such uses, be protected against flood damage at the time of initial construction;
  - c. Control the alteration of natural floodplains, stream channels and natural protective barriers, which are involved in the accommodation of flood waters;
  - d. Control filling, grading, dredging and other development which may increase flood damage; and
  - e. Prevent or regulate the construction of flood barriers which will unnaturally divert flood waters or which may increase flood hazards to other lands.

**B. General Provisions**

1. *Lands to which this Article applies.* This Article shall apply to all areas within the jurisdiction of the Town. If a lot or parcel lies partly within a floodplain, floodway, flood fringe, or other designated area, or has been removed from a flood fringe by a LOMR-Fill, the part(s) of such lot or parcel lying within such area or areas shall meet all the standards and requirements applicable to such area as prescribed by this Article. If lands located outside the Town limits are included within a flood hazard area, the requirements of this Article shall apply to such lands upon annexation and thereafter, and any development activities upon such lands after the date of annexation shall comply with this Article.
  
2. *Basis for establishing the Special Flood Hazard Area.* The Special Flood Hazard Areas identified by the Federal Emergency Management Agency in the most recent scientific and engineering reports entitled, "The Flood Insurance Study for Larimer County, Colorado and Incorporated Areas," dated January 15, 2021, and "The Flood Insurance Study for Weld County, Colorado and Incorporated Areas," dated January 20, 2016, both with accompanying Flood Insurance Rate Maps and any revisions thereto are hereby



adopted by reference and declared to be a part of this Article. These Special Flood Hazard Areas identified by the FIS and attendant mapping are the minimum area of applicability of this Article and may be supplemented by studies designated and approved by the Town Council. The Floodplain Administrator shall keep a copy of the Flood Insurance Study (FIS), DFIRMs, FIRMs and/or FBFMs on file and available for public inspection at Town Hall

3. *Establishment of Floodplain Development Permit.* A Floodplain Development Permit shall be required to ensure conformance with the provisions of this Article.
4. *Compliance.* No structure or land shall hereafter be located, altered or have its use changed within the Special Flood Hazard Area without full compliance with the terms of this Article and other applicable regulations. Nothing herein shall prevent the Town Council from taking such lawful action as is necessary to prevent or remedy any violation. These regulations meet the minimum requirements as set forth by the Colorado Water Conservation Board and the National Flood Insurance Program.
5. *Abrogation and greater restrictions.* This Article is not intended to repeal, abrogate or impair any existing easements, covenants or deed restrictions. However, where this Article and another ordinance, easement, covenant or deed restriction conflict or overlap, whichever imposes the more stringent restrictions shall prevail.
6. *Interpretation.* In the interpretation and application of this Article, all provisions shall be:
  - a. Considered as minimum requirements;
  - b. Liberally construed in favor of the governing body; and
  - c. Deemed neither to limit nor repeal any other powers granted under state statutes.
7. *Warning and disclaimer of liability.* The degree of flood protection required by this Article is considered reasonable for regulatory purposes and is based on scientific and engineering considerations. On rare occasions greater floods can and will occur and flood heights may be increased by man-made or natural causes. This Article does not imply that land outside the Special Flood Hazard Area or uses permitted within such areas will be free from flooding or flood damages. This Article shall not create liability on the part of the Town or any official or employee thereof for any flood damages that result from reliance on this Article or any administrative decision lawfully made thereunder.
8. *Severability.* This Article and the various parts thereof are hereby declared to be severable. Should any section of this Article be declared by the courts to be unconstitutional or invalid, such decision shall not affect the validity of this Article as a whole or any portion thereof other than the section so declared to be unconstitutional or invalid.

### C. Administration

1. *Designation of Floodplain Administrator.* The Director is hereby appointed as Floodplain Administrator to administer, implement, and enforce the provisions of this Article and other appropriate sections of 44 CFR (National Flood Insurance Program Regulations) pertaining to floodplain management.
2. *Duties and responsibilities of Floodplain Administrator.* Duties and responsibilities of the Floodplain Administrator shall include, but not be limited to, the following:
  - a. Maintain and hold open for public inspection all records pertaining to the provisions of this Article including the actual elevation (in relation to mean sea



- level) of the lowest floor (including basement) of all new or substantially improved structures and any floodproofing certificate required this Article
  - b. Review, approve or deny all applications for Floodplain Development Permits required by adoption of this Article.
  - c. Review Floodplain Development Permit applications to determine whether a proposed building site, including the placement of manufactured homes, will be reasonably safe from flooding.
  - d. Review permits for proposed development to assure that all necessary permits have been obtained from those federal, state or local governmental agencies (including Section 404 of the Federal Water Pollution Control Act Amendments of 1972, 33 U.S.C. § 1334) from which prior approval is required.
  - e. Inspect all development at appropriate times during the period of construction to ensure compliance with all provisions of this Article, including proper elevation of the structure.
  - f. Where interpretation is needed as to the exact location of the boundaries of the Special Flood Hazard Area (for example, where there appears to be a conflict between a mapped boundary and actual field conditions), the Floodplain Administrator shall make the necessary interpretation.
  - g. When Base Flood Elevation data has not been provided in accordance with Subsection 17-263(b) of this Article, the Floodplain Administrator shall obtain, review and reasonably utilize any Base Flood Elevation data and floodway data available from a federal, state or other source, in order to administer the provisions of Section 17-265 of this Article.
  - h. For waterways with Base Flood Elevations for which a regulatory floodway has not been designated, no new construction, substantial improvements or other development (including fill) shall be permitted within Zones A1-30 and AE on the community's FIRM, unless it is demonstrated that the cumulative effect of the proposed development, when combined with all other existing and anticipated development, will not increase the water surface elevation of the base flood more than one-half (½) foot at any point within the community.
  - i. Under the provisions of 44 CFR Chapter 1, Section 65.12, of the National Flood Insurance Program regulations, a community may approve certain development in Zone A1-30, AE or AH, on the community's FIRM which increases the water surface elevation of the base flood by more than one-half (½) foot, provided that the community first applies for a conditional FIRM revision through FEMA (Conditional Letter of Map Revision), fulfills the requirements for such revisions as established under the provisions of Section 65.12 and receives FEMA approval.
  - j. Notify, in riverine situations, adjacent communities and the state coordinating agency, which is the Colorado Water Conservation Board, prior to any alteration or relocation of a watercourse, and submit evidence of such notification to FEMA.
  - k. Ensure that the flood-carrying capacity within the altered or relocated portion of any watercourse is maintained.
3. **Permit procedures.** Prior to any development or construction within any areas of Special Flood Hazard, an application for a Floodplain Development Permit shall be presented to and approved by the Floodplain Administrator. The Town shall provide application forms and submittal checklists, which may include, but not be limited to, plans drawn to scale showing the location, dimensions, and elevation of proposed landscape alterations, existing and proposed structures, including the placement of manufactured homes, and the location of the foregoing in relation to Special Flood Hazard Area. Additionally, the following information is required:



- a. Elevation (in relation to mean sea level), of the lowest floor, including without limitation the crawl space or basement, heating, cooling or other mechanical components, and garage of all new and substantially improved structures;
  - b. Elevation in relation to mean sea level to which any nonresidential structure shall be floodproofed;
  - c. A certificate from a registered Colorado professional engineer or architect that the floodproofing methods meet the floodproofing criteria of Paragraph 17-265(b)(2);
  - d. Description of the extent to which any watercourse or natural drainage will be altered or relocated as a result of proposed development; and
  - e. A written report showing to the satisfaction of the Floodplain Administrator that the floodplain development permit may be issued in compliance with all criteria for approval;
  - f. Specifications for building construction and materials, filling, dredging, grading, channel improvements and changes, storage of materials, water supply and sanitary facilities;
  - g. Detailed information documenting compliance with any specific requirements applicable to the proposed development or activity pursuant to this Article; and
  - h. An emergency response and preparedness plan, if required pursuant to this Article; provided, however, that this requirement may be considered a floodplain development permit condition to be met prior to issuance of a certificate of occupancy, pursuant to Subsection (g) below.
  - i. An application for a floodplain development permit may be subject to a permit application fee plus the applicable review fees for any and all associated analyses.
4. The Floodplain Administrator may require the applicant to furnish such additional information as he or she deems necessary to evaluate the effects of the proposed construction upon any flood hazard areas, which information may include, but shall not be limited to, the following:
- a. Valley cross-sections showing the floodplain surrounding the watercourse, cross-sections of the area to be occupied by the proposed development, and 1% flood maximum water-surface elevation information;
  - b. A profile showing the slope of the bottom of the channel or thalweg of the watercourse;
  - c. A floodplain analysis of the flood profile, base flood elevation and velocity, and floodplain, flood fringe, floodway and erosion buffer zone boundaries, along with boundaries of any other delineated areas, using floodplain modeling guidelines established or approved by the Town Planner, which analysis shall include existing and anticipated uses and shall show the impact the proposed construction or development will have on the elevation of the water-surface of the 1% flood;
  - d. A structural analysis showing that any proposed structures will be adequately designed and constructed to prevent floatation, collapse, or lateral movement of the structure resulting from hydrodynamic and hydrostatic loads, including the effects of buoyancy and scouring; and
  - e. A stability analysis for any proposed development within an erosion buffer zone or for any floodway encroachment or modification.
5. Plans, drawings, specifications or reports for structures, other improvements, features or encroachments, or other impacts of proposed activities shall be prepared and certified by a Colorado registered professional engineer as necessary to provide for an adequate technical basis for floodplain development permit, variance or other decisions under this Article.



6. When reviewing and making a final determination of approval or denial of the application for a floodplain development permit, the Floodplain Administrator shall determine which portions of any flood hazard areas are affected by the particular development request and then shall apply the provisions of this Article as applicable. The Floodplain Administrator also shall determine whether the proposed construction or development is consistent with the need to minimize flood damage and meets the intent of this Article after considering the following factors:
  - a. The effects upon the efficiency or capacity of the floodway;
  - b. The effects upon lands upstream, downstream and in the immediate vicinity;
  - c. The effects upon the 1% flood profile and channel stability;
  - d. The effects upon any tributaries to the main stream, drainage ditches, and any other drainage facilities or systems;
  - e. Whether additional public expenditures for flood protection or prevention will be required;
  - f. Whether the proposed use is for human occupancy, and, if so, the impacts to human safety and the extent to which emergency response and preparedness and other measures are required and have been assured in order to reduce safety risk;
  - g. The potential danger to persons upstream, downstream, and in the immediate vicinity;
  - h. Whether any proposed changes in watercourse will have an adverse environmental effect on the watercourse, including without limitation, erosion of stream banks, and streamside trees, vegetation, and wildlife habitat;
  - i. Whether any proposed water supply and sanitation systems and other public utility systems are located and constructed to minimize flood damage and to prevent disease, contamination and unsanitary or hazardous conditions during a flood;
  - j. Whether any proposed facility and its contents will be susceptible to flood damage and the effect of such damage;
  - k. The relationship of the proposed development to elements of the Johnstown Comprehensive Plan and any applicable floodplain management programs;
  - l. Whether safe access is available to the property in times of flood for ordinary and emergency vehicles;
  - m. Whether the cumulative effect of the proposed development with other existing and anticipated uses will increase flood elevations; and
  - n. Whether the expected flood elevations, velocities, duration, rate of rise, channel stability and sediment transport of the floodwaters expected at the site will adversely affect the development or surrounding property, and whether adequate drainage is provided to reduce exposure to flood damage.
7. All floodplain mapping shall meet the requirements set forth in the version of the FEMA publication "Guidelines and Specifications for Flood Hazard Mapping Partners" in effect at the time of the completion of the mapping.
8. If the Floodplain Administrator determines that the application meets the purposes and requirements of this Article, he or she shall issue the permit and may attach such conditions as he or she deems necessary to further the purposes of this Article or to ensure compliance with the same. The Floodplain Administrator may require a deposit of escrowed funds or other means of securing the performance of permit conditions, and may request that the Town building official condition the release of a certificate of occupancy or other final approval upon submission of final documentation of compliance with conditions, as appropriate.





9. A floodplain development permit shall expire three years after its date of issuance if the permittee has not started construction (see definition of *start of construction*) under the permit. If a floodplain use permit is issued in connection with the issuance of a building permit, and the building permit expires, then the floodplain development permit shall be reevaluated based on any new criteria or data established or available since the issuance of the permit, and a new floodplain development permit may be required in connection with a new building permit, if the permit would not comply with this Section in light of such new criteria or data.
10. No person who has obtained a floodplain development permit shall fail to construct in accordance with the approved application and design or terms of said permit.
11. Variance procedures.
  - a. The Town Council shall hear and render judgment on requests for variances from the requirements of this Article.
  - b. The Town Council shall hear and render judgment on an appeal only when it is alleged there is an error in any requirement, decision, or determination made by the Floodplain Administrator in the enforcement or administration of this Article.
  - c. Any person or persons aggrieved by the decision of the Town Council may appeal such decision in the courts of competent jurisdiction.
  - d. The Floodplain Administrator shall maintain a record of all actions involving an appeal and shall report variances to the Federal Emergency Management Agency upon request.
  - e. Variances may be issued for the reconstruction, rehabilitation, or restoration of Historic Structures, without regard to the procedures set forth in the remainder of this Article, provided such reconstruction, rehabilitation or restoration will not cause the structure to lose the Historic Structure designation.
  - f. Variances may be issued for new construction and substantial improvements to be erected on a lot of one-half (½) acre or less in size contiguous to and surrounded by lots with existing structures constructed below the base flood level, provided that the relevant factors in Subsection (c) above have been fully considered. As the lot size increases beyond the one-half (½) acre, the technical justification required for issuing the variance increases.
  - g. Upon consideration of the factors noted above and the intent of this Article, the Town Council may attach such conditions to the granting of variances as it deems necessary to further the purpose and objectives of this Section).
  - h. Variances shall not be issued within any designated floodway if any increase (e.g. greater than 0.00' rise) in flood levels during the base flood discharge would result.
  - i. Variances may be issued for the repair or rehabilitation of historic structures upon a determination that the proposed repair or rehabilitation will not preclude the structure's continued designation as a historic structure and the variance is the minimum necessary to preserve the historic character and design of the structure.
  - j. Prerequisites for granting variances:
    - (1) Variances shall only be issued upon a determination that the variance is the minimum necessary, considering the flood hazard, to afford relief.
    - (2) Variances shall only be issued upon:
      - (a) Showing a good and sufficient cause;
      - (b) A determination that failure to grant the variance would result in exceptional hardship to the applicant; and
      - (c) A determination that the granting of a variance will not result in increased flood heights, additional threats to public safety,



- extraordinary public expense, create nuisances, cause fraud on or victimization of the public, or conflict with existing local laws or ordinances.
- (3) Any applicant to whom a variance is granted shall be given written notice that the structure will be permitted to be built with the lowest floor elevation below the Base Flood Elevation, and that the cost of flood insurance will be commensurate with the increased risk resulting from the reduced lowest floor elevation.
- k. Variances may be issued for new construction and substantial improvements and for other development necessary for the conduct of a functionally dependent use, provided that:
- (1) The criteria outlined in Paragraphs (11)(a. – i.) of this Section are met; and
- (2) The structure or other development is protected by methods that minimize flood damages during the base flood and create no additional threats to public safety.
- Non-conforming structures use may be continued, notwithstanding the provisions of this Article, subject to the following conditions:
- (a) If a non-conforming structure is abandoned for 12 consecutive months, the structure shall conform to the requirements of this Article prior to any future use. Intent to resume active operations shall not affect the foregoing.
- (b) If any non-conforming structure is substantially damaged (>50% of value) by any means, including floods, such structure shall not be reconstructed, except in conformity with the provisions of this Article.
- (c) Any substantial improvement to a non-conforming structure in a FEMA basin floodplain shall be made only in conformity with the provisions of this Article.
- (d) No person shall change the use of a non-conforming structure in any floodway from a nonresidential structure to a residential structure or a mixed-use structure, or to increase the residential use area of a mixed-use structure.
- (e) No person shall change the use of a non-conforming structure in any flood fringe from a nonresidential structure to either a residential structure or a mixed-use structure with residential use below the regulatory flood protection elevation, or to increase the residential use area of a mixed-use structure below the regulatory flood protection elevation.
- (f) No person shall change the use of a non-conforming structure or existing structure that is not a critical facility to use as a critical facility contrary to the provisions of this Section, or change the use of a critical facility to another type of critical facility, or increase the physical area in use for a non-conforming critical facility, contrary to the provisions of this Section.
- (g) A non-conforming structure may not be relocated, except that a non-conforming critical facility may be relocated within the same parcel of land without losing its legal non-conforming status.
12. **Penalties for noncompliance.** No structure or land shall hereafter be constructed, located, extended, converted, or altered without full compliance with the terms of this ordinance and other applicable regulations. Violations of the provisions of this ordinance by failure to comply with any of its requirements (including violations of conditions and safeguards established in connection with conditions) shall constitute a misdemeanor. A person who



violates the requirements of this Article shall be punished by a fine not exceeding the amount set forth in Article IV of Chapter 1 of the Code. Each day that any such violation continues shall constitute a separate violation and shall subject the perpetrator to a separate penalty. Nothing herein contained shall prevent the Town from taking such other lawful action as is necessary to prevent or remedy any violation.

#### D. Provisions for Flood Hazard Reduction

1. **General standards.** In all Special Flood Hazard Areas, the following provisions are required for all new construction and substantial improvements:
  - a. All new construction or substantial improvements shall be designed (or modified) and adequately anchored to prevent flotation, collapse, or lateral movement of the structure resulting from hydrodynamic and hydrostatic loads, including the effects of buoyancy;
  - b. All new construction or substantial improvements shall be constructed by methods and practices that minimize flood damage;
  - c. All new construction or substantial improvements shall be constructed with materials resistant to flood damage;
  - d. All new construction or substantial improvements shall be constructed with electrical, heating, ventilation, plumbing, and air conditioning equipment and other service facilities that are designed and/or located so as to prevent water from entering or accumulating within the components during conditions of flooding;
  - e. All manufactured homes shall be installed using methods and practices which minimize flood damage. For the purposes of this requirement, manufactured homes must be elevated and anchored to resist flotation, collapse, or lateral movement. Methods of anchoring may include, but are not limited to, use of over-the-top or frame ties to ground anchors. This requirement is in addition to applicable state and local anchoring requirements for resisting wind forces.
  - f. All new and replacement water supply systems shall be designed to minimize or eliminate infiltration of flood waters into the system;
  - g. New and replacement sanitary sewage systems shall be designed to minimize or eliminate infiltration of flood waters into the system and discharge from the systems into flood waters; and
  - h. On-site waste disposal systems shall be located to avoid impairment to them or contamination from them during flooding.
  
2. **Specific standards.** In all Special Flood Hazard Areas where base flood elevation data has been provided as set forth in (i) Subsection B.2; Subsection C.2.g; or (iii) Subsection D.7, the following provisions are required:
  - a. **Residential construction.** New construction and substantial improvement of any residential structure shall have the lowest floor (including basement), electrical, heating, ventilation, plumbing and air conditioning equipment and other service facilities (including ductwork), elevated to 1 foot above the base flood elevation. Upon completion of the structure, the elevation of the lowest floor, including basement, shall be certified by a registered Colorado professional engineer, architect or land surveyor. Such certification shall be submitted to the Floodplain Administrator.
  
  - b. **Nonresidential construction.** With the exception of Critical Facilities, outlined in Subsection (h) of this Section, new construction and substantial improvements of any commercial, industrial or other nonresidential structure shall either have the lowest floor (including basement), electrical, heating, ventilation, plumbing and air



conditioning equipment and other service facilities (including ductwork) elevated to 1 foot above the base flood elevation or, together with attendant utility and sanitary facilities, be designed so that, at 1 foot above the base flood elevation, the structure is watertight with walls substantially impermeable to the passage of water and with structural components having the capability of resisting hydrostatic and hydrodynamic loads and effects of buoyancy. A registered Colorado professional engineer or architect shall develop and/or review structural design, specifications and plans for the construction, and shall certify that the design and methods of construction are in accordance with accepted standards of practice as outlined in this Subsection. Such certification shall be maintained by the Floodplain Administrator, as proposed in Subsection D.3 above.

- c. **Enclosures.** New construction and substantial improvements, with fully enclosed areas below the lowest floor that are usable solely for parking of vehicles, building access or storage in an area other than a basement and which are subject to flooding shall be designed to automatically equalize hydrostatic flood forces on exterior walls by allowing for the entry and exit of floodwaters. Designs for meeting this requirement must either be certified by a registered Colorado professional engineer or architect or meet or exceed the following minimum criteria:
- (1) A minimum of 2 openings having a total net area of not less than 1 square inch for every square foot of enclosed area subject to flooding shall be provided.
  - (2) The bottom of all openings shall be no higher than 1 foot above grade.
  - (3) Openings may be equipped with screens, louvers, valves or other coverings or devices, provided that they permit the automatic entry and exit of floodwaters.
- d. **Manufactured homes.** All manufactured homes that are placed or substantially improved within Zones A1-30, AH and AE on the community's FIRM on sites (i) outside of a manufactured home park or subdivision, (ii) in a new manufactured home park or subdivision, (iii) in an expansion to an existing manufactured home park or subdivision, or (iv) in an existing manufactured home park or subdivision on which a manufactured home has incurred "substantial damage" as a result of a flood, be elevated on a permanent foundation such that the lowest floor of the manufactured home, electrical, heating, ventilation, plumbing and air conditioning equipment and other service facilities (including ductwork) are elevated to 1 foot above the base flood elevation and be securely anchored to an adequately anchored foundation system to resist flotation, collapse and lateral movement. All manufactured homes placed or substantially improved on sites in an existing manufactured home park or subdivision within Zones A1-30, AH and AE on the community's FIRM that are not subject to the provisions of the above Paragraph shall be elevated so that either:
- (1) The lowest floor of the manufactured home, electrical, heating, ventilation, plumbing and air conditioning equipment and other service facilities (including ductwork), are 1 foot above the base flood elevation; or
  - (2) The manufactured home chassis is supported by reinforced piers or other foundation elements of at least equivalent strength that are no less than 36 inches in height above grade and all securely anchored to an adequately anchored foundation system to resist flotation, collapse and lateral movement.



- e. **Recreational vehicles.** All recreational vehicles placed on sites within Zones A1-30, AH and AE on the community's FIRM shall either:
- (1) Be on the site for fewer than 180 consecutive days;
  - (2) Be fully licensed and ready for highway use. A recreational vehicle is ready for highway use if it is on its wheels or jacking system, is attached to the site only by quick disconnect type utilities and security devices and has no permanently attached additions.; or
  - (3) Meet the permit requirements of Subsection D.3 and the elevation and anchoring requirements for manufactured homes in Subsection D.2.d above.
- f. **Prior approved activities.** Any activity for which a Floodplain Development Permit was issued by the Town or a CLOMR was issued by FEMA prior to January 1, 2021 may be completed according to the standards in place at the time of the permit or CLOMR issuance and will not be considered in violation of this Article if it meets such standards.
3. **Standards for areas of shallow flooding (AO/AH zones).** Located within the Special Flood Hazard Area established in Subsection C.2 are areas designated as shallow flooding. These areas have special flood hazards associated with base flood depths of 1 to 3 feet where a clearly defined channel does not exist and where the path of flooding is unpredictable and where velocity flow may be evident. Such flooding is characterized by ponding or sheet flow; therefore, the following provisions apply:
- a. **Residential construction.** All new construction and substantial improvements of residential structures must have the lowest floor (including basement), electrical, heating, ventilation, plumbing and air conditioning equipment and other service facilities (including ductwork) elevated above the highest adjacent grade at least 1 foot above the depth number specified in feet on the community's FIRM (at least 3 feet if no depth number is specified). Upon completion of the structure, the elevation of the lowest floor, including basement, shall be certified by a registered Colorado professional engineer, architect or land surveyor. Such certification shall be submitted to the Floodplain Administrator.
  - b. **Nonresidential construction.** With the exception of Critical Facilities, outlined in Subsection D.12, all new construction and substantial improvements of nonresidential structures, must have the lowest floor (including basement), electrical, heating, ventilation, plumbing and air conditioning equipment and other service facilities (including ductwork) elevated above the highest adjacent grade at least 1 foot above the depth number specified in feet on the community's FIRM (at least 3 feet if no depth number is specified) or, together with attendant utility and sanitary facilities, be designed so that the structure is watertight to at least 1 foot above the base flood level with walls substantially impermeable to the passage of water and with structural components having the capability of resisting hydrostatic and hydrodynamic loads or effects of buoyancy. A registered Colorado professional engineer or architect shall submit a certification to the Floodplain Administrator that the standards of this Section, as proposed in Subsection D.3, are satisfied. Within Zone AH or AO, adequate drainage paths around structures on slopes are required to guide floodwaters around and away from proposed structures.
4. **Standards for determination of the lowest floor elevation.** The lowest floor elevation of the structure shall be determined based on the type of foundation. If more than one





- foundation type is used, the lowest floor elevation shall be determined separately for each portion of the structure with a different foundation type.
- a. *Slab-on-grade.* The lowest floor elevation of a slab-on-grade structure shall be measured at the top of the slab.
  - b. *Basement.* The lowest floor elevation of a structure with a basement shall be measured at the top of the basement slab.
  - c. *Crawl space.* The lowest floor elevation of a structure with a crawl space shall be measured at the top of the floor of the lowest finished area.
  - d. *Enclosure.* The lowest floor elevation of a structure with an enclosure shall be measured at the lowest interior grade of the enclosure.
5. *Elevation certificate required.* A FEMA elevation certificate, signed and certified by a Colorado registered professional land surveyor, accurately documenting the as-built elevation of the improvements, must be submitted to the Floodplain Administrator and accepted before release of a certificate of occupancy for the structure.
6. *Standards for floodproofing.* Any structure or portion of a structure eligible to substitute floodproofing in lieu of compliance with the applicable elevation requirements of Section 17-265 shall meet the following requirements, which shall be referred to as *floodproofing requirements*:
- a. In order for a structure to be eligible to comply with this Article through these floodproofing requirements:
    - (1) The structure must be a nonresidential structure, a nonresidential use portion of a mixed-use structure, an accessory structure or an attached garage; and
    - (2) The flood depth surrounding the structure must not exceed three (3) feet.
  - b. The structure must be designed and constructed to be floodproofed so that:
    - (1) Below the regulatory flood protection elevation, the structure is watertight with walls substantially impermeable to the passage of water;
    - (2) All structural components are capable of resisting hydrostatic and hydrodynamic loads and effects of buoyancy from flooding;
    - (3) The structure complies with the FEMA flood-resistant materials and floodproofing requirements in effect as of the date of the floodplain development permit; and
  - c. The following must be submitted to the Floodplain Administrator and accepted as completed prior to issuance of a floodplain use permit and a building permit:
    - (1) A pre-construction floodproofing certificate, signed and certified by a registered professional engineer or architect, accurately documenting the proposed floodproofing elevation;
    - (2) Detailed plans for floodproofing measures that include:
      - (a) The benchmark used;
      - (b) Design details and locations of the specific floodproofing measures;
      - (c) The direction and distance that all doors swing, in order to show that floodproofing closure shields, if any, cannot block doors from opening when shields are in place; and
      - (d) The signature and certification of a registered professional engineer or architect;



- (3) Manufacturer's specification sheets if using manufactured measures, such as, for example, sealants;
  - (4) Manufacturer's catalog cuts if ordering measures, such as, for example, gates or shields, from a catalog;
  - (5) A statement of the wording of the directions for securing and releasing any gate or closure shield, which directions are required to appear on the back of any gate or closure shield;
  - (6) An emergency action plan that includes:
    - (a) A description of where the floodproofing measures will be stored;
    - (b) A description of who will be responsible for ensuring that the measures are in place, and who will monitor any closure shields, if the structure is an occupied structure; and
    - (c) An annual schedule of when the floodproofing measures will be in use;
  - (7) A statement of the wording of notices to be posted in conspicuous locations on each floor of the structure, in such form, locations and numbers as are reasonably necessary to inform occupants of the structure that the structure is floodproofed and identifying the specific location of any floodproofing equipment requiring human operation in order for the floodproofing to be effective;
  - (8) A plan of the structure showing the location of the required floodproofing notices; and
  - (9) A plan for maintenance and inspection of the floodproofing measures.
- d. A post-construction floodproofing certificate, signed and certified by a registered professional engineer or architect, accurately documenting the as-built elevation of the floodproofing improvements, must be submitted to the Floodplain Administrator and accepted before release of a certificate of occupancy for the structure.
7. *Standards for venting.* Any structure or portion of a structure eligible to substitute venting in lieu of compliance with the applicable elevation requirement in Subsection E. shall meet the following requirements:
- a. The structure must provide 1 square inch of venting for every square foot of enclosed area;
  - b. The structure must provide at least two vents located on different sides of the structure, with one being located on the upstream side of the structure if possible;
  - c. The bottom of required vents must be no higher than 1 foot above grade;
  - d. The required vents must be freely open with no human intervention required;
  - e. The area below the regulatory flood protection elevation must be unfinished and constructed of flood-resistant materials as the same are defined by FEMA. Sheetrock (drywall) used for fire protection is permitted in unfinished areas;
  - f. All ductwork, heating, ventilation and air conditioning systems, electrical and hot water heaters included as part of the structure must be elevated to above the regulatory flood protection elevation;
  - g. The structure must be securely anchored to resist floatation;
  - h. All of the above required features must be shown on the building plans submitted for the floodplain permit and building permit;
  - i. An elevation certificate documenting the venting features included in a structure in a form satisfactory to the Floodplain Administrator must be submitted prior to the issuance of a certificate of occupancy for the structure. For an accessory structure, a certification shall not be required, provided that the structure is



inspected during routine inspection in connection with a building permit or certificate of occupancy.

8. **Floodways.** Floodways are administrative limits and tools used to regulate existing and future floodplain development. The State has adopted floodway standards that are more stringent than the FEMA minimum standard (see definition of *Floodway* in Subsection B.). Located within Special Flood Hazard Area (as established in Subsection C.2) are areas designated as floodways. Since the floodway is an extremely hazardous area due to the velocity of floodwaters which carry debris, potential projectiles and erosion potential, the following provisions shall apply:
  - a. Encroachments are prohibited, including fill, new construction, substantial improvements and other development within the adopted regulatory floodway Unless it has been demonstrated through hydrologic and hydraulic analyses performed by a licensed Colorado professional engineer and in accordance with standard engineering practice that the proposed encroachment would not result in any increase (requires a no-rise certification) in flood levels within the community during the occurrence of the base flood discharge.
  - b. If Paragraph D.8.a above is satisfied, all new construction and substantial improvements shall comply with all applicable flood hazard reduction provisions of this Section.
  - c. Under the provisions of 44 CFR Chapter 1, Section 65.12, of the National Flood Insurance Regulations, a community may permit encroachments within the adopted regulatory floodway that would result in an increase in Base Flood Elevations, provided that the community first applies for a CLOMR and floodway revision through FEMA.
  
9. **Alteration of a watercourse.** For all proposed developments that alter a watercourse within a Special Flood Hazard Area, the following standards apply:
  - a. Channelization and flow diversion projects shall appropriately consider issues of sediment transport, erosion, deposition and channel migration and properly mitigate potential problems through the project, as well as upstream and downstream of any improvement activity. A detailed analysis of sediment transport and overall channel stability should be considered, when appropriate, to assist in determining the most appropriate design.
  - b. Channelization and flow diversion projects shall evaluate the residual 100-year floodplain.
  - c. Any channelization or other stream alteration activity proposed by a project proponent must be evaluated for its impact on the regulatory floodplain and be in compliance with all applicable federal, state and local floodplain rules, regulations and ordinances.
  - d. Any stream alteration activity shall be designed and sealed by a registered Colorado professional engineer or Certified Professional Hydrologist.
  - e. All activities within the regulatory floodplain shall meet all applicable federal, state and the Town floodplain requirements and regulations.
  - f. Within the regulatory floodway, stream alteration activities shall not be constructed unless the project proponent demonstrates through a floodway analysis and report, sealed by a registered Colorado professional engineer, that there is not more than a 0.00-foot rise in the proposed conditions compared to existing conditions floodway resulting from the project, otherwise known as a no-rise certification, unless the community first applies for a CLOMR and floodway revision in accordance with Subsection D.4.
  - g. Maintenance shall be required for any altered or relocated portions of watercourses so that the flood-carrying capacity is not diminished.



10. *Properties removed from floodplain by fill.* A Floodplain Development Permit shall not be issued for the construction of a new structure or addition to an existing structure on a property removed from the floodplain by the issuance of a FEMA Letter of Map Revision Based on Fill (LOMR-F) unless such new structure or addition complies with the following:
- a. *Residential construction.* The lowest floor (including basement) electrical, heating, ventilation, plumbing and air conditioning equipment and other service facilities (including ductwork) must be elevated to minimum of 1 foot above the Base Flood Elevation that existed prior to the placement of fill.
  - b. *Nonresidential construction.* The lowest floor (including basement) electrical, heating, ventilation, plumbing and air conditioning equipment and other service facilities (including ductwork) must be elevated to minimum of 1 foot above the Base Flood Elevation that existed prior to the placement of fill, or, together with attendant utility and sanitary facilities, be designed so that the structure or addition is watertight to at least 1 foot above the base flood level that existed prior to the placement of fill with walls substantially impermeable to the passage of water and with structural components having the capability of resisting hydrostatic and hydrodynamic loads or effects of buoyancy.
  - c. All fill materials to be used in the floodplain shall be designed to withstand the erosional forces associated with the Base Flood, and shall be certified by a registered Colorado professional engineer prior to placement. Said certification shall be submitted to the Floodplain Administrator for review and approval.
11. Standards for subdivision and development proposals, including the placement of manufactured home parks and subdivisions.
- a. All subdivision and development proposals, shall be reasonably safe from flooding. If a subdivision or other development proposal is in a flood-prone area, the proposal shall minimize flood damage.
  - b. All proposals for the development of subdivisions and other applicable development shall meet Floodplain Development Permit requirements of Subsection C.2; D.3; and the provisions of this subsection.
  - c. Base Flood Elevation data shall be generated for subdivision proposals and other proposed development, which is greater than fifty (50) lots or five (5) acres, whichever is lesser, if not otherwise provided pursuant to Subsection C.2 or Subsection D.2..
  - d. All subdivision proposals shall have adequate drainage provided to reduce exposure to flood hazards.
  - e. All subdivision proposals shall have public utilities and facilities, such as sewer, gas, electrical and water systems, located and constructed to minimize or eliminate flood damage.
12. *Standards for Critical Facilities.* A Critical Facility is a structure or related infrastructure, but not the land on which it is situated, as specified in Rule 6 of the Rules and Regulations for Regulatory Floodplains in Colorado, that, if flooded, may result in significant hazards to public health and safety or interrupt essential services and operations for the community at any time before, during and after a flood.
- a. *Classification of Critical Facilities.* Critical Facilities are classified under the following categories: (i) essential services; (ii) hazardous materials; (iii) at-risk populations; and (iv) vital to restoring normal services. It is the responsibility of the Town Council to identify and confirm that specific structures in their community meet the following criteria:



- (1) Essential services facilities include public safety, emergency response, emergency medical, designated emergency shelters, communications, public utility plant facilities and transportation lifelines.
  - (a) These facilities consist of:
    - (i) Public safety (police stations, fire and rescue stations, emergency vehicle and equipment storage and emergency operation centers);
    - (ii) Emergency medical (hospitals, ambulance service centers, urgent care centers having emergency treatment functions and non-ambulatory surgical structures, but excluding clinics, doctors' offices, and nonurgent care medical structures that do not provide these functions);
    - (iii) Designated emergency shelters;
    - (iv) Communications facilities, such as main hubs and control centers for telephone, broadcasting satellite dish systems, cellular systems, television, radio and other emergency warning systems, but excluding towers, poles, lines, cables and conduits);
    - (v) Public utility plant facilities for generation and distribution (hubs, treatment plants, substations and pumping stations for water, power and gas, but not including towers, poles, power lines, buried pipelines, transmission lines, distribution lines and service lines); and
    - (vi) Air transportation lifelines (airports [municipal and larger], helicopter pads and structures serving emergency functions and associated infrastructure, such as aviation control towers, air traffic control centers and emergency equipment aircraft hangars).
  - (b) Specific exemptions to this category include wastewater treatment plants (WWTP), non-potable water treatment and distribution systems and hydroelectric power generating plants and related appurtenances.
  - (c) Public utility plant facilities may be exempted if it can be demonstrated to the satisfaction of the Town Council that the facility is an element of a redundant system for which service will not be interrupted during a flood. At a minimum, it shall be demonstrated that redundant facilities are available (either owned by the same utility or available through an intergovernmental agreement or other contract) and connected, the alternative facilities are either located outside of the 100-year floodplain or are compliant with the provisions of this Article, and an operations plan is in effect that states how redundant systems will provide service to the affected area in the event of a flood. Evidence of ongoing redundancy shall be provided to the Town Council on an as-needed basis upon request.
- (2) Hazardous materials facilities include facilities that produce or store highly volatile, flammable, explosive, toxic and/or water-reactive materials.
  - (a) These facilities may include:





- (i) Chemical and pharmaceutical plants (chemical plant, pharmaceutical manufacturing);
  - (ii) Laboratories containing highly volatile, flammable, explosive, toxic and/or water-reactive materials;
  - (iii) Refineries;
  - (iv) Hazardous waste storage and disposal sites; and
  - (v) Aboveground gasoline or propane storage or sales centers.
- (b) Facilities shall be determined to be Critical Facilities if they produce or store materials in excess of threshold limits. If the owner of a facility is required by the Occupational Safety and Health Administration (OSHA) to keep a Material Safety Data Sheet (MSDS) on file for any chemicals stored or used in the work place, AND the chemicals are stored in quantities equal to or greater than the Threshold Planning Quantity (TPQ) for that chemical, then that facility shall be considered to be a Critical Facility. The TPQ for these chemicals is: either 500 pounds or the TPQ listed (whichever is lower) for the 356 chemicals listed under 40 C.F.R. § 302 (2010), also known as Extremely Hazardous Substances (EHS); or 10,000 pounds for any other chemical. This threshold is consistent with the requirements for reportable chemicals established by the Colorado Department of Public Health and Environment. OSHA requirements for MSDS can be found in 29 C.F.R. § 1910 (2010). The Environmental Protection Agency (EPA) regulation "Designation, Reportable Quantities, and Notification," 40 C.F.R. § 302 (2010) and OSHA regulation "Occupational Safety and Health Standards," 29 C.F.R. § 1910 (2010) are incorporated herein by reference and include the regulations in existence at the time of the promulgation the ordinance codified herein, but exclude later amendments to or editions of the regulations.
- (c) Specific exemptions to this category include:
- (i) Finished consumer products within retail centers and households containing hazardous materials intended for household use and agricultural products intended for agricultural use.
  - (ii) Buildings and other structures containing hazardous materials for which it can be demonstrated to the satisfaction of the local authority having jurisdiction by hazard assessment and certification by a qualified professional (as determined by the local jurisdiction having land use authority) that a release of the subject hazardous material does not pose a major threat to the public.
  - (iii) Pharmaceutical sales, use, storage and distribution centers that do not manufacture pharmaceutical products.
  - (iv) These exemptions shall not apply to buildings or other structures that also function as Critical Facilities under another category outlined in this Article.



- (3) At-risk population facilities include those facilities that house or provide shelter or services to children, the infirm, or other persons requiring special assistance or care or life support:
    - (a) Hospitals;
    - (b) Non-ambulatory surgery center;
    - (c) Residential care and group homes;
    - (d) Elder care;
    - (e) Nursing homes and assisted living;
    - (f) Congregate care ;
    - (g) Public and private schools (pre-schools, K-12 schools), before-school and after-school care serving 12 or more children;
    - (h) Day care and day camps;
    - (i) Other housing and facilities intended to serve those insufficiently mobile to avoid death or injury during a flood without special assistance.
  - (4) Facilities vital to restoring normal services including government operations. These facilities consist of:
    - (a) Essential government operations (public records, courts, jails, building permitting and inspection services, community administration and management, maintenance and equipment centers);
    - (b) Essential structures for public colleges and universities (dormitories, offices and classrooms only).
    - (c) These facilities may be exempted if it is demonstrated to the Town Council that the facility is an element of a redundant system for which service will not be interrupted during a flood. At a minimum, it shall be demonstrated that redundant facilities are available (either owned by the same entity or available through an intergovernmental agreement or other contract), the alternative facilities are either located outside of the 100-year floodplain or are compliant with this Section and an operations plan is in effect that states how redundant facilities will provide service to the affected area in the event of a flood. Evidence of ongoing redundancy shall be provided to the Town Council on an as-needed basis upon request.
- b. *Protection for Critical Facilities.* All new and substantially improved Critical Facilities and new additions to Critical Facilities located within the Special Flood Hazard Area shall be regulated to a higher standard than structures not determined to be Critical Facilities. For the purposes of this Article, protection shall include one of the following:
- (1) Location outside the Special Flood Hazard Area; or
  - (2) Elevation of the lowest floor or floodproofing of the structure, together with attendant utility and sanitary facilities, to at least 2 feet above the Base Flood Elevation.
- c. *Ingress and egress for new Critical Facilities.* New Critical Facilities shall, when practicable as determined by the Town Council, have continuous non-inundated access (ingress and egress for evacuation and emergency services) during a 100-year flood event.



E. **Definitions.** The following terms shall have the specific meaning given when used in this section. All other terms shall have their plain and ordinary meaning unless specifically defined for use throughout this Chapter in Article 11.

**1-percent (1%) flood.** A flood having a recurrence interval that has a one-percent chance of being equaled or exceeded during any given year (one-percent-annual-chance flood). The terms *one-hundred-year flood* and *one-percent-chance flood* is synonymous with the term *100-year flood*. This term does not imply that the flood will necessarily happen only once every 100 years.

**1% floodplain.** The area of land susceptible to being inundated as a result of the occurrence of a 1% flood.

**100-year flood.** See “1% flood.”

**0.2-percent (0.2%) flood.** A flood having a recurrence interval that has a two-tenths percent chance of being equaled or exceeded during any given year (0.2-percent-chance annual flood). The terms *five-hundred-year flood* and *0.2 percent-chance flood* is synonymous with the term *500-year flood*. This term does not imply that the flood will necessarily happen only once every 500 years.

**0.2% floodplain.** The area of land susceptible to being inundated as a result of the occurrence of a 0.2% flood.

**500-year flood.** See “0.2% flood”

**Abandoned.** Any structure that has been used or was intended for use as an occupied structure, in whole or in part, including an accessory building, that has become vacant or unused for a period of at least 365 consecutive days, and meets at least two of the following conditions:

- (1) Is open to casual entry or trespass;
- (2) Is damaged by fire, flood, weather or vandalism to an extent that prevents safe occupation;
- (3) Is the site of loitering or vagrancy;
- (4) Demonstrates a lack of property maintenance and upkeep as evidenced by one or more violations of the International Property Maintenance Code, as adopted in § 5-47 of this Code;
- (5) Is under notice for being in violation of one or more City ordinances;
- (6) Has been secured or boarded up for at least three hundred sixty-five (365) consecutive days;
- (7) Has utilities disconnected or not in use;
- (8) Is subject to a condemnation notice or legal order to vacate;
- (9) Is structurally unsound to an extent that prevents safe occupation; or
- (10) Is a potential hazard or danger to the public.

**Accessory structure.** A structure that is located on the same parcel of property as the principal structure and is used solely for parking and/or storage.

**Addition.** Any activity that expands the enclosed footprint or increases the square footage of an existing structure.

**Alluvial fan flooding.** A fan-shaped sediment deposit formed by a stream that flows from a steep mountain valley or gorge onto a plain or the junction of a tributary stream with the main stream. Alluvial fans contain active stream channels and boulder bars, and recently abandoned channels. Alluvial fans are predominantly formed by alluvial deposits and are modified by infrequent sheet flood, channel avulsions and other stream processes.

**Area of shallow flooding.** A designated Zone AO or AH on a community's Flood Insurance Rate Map (FIRM) with a one-percent chance or greater annual chance of flooding to an average depth of 1 to 3 feet



where a clearly defined channel does not exist, where the path of flooding is unpredictable and where velocity flow may be evident. Such flooding is characterized by ponding or sheet flow

*At-risk population.* Children, the infirm, and other persons requiring special assistance or care, or life support.

*Base flood.* The flood having a one-percent chance of being equaled or exceeded in any given year, whether designated as such by FEMA or by the Town Council in the manner provided in this Article. *Base Flood Elevation (BFE)* means the elevation shown on a FEMA Flood Insurance Rate Map for Zones AE, AH, A1-A30, AR, AR/A, AR/AE, AR/A1-A30, AR/AH, AR/AO, V1-V30 and VE that indicates the water surface elevation resulting from a flood that has a one-percent chance of equaling or exceeding that level in any given year.

*Basement.* Any area of a building having its floor sub-grade (below ground level) on all sides.

*Benchmark.* An established monument with a documented elevation in relation to mean sea level.

*Channel.* The physical confine of a stream or waterway consisting of a bed and stream banks, existing in a variety of geometries.

*Channelization.* The artificial creation, enlargement or realignment of a stream channel.

*Code of Federal Regulations (CFR).* The codification of the general and permanent Rules published in the Federal Register by the executive departments and agencies of the federal government. It is divided into fifty titles that represent broad areas subject to federal regulation.

*Community.* Any political subdivision in the State that has authority to adopt and enforce floodplain management regulations through zoning, including but not limited to cities, towns, unincorporated areas in the counties, Indian tribes and drainage and flood control districts.

*Conditional Letter of Map Revision (CLOMR).* A letter from FEMA officially commenting on a proposed project, which, if constructed in conformance with the CLOMR submittal contained plans would, upon construction, affect the hydrologic or hydraulic characteristics of a flooding source and thus result in a revision to the effective Flood Insurance Rate Map to show changes in zones, delineations, and flood elevations of floodplains and floodways. A CLOMR does not revise an effective Flood Insurance Rate Map.

*Conditional physical map revision (CPMR).* A letter from FEMA officially commenting on, but not revising, the effective Flood Insurance Rate Map, for a proposed project that would, upon completion, affect the hydrologic or hydraulic characteristics of a flooding source and thus result in a revision to, and republication of, one or more panels of the effective Flood Insurance Rate Map to show changes in flood risk zones, delineations and flood elevations of floodplains and floodways.

*Crawl space.* Any unfinished area of a building having its improved or unimproved floor subgrade (below ground level) on all sides and the interior height of which, measured from the lowest interior grade to the highest point of the foundation, is 4 feet or less.

*Critical Facility.* A structure or related infrastructure, but not the land on which it is situated, as specified in Subsection E.8 that, if flooded, may result in significant hazards to public health and safety or interrupt essential services and operations for the community at any time before, during and after a flood. See Subsection E.8.

*Cumulative substantial improvement.* Any combination of repairs, demolition, reconstruction, rehabilitation and/or other improvements of a structure taking place during the time the structure has been



located in a designated floodplain, the cumulative cost of which equals or exceeds 50% of the market value of the structure before the start of construction of the improvement, provided that the footprint of the structure is not increased. The term *cumulative substantial improvement* shall include any repair or reconstruction work on structures that have incurred substantial damage. It shall not include any project for improvement of a structure to correct violations of state or local health, sanitary or safety code specifications that have been identified by the local code enforcement official, including only the minimum improvements necessary to assure safe living conditions. Also, *cumulative substantial improvement* shall not include ordinary maintenance activities, such as interior or exterior painting or decoration, replacement of windows, doors or other nonstructural elements, repair or replacement of heating or air conditioning appliances or hot water heaters, reroofing, and utility connections, provided that such improvements shall not be excluded from the overall work when carried out in connection with structural improvements.

**Development.** Any man-made change in improved and unimproved real estate, including but not limited to: new buildings or other structures, modifications or improvements to existing structures, mining, dredging, filling, grading, paving, land clearing, excavation or drilling operations, or permanent storage of equipment or materials. Development shall also mean any change to, or change of use of, a property or structure that is within the scope of a restriction or equipment set out in this Article.

**DFIRM database.** A database (usually spreadsheets containing data and analyses that accompany DFIRMs). The FEMA Mapping Specifications and Guidelines outline requirements for the development and maintenance of DFIRM databases.

**Digital Flood Insurance Rate Map (DFIRM).** A FEMA digital floodplain map. These digital maps serve as "regulatory floodplain maps" for insurance and floodplain management purposes.

**Drainageway.** A natural or artificial land surface depression with or without perceptibly defined beds and banks to which surface runoff gravitates and collectively forms a flow of water continuously or intermittently in a definite direction.

**Elevated building.** A non-basement building (i) built, in the case of a building in Zones A1-30, AE, A, A99, AO, AH, B, C, X and D, to have the top of the elevated floor above the ground level by means of pilings, columns (posts and piers) or shear walls parallel to the flow of the water; and (ii) adequately anchored so as not to impair the structural integrity of the building during a flood of up to the magnitude of the base flood. In the case of Zones A1-30, AE, A, A99, AO, AH, B, C, X and D, *elevated building* also includes a building elevated by means of fill or solid foundation perimeter walls with openings sufficient to facilitate the unimpeded movement of flood waters.

**Emergency response and preparedness plan.** A plan, and related preparations and systems, that are intended to provide both a reasonable measure of preparedness for flooding and other emergencies that may occur in conjunction with flooding, and a reasonable ability to respond to such circumstances so as to avoid and minimize potential harm to persons or property.

**Enclosure.** An unfinished area below the finished area of a building that is partially or fully shut in by rigid walls, where the lowest interior grade is at or above the outside grade on all sides.

**Encroachment.** An addition to or change to the physical condition of a specified type of flood hazard area that results in the blockage, diversion or displacement of floodwaters.

**Essential services facilities.** Facilities for the provision of services needed before, during and after a flood event in order to protect public health and safety.

**Existing manufactured home park or subdivision.** A manufactured home park or subdivision for which the construction of facilities for servicing the lots on which the manufactured homes are to be affixed





(including, at a minimum, the installation of utilities, the construction of streets and either final site grading or the pouring of concrete pads) is completed before the effective date of the floodplain management regulations adopted by a community.

**Expansion to an existing manufactured home park or mobile building development.** The preparation of additional sites by the construction of facilities for servicing the lots on which the manufactured homes or mobile buildings are to be affixed (including the installation of utilities, the construction of streets and either final site grading or the pouring of concrete pads). Installation of a manufactured home or mobile building on a previously improved lot within a manufactured home park or mobile building development shall not be deemed to constitute expansion of manufactured home park or mobile building development.

**Federal Register.** The official daily publication for Rules, proposed Rules and notices of federal agencies and organizations, as well as executive orders and other presidential documents.

**FEMA.** The Federal Emergency Management Agency, or successor agency

**FEMA floodplain basin.** The land in a 1% floodplain designated by FEMA. This includes both areas of a floodplain designated as Zones A, AE, AO, AH and A1—A30 on the Flood Insurance Rate Map and any other areas in a basin for which FEMA has issued a floodplain map that the Town designates as 1% floodplain.

**FEMA special flood hazard area.** Areas delineated on the Flood Insurance Rate Map and designated as Zones A, AE, AO, AH and A1—A30.

**Fill.** A deposit of materials of any kind placed by artificial means. **Finished area** shall mean an enclosed area that has more than 20 linear feet of finished walls (paneling, wallboard or other non-flood-resistant material, for example) or that is used for any purpose other than solely for parking of vehicles, building access or storage.

**Floatable materials.** Any material that is not secured in place or completely enclosed in a structure, so that it could float off site during the occurrence of a flood and potentially cause harm to downstream property owners, or that could cause blockage of a culvert, bridge or other drainage facility. This includes, without limitation, lumber, vehicles, boats, equipment, trash dumpsters, tires, drums or other containers, pieces of metal, plastic or any other item or material likely to float. **Floatable materials** shall not include motor vehicles parked temporarily on property for the purpose of customer or employee parking, or a business's temporary outdoor display of inventory during its usual hours of operation.

**Flood or flooding.** A general and temporary condition of partial or complete inundation of normally dry land areas from:

- (a) The overflow of water from channels and reservoir spillways;
- (b) The unusual and rapid accumulation or runoff of surface waters from any source; or
- (c) Mudslides or mudflows that occur from excess surface water that is combined with mud or other debris that is sufficiently fluid so as to flow over the surface of normally dry land areas (such as earth carried by a current of water and deposited along the path of the current).

**Flood control structure.** A physical structure designed and built expressly or partially for the purpose of reducing, redirecting or guiding flood flows along a particular waterway. These specialized flood modifying works are those constructed in conformance with sound engineering standards.

**Flood fringe.** That portion of the 1% floodplain between the floodway boundary and the upper limits of the base flood. Sheet flow areas with flood depths of less than 1 foot shall not be considered part of the *flood fringe*. Sheet flow areas with flood depths between 1 and t3 feet, inclusive, shall be considered part of the *flood fringe*.



**Flood hazard area** shall mean the Big Thompson or Little Thompson floodplain, a FEMA basin floodplain, a Town basin floodplain, an area removed from a floodplain by a LOMR-Fill, or an erosion buffer zone.

**Flood Insurance Rate Map (FIRM).** An official map of a community on which the Federal Emergency Management Agency has delineated both the Special Flood Hazard Areas and the risk premium zones applicable to the community.

**Flood Insurance Study (FIS).** The official report provided by FEMA. The report contains the Flood Insurance Rate Map, as well as flood profiles and water surface elevation of the base flood.

**Floodplain or flood-prone area.** Any land area susceptible to being inundated as the result of a flood, including the area of land over which floodwater would flow from the spillway of a reservoir.

**Floodplain Administrator.** The community official designated by title to administer and enforce the floodplain management regulations.

**Floodplain Development Permit.** A permit required before construction or development begins within any Special Flood Hazard Area (SFHA). If FEMA has not defined the SFHA within a community, the community shall require permits for all proposed construction or other development in the community including the placement of manufactured homes, so that it may determine whether such construction or other development is proposed within flood-prone areas. Permits are required to ensure that proposed development projects meet the requirements of the NFIP and this Article.

**Floodplain management.** The operation of an overall program of corrective and preventive measures for reducing flood damage, including but not limited to emergency preparedness plans, flood control works and floodplain management regulations. Floodplain management refers to those activities that are implemented with the intent to promote the public health, safety and general welfare, to minimize public and private losses due to flood conditions and to maintain, enhance and improve the natural and beneficial functions of floodplains.

**Floodplain management regulations.** Land use and zoning ordinances, subdivision regulations, building codes, health regulations, special purpose ordinances (such as a floodplain ordinance, grading ordinance and erosion control ordinance) and other applications of police power. The term describes such state or local regulations, in any combination thereof, which provide standards for the purpose of flood damage prevention and reduction.

**Floodproofing.** Any combination of structural provisions, and/or nonstructural additions, changes or adjustments to properties and structures subject to flooding, primarily for the reduction or elimination of flood damage to properties, water and sanitary facilities, structures and contents of buildings in a floodplain area.

**Floodway (regulatory floodway).** The channel of a river or other watercourse and adjacent land areas that must be reserved in order to discharge the base flood without cumulatively increasing the base flood water surface elevation more than one-half ( $\frac{1}{2}$ ) foot (six [6] inches). Letters of Map Revision to existing floodway delineations may continue to use the floodway criteria in place at the time of the existing floodway delineation.

**Floodway modification.** Any alteration to a channel thalweg, bed or banks of a floodway that would change the delineation of the floodway. **Footprint** shall mean the aerial extent and location of a structure at the point at which it meets the ground at grade level, or at which the floor projects horizontally above the ground, to the extent portions of the structure do not meet the ground.

**Freeboard.** The vertical distance in feet above a predicted water surface elevation, intended to provide a margin of safety to compensate for unknown factors that could contribute to flood heights greater than the



height calculated for a selected size flood such as debris blockage of bridge openings and the increased runoff due to urbanization of the watershed.

**Functionally dependent use.** A use which cannot perform its intended purpose unless it is located or carried out in close proximity to water. The term includes docking facilities, but does not include long-term storage or related manufacturing facilities.

**Hardship.** The effect of a floodplain designation on the use of a property in light of unusual physical characteristics of the land that are exceptional or peculiar to the property and not shared by adjacent parcels. *Hardship* does not include personal or financial circumstances of the current owner of the land, such as increased costs, inconvenience, aesthetic considerations, physical disability, timing, mistakes by contractors or advisors, personal preferences, or the disapproval of neighbors.

**Hazardous materials facilities.** Facilities that produce, use or store highly volatile, hazardous, flammable, explosive, toxic and/or water-reactive materials, liquids, gases or solids, as defined under the Hazardous Materials Transportation Act, 49 U.S.C. Secs. 1801-1812, and cemeteries. *Hazardous materials facilities* shall include, but not be limited to: chemical and pharmaceutical plants; laboratories; refineries; hazardous waste storage and disposal sites; gasoline storage or sales facilities; automobile oil and lubrication, repair or paint facilities; warehouses; manufacturing facilities; and propane storage or sales facilities. *Hazardous materials facilities* shall not include retail structures and facilities that only stock and store products in factory-sealed containers.

**Highest adjacent grade.** The highest natural elevation of the ground surface prior to construction next to the proposed walls of a structure.

**Historic structure.** Any structure that is:

- (a) Listed individually in the National Register of Historic Places (a listing maintained by the Department of the Interior) or preliminarily determined by the Secretary of the Interior as meeting the requirements for individual listing on the National Register;
- (b) Certified or preliminarily determined by the Secretary of the Interior as contributing to the historical significance of a registered historic district or a district preliminarily determined by the Secretary of the Interior to qualify as a registered historic district;
- (c) Individually listed on a state inventory of historic places in states with historic preservation programs which have been approved by the Secretary of the Interior; or
- (d) Individually listed on a local inventory of historic places in communities with historic preservation programs that have been certified either:
  1. By an approved state program as determined by the Secretary of the Interior; or
  2. Directly by the Secretary of the Interior in states without approved programs.

**Infrastructure.** Any facility, excluding structures, of a public or private utility providing electric, telephone, cable TV, fiber-optic, telegraph, water, wastewater, storm sewer or any other public utility service; stormwater improvements identified in any Town-approved drainage master plan; public roads, bridges and culverts; and traffic signaling equipment that is provided, required or authorized by any governmental entity having jurisdiction.

**Letter of map amendment (LOMA).** A letter from FEMA officially revising the effective Flood Insurance Rate Map that establishes that a property is not located in a FEMA special flood hazard area.

**Letter of Map Revision (LOMR).** FEMA's official revision of an effective Flood Insurance Rate Map (FIRM) or Flood Boundary and Floodway Map (FBFM), or both. LOMRs are generally based on the implementation of physical measures that affect the hydrologic or hydraulic characteristics of a flooding source and thus result in the modification of the existing regulatory floodway, the effective Base Flood Elevations (BFEs) or the Special Flood Hazard Area (SFHA).



**Letter of Map Revision based on Fill (LOMR-F).** A letter from FEMA stating that a structure or parcel of land that has been elevated by fill would not be inundated by the base flood.

**Levee.** A man-made embankment, usually earthen, designed and constructed in accordance with sound engineering practices to contain, control or divert the flow of water so as to provide protection from temporary flooding. For a levee structure to be reflected on the FEMA FIRMs as providing flood protection, the levee structure must meet the requirements set forth in 44 CFR § 65.10.

**Levee system.** A flood protection system which consists of a levee or levees and associated structures, such as closure and drainage devices, which are constructed and operated in accordance with sound engineering practices.

**Lowest adjacent grade (LAG).** The elevation of the natural ground or properly compacted fill that comprises a component of a building's foundation system, sidewalk, patio, deck support or basement entryway immediately next to a structure and after the completion of construction.

**Lowest floor.** The lowest floor of the lowest enclosed area (including basement), and includes any floor used for living purposes which includes working, storage, sleeping, cooking and eating or recreation, or any combination thereof. This includes any floor that could be converted to such a use, such as a basement or crawl space. The lowest floor is a determinate for the flood insurance premium for a building, home or business. An unfinished or flood-resistant enclosure, usable solely for parking of vehicles, building access or storage in an area other than a basement area is not considered a building's lowest floor; provided that such enclosure is not built so as to render the structure in violation of the applicable non-elevation design requirement of Section 60.3 of the National Flood Insurance Program regulations.

**Manufactured home.** A structure that is used or intended for use as a residential structure that is transportable in one or more sections, which is built on a permanent chassis and is designed for use with or without a permanent foundation when connected to the required utilities. The term *manufactured home* does not include a recreational vehicle.

**Manufactured home park or subdivision.** A parcel (or contiguous parcels) of land divided into two or more manufactured home lots for rent or sale.

**Market value.** The value of a structure, excluding the value of the underlying land, based upon the market for comparable properties in the local real estate market among willing buyers and sellers. Market value may be established by the County Assessor's assessment of the actual value of the structure, or may be established by an independent certified appraisal consistent with FEMA standards for the appraisal of improvements.

**Material Safety Data Sheet (MSDS).** A form with data regarding the properties of a particular substance. An important component of product stewardship and workplace safety, it is intended to provide workers and emergency personnel with procedures for handling or working with that substance in a safe manner, and includes information such as physical data (melting point, boiling point, flash point, etc.), toxicity, health effects, first aid, reactivity, storage, disposal, protective equipment and spill-handling procedures.

**Mean sea level.** For purposes of the National Flood Insurance Program, the North American Vertical Datum (NAVD) of 1988 or other datum, to which Base Flood Elevations shown on a community's Flood Insurance Rate Map are referenced.

**Mixed-use structure.** Any structure that is used or intended for use for a mixture of nonresidential and residential uses in the same structure. **National Flood Insurance Program (NFIP)** means FEMA's program of flood insurance coverage and floodplain management administered in conjunction with the Robert T. Stafford Relief and Emergency Assistance Act. The NFIP has applicable federal regulations promulgated



in Title 44 of the Code of Federal Regulations. The U.S. Congress established the NFIP in 1968 with the passage of the National Flood Insurance Act of 1968.

**New construction.** A new structure (including the placement of a mobile home) or facility or the replacement of a structure or facility which has been totally destroyed. New manufactured home park or subdivision. A manufactured home park or subdivision for which the construction of facilities for servicing the lots on which the manufactured homes are to be affixed (including at a minimum, the installation of utilities, the construction of streets and either final site grading or the pouring of concrete pads) is completed on or after the effective date of floodplain management regulations adopted by a community.

**No-rise certification.** A record of the results of an engineering analysis conducted to determine whether a project will increase flood heights in a floodway. A no-rise certification must be supported by technical data and signed by a registered Colorado professional engineer. The supporting technical data should be based on the standard step-backwater computer model used to develop the 100-year floodway shown on the Flood Insurance Rate Map (FIRM) or Flood Boundary and Floodway Map (FBFM).

**Physical Map Revision (PMR)/** FEMA's formal action whereby one or more map panels of the effective National Flood Insurance Rate Map (FIRM) are physically revised and republished. A PMR is used to show changes in flood risk zones, floodplain and/or floodway delineations, flood elevations, and/or planimetric features.

**Reconstruct or reconstruction.** To rebuild a structure without increasing its footprint, when the structure has been: (a) partially or completely destroyed by any cause (i.e., fire, wind, flood), or (b) partially or completely torn down. *Reconstruction* that also meets the definition of *redevelopment* shall be regulated hereunder as redevelopment.

**Recreational vehicle.** A vehicle which is:

- (a) Built on a single chassis;
- (b) 400 square feet or less when measured at the largest horizontal projections;
- (c) Designed to be self-propelled or permanently towable by a light duty truck; and
- (d) Designed primarily not for use as a permanent dwelling but as temporary living quarters for recreational, camping, travel or seasonal use.

**Redevelop or redevelopment.**

- (a) To construct any substantial improvement that will result in the removal or replacement of more than 50% of the wall perimeter of any floor of a structure that is completely or partially below the base flood elevation, provided that the footprint of the structure is not increased; or
- (b) To repair or reconstruct any structure that has sustained substantial damage, which damage has caused the removal or replacement of more than 50% of the wall perimeter of any floor of a structure that is completely or partially below the base flood elevation, provided that the footprint of the structure is not increased.

**Regulatory flood protection elevation.** The elevation above the base flood elevation to which a structure must be elevated, as set forth in the applicable requirements of this Section.

**Regulatory floodplain.** The floodplain that is regulated by the Town, including the Big Thompson and Little Thompson floodplains and other FEMA or Town-delineated basin floodplains.

**Rehabilitation or rehabilitate.** To make any improvements and repairs to the interior and exterior of a structure that do not result in any increase in the footprint of the structure. The construction of a vertical addition is considered to constitute *rehabilitation*.

**Remodel or remodeling.** (See *rehabilitation* or *rehabilitate*.)





**Residential structure.** Any structure that is used for, or designed as and capable of being used for, the temporary or permanent domicile of persons, including without limitation a dwelling, a boarding house, a hotel, a motel and similarly used structure and a manufactured home. A *mixed-use structure* shall not be deemed to constitute a *residential structure*.

**Shallow flooding area.** Either: (a) a designated AH or AO zone shown on the Flood Insurance Rate Map; or (b) designated as a shallow flooding area by the City in a 1% floodplain having an average depth of from one 1 to 3 feet, inclusive, where a clearly defined channel does not exist, where the path of flooding is unpredictable and where velocity flow may be evident. Such flooding is characterized by ponding or sheet flow.

**Sheet flow area.** A portion of the 1% floodplain that is characterized by undefined flow paths. *Sheet flow areas* with flood depths of less than 1 foot shall not be considered part of the flood fringe. *Sheet flow areas* with flood depths between 1 and 3 feet, inclusive, shall be considered part of the flood fringe.

**Special Flood Hazard Area (SFHA).** The land in the floodplain within a community subject to a 1% or greater chance of flooding in any given year, i.e., the 100-year floodplain.

**Start of construction.** The date the building permit was issued, including substantial improvements, provided that the actual start of construction, repair, reconstruction, rehabilitation, addition, placement or other improvement was within 180 days of the permit date. The *actual start* means either the first placement of permanent construction of a structure on a site, such as the pouring of slab or footings, the installation of piles, the construction of columns or any work beyond the stage of excavation; or the placement of a manufactured home on a foundation. *Permanent construction* does not include land preparation, such as clearing, grading and filling; nor does it include the installation of streets and/or walkways; nor does it include excavation for basement, footings, piers or foundations or the erection of temporary forms; nor does it include the installation on the property of accessory buildings, such as garages or sheds not occupied as dwelling units or not part of the main structure. For a substantial improvement, the *actual start of construction* means the first alteration of any wall, ceiling, floor or other structural part of a building, whether or not that alteration affects the external dimensions of the building.

**Storage of floatable materials.** Storage outside of any structures of materials, products, equipment, vehicles or any other item that is not a structure, if the stored material or item meets the definition of *floatable material*. *Structure* shall mean a structure with two or more outside rigid walls from floor to roof and a fully secured roof that is affixed to a permanent site, a mobile building or manufactured home or a gas or liquid storage tank that is principally aboveground. An attached garage or addition shall be considered part of the structure to which it is attached.

**Substantial damage.** Damage of any origin sustained by a structure whereby the cost of restoring the structure to its before-damaged condition would equal or exceed 50% of the market value of the structure (but not of the land where it is located) just prior to when the damage occurred.

**Substantial improvement.** Any reconstruction, rehabilitation, addition or other improvement of a structure, the cost\*\* of which equals or exceeds 50% of the market value of the structure before start of construction of the improvement. The value of the structure shall be determined by the local jurisdiction having land use authority in the area of interest. This includes structures which have incurred substantial damage, regardless of the actual repair work performed. The term does not, however, include either:

- (a) Any project for improvement of a structure to correct existing violations of state or local health, sanitary or safety code specifications which have been identified by the local code enforcement official and which are the minimum necessary conditions; or
- (b) Any alteration of a historic structure, provided that the alteration will not preclude the structure's continued designation as a historic structure.



**Threshold Planning Quantity (TPQ).** A quantity designated for each chemical on the list of extremely hazardous substances that triggers notification by facilities to the State that such facilities are subject to emergency planning requirements.

**Unfinished area.** An enclosed area that is used only for the parking of vehicles, building access or storage purposes and does not meet the definition of finished area.

**Vertical addition.** An addition to a structure that does not result in an increase in the structure's footprint, provided that the associated work does not constitute redevelopment of the structure.

**Variance.** A grant of relief to a person from the requirement of this Article when specific enforcement would result in unnecessary hardship. A variance, therefore, permits construction or development in a manner otherwise prohibited by this Article. (For full requirements, see Section 60.6 of the National Flood Insurance Program regulations.)

**Violation.** The failure of a structure or other development to be fully compliant with the community's floodplain management regulations. A structure or other development without the elevation certificate, other certifications or other evidence of compliance required in Section 60.3(b)(5), (c)(4), (c)(10), (d)(3), (e)(2), (e)(4) or (e)(5) is presumed to be in violation until such time as that documentation is provided.

**Water surface elevation.** The height, in relation to the North American Vertical Datum (NAVD) of 1988 (or other datum, where specified), of floods of various magnitudes and frequencies in the floodplains of coastal or riverine areas.

**Water surface profile.** A graph that shows the relationship between the vertical elevation of the top of the floodwater and of the streambed with the horizontal distance along the stream channel.

**Watercourse.** A stream, creek, pond, slough, gulch, reservoir, lake or portion of the floodplain functioning as a natural or improved channel carrying flows, not constituting a flood. The term shall include, but not be limited to, established natural and human-made drainageways for carrying storm runoff, but it shall not include irrigation ditches.

**Zone.** An area designated on the FEMA Flood Insurance Rate Map, indicating the likelihood and potential extent of flooding:

- (a) **A zone.** An area inundated by the 1% Flood, as shown on the FEMA Flood Insurance Rate Map. Base flood elevations are not determined in an A zone.
- (b) **A1—A30 and AE zone.** Areas inundated by the 1% Flood, as shown on the FEMA Flood Insurance Rate Map. Base flood elevations are determined for these zones.
- (c) **AH zone.** An area of one-hundred-year shallow flooding as shown on the FEMA Flood Insurance Rate Map where depths are between 1 and 3 feet (usually shallow ponding). Base flood elevations are determined for this zone.
- (d) **AO zone.** An area of one-hundred-year shallow flooding as shown on the FEMA Flood Insurance Rate Map where depths are between 1 and 3 feet (usually sheet flow on sloping terrain). Average flood depths are determined for this zone.
- (e) **X zone.** One or more of the following: the area inundated by the 0.2% flood; a sheet flow area inundated by the 1% flood with an average flood depth of less than 1 foot; or an area protected by one or more levees from inundation by the 1% flood.



### 17-10-3 Natural Resource Extraction & Energy Development

- A. **Intent.** State law recognizes that surface and mineral estates are separate and distinct interests in land and that one may be severed from the other. Additionally, energy development is of community interest and impact. The Town has the responsibility to protect Town infrastructure and resources, manage and mitigate adverse land use impacts, and protect the health, safety, and general welfare of the public, while permitting such uses to be developed in a responsible and compatible manner. This Section has the following intent with regard to the rights of surface and mineral estates as well as energy development:
1. Ensure and monitor compliance with all State and Federal laws and rules;
  2. Enable the right to use that part of the surface estate reasonably for such uses;
  3. Minimize or mitigate adverse land use impacts and protect community interests.
  4. Protect the Town's infrastructure and groundwater resources to ensure these resources are not harmed.
  5. Mitigate potential negative impacts from such development on property owners, adjacent or future land uses, and ecological resources through reasonable regulations for construction, operation and reclamation related to natural resource extraction and energy development.
- B. **Applicability.** The standards and procedures in this Section apply to all natural resource extraction and energy development operations located on surface property in the Town limits.
- C. **Process.** No such development shall be operated, and no site development or equipment shall be located prior to the following:
1. *Use by Special Review* according to the procedures and criteria in Section 17-2-7.
  2. *Site Plan.* Approval of a site plan in association with the *Use by Special Review* approval, or in accordance with the procedures and criteria in Section 17-2-5 for any new or relocated facilities, and provided it is compliance with an approved *Use by Special Review* and the standards of this Section.
  3. *Notice to Proceed.* Prior to commencement of construction operations for which a *Use by Special Review* has been previously granted, a "Notice to Proceed" shall be obtained from the Town. A copy of any necessary state or federal permit issued for the operation shall be provided to the Town.
  4. *Building Permits.* Building permits shall be obtained as required by the Town's adopted Building and Fire Codes and all other applicable codes and regulations.
  5. For natural resource extraction the initial *Use by Special Review* permit shall allow any twinning, sidetracking, deepening, recompleting or reworking of a well and relocation of accessory equipment or gathering and transmission lines so long as all applicable regulations of this jurisdiction and the state are met. If any twinning, sidetracking, deepening, recompleting or reworking of a well, or relocation of accessory equipment or gathering and transmission lines occurs, then the operator shall submit a revised site plan according to the procedures and criteria in Section 17-2-7.
- D. **Site & Development Supplementary Standards.** All natural resource extraction and energy facility development projects shall meet the following supplementary site and development standards:
1. **General Provisions.** Operators shall conform to the following:
    - a. Town, county, state, and federal regulations and standards, including those concerning air quality, water quality, odor and noise and other possible nuisances.
    - b. Town sanitation and environmental standards.



2. **Flow Lines.** All flow lines, including transmission and gathering systems, shall have the legal description of the location recorded with the County Clerk and Recorder within 30 days of completion of construction. Abandonment of any flow lines shall be recorded with the County Clerk and Recorder within 30 days after abandonment.
3. **Impact Mitigation.**
  - a. All equipment and facilities shall be adequately fenced to restrict access by unauthorized persons and mitigate visual clutter and impacts. All facilities and equipment shall be surrounded by a fence at least six feet but no more than 10 feet in height, of noncombustible material and which includes a gate which shall be locked. Fencing surrounding well heads may be an open design. Fencing surrounding oil and gas equipment and production pads shall be a solid and durable material that provides screening.
  - b. All sites shall remain clear of all nonessential equipment and vehicles.
  - c. Where possible, operators shall provide for the development of multiple reservoirs by drilling on existing pads or by multiple completions or commingling in existing well bores.
  - d. Use of electric motors, only, permitted.
  - e. Drilling operations may be subject to noise mitigation and sound walls.
  - f. Noise management plan may be required to identify hours of maximum noise emissions, type, frequency and level of noise to be emitted and proposed mitigation measures.
  - g. Construction of noise-abating structures may be required where facilities create noise and visual impacts which cannot otherwise be mitigated. Based on the duration of anticipated impacts these structures may be temporary or permanent in nature.
  - h. Exhaust from engines, motors, coolers and other mechanized equipment shall be vented in a direction away from all habitable buildings that be reasonably by impacted.
  - i. Exterior lighting shall be down-directional and directed away or shielded from residential areas to eliminate glare.
  - j. Facilities and equipment shall not be located within regulatory flood hazard areas.
  - k. When facilities are located within or in close proximity to any area identified with sensitive ecological features or natural habitat, the Town may require consultation with Colorado Parks and Wildlife and or provide an ecological survey to obtain recommendations for appropriate site specific and cumulative impact mitigation procedures.
  - l. Other measures that may be needed to mitigate impacts to the community or public infrastructure.
- E. **Coordination with COGCC Rules.** In addition to any other standards that are part of a *Use by Special Review* approval, all oil and gas facilities shall comply with the current rules of the Oil and Gas Conservation Commission of the State of Colorado (COGCC). All requisite approvals may be submitted and reviewed concurrently, but shall receive final approvals by the COGCC prior to the Town issuing Notice to Proceed. Evidence of such approvals shall be provided to the Town.
- F. **Supplementary Application Materials – Oil & Gas.** In addition to all submittal requirements for a *Use by Special Review* and site plan required by Section 17-2-7, oil and gas facilities may be required to submit the following:
  1. Copies of all information submitted to the COGCC.
  2. If any of the following is not included on the COGCC information, it shall be incorporated into plans submitted to the Town:



- a. The proposed location of production site facilities or well site facilities. Future development of the resource shall be considered in the location of the tank battery. Existing tank batteries and transmission and gathering lines within 500 feet of the well site shall be shown.
  - b. The location of the drilling equipment and related facilities and structures.
  - c. The following information within a radius of 500 feet of the proposed well or production site:
    - (1) Existing surface improvements;
    - (2) Existing utility easements and other rights-of-way of record; and
    - (3) Existing irrigation or drainage ditches.
    - (4) Names of abutting subdivisions or owners of abutting unplatted property
  - f. Well site or production site's existing lease boundaries, well name and number. .
3. **Other Items.**
- a. The operator's and surface owner's names and addresses, copies of any required COGCC Form 2 and designation of agent, if applicable.
  - b. An operating plan.
  - c. A list of all permits or approvals obtained or yet to be obtained from local, state or federal agencies other than COGCC.
  - d. An emergency response plan that is mutually acceptable to the operator and the appropriate fire district that includes a list of local telephone number of public and private entities and individuals to be notified in the event of an emergency, the location of the well and provisions for access by emergency response entities.
  - e. A plan for minimizing negative impacts, including noise and vibration levels, air and water quality, odor levels, visual impacts, wildlife impacts, waste disposal, traffic and roadway impacts, and public safety.
  - f. A fire protection plan that is mutually acceptable to the operator and the appropriate fire district that includes planned actions for possible emergency events and any other pertinent information.
- G. **Review Criteria.** In addition to all other general criteria in Section 17-2-7 for *Use by Special Review*, the Town shall consider the following for natural resource extraction and energy development facilities:
- 1. The submittal of all necessary information demonstrates compliance with all federal, state and local laws and regulations regarding siting and operating facilities.
  - 2. The site plans demonstrate compliance with all standards in this Section.
  - 3. The site plan or any additional mitigation plans meet the standards, guidelines and criteria for the specific location and context.
  - 4. No other conditions or circumstances exist that will undermine the intent of this Section.
- H. **Inspections.** The operator shall allow inspections of all facilities by Town personnel at any reasonable hour.
- 1. Failure to allow inspections for more than ten days shall result in scheduling a *Use by Special Review* permit revocation hearing before the Town Council. The Town Council's decision on a *Use by Special Review* revocation based on failure to allow inspections shall be final.
  - 2. Each year the operator of any producing oil or gas well shall provide the following to the Town:
    - a. Proof of insurance and bonding required by any Town, county, state or federal law or regulation.
    - b. Certification of compliance with the conditions of this Section, the Uniform Building and Fire Codes, and other applicable regulations.
    - c. Annual inspection fees may be established by the Town to cover inspection costs.





- I. **Defined Terms.** The following terms used in this Section shall have the meaning given below. All terms not listed but that are defined in the Act, or in regulations by the COGCC or CDPHE authorized under the Act, shall defer to those definitions, and any conflicts resolved in favor of the state definitions. All other terms shall have their plain and ordinary meaning unless specifically defined for use throughout this Chapter in Article 11.

*Act* shall mean the Oil and Gas Conservation Act of the State of Colorado.

*Commission or COGCC* shall mean the Oil and Gas Conservation Commission of the State of Colorado.

*Inspector, Town* shall mean any person designated by the Town Manager or by the Manager's designee, who shall have the authority to inspect a well site to determine compliance with this Chapter and other applicable ordinances of the Town.

*Operating plan* shall mean a general plan which describes an oil and gas exploration and production facility identifying purpose, use, typical staffing pattern, seasonal or periodic considerations, routine hours of operation, source of services/infrastructure, any mitigation plans and any other information related to regular functioning of that facility.

*Operator* shall mean the person or entity designated by the owner or lessee of the mineral rights as the operator for oil and gas sites.

*Operations / Operating* shall mean use of the facility, once construction activities are complete and the site is in day-to-day operations.

*Production facilities* shall mean all storage, separation, treating, dehydration, artificial lift, power supply, compression, pumping, metering, monitoring, flow lines and other equipment directly associated with oil wells, gas wells or injection wells.

*Sidetracking* shall mean entering the same wellhead from the surface, but not necessarily following the same well bore, throughout its subsurface extent when deviation from such well bore is necessary to reach the objective depth because of an engineering problem.

*Surface owner* shall mean any person having title or right of ownership in the surface estate of real property or leasehold interest therein.

*Twining* shall mean the drilling of a well adjacent to or near an existing well when the well cannot be drilled to the objective depth or produced due to an engineering problem, such as a collapsed casing or formation damage.

*Well* shall mean any oil or gas well, a hole drilled for the purpose of producing oil or gas, or a well into which fluids are injected.

*Well site* shall mean the areas which are directly disturbed during the drilling and subsequent operation of, or affected by production facilities directly associated with, any oil well, gas well or injection well.

*Wellhead* shall mean the mouth of the well at which oil or gas is produced.



## Article 11. Definitions

- 17-11-1 Description of Uses
  - 17-11-2 Defined Terms
  - 17-11-3 Design & Architecture Terms
- 

### 17-11-1 Description of Uses

This section provides descriptions of uses of land and buildings associated with Table 4-2: Permitted Uses. It is organized by categories and types of uses. Categories are general groupings of uses with similar characteristics, and types are based on common physical or operational characteristics, such as typical scale or format. Where a proposed use is not generally listed or appears to meet the description of more than one use type, the Director shall make an interpretation on the most equivalent described use category and/or type, considering:

1. The similarity of the use in terms of scale, impact, and operations to other described uses;
2. The typical building format and site design associated with the use from existing examples; and
3. The potential contribution of the use, in its typical format and design, to the intent of the zoning district, and the ability to complement and be compatible with other permitted uses.

Any uses that may not be interpreted as equivalent to a use in Table 4-2 is not anticipated by these regulations and may only be allowed by an amendment to the development code.

#### A. Residential Uses

1. *Household Living.* Residential occupancy of a dwelling unit by a single household, with tenancy arranged on a monthly or longer basis. Household living occurs in a variety of types based on the scale and format of buildings and arrangement of dwelling units.

*One-unit Dwelling.* A residential building designed for one primary dwelling unit. One-unit dwellings include variations based on the lot size.

*Multi-unit Dwelling.* A residential building designed for two or more principal dwelling units. Multi-unit dwellings include variations based on the building type and scale, including duplexes, multi-unit houses, row houses, or apartments.

*Live / Work Dwelling.* A combination of residential commercial activity located in a dwelling unit or sharing the same building as a dwelling sharing a common wall or with direct access between the residential and commercial elements, and where each is intended as a principal use.

*Mixed-use Dwelling.* A residential use in a building designed for street level retail, service or employment uses, and where dwelling units are accommodated on upper stories, or otherwise separated from the principal commercial function of the building.

*Manufactured or Small Format Home Communities.* A parcel of land planned and designed for multiple home sites for the placement of manufactured, mobile or other small homes, and used for the principal dwelling of households for long-term residency. These communities include internal common areas, circulation systems and accessory



uses and facilities to support the community. Dwellings may either be located on home sites designated within a larger project or on single lots owned through appropriate condominium procedures or platted under certain conditions.

*Established Residential (all building types).* Any residential building and use, legally established when it originated but where new development of the same use or similar building type is no longer permitted in the zone district. Where permitted, continued use and further investment in the building and use is not discouraged.

2. *Group Living.* Residential occupancy of a structure by a group of people that do not meet the definition of a household, with tenancy arranged on a monthly or longer basis. Group living structures typically have a common eating area for residents, and they may receive some level of care, training, or services associated with their residency. Group living occurs in a variety of types based on the scale and format of buildings, arrangement of dwelling units, and the degree or intensity of associated services.

*Group Home- Small.* The use of a residential building as a single primary dwelling which provides permanent residence, supervision, and other services for up to 8 unrelated persons with intellectual and developmental disabilities, behavioral or mental health disorders, or who are over the age of 65 years old and need of special care due to physical conditions or infirmities. The group home includes up to 2 residential caregivers, and shall be licensed, operated, or owned by a governmental agency or non-profit qualified to provide care and supervision. Group homes shall not include interim care treatment or rehabilitation facilities, or other housing facilities serving as an alternative to incarceration.

*Residential Care – Limited.* A residential building or grouping or residential buildings used as the permanent residence of individuals that require a limited level of assistance, medical care, therapy, or supervisions for daily living activities, or where shared social and recreational activities provide a common amenity for residents. Support services are accessory to the residential use and character of the buildings, and do not require 24-hour staffing, other than security. Typical examples include assisted living, co-housing, group homes larger than 8 individuals or that otherwise do not meet the criteria for Group Home - Small, and retirement communities.

*Residential Care - General.* A residential or institutional building, or group of buildings, designed to provide a primary or interim residence and health care for persons who require care on a full-time basis. Meals, medical support, rehabilitative services, social and recreational activities are provided on site with facilities and professional staff. Typical examples include nursing homes, long-term care facility, treatment centers, continuing care facility, congregate care communities, or hospices.

*Residential Care - Institutional.* A residential or institutional building, or group of buildings, designed and operated to provide interim or temporary housing, twenty-four-hour care, and supervision for residents who are at risk or in need of special support services. Typical examples include halfway house, rehabilitative residence, protective housing, or shelters.

## B. Public / Institutional Uses

1. *Assembly.* An institutional or civic use designed to serve the community for regular or periodic events, including worship, civic, social, recreation, or entertainment, and accessory uses associated with organized activities, including child care, concession



services, education, and recreation events. They can be available to the public at large, by voluntary affiliation, or for private organizations limited by membership.

*Assembly – Limited (< 400 capacity and < 2 acre lot).* A place of public assembly designed and located to serve immediately adjacent uses and nearby neighborhoods, or be accessory to other uses and typically designed for less than 400 people. All buildings and facilities are located on a lot of less than 2 acres. Examples include a small neighborhood association clubhouse or recreation center, common meeting rooms or meeting hall, or small religious facilities.

*Assembly – General (400-800 occupants or 2 to 5 acres).* Places of public assembly designed and located to serve community or civic needs of a broad vicinity and typically designed for 400 – 800 people. All buildings and facilities fit on a lot or are arranged in a small campus of between 2 and 5 acres. Examples include a community/recreation center, small event hall or large religious facility.

*Assembly – Large (800+ occupants or 5+ acres).* Places of public assembly designed and located to serve community or civic needs of the Town or region and typically designed for more than 800 people. Buildings and facilities require large lots or campuses that are difficult to integrate into the surrounding block structure, are disruptive to connected development patterns, and require special siting and civic design considerations. Examples include an auditorium, large event hall, major worship hall or campus, or convention and conference center.

2. *Civic & Institutional Buildings.* The use of land and buildings to serve public or community interest through government or non-profit agencies through cultural, social, or education offerings, or for the administration operations of organizations providing these services.

*Government and Town.* A public use that supports the community at large by through public health and safety, protective or related services. Examples include police and fire stations, dispatch, and related facilities, or similar government and quasi-government buildings and grounds.

*Library, public.* A public facility for the use, but not sale, of literary, musical, artistic, or reference materials.

*Museum, cultural.* A building having public significance by reason of its architecture or former use or occupancy; or serving as a repository for a collection of nature, scientific, or literary curiosities, or objects of interest, or works of art, and accessory sales related to the subject matter or activities on the site (i.e. museum gift shop small scale sit-down restaurants or cafes).

*School.* Building or group of buildings designed to provide structured, seasonal or year-round education opportunities for the community. Schools are typically integrated into the surrounding context and development pattern as a civic amenity (whether single buildings or a campus), based on the scale of the facilities. Typical examples include elementary or secondary public or private schools, colleges and universities, or other special purpose or specific-need schools that have a course of study and education environment similar to that of public schools.

3. *Park and Open Space.* Any parcel or area of land or water unimproved with any residential, commercial, or industrial uses and dedicated or reserved for public and/or private use and enjoyment, or public lands managed by a public entity for the conservation or stewardship of resources. Specific uses and purposes include



agricultural, recreational, education, cultural, scenic or environmental purposes, and the land is characterized by open or natural landscape features.

*Athletic Field.* Land, often requiring equipment, owned by a unit of government and designed for outdoor games and sports such as lacrosse, baseball, football, and soccer.

*Recreation Center or Grounds.* A private or public facility for cultivation of fruits, flowers, vegetables, or ornamental plants by more than one person or household. Examples include a community gym, pool, club, golf course, or similar recreational facilities that serve as an organizing element or focal point for surrounding development.

*Park, Trail or Civic Space.* A public, common, or private open areas designed and used for both active or passive recreation. (See Section 3-2 for specific designs and types.)

4. *Utilities.* A service use owned by a governmental entity, or any entity defined as a public utility for any purpose by the state public utilities commission, and used in connection with the distribution, collection, or transmission of energy, water, sanitary sewerage, communication, or municipal services on a local level. All utilities may be further limited by site design and landscape standards of this code, or more specifically regulated and permitted by licensing agencies, franchise agreements, or specific conditions and design requirements of any easement authorizing the location of facilities. For the purposes of the development code, utility facilities are further classified as follows.

*Minor Utility Facility.* Small-scale facilities that provide utilities necessary to support development either within a specific sub-area of the Town or the immediate vicinity of the facility. This use typically involves the construction or installation of only minor structures. Employees typically are not located at the site. Examples include electric transformer stations; gas regulator stations; telephone exchange buildings; well, water, and sewer pumping stations, power lines; storm drainage facilities; pump stations and hydrants; switching boxes; and other structures to serve adjacent properties. A minor utility facility may be either a principal or accessory use of land, but does not include accessory facilities serving the customary needs of uses, buildings, and land in the zoning district through required improvements in easements, rights-of-way, or private service lines

*Major Utility Facility.* Large-scale facilities typically serving utilities to the region, the entire Town, or a significant sub-area of the Town, which normally entails the construction of new buildings or structures, and that often have employees at the site. Major utility facilities have potential major impacts on an area or Town by virtue of their appearance, noise, size, traffic generation, externalities, or other operational characteristics. Examples include water works, reservoirs, power or heating plants, energy/power transmission lines, power generating plants, and sewage or wastewater treatment plant.

### C. Agriculture Uses

1. *Agritourism.* The use of a farm or agricultural resources, process, or products for special events, retail and restaurant activities, or cultural promotion of agricultural heritage in typical agricultural structures or settings, and in association with maintaining and promoting the continued agricultural use and character of the building, property, or general vicinity.

*Roadside Stands.* A small retail operation selling agriculture products produced on or near a site, typically involving a small kiosk, tent or truck with temporary facilities, or on sites in more rural contexts it may include permanent structures.





*Farmers Market.* The use of a commercial farm or other permitted non-residential use or open and civic space for the periodic sale of produce from farms and other accessory products, which may include temporary, interim, or permanent structures to facilitate events

*Community Farm.* A small farm open to the public generally or periodically but on a regular basis for commercial or cultural purposes, such as events, sale of agricultural produce, dining utilizing primarily farm products, or tours that demonstrate agricultural process and practices.

2. *Farming.* A commercial use of property for planting, cultivating, harvesting and storage of grains, hay or plants, and/or the raising and feeding of livestock and poultry. The storage of crops, grains, feeds or other products shall be limited to those raised on or to be consumed on the premises.

*Farming – Limited.* The primary use of land for small-scale production of field crops or horticulture for food, or raising small animals where limited accessory storage facilities and light machinery is necessary and the land area is typically under 10 acres.

*Farming – General.* The primary use of land for commercial production of field crops for food or raw materials in other agriculture operations; the raising or breeding of livestock, poultry, fish or other animals; or plant production such as nursery, orchard, vineyard. The land area is typically over 10 acres.

*Farming – Large / Industrial.* A large-scale farming and agricultural processing operation where heavy machinery, storage of large quantities of byproducts or intensive animal operations occur, such as feedlots or the commercial feeding of offal or garbage to swine or to other animals, commercial production and sale of livestock, or other similar intensive operations.

#### D. Commercial Uses

1. *Animal Care / Sales.* Commercial service and retail uses that provide the sale, care, or boarding for domesticated animals that is further refined by the scale and intensity of the operations, as follows:

*Animal Care - Limited (< 3K, no boarding).* A small office or shop providing animal care or sales. The use involves less than 3,000 square feet of commercial area, and all activities occur indoors (except routine daily pet care), Examples include a veterinary office, small pet store, or small pet grooming or training,

*Animal Care – Small (3K – 8K or limited boardings).* An office or store providing animal care or sales, and where any overnight boarding is limited to that necessary for medical care or observation. The use involves less than 8,000 square feet of commercial space and limited outdoor activity areas necessary to accommodate the care animals. Examples include a veterinary clinic, large pet store, or large pet grooming or training.

*Animal Care – General (8K – 30K or boarding).* A large office or store providing animal care or sales, or any use offering routine daily care for animals, whether less than 24 hours or overnight boarding. The use involves between 8,000 and 30,000 square feet of commercial space, or all scales of daily animal care with indoor or outdoor space where multiple animals are cared for on a daily basis. Examples include a large pet store, large grooming or training facility, animal hospital, or any animal day care, kennel, or boarding service.



*Animal Care – Large (Outdoor or over 30K).* A large facility or grounds providing animal care, training, or boarding. The use involves over 30,000 square feet of commercial space, or is of a nature where a substantial amount of care, training, or boarding occurs in outdoor facilities. Examples include large animal hospitals, and large commercial/outdoor kennels, animal shelters, stables, or breeding facilities.

2. *Dependent Care.* A commercial use of nonresidential property for the care of a child away from his/her own home or for any adult in need of supervisory care, for any part of the 24-hour day. This does not include services accessory to schools, religious services, or employment activities, or licensed childcare home occupations accessory to a principal dwelling.

*Dependent Care – Limited (< 3K).* A dependent care use less than 3,000 square feet of commercial area, within a small building or in a portion of a mixed-use building.

*Dependent Care– General (3K –8K).* A dependent care use between 3,000 and 8,000 square feet of commercial area, typically within one moderate-sized building or in a portion of a larger mixed-use building.

*Dependent Care – Large. (> 8K).* A dependent care use with more than 8,000 square feet, typically within one large building or involving more than one building in a campus or multi-building complex.

3. *Entertainment & Recreation.* Commercial service uses engaged in the business of providing daily or regularly scheduled activities for entertainment, leisure, training and instruction, or recreation, offered to the to the public at large, through individual membership, or through group arrangements. This use type is further refined by the scale, format and intensity as follows:

*Entertainment & Recreation – Indoor / Limited (< 8K).* An indoor entertainment and recreation use that involves a building less than 8,000 square feet. Examples include a small bowling alley, billiard hall, a small theater, or dance or yoga studio.

*Entertainment & Recreation - Indoor / General (8K - 30K).* An indoor entertainment and recreation use that involves a building that is between 8,000 and 30,000 square feet or more. Examples include a small sports and recreation center, larger arcade or game center, or a moderate sized theater complex,

*Entertainment & Recreation - Indoor / Large (30K+ ).* An indoor entertainment and use that involves a building that is 30,000 square feet or more. Examples include a large bowling alley, a sports and recreation center, a large theater or theater complex, or skating rink

*Recreation/Entertainment – Outdoor.* Any outdoor entertainment and recreation use, where a commercial business offers the grounds use of patrons. Examples include racquet club, miniature golf, driving range, golf course, batting cages, sports and athletic complex, or band shell or amphitheater.

4. *Food & Beverage Service.* A specific service and retail use engaged in the business of serving prepared food and/or beverages to the public for immediate consumption. The serving of alcoholic beverages is accessory to this use but may be further regulated by business and liquor licenses. Whether the use includes drive-through facilities is regulated by the accessory use provisions and site design standards for the district and



street. Food & Beverage Service are further refined by scale, format and intensity based on the following:

*Restaurant – Limited (< 3K).* An accessory or small-scale restaurant under 3,000 square feet of commercial area, located in a small or mixed-use building or sometimes associated with other uses, such as a cafe, lunch counter, walk-up window or similar small retail sales food outlet.

*Restaurant – Small (3K – 8K).* A small-scale restaurant between 3,000 and 8,000 of commercial area, and typically includes separate kitchen dining facility, a accessory bar and entertainment areas.

*Restaurant – General (> 8K).* A moderate- or large-scale restaurant between 3,000 and 8,000 of commercial area, and typically includes separate kitchen dining facility, a accessory bar and entertainment areas, and may include accessory craft manufacturing or packaged retail sales of food and beverages.

5. *Lodging.* Commercial uses providing accommodations for temporary overnight occupancy on a less than monthly basis, and accessory uses associated with typical guest services such as food service, recreation or similar accommodations to support overnight-guests. Lodging is refined to the following scales based on building type, format, and intensity of use:

*Bed and Breakfast (up to 5 rooms).* A small residential building used for commercial short-term lodging with shared living space between the operator as the primary occupant and the patrons. The use includes no more than 5 bedrooms or 8 guests, and where meals may be offered to overnight guests for compensation.

*Inn (6 to 40 rooms).* A small commercial or large residential building providing short-term lodging and includes at least 6 but no more than 40 rooms.

*Lodging – Hotel / Motel General (40+ Rooms).* A large commercial building providing short-term lodging and includes 41 or more rooms.

6. *Marijuana Uses.* Uses involved in the production, distribution, prescription, or sale of cannabis as may be further described in the Colorado State Constitution or Colorado Revised Statutes.
7. *Medical Service.* Commercial services uses providing medical, dental, or physical health or wellness care to the public. This use type is further categorized by the following formats:

*Medical Service – Limited (< 8K).* A medical care use offering routine outpatient services, that occupies less than 8,000 square feet of diagnostic or treatment area, includes no surgical or in-patient facilities, and operates in normal business hours. Examples include a small doctor or dentist office, eye-care center, or urgent care center that is accessory to a larger retail or pharmacy use.

*Medical Service– General (8K – 30K).* A medical care use offering routine outpatient services, or provides diagnostic testing, laboratory services, and limited custom fabrication of medical supplies. The use occupies between 8,000 and 30,000 square feet for research, diagnostic, or treatment areas, includes no inpatient facilities, and operates in normal business hours. Examples include a larger doctor or dentist group practice, small clinic or analytical lab, or small outpatient urgent care or surgical center.



*Medical Care – Large (> 30K).* A medical care use offering a full range of services, that occupies more than 30,000 square feet for diagnostic or treatment areas, and may include emergency care, surgical services, or other inpatient treatment. The use may include accessory retail, food service, pharmacy or wellness/fitness uses. Examples include hospital, large clinic or analytical labs, regional medical campus or centers.

8. *Office.* Commercial uses focused on employment and engaged in the administrative, technical, or management aspects of business or professional services that typically do not have frequent or unscheduled on-premise interaction with the public or clients. Examples include accountants, lawyers, architects, engineers, insurance, or other professional or administrative services. Office uses are further refined by the scale and format of buildings based on the following:

*Office – Limited (< 8K or < 33% of mixed-use projects).* An office use less than 8,000 square feet of commercial area, within a small building or occupying a portion of a mixed-use building or site with a floor area of all non-residential uses is less than 33%, considering other uses in the building or on the site.

*Office – General (8K – 30K).* An office use between 8,000 and 30,000 square feet of commercial area, typically within one moderate-sized building.

*Office – Large. (> 30K).* An office use with more than 30,000 square feet, typically within one large building or involving more than one building in a campus pattern.

9. *Personal Service.* Commercial uses engaged in the business of providing personal or instructional services to the public that may include frequent or unscheduled interaction with clients or customers on-premises. Examples include a barbershop or beauty salon, travel agency, fitness services, tailor, repair of household goods, print shop, delivery outlets, bank, or personal financial services. Personal service uses are further refined by scale, intensity and format based on the following:

*Personal Service – Limited (< 3K or < 33% of mixed-use projects).* A personal service use less than 3,000 square feet of commercial area, within a small building or occupying a portion of a mixed-use building or site where all nonresidential uses have floor area less than 33%, considering other uses in the building or on the site.

*Personal Service– Small (3K – 8K).* A personal service use between 3,000 and 8,000 square feet of commercial area, located in a small building.

*Personal Service – Large (> 8K).* A service use encompassing more than 8,000 square feet, typically in a large-freestanding building or part of a large mixed-use project

10. *Retail.* Commercial uses primarily engaged in the sale, lease, or rental of products to the general public with frequent interaction of patrons or consumers on premises. Retail uses are further refined by scale, intensity, and format based on the following types:

*Retail – Limited (< 3K or 33% of mixed-use buildings / projects).* A small-scale retail use with under 3,000 square feet of commercial area, or occurring in a building where all nonresidential uses have floor area less than 33%, considering other uses in the building or on the site.



**Retail – Small (3K - 8K).** A retail use with at least 3,000 but less than 8,000 square feet of commercial area, typically located in a small building or a multi-tenant, mixed-use building.

**Retail – General (8K - 30K).** A moderate-scale retail use at least 8,000 but less than 30,000 square feet of commercial area, typically located in a moderate free-standing building or a large multi-tenant or mixed-use building.

**Retail – Large (> 30K).** A large-scale retail use with at least 30,000 square feet of commercial area. in a large-freestanding or part of a part of a large mixed-use project.

**Retail – Outdoor & Equipment Sales.** A specific retail use where the primary business is associated with merchandise that typically must be displayed outside and on a year-round basis. Examples include a garden center, a greenhouse / nursery, a lumber yard, or a small machine or equipment sales.

11. **Retail – Grocery Store.** A specific retail use selling food, produce, and household products for general household consumption, including a significant portion of inventory in fresh produce, baked goods, meats, or seafood. Accessory sales of prepared food for on-site consumption is limited to no more than 20% of the transactions. These uses often serve as a key anchor for neighborhood and community centers which justifies slightly larger scale than other general retail uses, provided they can still fit into the block structure, development pattern, and public-realm framework of the area. To accommodate this, Retail Grocery Store is further refined by scale and format as follows:

**Grocery – Small (< 8K).** A small grocery offering limited selection of products or specialty foods or produce in a small-scale format under 8,000 square feet. Examples include a corner store, butcher shop, produce market, or other specialty market.

**Grocery – General (8K – 30K).** A mid-sized grocery offering a range of food and household products, and limited accessory services in a mid-sized building format, at least 8,000 square feet but less than 30,000 square feet. Examples include a neighborhood market, urban-format groceries

**Grocery – Large (> 30K).** A large grocery store offering a wide range of food and household products and associated accessory services in a large-scale format. Examples include a conventional full-service grocery store, large-format grocery or supermarket, or a similar function housed within a larger warehouse retail store.

12. **Vehicle & Equipment Uses.** Commercial uses that include the sale, rental, or maintenance of motor vehicles or similar large-scale equipment which have a scale or format oriented to the vehicles and large equipment, typically including large parking areas, and outdoor storage or circulation of vehicles and equipment. Use types include:

**Gas Station -Limited (1 - 8 pumps).** A commercial use designed to supply motor vehicles with gasoline or other fuel source, oils, greases, and may involve limited accessory sales of convenience goods. This use may be combined with accessory vehicle service and repair uses, subject to the service bay limitations stated below. A limited vehicle gas station includes no more than 8 fueling stations, no more than 2 service islands, no more than 2 accessory vehicle service bays and no more than 1,500 square feet of accessory retail or service areas. Examples include small, neighborhood service stations.

**Gas Station -General (9-17 pumps).** A vehicle gas station limited to between 9 and 16 fueling stations, no more than 4 service islands, no more than 3 accessory vehicle





service bays and no more than 3,000 square feet of accessory retail or service areas. Examples include general stores and gas stations.

*Gas Station - Large (17+ pumps).* A vehicle gas station that contains more than 16 fueling stations, more than 4 islands, and up to 4 accessory vehicle service bays and no more than 8,000 square feet of accessory retail or service areas. Examples include a large convenience center and gas station, or truck stops and travel centers.

*Automobile Repair – Limited.* A commercial use engaged in the repair and maintenance of automobiles, motorcycles, trucks, trailers, or similar vehicles, not including body or fender work. Minor paint or decorative wrap work may be included, however, not including a full paint booth.

*Automobile Repair - Body Shop.* A commercial use designed for service, repair, and restoration of vehicles, including major repairs, paint, and body work.

*Automobile, RV, or Equipment Sales / Rental.* A commercial use designed for the display, sale, leasing, or rental of new or used motor vehicles, recreational vehicles, boats, or similar large equipment. Any repair or service work is accessory to the sale, leasing or rental of operable vehicles and equipment.

*Car Wash and Automobile Detailing.* A commercial service use that washes, cleans, or refurbishes motor vehicles, whether through self-service, mechanical service, or personal service, and whether as a principal use or an accessory use to another commercial use.

#### D. **Manufacturing / Industrial Uses**

1. *Industrial Services.* A business engaged in service to other businesses and industries, or engaged in services to the general public but where industrial equipment or processes are necessary for service, or where services are dispatched from a central location for storage of vehicles, equipment, or merchandise. Examples include plumbing, exterminators, HVAC repair, utility contractors, janitorial services, commercial laundry services, or other similar business.

*Contractors Office or Fleet Services.* A small, centralized location for industrial service uses, where administrative offices, dispatch services, and limited on-site storage of equipment and fleet vehicles can occur during non-business hours.

*Industrial Services – Light.* A small-scale or low-impact industrial service use with limited outdoor storage needs, where surface parking, vehicle storage, and general storage needs are similar to other industrial or commercial uses, and where areas dedicated to storage of equipment and vehicles during non-business hours can occur indoors, or in well-screened areas.

*Industrial Services – Heavy.* A large-scale industrial service use which may produce a higher degree of adverse impacts (e.g. noise, glare, dust, odor, or vibrations), or which may need substantial outdoor storage, large warehouses, or significant parking and storage for vehicles or equipment.

*Vehicle / Fleet Maintenance Facility.* An industrial service use that provides mechanical and repair services to commercial vehicles, large equipment, or other similar services, whether the service is offered to other business with large vehicles and equipment or whether it is accessory to the business maintaining its own fleet and equipment.



2. **Manufacturing.** A use engaged processing, fabrication, packaging, or assembly of goods, from raw materials or partially completed secondary materials. Products may be finished or semi-finished, and are typically stored and shipped to other areas for distribution to businesses, consumers or retail outlets, although limited accessory sales, display, or customer service areas may be provided.

**Manufacturing – Limited / Artisan.** A small-scale manufacturing use producing primarily finished products with limited need for storage of materials or finished products. The use produces no negative byproducts such as smoke, odor, dust or noise discernable from outside of the building, and deliveries and distribution are made by general commercial delivery services requiring no special large truck access. Products or services are often made available to the public on premises generating customer activity. Examples include artists' studios, small bakery, brewpub, or small wood or metal shops.

**Brewery, Distillery, or Winery.** Any establishment, licensed by the appropriate State and Federal authorities, where malt liquors, fermented malt beverages, spiritous liquors, and vinous liquors are manufactured. This does not include and is distinct from accessory craft food and beverage manufacturing, which is accessory to a permitted restaurant use. However, this manufacturing use may include accessory retail, tasting, or restaurant uses.

**Manufacturing – Light.** A manufacturing use that produces little or no byproducts such as smoke, odor, dust, or noise discernable from beyond the property; limited outside storage may be necessary, and distribution and delivery or distribution needs require occasional large truck access. Examples include research labs or facilities, small equipment or commodity assembly, non-retail laundry services, commercial bakery, or food and beverage processing.

**Manufacturing – Heavy.** An industrial manufacturing use, where raw and other materials are made into other materials or finished products. The activities may produce byproducts such as noise, dust, smoke, or odor, but are mitigated to limit impacts beyond the property boundary. Outside storage and activities may be necessary, and distribution and delivery needs involve frequent or large truck access. Examples include large-scale manufacturing or fabrication plants, large equipment assembly, metal fabrication plants, chemical laboratories or other similar high-intensity manufacturing or distribution operations.

3. **Warehousing / Storage.** An industrial or commercial use involved in the temporary keeping of goods and products for interim or long-term periods and for distribution to other businesses and industries, including any logistic services related to this business such as labeling, bulk packaging, inventory control, or light assembling. This use may support their own business, or be offered as a service to other businesses in the chain of production..

**Wholesale – Sales & Distribution.** An establishment primarily engaged in the sale or distribution of goods and materials in large quantity to retailers or other businesses for resale to individual or business customers, or the sale, storage, and delivery of large items directly to customers from distribution centers.

**Indoor Storage.** A storage use where all activities occur indoors except for the limited loading and unloading of goods at discrete loading docks. Examples include indoor self-storage and long-term garages.



**Outdoor Storage.** A storage use where all or a portion of the storage of materials or products occurs outdoors. Examples include boat or RV storage, towing service storage yard, and industrial supply storage yards.

**Fuel Storage.** Industrial-scale storage of fuels as a principal use of land in above ground or below ground storage containers designed for wholesale distribution or mass consumption.

4. **Waste / Salvage.** A use that receives solid or liquid wastes for disposal on site, or for storage and processing for further distribution of disposed items. Specific use types include:

**Automobile Wrecking / Salvage Yard.** A business engaged in wrecking and dismantling, storage, sale, or dumping of dismantled, obsolete, or wrecked vehicles.

**Hazardous Waste Handling.** A facility where the principal use is to collect, store, or processes waste that is ignitable (combustible or flammable), corrosive, reactive (explosive), or toxic and requires special handling to avoid illness or injury to persons or damage to property or the environment, or any other manufacturing or industrial use where the process or byproducts could produce these hazards and otherwise needs to be contained and treated to protect the general public health and safety.

**Recycling Operation, Enclosed or Unenclosed.** A facility that collects, stores, process and distributed waste materials that can be treaded and returned to a condition in which they may again be used for production or consumption. Recycling operations may be “enclosed” where all activities other than remote and discrete loading areas are indoors, or they may be unenclosed, where a portion of the collection, storage, or processing occurs outside.

**Waste Transfer Station.** A facility or structure where trash is collected, including appropriate structures and mechanical equipment for the collection, compaction, and/or loading of trash.

## 17-11-2 Defined Terms

All terms used in this code shall have their plain and commonly accepted meaning, based upon the context of their use in the code. The following terms shall have the meaning given below, unless more specifically described, limited or qualified within the standards of this code. Some Articles have specific definitions where the terms have the given meaning for interpretation of that article.

**Accessory Building, Structure or Use.** A building, structure or use located or conducted upon the same lot (or on a contiguous lot, under one deed, in the same ownership) as the principal building, structure or use to which it is related, and which is clearly incidental and subordinate to and customarily found in connection with the principal building or use.

**Alley.** A public or private way at the rear or side of the property, permanently dedicated as a means of vehicular access to the abutting property and generally having less width than a street.

**Appeal.** A review of a final decision by a higher authority according to the standards and procedures of this code, or as otherwise allowed by other laws.




**Applicant.** The owners or lessees of property, their agent, or persons who have contracted to purchase property, or the city or other quasi-governmental entity that is proposing an action requiring review and approval by one or more of the sections in this title. An applicant may subsequently become the Developer once approval is granted and, in this case, the terms shall be interchangeable.

**Art.** All forms of original creations of visual art, including, but not limited to, sculpture; mosaics; painting, whether portable or permanently fixed, as in the case of murals; photographs; crafts made from clay; fiber and textiles; wood; glass; metal; plastics; or any other material or any combination thereof; calligraphy; mixed media composed of any combination of forms or media; unique architectural styling or embellishment, including architectural crafts, environmental landscaping; or restoration or renovation of existing works of art of historical significance. Works of art are not intended to be used for commercial advertising purposes.

**Basement.** The portion of a building between floor and ceiling which is entirely below grade, or partly below and partly above grade but so located that the vertical distance from grade to the floor below is more than the vertical distance from grade to ceiling.

**Block.** A group of platted lots and tracts connected as a distinct subset of the development pattern, and surrounded by streets or by other features that interrupt the street network such as parks, railroad rights-of-way, or municipal boundary lines; or the perimeter of all lots fronting on the street in the case of a cul-de-sac.



**Block face.** All lots on one side of a block and fronting on the same street.

**Buffer.** An area of a site used to promote separation and enhance compatibility between land uses of different intensities, and using space, landscape, or the arrangement of buildings and structures, or any combination of these to create separation or mitigate impacts.

**Building.** Any structure built for the shelter or enclosure of persons, animals, chattels, property or substance of any kind, excluding fences. The word *building* includes the word *structure*.

**Building Floor Area.** The maximum horizontal area within the outer perimeter of the building walls.

**Building Footprint (building coverage).** That area or portion of a lot which is occupied or covered by all buildings on that lot.

**Building, Detached.** Any single building or building separated from another building on the same lot.



**Building, Enclosed.** A building separated on all sides from adjacent open space or other buildings by fixed exterior walls or party walls, with opening only for windows and doors, and covered by a permanent roof.

**Building Frontage.** The area of the lot along the front building line, and when referring to design standards it may include relationship between this area, the streetscape, and the primary facade of the building.

**Building Frontage, Principal.** The horizontal linear dimension which is designated as the primary facade of that portion of a building occupied by a single use or occupancy for the purposes of allocating signs and other design requirements.

**Building Frontage, Secondary.** That dimension of a building abutting a public right-of-way other than the principal building frontage for the purposes of allocating signs and other design requirements.

**Building Height.** The vertical distance from the grade level at the main entrance of a building to the top of the parapet that comprises the majority of the perimeter of the building for a flat roof; or to the mean/average height between the eaves and ridges for pitched roofs. In instances where substantial grading occurs to prepare a site the pre-existing grade or comparable grade in relation to the street may be used. In instances where buildings are integrated into the existing grade, the average grade along the building frontage may be used. In addition to height design standards and story heights may be used to address the relative scale and massing of buildings (See Section 11-3 Design & Architecture Terms)

**Building Line.** The actual line at which a building is constructed, and the location of other elements on the lot or adjacent lots may refer to this line extended outward from the building to the sides of the lot.

**Building Line, Required Front.** The portion (usually expressed as a percentage) of the lot frontage required to be occupied by the front facade of a principle structure, or other specifically permitted substitutes which may include accessory structures or landscape associated with the frontage design.

**Building, Principal.** One building housing the principal (primary or most important) uses permitted for the lot upon which it is located.

**Building Setbacks.** The minimum required distance between any property line and the building or structure. When front building setbacks are expressed as a range (i.e. 10' to 25'), it shall be interpreted as a front build to" range, within which distance the front building line of the principal structure shall be established.

**Building Types.** A range or specific category of buildings that share common physical attributed in terms of lot size, lot coverage, height, and building form, scale, or massing. Building types may also be grouped by other attributes that ensure they function or are operated in a compatible manner as other buildings in the vicinity, but are primarily addressing physical compatibility.

**Canopy Tree.** A large deciduous (foliage that sheds annually) woody plant that normally grows with a main trunk and has a mature height of 30 feet or more and where the understory is clear of branches and leaves below 10 to 15 feet, resulting in shaded usable areas during spring and summer months, and sunlit useable areas during fall or winter months.

**Change of Use.** A use that substantially differs from the previous use of a building or land and which may affect such things as parking, drainage, circulation, traffic, landscaping, building configuration, utility demands, noise, or lighting. A change of ownership which does not include any of the factors listed above shall not be considered a change of use.

**Clearance.** The vertical distance from the lowest point of an overhead object to the highest point of the ground or sidewalk directly below the object.





**Comprehensive Plan.** The Johnstown Comprehensive Plan, as amended. The Comprehensive Plan may include any other plans, policies, or programs officially adopted or approved by the Town under the guidance of that plan, including the Town’s Three Mile Area Plan.

**Construction Sign.** A temporary sign announcing construction, remodeling or other improvements of a property.

**Coverage, Lot.** Land area which is covered with impervious surfaces, such as buildings, patios, or decks with roofs, carports, swimming pools, tennis courts, or land area covered by any other type of structure, including parking lots.

**Density.** The total number of dwelling units on a property, divided by the gross area in acres of such property. Density is typically used to measure planning impacts on broad areas, but is not appropriate for measuring the scale or intensity of development on a particular lot. (See Building Types.)

**Design Standards.** References the current adopted Johnstown Engineering Specifications and Design Standards, which may also be commonly known as the Standards and Specifications.

**Developer.** Any person, partnership, joint venture, association, or corporation or other legal entity who or which shall participate as owner, promoter, designer, builder, or sales agent in the planning, platting, development, promotion, sale, or lease of a subdivision. Interchangeable with “Applicant” for the purposes of this code.

**Development.** The activity of initiating a change of landscape, buildings, access, use, or operation on a property through activities such as grading, filling, paving, excavating, construction, erection, repair, or rehabilitation of or to existing physical elements of property.

**Development Pattern.** The physical layout of blocks, streets, open spaces, lots and uses where common attributes or associated elements define distinct areas of the community by the scale, intensity, or other physical barriers or transitions.

**Drive-through, Accessory.** An accessory site design and building design component of any business in which the provision of services or the sale of food or merchandise to the customer in a motor vehicle without the need for the customer to exit the motor vehicle. This definition includes, but is not limited to, bank drive-up tellers and drive-through fast food restaurants.

**Driveway.** An improved concrete or asphalt path, or other area dedicated to vehicle access to a site or leading directly to one or more Town-approved parking spaces or parking spaces on a lot or within a building.

**Dwelling:** Any building or portion of building that is used as the residence of one or more households, but not including visitor accommodations, clubs, hospitals, tents, or similar uses providing transient or temporary accommodation.

**Dwelling Unit.** One or more rooms and a single principal kitchen and at least one bathroom, designed, occupied, or intended for occupancy as separate quarters for the exclusive use of a single household, for household living purposes (i.e., living, cooking, and sanitary purposes), located in a dwelling.

**Dwelling Unit, Accessory.** A dwelling unit that is subordinate, incidental to, and on the same lot as a principal dwelling unit.

**Easement.** A right granted by a property owner permitting a designated part of interest in the owner’s property to be used by others for a specific use or purpose.



**Household.** An individual; 2 or more individuals related by blood, marriage, or legal adoption or guardianship; or a functional household when three or more individuals are not so related, and living as a single housekeeping unit sharing a dwelling. For purposes of this Chapter, a functional household is one that shares the living spaces of a dwelling unit, shares household duties, and regularly shares meals; in contrast, a group of multiple individual households living together may employ individual or non-concurrent leases, lock-out bedrooms; separate entrances; distinct private vs. common areas; or each buying their own groceries.

**Façade.** The exterior face of a building.

**Family.** See *Household*.

**Flag.** A type of sign, typically displayed on a piece of fabric, with a distinctive design.

**Frontage.** The area of a lot between the front building line and the front lot line that establishes the primary relationship between the building and site and the public streetscape.

**Grade (adjacent ground elevation).** The average elevation of the graded surface of the ground, paving or sidewalk adjoining the base of a structure, in all directions.

**Green.** A larger civic gathering space that is primarily landscaped area with formal designed spaces for trails, seating, performance, or other pedestrian activity.

**Greenway.** A strip of undeveloped land, in an urban or rural area, set aside for recreational use or environmental protection.

**Gross Leasable Area (GLA).** The area of a building that can be leased to tenants, including storage areas and common areas apportioned to the number of tenants sharing the area. Gross leasable area shall be measured in the same manner of gross floor area, but is apportioned to specific uses or tenants in the building.

**Ground Cover.** Materials that typically do not exceed one foot in height used to provide cover of the soil in landscaped areas, which may include a combination of, but not limited to river rock, cobble, boulders, concrete pavers, grasses, flowers, low-growing shrubs and vines, and those materials derived from once-living things, such as wood mulch. In no event shall weeds be considered ground cover.

**Hazard.** A source of danger to persons or damage to property.

**Height.** Sign height is generally measured from the existing lowest grade directly below the sign. The average grade of all areas directly below the sign may be used, provided the high and low point do not have a differential greater than 10 feet; otherwise the elevation 10 feet above the lowest grade shall be used.

**Home Occupation.** A business conducted accessory to and within a residence and subject to other standards and procedures of this code to ensure that it is subordinate and customarily incidental to the residence.

**Illuminated Sign.** A sign lighted by or exposed by artificial light.

**Landscape Area.** Land set apart for the planting of grass, shrubs, trees, or similar living plants. Such land may include trees and plants arranged in a formal pattern to support outside gathering and include other constructed elements such as a plaza, pedestrian area, fences, walls or nonorganic displays integral to the design of the space.



**Lot.** A parcel of land, established by a subdivision plat, having the required minimum dimensions, which shall be located on either a public right-of-way or on a legal and perpetual access and which is occupied or designed to be occupied by one or more principal buildings, structures, or uses. (See Outlot, Parcel, and Tract)

**Lot Area.** The area bounded by the front, rear and side lot lines, or when expressed as a range, it shall be interpreted as a minimum and a maximum.



**Lot Depth.** The horizontal distance between the front and rear lot lines measured at right angles to the front right-of-way lines. Where the front and rear lines are not approximately parallel, the lot depth shall be the average when measured from at least three different points along the front lot line, including the two corners at the front lot line.

**Lot Frontage.** The portion of the lot that establishes the relationship between the building or site and the public realm or street upon which the lot fronts.



**Lot Line.** A line dividing one lot from another lot or parcel, or from a street or alley.

**Lot Line, Front.** The property line dividing a lot from a street or public or common space on which the building and lot orients. On a corner lot, generally the shorter street frontage shall be considered as a front lot line, except that the context of the block and abutting lots may allow the following arrangements:



- **Standard Corner.** The building orients to the same front as all other buildings on the same street, and an expanded side setback applies on the other street side of the lot. Side and rear setbacks apply to the remaining sides.
- **Reverse Corner.** The building orients to the end-grain of the block (not the same as other buildings on the interior of the block), and the front setback and frontage design applies to that street. The other street-side setback is the greater of (a) the stated street-side setback for that building type or (b) 10 feet in front of the forward-most point of the front building line of the abutting lot. Side and rear setbacks apply to the remaining sides.
- **Corner Orientation.** The building orients to both streets, with the front setback and frontage design applying on both street sides. The two remaining lot lines are treated as side setbacks and there is no rear setback.



Standard Corner



Reverse Corner



Corner Orientation



**Lot Line, Interior Side.** A side lot line which is adjacent to a side lot line of another lot.

**Lot Line, Rear.** The line opposite the front lot line. Where the side lot lines meet in a point, the rear lot line shall be assumed to be a line not less than ten feet long, lying within the lot and parallel to the front lot line.

**Lot Line, Side.** Any lot lines other than the front or rear lot line.

**Lot Line, Street Side,** A side lot line which separates the lot from a street.

**Lot Width.** The horizontal distance between the side lot lines, typically measured at the front lot line, but for irregular lots it may be measured at the front setback line.

**Marijuana or Recreational Marijuana.** All parts of the plant of the genus *cannabis*, whether growing or not, the seeds thereof, the resin extracted from any part of the plant and every compound, manufacture, salt, derivative, mixture or preparation of the plant, its seeds or its resin, including marijuana concentrate. Marijuana includes marijuana products as defined herein. Marijuana does not include industrial hemp, nor does it include fiber produced from the stalks, oil or cake made from the seeds of the plant, sterilized seed of the plant which is incapable of germination or the weight of any other ingredient combined with marijuana to prepare topical or oral administrations, food, drink or other product.

**Natural Area.** Aquatic or terrestrial habitats or areas which exist in their natural condition, and which have not been significantly altered by human activity or which have been restored to as close to their natural condition if disturbed previously by human activity.

**Natural Feature.** Features which give an area its general appearance and ecological character and which attract or support the wildlife species that use or inhabit the area.

**Nonconforming.** A condition of property which was lawfully established or constructed prior to the effective date of this Chapter and which does not conform to the requirements of these regulations.

**Nuisance.** Activity which arises from unreasonable, unwarranted or unlawful use by a person of his or her own property, working obstruction or injury to a right of another or to the public and producing such material annoyance, inconvenience and discomfort that the law will presume resulting damage.

**Official Zoning Map.** The Town's official graphic record of the boundaries of zoning districts, as it may be amended from time to time, and containing other information as specified in this Chapter.

**Open Space, Common.** A common area permanently set aside for the common use and enjoyment of residents or occupants of a development or members of a homeowners' association, which open area may be landscaped and/or left with natural vegetation cover and which may include swimming pools and other recreational leisure facilities; areas of scenic or natural beauty and habitat areas; hiking, riding, or off-street bicycle trails; and landscape areas adjacent to roads which are in excess of minimum required rights-of-way.

**Open Space, Private or On-lot.** An outdoor area not intended for habitation, directly adjoining a dwelling unit or building, which is intended for the private enjoyment of the residents or occupants of the adjacent dwelling unit or building and which is defined in such a manner that its boundaries are evident. Private or on-lot open space may include lawn area, decks, balconies, and/or patios.

**Open Space, Required.** That portion or percentage defined by the zoning standards of a lot required to be open and unobstructed. The area must not be covered by any structure or impervious surface, such as sidewalks or driveways, with the exception of required amenities, identity features, or useable open space required pursuant to this code.



**Open Space, Usable.** That portion of a lot or site available to all occupants of the building or site for recreational and other leisure activities that are customarily carried on outdoors.

**Ornamental Tree.** A small deciduous tree planted primarily for its ornamental value or for screening and which will typically be smaller than a canopy tree approximately 15 to 30 feet in height.

**Outlot.** A parcel or parcels of land designated on a plat and intended to be further subdivided before development at some point in the future, but which may be initially created under single ownership through a subdivision process. (See Lot, Parcel, and Tract)

**Parcel.** A unit or contiguous units of land used by the county assessor to identify taxable property, typically referring to unplatted land, in the possession of, or recorded as the property of one person, partnership, joint venture, association or corporation, or other legal entity. (See Lot, Outlot, and Tract)

**Park.** Any dedicated and accepted public or private land available for recreational or scenic purposes.

**Patio.** An unenclosed paved area typically used for seating in a side or rear yard, accessory to a structure.

**Porch.** A roofed or unroofed open structure projecting from the front, side or rear wall of a building and serving as a primary or secondary entrance into the building.

**Primary Entrance.** The entrance to a building or structure which is intended to be the main pedestrian or public entrance and which shall typically be located on the front of the building or structure, and therefore includes enhancements and human-scale details to show the priority and importance of the space to the public.

**Principal Building, Structure or Use.** A primary permitted building, structure or use of land as specified in the district regulations of this Chapter, other than an accessory building, dwelling or use or special use.

**Private Streetscape.** Access and internal circulation within a site and typically used to organize, break-up, and create transitions within larger sites through transportation and urban design elements that mimic the appearance and function of public streetscapes.

**Replacement Value.** The amount it would cost to replace a structure or restore a site to its previous condition considering all aspects of the investment at their current market costs. This amount may be based on estimates or where discrepancies exist the average of three independent estimates, in the sole discretion of the Town.

**Shrub.** A woody plant which consists of a number of small stems from the ground or small branches near the ground and which may be deciduous or evergreen.

**Sidewalk.** A paved, surfaced, or leveled area, parallel to and usually separated from the street, used as a pedestrian path, or which otherwise provides pedestrian circulation and access to important destinations and principal building entrances within a site.

**Sign.** Any advertisement, announcement, or direction of communication produced in whole or in part by the construction, erection, affixing or placing of a structure, or produced by painting on or pasting or placing any printed, lettered, pictured, figured or colored materials on any building, structure or surface; provided, however, that signs placed or erected by the Town or the State for the purpose of showing street names or traffic directions or regulations or for other municipal or government purposes shall not be included herein. Not to include public art or murals – see Art.





**Sign, Abandoned.** A sign which advertises or identifies an out-of-business, moved, or non-existing business, service, or other use of premises.

**Sign, Freestanding.** A sign which is supported by its own structure not associated with a building.

**Sign, Monument.** A sign supported by or mounted directly upon the ground by a base that is integral to the entire sign structure and incorporates the sign.

**Sign, Portable.** A sign that is not permanently affixed to a building, structure, or into the ground, but which have a durable design and stable support to allow placement of the sign on an interim or more permanent basis than temporary signs.

**Sign, Temporary.** A sign which is not intended as a permanent sign and which is easily relocated or removed.

**Sign, Wall.** A sign incorporated in, painted on, attached to or erected against the facade of a building.

**Sign, Window.** A sign painted on or applied to a window.

**Square.** A civic gathering space with direct pedestrian access to a street or streetscape, with a mix of formal and landscape elements.

**Story.** The part of a building included between the surface of one floor and the surface of the floor next above, or if there is no floor above the ceiling above. Story heights shall generally be 9 to 10 feet except the following guidelines can be used to address the effective scale and massing of buildings within permitted heights. (See Building Height);

- The first story for residential buildings should be 9 feet to 14 feet;
- The first story in non-residential buildings should be 12 feet to 20 feet;
- Building types or parts of buildings that require high floor-to-ceiling heights, such as a gymnasium, atrium or warehouse, shall have the number of stories calculated as: the finished floor-to-ceiling height divided by 15.
- Any ground story that has more than 4 feet of its height exposed above finished grade along more than 50% of the foundation perimeter shall count as a story.
- A half-story is the space under a sloping roof that has a line of intersection of the roof and exterior wall face not more than 2 feet above the floor level, and where the possible floor area with head room of 7 feet or more is no greater than 60% of the total floor area of the story directly beneath.

**Street** means a public thoroughfare, dedicated or deeded, for the purpose of providing a principal means of access to abutting property.

**Street, Design Type.** A reference to the design attributes of a specific segment of the street, regardless of the functional class, and including lane widths, number of lanes, parking, streetscape, and sidewalks. Street design types allow the design of segments of streets to transition and relate better to the context and anticipated abutting land uses, without disrupting the overall role of the street in the functional classification system.

**Street, Functional Classification.** A system of categorizing streets based on their role in the overall street network, considering traffic volumes, traffic speeds, and continuity of the street. These include arterial, collector, and local.

**Street Frontage.** The property line which abuts a public right-of-way.



**Street Tree.** A tree planted in close proximity to a street in order to provide shade over the street and to soften the street environment, typically a canopy tree although ornamental trees may be substituted in specific circumstances.

**Streetscape.** The scene that may be observed or the area designed for activity along a street, including both natural and non-natural components, including vegetation, buildings, paving, plantings, lighting fixtures and miscellaneous structures.

**Structural Alteration.** Any change in the support members of a building, such as bearing walls, columns, beams or girders.

**Structure.** Anything constructed or erected, including a fence, sign or building, with a fixed location on the ground.

**Temporary.** For a limited period of time, not permanent.

**Tract.** A parcel of land platted in a subdivision for a specific purpose, which shall be shown on the face of the plat. Specific purposes may include, but are not limited to, drainage areas, stormwater detention or retention areas, parks, open space, or land areas reserved for other public facilities. (See Lot, Outlot, and Parcel)

**Transparency.** When referring to the design of building facades, transparency is the percentage of windows and doors on the façade, intended (1) to break up the scale and massing of the façade and relate the building to the streetscape and public spaces; and (2) to provide connections – visual and perceived – between the activities on the site and the public streetscape or spaces. Therefore, transparency has two measurements: (1) the extent of transparency, which is the percentage of the overall façade, measured at each story but which includes non-transparent components associated with the opening such as molding, casing or frames; and (2) the degree of transparency, which is typically the clarity of the glass used for the opening. A door may count to this requirement if at least 25% of the door or door assembly meets the clarity requirement with windows in the door, or transom or side light doors alongside of the door. The clarity of the glass in the opening is met by a minimum Visible Light Transmission of 60% (VLT = the percent of total visible light that is transmitted through a glazing system) and a maximum Visible Light Reflectance of 15%. (VLR = the percent of total visible light that is reflected by a glazing system) For upper story windows, these measures may be 40% VLT and 20% VLR.

**Yard.** That portion of the open area on a lot extending open and unobstructed from the ground upward from a lot line to a principal building.

**Yard, Front.** That portion of a lot extending across the full width of the lot between the front lot line and the nearest line or point of the principal building.

**Yard, Rear.** That portion of a lot extending across the full width of the lot between the rear lot line and the nearest line or point of the principal building.

**Yard, Required.** That portion of the open area on a lot extending open and unobstructed from the ground upward from a lot line for a depth or width specified by the regulations for the zone district in which the lot is located.

**Yard, Side.** That portion of a lot extending from the front yard to the rear yard between the side lot line and the nearest line or point of the principal building.



### 17-11-3 Design & Architecture Terms

This section is a glossary of architecture and design terms explains concepts, strategies, and techniques that are used to affect building and site design.

A. **Architectural Style.**

When used generally, architectural style refers to a distinctive manner of expression, fashion or composition of building elements at a specific time.

When used specifically, architectural style refers to a prevalent or historical style that is documented with common or typical patterns in assembling building elements and form, and where variations within the style follow common rules of application for materials, massing or composition of the details. (i.e. Art Deco, Colonial Revival, Craftsman, Mid-Century Modern, Mission, Spanish Colonial Revival, Tudor Revival, Victorian, etc. See *Colorado's Historic Architecture & Engineering Guide*, [www.historycolorado.org/colorados-historic-architecture-engineering-guide](http://www.historycolorado.org/colorados-historic-architecture-engineering-guide) )

B. **Building Elements.** Buildings are made up of vertical elements, horizontal elements, details, and ornamentation that break up the building elevations into distinct components and establish the form and scale of the building. Building elements include:

1. **Awning.** A sloped or rounded framed projection attached to a wall and extended over a window or door to provide protection from the elements.
2. **Bay (window).** A bump out in the facade typically associated with an element of the interior floor plan but located to provide balance and relief to the massing on the exterior facade. A bay is usually associated with a window.
3. **Belt Course.** A continuous row or layer of stones, brick or other primary building material set in a wall and in line with changes in stories, changes in materials, or window sills. Belt courses make a visually prominent horizontal line to break up a wall plane by using a distinct material and/or implementing a pronounced and distinct pattern of the material.
4. **Bracket.** A projecting support placed under an eave or other projection with design qualities and details that add emphasis to the roof structure or massing element.
5. **Canopy.** A flat roofed projection attached to a wall and extended over a window, door, or walkway, or a freestanding structure over walkway or service area that gives protection from the elements.
6. **Clerestory Window.** A window high on a wall section above eye level and used to permit light or air into areas that otherwise do not have windows due to functional constraints of the building.
7. **Column.** A supporting pillar, especially one consisting of design qualities and details that add emphasis and ornamentation to a portion of the facade, or any roof structure or area it supports.
8. **Cornice.** An ornamental topping projecting from the wall with design qualities and details that crowns a structure along the top near the roof, with an emphasis that is compatible with but more elaborate than other similar details and ornamentation on the building.
9. **Eaves.** An overhang of the roof structure, where larger eaves can increase the prominence of the roof as a “cap” to the building and protect portions of the facade (particularly windows) from the elements.
10. **Entry Feature.** A structural component of the building or building footprint used to emphasize and add interest to the entry into the building, provide active social space protected from elements, contribute human scale to the building elevation, and create transitions from public to private space.
11. **Facia.** The exposed vertical edge of the roof often with design qualities and details that add emphasis and ornamentation to the roof structure.



12. **Foundation.** The base upon which the entire structure sits, designed with stronger, heavier materials, and often includes details and ornamentation to emphasize a building's connection to the ground, a sense of permanence, and transition to the main wall plane for vertical articulation.
  13. **Gable.** The triangular and vertical portion of a wall plane between intersecting roof pitches.
  14. **Lintel.** A horizontal beam, typically over a door, window or storefront to support the structure above it and add accent to the door, window, or storefront.
  15. **Parapet.** A vertical extension of the wall plane above the roof, typically used to hide a flat or low-sloped roof and the rooftop equipment, or function as a firewall for attached structures, and usually including ornamentation to provide a visually prominent “cap” to the building.
  16. **Pediment.** A gable or ornamental tablet or panel, typically triangular or arched, placed above a point of emphasis on a facade and often supported by columns or pilasters.
  17. **Pilaster.** A projecting vertical element on a wall plane used to give the appearance of a supporting column and used to articulate the extent of a wall plane or other component of a facade.
  18. **Sidelight.** A window with a vertical orientation along an opening (door or window) that is narrower than the opening but provides emphasis to the importance of the opening with expanded transparency, additional trim and ornamentation, or other architectural details.
  19. **Transom.** A window above an opening (door or window) built on a horizontal crossbar that may provide light and/or swing open to add ventilation.
- C. **Building Form.** Building form refers to the outward three-dimensional envelope of a building or space affected by the mass, shape, composition, and articulation of building elements.
1. **Mass.** Mass is the volume (height x width x depth or height x building footprint) defined by a structure relative to its surroundings.
  2. **Shape.** Shape affects the massing and refers to the simplicity or complexity of the outer dimensions of surface planes (wall planes or roof planes), and their orientation (horizontal / vertical; symmetrical / asymmetrical).
  3. **Composition.** Composition is how the different building elements or materials are arranged to either distinguish or coordinate a particular shape or mass.
  4. **Articulation.** Articulation is using architectural elements to clearly call out a different portion of the composition, shape, or mass and break the building form into smaller, identifiable pieces.
    - (a) **Horizontal Articulation.** Breaking the mass down through different levels of height on the building, particularly for taller buildings, or by a step back or other voids in the massing.
    - (b) **Vertical Articulation.** Breaking the mass down through different bays or structural components along the length of the building elevation, particularly for longer, larger footprint buildings.
  5. **Altering Form.** Techniques to alter the form of a building and affect the scale include:
    - (a) Main mass and wing or secondary masses;
    - (b) Stepping back in the wall plane, usually larger differences (i.e. 4 feet +) at upper story(ies);
    - (c) Cantilever or overhangs, usually a smaller distance (i.e. 1 to 4 feet) over a lower story;
    - (d) Off-sets or breaks in a wall plane in relation to interior floor plan or outside space, not to the level of creating a wing or secondary mass;
    - (e) Dormers, including a window and sub-roof within roof structure;
    - (f) Projections of an element of the facade composition such as a bay window, entry feature, or eaves; and



- (g) Articulation and composition of the facade in relation to, or in addition to any of the above techniques.

D. **Scale.**

Scale refers to the perceived or relative size of a form in relation to something else – usually a person, a social space (courtyard, lot, streetscape, etc.), or another building. For example, “human scale” refers to how spaces or objects relate to and are experienced or perceived by people at a close range and a slow pace. Scale can be affected by the mass, shape, composition, or articulation of the form to make an otherwise larger form seem smaller or more relatable based on how the components are perceived.

E. **Compatibility.** Compatibility refers to the similarity of buildings and sites to adjacent properties or to prevalent patterns and themes in an area. In general, the elements of compatibility will include combinations of the following:

1. Similar proportions of building masses, particularly nearest the property lines and other adjacent buildings;
2. Similar orientation of the building including the relationship to streetscapes, the shaping of open spaces, and the locations and arrangements of the building footprint;
3. Similar window and door patterns, including location, size, and proportions;
4. Similar roof lines (planes, pitches, profiles and details);
5. Similar building materials, particularly primary building materials, or where materials differ they share common textures or color palates;
6. A common architecture style, including the facade composition and materials; however, many styles can allow differences in design within the style.

*Note:* Compatibility does not necessarily mean the same, but rather a sensitivity to the context, adjacencies, and character of the area. While not all of the above elements are necessary for compatibility, the greater the number that are similar, the greater the compatibility will be; significant departures from any one element should be compensated with either greater similarity of other elements or by similarity of more elements. Where things are not compatible, transitions should occur through space and landscape buffer designs.





SUMMARY OF CONTENTS:

**Article 1 General Provisions**

- 17-1-1 Title
- 17-1-2 Authority
- 17-1-3 Purposes
- 17-1-4 Applicability
- 17-1-5 Administration
- 17-1-6 Interpretation
- 17-1-7 Nonconformities
- 17-1-8 Enforcement

**Article 2 Procedures**

- Summary Table
- 17-2-1 General – All Applications
- 17-2-2 Platting
- 17-2-3 Zone Change
- 17-2-4 Planned Development
- 17-2-5 Site Development Plan
- 17-2-6 Alternative Compliance
- 17-2-7 Use by Special Review
- 17-2-8 Variances
- 17-2-9 Appeal of Administrative Decisions
- 17-2-10 Text Amendments
- 17-2-11 Vested Property Rights
- 17-2-12 Annexation & Establishment of Zone District(s)

**Article 3 Subdivision & Community Design**

- 17-3-1 Street Design
- 17-3-2 Open & Civic Space Design
- 17-3-3 Blocks & Lots
- 17-3-4 Required Improvements
- 17-3-5 Community Facilities & Fees

**Article 4 Zone Districts & Uses**

- 17-4-1 Zone Districts
- 17-4-2 Permitted Uses / Use table
- 17-4-3 Specific Use Standards
- 17-4-4 Accessory Uses
- 17-4-5 District Performance Standards

**Article 5 Residential Development & Design**

- 17-5-1 Intent & Applicability
- 17-5-2 Residential Development Standards
- 17-5-3 Neighborhood Design
- 17-5-4 Courtyard Pattern
- 17-5-5 Conservation Pattern
- 17-5-6 Manufactured & Small Format Housing District

**Article 6: Nonresidential Development & Design**

- 17-6-1 Intent & Applicability
- 17-6-2 Nonresidential Development Standards
- 17-6-3 Frontage Design
- 17-6-4 Building Design
- 17-6-5 Open Space Design
- 17-6-6 Specific Frontage & Design Plans

**Article 7 Access & Parking**

- 17-7-1 Intent & Applicability
- 17-7-2 Access & Circulation
- 17-7-3 Required Parking
- 17-7-4 Parking Design

**Article 8 Landscape Design**

- 17-8-1 Intent & Applicability
- 17-8-2 Plant Requirements
- 17-8-3 Buffers & Screens
- 17-8-4 Plant Specifications
- 17-8-5 Fences & Walls

**Article 9 Signs**

- 17-9-1 Intent & Applicability
- 17-9-2 Exempt Signs
- 17-9-3 Permitted Sign Types & Allowances
- 17-9-4 Standards for Specific Signs
- 17-9-5 General Standards – All Signs

**Article 10 Supplemental Standards**

- 17-10-1 Wireless Communication Facilities
- 17-10-2 Floodplain Management & Flood Damage Preventions
- 17-10-3 Natural Resource Extraction & Energy Development

**Article 11 Definitions**

- 17-11-1 Description of Uses
- 17-11-2 Defined Terms
- 17-11-3 Design & Architecture Terms



ARTICLE 1, GENERAL PROVISIONS		
Proposed Sections	Current Sections	Notes:
<b>17-1-1 Title</b>	n/a	Basic section; wording changes to address combination of Chapter 16 (zoning) and Chapter 17 (subdivisions) into a single development code.
<b>17-1-2 Authority</b> A. Authority B. Jurisdiction	16-61 Authority 17-11 Control 17-12 Jurisdiction	Basic section to establish connection to Statutes and Town Charter. (coordinates some scattered references in current code).
<b>17-1-3 Purposes</b>	16-1 Declaration of Purpose (Zoning) 17-1 Declaration of Purpose (Subdivisions)	Revised to align more clearly with broad policies of the comprehensive plan, and set up more detailed hierarchy of non-regulatory, guiding language throughout the code that will be used to interpret standards and apply criteria: <ul style="list-style-type: none"> <li>• Purposes (broad, town-wide planning principles) – This section</li> <li>• Intent (general, topical goals and context application) – throughout, primarily at beginning of chapters or topical sections.</li> <li>• Design Objectives (specific, intended outcomes) – throughout, for specific sections particularly dealing with design standards.</li> </ul>
<b>17-1-4 Applicability</b> A. General Applicability B. Effective Date C. Transition Provisions D. Severability	16-42 Building Permits; 16-43 Application for Building Permit; 16-44 Certificates of zoning Compliance; 16-46 Construction and use to be as provided in plans permits. Chapter 16, Article VIII General Application of Regulations Sections 121, 122, 123, 124 16-161 General (Application of individual Lot Regulations) 16-162 Use Regulations (Application of Individual Lot Regulations) 16-163 Lot Size (Application of Individual Lot Regulations)	Coordinate legal prerequisites and basic statements of where and how the regulations apply, what triggers zoning review, but then defer to Article 2, Procedures for the details of when / how different standards and applications apply. Transition provisions deal with the specifics of merging to the new code for past applications, and effect of prior code on existing development / pending applications. (Note: this coordinates with general rules on nonconformances.)
<b>17-1-5 Administration</b> A. Staff B. Planning & Zoning Commission C. Town Council D. Board of Adjustment	16-41 Administrative Official 16-81 Establishment (Board of Adjustment) 16-83 Powers and Duties (Board of Adjustment)	Organize all authority and decision-making roles in a single section and simplify. Note: the BoA has a more detailed section because it is established by and exists only within the development code; in contrast the Planning Commission and Town Council are established by Statute, Charter, or Municipal Code, and have roles outside of the development code.
<b>17-1-6 Interpretation</b> A. Rules of Construction B. Conflicts C. Computations of Time D. Interpretation of Zoning Map E. Non-regulatory Provisions F. Resources, Guides, & Industry Standards	16-11 Rules of construction of language 16-24 Interpretation of district boundaries 17-14 Interpretation	Expand on existing provisions to provide a broad range of interpretation rules. This mechanism and approach enables a “plain language” drafting style throughout the code (i.e., avoid soft and qualify language or other lengthy explanation of how something is interpreted in context.), and supports the flexibility and decision-making purpose for many other sections of the code.



ARTICLE 1, GENERAL PROVISIONS		
Proposed Sections	Current Sections	Notes:
<b>17-1-7 Nonconformities</b> A. Intent B. Nonconforming Uses C. Nonconforming Structures. D. Nonconforming Site Conditions E. Nonconforming Lots F. Nonconforming Signs G. Burden of Proof	16-125 Legal nonconformity	Expand on current standards to include more refinements to the types of nonconforming situations that may arise and giving more leniency to minor situations, based on general planning principles; overall coordinating conformity with the degree of investment but maintaining leverage for things that are problematic to surrounding property or future development.
<b>17-1-8 Enforcement</b> A. <i>Violations</i> B. <i>Enforcement</i> C. <i>Penalty</i>	16-47 Complaints regarding violations 16-370 Enforcement (Signs)	Similar to existing sections but stating in a manner that it only is stated once in the entire code and can leverage other municipal code enforcement powers and penalties.



ARTICLE 2, PROCEDURES		
Proposed Sections	Current Sections	Notes:
<p><b>17-2-1 General – All Applications</b></p> <p>A. Applications &amp; Fees            B. Concurrent Applications            C. Pre-application Meeting            D. Neighborhood Meeting            E. Staff Review            F. Notice            G. Public Hearings            H. Action by Review Bodies            I. Appeals            J. Technical Studies            K. Permits            L. Successive Applications</p>	<p>16-48 Public hearings            16-45 Expiration of Building permit            16-62 Procedure            16-63 Protest of amendments            16-82 Proceedings (Board of Adjustments)            16-86 Procedure (Board of Adjustment)            17-13 Fees            Chapter 17, Article V Subdivision Procedure (sections generic to all applications)</p>	<p>Locate all elements that impact two or more procedures here; these items are then activated by indications of the table and/or cross-references in the application specific sections. This allows a simpler presentation of procedures and eliminates the need to repeat similar sections throughout the code, thereby reducing the risk of conflicts or interpretation errors. This includes things like application forms, fees, preapplication steps, staff &amp; public review, and notice requirements. Each specific application in the following sections then only have things unique to that application.</p>
<p><b>17-2-2 Platting</b></p> <p>A. Applicability            B. Types of Plat Applications            C. Minor Subdivision (Eligibility; Review Criteria; Review Procedure; Effect of Decision)            D. Major Subdivisions (Review Criteria; Review Procedure; Effect of Decision)            E. Final Plat (Review Criteria; Review Procedure; Effect of Decision)</p>	<p>17-31 Procedure (Subdivisions)            17-32 Criteria for grant of variances or modifications            Chapter 17, Article V Subdivision Procedure (sections specific to platting)</p>	<p>Address unique levels of review for minor subdivisions (routine / staff level), major subdivisions (preliminary and final plats), and plat corrections (vacations of easements or other technical items that require Town Council approval).</p> <ul style="list-style-type: none"> <li>• Minor = more routine record-keeping plats or slight property adjustments approved by staff</li> <li>• Major (preliminary / final or combined) = more significant platting that has dual public hearings at PC / TC for preliminary, public hearing at TC for final.</li> </ul>
<p><b>17-2-3 Rezoning</b></p> <p>A. Applicability            B. Review Criteria            C. Review Procedure            D. Effect of Decision</p>	<p>16-22 Changes in official zoning district map</p>	<p>Incorporate the current process to change zones. Emphasize criteria of matching intent statements of districts to elements of the comprehensive plan.</p>
<p><b>17-2-4 Planned Development</b></p> <p>A. Applicability            B. Development Plan            C. Review Criteria            D. Review Procedure            E. Effect of Decision</p>	<p>Chapter 16, Article XVII Planned Unit Development (sections 301-305 on procedures. (Note section 16-306 Design Standards should be better addressed through basic design standards applicable to all development, then alternative compliance to go above/beyond for planned zoning applications.            Chapter 17, Article IX Planned Unit Development, Sections 131, 132, and 133</p>	<p>Improve the PD process to build better expectations in the review and policies for allowing flexibility for innovative projects, and improve on the long-term administration of property and development in planned districts as things change over time. This approach is based on established a uniform approach to the types of plans necessary to support flexibility, ensuring that these plans are based on design / development principles supported by the Comprehensive Plan and this code; and using the base zoning district standards and design standards as the starting point, while using the plan process for specifically identified additions, subtractions, or deviations. This will improve the implementation of PDs, and more easily allow administration and interpretation of PDs as things change over long periods of time.</p>



ARTICLE 2, PROCEDURES		
Proposed Sections	Current Sections	Notes:
<b>17-2-5 Site Development Plan</b> A. Applicability B. Review Criteria C. Review Procedure D. Effect of Decision	16-145 Approval of site development plans 17-101 General site considerations	New approach to allow site development plans to be reviewed in an administrative capacity, with the ability to elevate the case to Planning Commission and Town Council in situations with more intensive impacts on the community (traffic, infrastructure, etc).
<b>17-2-6 Alternative Compliance</b> A. Applicability B. Review Criteria C. Review Procedure D. Effect of Decision	n/a – new section	New approach to allow more administrative flexibility. Encourages the shift from current PUD processes, corresponding with the increased emphasis on design standards – which warrant greater flexibility than offered by the statutory variance process. Additionally, coordinating with the design objectives (guiding flexibility), objective design standards with subjective guidelines / techniques, and decision-making criteria for alternative compliance helps raise expectations for outcomes while being flexible with decisions. Ultimately unresolved decisions have an appeal mechanism through other established processes (site plan, use by special review, or variance).
<b>17-2-7 Use by Special Review</b> A. Applicability B. Review Criteria C. Review Procedure D. Effect of Decision	Chapter 16, Article VII Conditional Use Grants (Sections 16-101, 102, 103, 104, 105, and 106 to the extent it is not repetitive of 17-2-1.	Incorporate the current Conditional Use Grant into Use by Special Review. The increased emphasis on impact, scale, format, and design may allow uses to be considered in different districts provided the basic scale, format, and design of the district buildings are followed. (See Use table in Article 4)
<b>17-2-8 Variance</b> A. Applicability B. Review Criteria C. Review Procedure D. Effect of Decision	16-83 Powers & Duties (Board of Adjustment) 16-84 Conditions (Board of Adjustment) 16-85 Decisions of the Board of Adjustment 16-86 Procedure (Board of Adjustment)	Incorporate the statutorily required process to allow the Board of Adjustment to consider variances to the standards; however, emphasize that these are for unique circumstances and hardship issues unanticipated by the ordinance when applied to a particular property. Otherwise, general flexibility and relief from standards should be handled in the CUG, or Site Development Plans.
<b>17-2-9 Appeal of Administrative Decision</b> A. Applicability B. Review Criteria C. Review Procedure D. Effect of Decision	16-83 Powers & Duties (Board of Adjustment) 16-84 Conditions (Board of Adjustment) 16-85 Decisions of the Board of Adjustment 16-86 Procedure (Board of Adjustment)	Incorporates the statutorily required process to offer appeals through the Board of Adjustment. [Note: this is different from appeals of applications established under the code and has subtle differences from a variance – i.e., “clear error” standard rather than uniqueness, hardship, etc.]
<b>17-2-10 Text Amendment</b> A. Applicability B. Review Criteria C. Review Procedure D. Effect of Decision	16-61 Authority; 16-62 Procedure; 16	Basic process to amend the code.
<b>17-2-11 Vested Property Rights</b> A. Applicability	Chapter 17, Article XIII Vested Property Rights, Sections 141- 149	Simplified section. Note: this deviates from the typical approach of incorporating the CO Vested Property Rights Act into a municipal code, due to the confusion in terminology and standard municipal processes in that statute. However, this provision satisfies the statute, as it





<b>ARTICLE 2, PROCEDURES</b>		
<b>Proposed Sections</b>	<b>Current Sections</b>	<b>Notes:</b>
<i>B. Review Criteria</i> <i>C. Review Procedure</i> <i>D. Effect of Decision</i>		incorporates many of the procedures and requirements of municipalities that have been well established despite that statute.
<b>17-2-12 Annexation &amp; Establishment of Zone District</b> <i>A. Applicability</i> <i>B. Review Criteria</i> <i>C. Review Procedure</i> <i>D. Effect of Decision</i>	Chapter 15 – Annexation (incomplete code as written)	This section outlines the basic requirements and steps in order to meet and coordinate with the statutory prerequisites that are necessary for all annexations, and provides a framework for applicants and staff that doesn't exist currently.



ARTICLE 3, SUBDIVISION & COMMUNITY DESIGN		
Proposed Sections	Current Sections	Notes:
<p><b>17-3-1 Street Design</b></p> <p>A. Intent B. Street Network C. Street Type &amp; Design D. Intersection Design E. Traffic Calming</p>	<p>16-141 Visibility at intersections 17-102 Streets Standards and Specifications F. Landscape Guidelines for Public Property</p>	<p>This section emphasizes streets as the primary community design element of the Town, and a crucial component of shaping development patterns consistent with the different contexts in the comprehensive plan. Key additions to the current standards include:</p> <ul style="list-style-type: none"> <li>• Prioritizing a higher degree of street connectivity. The standards are based on context zones in the plan (less connectivity in low intensity areas) and have built-in exceptions for when lack of connections is reasonable. This sets a much higher default for better street networks across multiple development projects.</li> <li>• Elevating the urban design standards of street designs. The standard uses the current default ROW and Street widths but add “design types” within each street classification. Design types address issues like parking, bike lanes, lane widths, landscape amenities and sidewalks – which can fluctuate within street networks (and even block-by-block) to better coordinate with the character and pattern of abutting development.</li> <li>• Complete street policies are included to recognize that deviations from the “default” design types may be necessary or desirable for a variety of reasons. However, the complete street guide produces benchmarks for each street design element so tradeoffs in design can be properly evaluated for any specific context.</li> <li>• Intersection details and traffic calming options that can round out decisions for more appropriate, multi-modal street networks and street designs. with the engineering and construction specifications</li> </ul> <p><i>Note:</i> These standards will also coordinate with the concurrent update to the Design Standards. The intent is that the planning and urban design components of street design is included in the LUDC, while the engineering and construction components of street design are included in the Design Standards, and there is coordination but not overlap or conflicts.</p>
<p><b>17-3-2 Open &amp; Civic Space Design</b></p> <p>A. Intent B. Required Open Space C. Open &amp; Civic Space System D. Open Space Design Guidelines</p>	<p>Chapter 16, Article XVI Recreation and Open Space District (plus coordinate with the lot-specific open spaces in various zoning districts)</p>	<p>Emphasize public, community, and neighborhood-scale open space systems as a key component of community design, and an extension of the character established by streetscape and street design. These systems should coordinate with the street networks in maximizing impacts on the community character. Key additions to the current standards include:</p> <ul style="list-style-type: none"> <li>• Establishing an “open space system” requirement at the first scale of development – subdivisions of larger properties. In this manner the open space requirements are viewed much like the street network and should be character-shaping frameworks for development to which all development should orient. These spaces are public or common spaces at the district, or neighborhood scale (as opposed to block or site scale spaces included in site development plans.)</li> <li>• Creating a large variety of open space types – both for different contexts in the community, but also for different sizes and scales of places. While many of these spaces are public or common “block-scale” spaces or larger, some may also be site scale.</li> <li>• Coordination with site, or lot-by-lot development and open space requirements in other chapters (often reflected in lot coverage or landscape requirements)</li> </ul>



<b>ARTICLE 3, SUBDIVISION &amp; COMMUNITY DESIGN</b>		
<b>Proposed Sections</b>	<b>Current Sections</b>	<b>Notes:</b>
<p><b>17-3-3 Blocks &amp; Lots</b>  <i>A. Intent</i>  <i>B. Block &amp; Lot Arrangement</i></p>	<p>17-101 General site considerations            17-103 Utility Easements            17-104 Blocks</p>	<p>Basic standards for the arrangements of blocks and lots within the street networks &amp; open space systems established in this Article. These standards will ensure that patterns are laid out efficiently in consideration of topography, other natural features and hazards, and ensure that all lots are buildable and served by service utilities and community facilities.</p>
<p><b>17-3-4 Required Improvements</b>  <i>A. Intent</i>  <i>B. General Requirements</i>  <i>C. Timing of Improvements</i>  <i>D. Improvements</i></p>	<p>Chapter 17, Article IV Dedication and Reservation of Land, Sections 51, 52, and 53            Chapter 17, Article VII Required improvements, sections 111, 112, and 113</p>	<p>Incorporates all standard elements and improvements required to serve development – in close collaboration with Public Works &amp; Utilities. Considers requirements necessary to serve the project and constructed in association with the project; those to be coordinated with other development in nearby areas; and those that require cooperation of other public entities to serve broader community needs. This section cross references various construction specifications and engineering standards for improvements, as well as considers the review of construction documents, agreements, and the timing of permitting, construction, inspection and acceptance of improvements.</p>
<p><b>17-3-5 Community Facilities &amp; Fees</b>  <i>A. Intent</i>  <i>B. Dedication &amp; Reservation of Land</i>  <i>C. Impact Fees Established</i>  <i>D. Establishment of Accounts &amp; Funds</i>  <i>E. Annual Report</i>  <i>F. 402 Interchange Fee</i></p>	<p>Chapter 17, Article XII Impact Fees, Sections 216-230</p>	<p>There are no substantive changes to this section. It simplifies and reorganizes the current standards and fees, with only changes directed by staff to reflect updates or current practices.</p>



ARTICLE 4, ZONE DISTRICTS & USES		
Proposed Sections	Current Sections	Notes:
<p><b>17-4-1 Establishment of Zone Districts</b></p> <p>A. Intent B. Official Zone Map C. Transition of Previous Districts</p>	<p>16-21 Official zoning district map Plus, Statement of Intent sections from Article XI through XVIII for all existing zoning districts (and any new, combined, or repurposed districts)</p>	<p>Lists all zone districts with improved intent statements with regard to the development patterns, scale/intensity of development, character, and transitions to other complimentary districts; and identify their relation to the comprehensive plan. Key changes include:</p> <ul style="list-style-type: none"> <li>• Changing some of the naming conventions to reflect the nature of development (i.e., R-2, Mixed-density Neighborhood as opposed to SF-2 Single-Family Attached Residential)</li> <li>• Addition of the R-E Rural Estate district, to bridge the gap between the current H-A (40 acres) and R-1/SF-1 (6K lot). This is for primarily in the very low intensity area, and ideally used in conjunction with conservation patterns that help meet other established policies for Ag/Open space preservation, housing mix (even in rural areas), community design and character, and development efficiency [See Section 17-5-6]</li> <li>• Merging the Gateway District and I-1 district into a single district. There are no significant differences in the enabled uses or development standards in the current code. [Note: staff and the consultant will monitor this through review of the initial draft, and based on approaches in the draft code whether a break of for more- or less-intense industrial districts is necessary.</li> <li>• Reformed approach to PDs/PUDs [See 17-2-4 and associated comments]</li> <li>• Added I-2 zone district to account for the heaviest and most intense uses.</li> </ul>
<p><b>17-4-2 Permitted Uses / Use Table</b></p>	<p>Consolidate all Use regulation sections from Articles XI through XVIII into one table and revise / improve.</p>	<p>This section converts all of the separate lists of allowed uses in the various zone districts into a table. The intent is to not change the categories or types of uses allowed in any district but to emphasize better distinctions in development patterns and character between districts. The approach in the current code (separate lists) results in many conflicts, overlaps, and interpretation issues, and results in the use lists having lots of distinctions without substantive differences in resulting development. (i.e., allowing “retail stores” in the NC district, or “hardware store” in the CB or GC district, yet neither distinguishes from the corner hardware store vs. Home Depot). Key additions and changes include:</p> <p>Generally, follow the current zone districts and uses but improve it in the following ways:</p> <ol style="list-style-type: none"> <li>(1) Follow the current districts/ uses but generalize uses more based-on descriptions of typical activities, and examples of specific uses;</li> <li>(2) Make distinctions within general use categories based on scale and format of uses;</li> <li>(3) Filter within the above based on the intent and context of each zone district, and which need a “S” (Use by Special Review process in 17-2-7) vs. “P” (generally permitted subject to district or specific use standards [See 17-4-3]).</li> <li>(4) Indoor and Outdoor Storage as principal use as USR only in Industrial zones.</li> </ol> <p>Additionally, there are criteria for interpreting uses where a use is either not listed, or a use may meet one or more category or type.</p>



ARTICLE 4, ZONE DISTRICTS & USES		
Proposed Sections	Current Sections	Notes:
<p><b>17-4-3 Specific Use Standards</b></p> <p>A. Live-Work Dwelling            B. Mixed-use Dwelling            C. Group Home - Small            D. Residential Care – Limited and General            E. Lodging – Bed &amp; Breakfast            F. Marijuana Uses            G. Gas Stations            H. Automobile Repair – Limited            I. Manufacturing – Limited / Artisan            J. Manufacturing – Breweries, Distilleries, and Wineries</p>	<p>16-25 Medical marijuana prohibitions            16-26 Recreational marijuana prohibitions</p>	<p>Based on the generalized approach to uses (explained above in 17-4-1) and the emphasis on scale, form, and design in the development standards (17-5-3 and 17-6-3 through 5), some uses warrant specific standards – either generally or in specific contexts. This section expands on some of the current uses that have specific standards to address known or anticipated situations.</p>
<p><b>17-4-4 Accessory Uses</b></p> <p>A. Accessory Uses, Generally            B. Accessory Dwelling            C. Home Occupation            D. Outdoor Storage, Residential            E. Outdoor Storage, Nonresidential            F. Drive-through Facilities            G. Outdoor Display and Service Area            H. Small Renewable Energy Equipment            I. Craft Food &amp; Beverage Manufacturing            J. Recycling Collection Point</p>	<p>16-123 Accessory uses and structures.            16-142 Home Occupations</p>	<p>Incorporates the current accessory use standards but improve the ability for many non-mentioned uses to be addressed through general accessory use enabling and performance standards. Key additions to this list with more specific standards include:</p> <ul style="list-style-type: none"> <li>• Accessory Dwelling Units</li> <li>• Drive Through Facilities (treated as an accessory site element, rather than a type of “use” that can be managed by zone districts; in this manner the restrictions elevate based on context – car-oriented vs. pedestrian-oriented)</li> <li>• Outdoor display and service areas (i.e., patios / sidewalk seating, garden sales)</li> <li>• Small renewable energy equipment</li> <li>• Craft food &amp; beverage uses (i.e., “manufacturing / distribution” use associated with a restaurant) [Note: this is different from the opposite – restaurant use associated with manufacturing, which is accounted for in either “artisan manufacturing” or in “breweries, distilleries, winery” [See 17-4-1 and 17-11-1]</li> </ul>
<p><b>17-4-5 District Performance Standards</b></p> <p>A. General Operation &amp; Performance Standards            B. Conditions &amp; Compatibility</p>	<p>16-263 Limitation on external effects of uses (I District)            16-273 Limitation on external effects of uses (Gateway District)</p>	<p>Expanded the applicability of general performance and “anti-nuisance” provisions and refined them for different contexts. Particularly with a more relaxed approach to uses and with a more design-based and flexible approach to development and design, this can raise expectations and add an additional enforcement mechanism for unintended outcomes. This also allows a simpler approach to the regulations and eliminates the need to anticipate all hypothetical negative outcomes and draft overly-restrictive standards based on that.</p>





ARTICLE 5, RESIDENTIAL DEVELOPMENT & DESIGN		
Proposed Sections	Current Sections	Notes:
<p><b>17-5-1 Intent &amp; Applicability</b>            A. Intent            B. Applicability</p>	n/a	<p>Added to guide interpretation and application of the standards based on emphasis on neighborhood design and mix of housing options.</p>
<p><b>17-5-2 Residential Building Types</b>            A. Building Types &amp; Development Standards            B. Dimension Exceptions            C. Accessory Buildings – Residential            D. Housing Diversity</p>	<p>16-165 Building Location (Application of Individual Lot Regulations)            16-166 Open Space (application of Individual Lot Regulations)            Plus – sub-sections of Density, Building location, open space standards sections from Articles XI through XIII for the residential districts – improved based on the building type approach</p>	<p>This section presents a shift from district standards (lot and dimension standards consistent for district) to a “building type” approach (lot and dimension standards keyed to a range of building types, and then each district can enable one or more building types. This is to achieve a greater range of housing options and in some districts or neighborhoods mix the types based on the Comp Plan policies and case study analysis early in this project. Key changes include:</p> <ul style="list-style-type: none"> <li>• More specific standards geared towards “missing middle” housing – small-scale, multi-unit building types. [See Duplex, Multi-unit house, row house, and apartment – small lot)</li> <li>• Smaller detached lot sizes (Small lot (4K and Compact 1.5K)</li> <li>• Refining “multi-family” into scales of apartment buildings, primarily for differentiation between the R-2 and R-3 district, and for differentiation between apartments in walkable contexts vs. apartments in more car-oriented / suburban contexts, which are typically organized into complexes rather than integrated into a block structure.</li> <li>• Establish tiers of accessory buildings, with more leniency for minor structures (conventional sheds) but elevated standards for secondary buildings (detached garages, accessory dwellings, or pool house, etc.)</li> <li>• Housing Diversity requirements [See Tables 5-3 and 5-4] based on groupings of the building types (Category I, II, and III, and based on the scale of the project, different housing mix requirements are established. This can be used to identify and scrutinize when large-scale subdivisions are being developed without appropriate transitions to either other housing or to other supporting land uses, and it can be used to enable some of the new and very compact housing types (i.e. the small lot or compact lot houses, present great additions to a neighborhood with a broader mix when used in strategic locations and limited application.)</li> </ul>



ARTICLE 5, RESIDENTIAL DEVELOPMENT & DESIGN		
Proposed Sections	Current Sections	Notes:
<p><b>17-5-3 Neighborhood Design</b>            A. Frontage Design            B. Building Design            C. Block &amp; Lot Open Space Design</p>	<p>New – but based on issues currently addressed in many outside guidelines that address these same topics in a wide variety of ways, and different degrees of specificity; and similar to topics also address disparately in PUD processes.</p>	<p>This section emphasizes neighborhood design per the comprehensive plan policies. This emphasis becomes more important when you are mixing housing options within neighborhoods and/or developing in a more compact and walkable pattern. The standards are based on three key physical components, and various patterns and application of those components in different contexts:</p> <ul style="list-style-type: none"> <li>• Frontages: building placement/orientation; access / driveways; garage placement / extent; landscape / streetscape design</li> <li>• Buildings: massing, façade design, transparency</li> <li>• Open space: coordinating lot open space and landscape with larger block or community scale spaces [See 17-3-2 discussion]</li> </ul> <p>Each takes a “style” neutral approach to elements and sets objective standards for each component. Flexibility is offered in the following ways:</p> <ul style="list-style-type: none"> <li>• Standards may vary depending on context or street frontage; and/or establish a flexible acceptable range.</li> <li>• Standards are measurable, but typically include a with a variety of techniques to meet the standard.</li> <li>• Standards have specific criteria to consider alternative compliance [See 17-2-7 discussion]</li> </ul> <p>In this manner, the design objectives and decision criteria are important for establishing expectations but still allowing a requisite amount of flexibility in the design standards. .</p>
<p><b>17-5-4 Courtyard Pattern</b>            A. Design Objective            B. Applicability            C. Eligible Building Types            D. Design Standards &amp; Exceptions</p>	<p>New – added a flexible option consistent with the comprehensive plan.</p>	<p>The courtyard pattern presents a way to get greater housing options while enhancing neighborhood design. Smaller lots arranged around a well-designed open space (essentially allowing multiple lots to share a common front yard) can provide additional efficiency and/or integrate projects into challenging spots within the street network or infill areas. This technique is applicable to a range of smaller-scale building types. The standard ensure that this pattern has enhanced design for the individual units / building types (fronting on the courtyard) and for the community (relation of the project to the block and streetscape).</p>
<p><b>17-5-5 Conservation Pattern</b>            A. Design Objective            B. Applicability            C. Density Bonus            D. Lot Sizes &amp; Building Types            E. Open Space</p>	<p>New – added a flexible option consistent with the comprehensive plan.</p>	<p>This is a specific application of a planning technique often called “cluster development” or “conservation subdivisions.” Essentially this allows transfer of development rights internal to a project, where an otherwise allowed development capacity is concentrated in a specific area to either (a) take advantage of efficiencies for developing in smaller areas (utilities, site work, and other development or on-going maintenance costs reduced); and/or (b) conserving larger amounts of contiguous open space, whether for recreation, aesthetic, ecological, and or agriculture purposes. It is directly applicable to the policies established for the very low intensity/density area and agriculture protection area of the comprehensive plan and can pair well with the H-A or R-E zoning to limit the effect of “rural sprawl” that can result from conventional development under those patterns. This specific proposal also includes the incentive of a density bonus – the more area is conserved; the more development capacity /</p>



ARTICLE 5, RESIDENTIAL DEVELOPMENT & DESIGN		
Proposed Sections	Current Sections	Notes:
<p><b>17-5-6 Manufactured &amp; Small Format Housing District</b></p> <ul style="list-style-type: none"> <li>A. Intent</li> <li>B. Applicability</li> <li>C. Development Standards</li> <li>D. Uses</li> <li>E. Common Areas</li> <li>F. Building Design</li> <li>G. Landscape &amp; Parking</li> <li>H. Subdivisions</li> </ul>	<p>Article XVIII – Planned Mobile Home Park Development Regulations</p>	<p>housing options are provided. In this way a broader range of building types from the overall building type approach can be used for the project.</p> <p>This section broadens the applicability of the current manufactured home standards which are geared towards conventional “trailer park” or “manufactured home park” formats. Based on generally applicable neighborhood design approaches used throughout the code, this section elevates the community design component of these areas and requires better integration with or compatibility with surrounding development. In exchange, a wider range of small format housing can be developed (i.e., not just a more conventional trailer/manufactured home, but patio homes, cottage clusters, tiny homes, etc. could be developed). Essentially this takes similar concepts of the Courtyard or Conservation pattern and elevates them up to a block-scale or entire neighborhood plan, which considers broader development and design issues. Note: it is intended that this be implemented as a specific type of PD (PD-M); however, based on the overall approach to other building types and patterns it could also be incorporated as a specific pattern application in some districts.</p>



ARTICLE 6, NONRESIDENTIAL DEVELOPMENT & DESIGN		
Proposed Sections	Current Sections	Notes:
<b>17-6-1 Intent &amp; Applicability</b> A. Intent B. Applicability	n/a	Added to guide interpretation and application of the standards based on emphasis on community design, mixed-use activity centers of various scales, and placemaking in different contexts.
<b>17-6-2 Nonresidential Development Standards</b> A. District Lot & Building Standards B. Dimension Exceptions C. Accessory Buildings – Nonresidential	16-165 Building Location (Application of Individual Lot Regulations) 16-166 Open Space (application of Individual Lot Regulations) Plus – sub-sections of Density, Building location, open space standards sections from Articles XIV through XVIII for the nonresidential districts	Consolidate all non-residential zoning district lot and development standards into a single table; improve based on the scale, intensity standards in the comprehensive plan; and revise based on relevant precedents from the case studies.
<b>17-6-3 Frontage Design</b> A. Design Objectives B. Frontage Design Standards C. Front Building Line D. Access & Parking Limits E. Landscape F. Alternative Compliance	N/a – new approach. However, many scattered sections mentioned with current code sections relevant 17-6-2 above, as well as the multiple sets of design guidelines currently used by the Town that exist outside the development code address these topics in disparate ways	Frontage types are keyed to the streetscape design and specifically the Street Types in Section 17-3-1.C. The frontage types can be used to vary the front setbacks established for district wide standards in 17-6-2; Table 17-6-1. Essentially this determines whether you are developing in a compact and walkable pattern (limited or no setback with higher degree of design details) or in a car-oriented pattern (larger setback with higher degree of buffer and separation). Therefore, default or “preferred” frontages are established based on the zone district, but adjustments and specific application should be based on a block-by-block basis coordinating the Street Design Type or streetscaped. Each frontage type then comes with a preset package of building placement, extent of building frontage, access spacing, parking placement, extent of front parking, and corresponding landscape design strategies. Flexibility in application is offered through the stated design objectives and alternative compliance criteria
<b>17-6-4 Building Design</b> A. Design Objectives B. Building Design Standards C. Massing & Modulation D. Entry Features E. Transparency F. Materials G. Alternative Compliance	N/a – new approach. Same references as immediately above	Focuses building design on a few basic elements that determine how well a building relates to the context/lot, to adjacent buildings, and to the streetscape. Similar to the residential design standards, this presents a “style” neutral approach to elements and sets objective standards for each component. Flexibility is offered in the following ways: <ul style="list-style-type: none"> <li>Standards vary depending on context or street frontage.</li> <li>Standards are presented in an objective and measurable way.</li> <li>Standard may be achieved with a variety of techniques.</li> <li>Criteria to consider alternative compliance are stated. [See 17-2-7 discussion]</li> </ul> In this manner, the design objectives and decision criteria are important for establishing expectations but still allowing a requisite amount of flexibility in the design standards.
<b>17-6-5 Open Space Design</b> A. Design Objectives B. Lot Open Space Design C. Alternative Compliance	N/a – new approach. Same references as immediately above and with 17-6-2 discussion	Coordinates lot open space and landscape requirements with larger block or community scale spaces [See 17-3-2 discussion]



**ARTICLE 6, NONRESIDENTIAL DEVELOPMENT & DESIGN**

<b>Proposed Sections</b>	<b>Current Sections</b>	<b>Notes:</b>
<b>17-6-6 Specific Frontage &amp; Design Plans</b>	N/a – new approach	The overall approach to design standards presents a framework for more strategic and nuanced placemaking. It sets default standards but then accommodates deviations either based on the context (location or street frontage) or to consider alternatives (based on design objectives and criteria.) Most great places have a mix of all of these components in a defined area, with subtle transitions on a block-by-block bases. As a result, using these simple tools and approaches is an effective way to do conceptual development planning or to do smaller-scale design and development planning for districts or neighborhoods. This section realizes the option of over-riding the default standards and specifically planning your streets, frontages, and design transitions. In this manner a specific development plan can more effectively implement the intent and design objectives of the code AND raise expectations for the development. This can be done with a simple street type / frontage type map (See 17-2-4] This section is reserved to allow these types of plans to be approved and incorporated into this code for a more specific application of the established standards.





ARTICLE 7, ACCESS & PARKING		
Proposed Sections	Current Sections	Notes:
<b>17-7-1 Intent &amp; Applicability</b> A. Intent B. Applicability	n/a	Added to guide interpretation and application of the standards and administer flexibility built into the parking requirements and design standards
<b>17-7-2 Access &amp; Circulation</b> A. Design Objectives B. Vehicle Access C. Sidewalks D. Bicycle Connections E. Alternative Compliance	n/a – New approach	Coordinates lot access standards with the street design types in 17-3-1; with the frontage types / driveway limits in 17-5-2 and 6-2; and with other best practices to balance vehicle, pedestrian, and multi-modal access to sites. Coordinates internal circulation for larger-scape projects. Emphasize pedestrian and bicycle access to sites along with vehicle access. These standards are coordinates with the Standards and Specifications or any access management policies from overall street or transportation plans, which can over-ride and/or warrant different vehicle access strategies. Additionally, the “design objectives” – “alternative compliance” pairing can also be used to administer these standards in a flexible, outcome-oriented way.
<b>17-7-3 Required Parking</b> A. Vehicle Parking Rates B. Maximum Parking C. Parking Reductions D. Shared Parking E. Bicycle Parking F. Accessible Parking G. Alternative Compliance	16-143 Off-street parking requirements Plus, all sections on Off-street Parking requirements from Article XI – XVIII for all zoning districts consolidated into a single parking rate table. 16-246 Special off-street parking requirements (CB Central Business District)	Consolidates all parking provisions into a single “required rate” table; improves flexibility to reduce the parking down based on exemptions, exceptions, and credits; implements a “soft-maximum” where additional parking over the required rate requires mitigation
<b>17-7-4 Parking Design</b> A. Design Objectives B. Landscape Areas C. Sidewalks D. Parking Dimensions E. General Design Standards F. Loading Requirements G. Alternative compliance	Various sections from above 16-144 Off Street loading requirements	Coordinate the layout, design, and landscape for parking areas in association with other site design issues. Consider a sliding scale that prioritizes smaller, decentralized lots and rewards locating parking on more remote portions of the site. Loading standards incorporate current standards and improve flexibility and options – particularly form smaller-scale uses or in more walkable and compact patterns.



ARTICLE 8, LANDSCAPE & SITE DESIGN		
Proposed Sections	Current Sections	Notes:
<b>17-8-1 Intent &amp; Applicability</b> A. Intent B. Applicability	Standards and Specifications A. Purpose B. Goals	Current specifications and standards document outside of development code
<b>17-8-2 Plant Requirements</b> A. Design Objectives B. Landscape Requirements C. Credits for Existing Vegetation D. Design & Location E. Alternative Compliance	Standards and Specifications E, Landscape Standards for Private Property H. General Landscaping Standards for All Areas	Organizes all requirements in a single table based on different components of the site – (1) streetscape[er] / frontage; (2) building / foundation area; (3) parking area; (4) open / civic spaces; (5) buffers; and (6) other unbuild areas. Encourages preserving existing vegetation with a credit and credit bonus. Provides flexibility for allocating plants to different areas based on context of the site, efficiency of the site layout, and guidance on how to co-locate valuable plantings and trees with other site elements and infrastructure. Additionally, the “design objectives” – “alternative compliance” pairing can also be used to administer these standards in a flexible, outcome-oriented way.
<b>17-8-3 Buffers &amp; screens</b> A. Design Objectives B. Buffer Planting C. General Screening D. Alternative Compliance	Standards and Specifications E, Landscape Standards for Private Property	Performance standards for high-intensity elements on a site (trash enclosures, storage, loading areas) or sensitive transitions. Uses three distinct types of buffers to be used depending on the context, adjacencies, and type / degree of separation that is needed. Additionally, the “design objectives” – “alternative compliance” pairing can also be used to administer these standards in a flexible, outcome-oriented way.
<b>17-8-4 Plant Specifications</b> A. Design Objectives B. Species C. Plant Specifications D. Tree Diversity E. Water Conservation Guidelines F. Stormwater Treatment G. Planting & Maintenance H. Alternative Compliance	Standards and Specifications H. General Landscaping Standards for All Areas	Standards for proper species, size, planting, and location, including additional criteria for tree diversity and for low water plants and landscape design (xeric). This section will be coordinated with outside manuals for landscape specifications on public and private grounds, and coordinated with updates to the Standards and Specifications
<b>17-8-5 Fences &amp; Walls</b> A. Design Objectives B. Fence & Wall Design C. Alternative Compliance	New – but currently addressed in the above referenced guidelines.	Basic standards for the design and location of fences in various contexts.



ARTICLE 9, SIGNS		
Proposed Sections	Current Sections	Notes:
<b>17-9-1 Intent &amp; Applicability</b> A. Intent B. Applicability C. Sign Measurements	16-361 Intent & Purpose 16-363 Permit requirements	Simplified intent statements and coordinated with some of the other design intent and community design objectives throughout the development code. Removed some of the detailed permitting and processes and deferred to the delegation of the ability to do forms and administrative processes to the department (similar to building permits) [See Article 2, generally and Section 17-2-1]
<b>17-9-2 Exempt Signs</b> <i>[A. – J. on various routine signs not subject to permits]</i>	16-365 Signs not subject to permit	Generalized some sign types into more appropriate or flexible categories; verified exemptions for typical / practical application; removed all content-specific standards to the maximum extent practical; coordinated exemptions with allowance.
<b>17-9-3 Sign Allowances</b> A. Permitted Sign Types B. Residential Districts C. Nonresidential Districts	16-366 Signs requiring a permit	Sign standards organized as follows: <ul style="list-style-type: none"> <li>• A few basic types –building signs, ground signs, pedestrian signs, and temporary signs.</li> <li>• Based on the context (zone district/street frontage), scale of the site, and scale / orientation of the building.</li> </ul> This eliminates the long list of overlapping and sometimes conflicting sign types (i.e., many times signs could meet multiple types under the current standards and thus be subject to several different allowances and size standards); which is difficult to interpret and implement through a site development review process. This approach yields a simple basic sign allowance for each of the main 4 types (unless exempt under 17-9-2), and then allows applicants to allocate all signs and various sub-types within that simplified sign allowance “budget.” The result of this could be a simple table allocating all signs to a sign schedule coordinating to the sign allowance.
<b>17-9-4 Standards for Specific Sign Types</b> A. Building Signs B. Ground Signs C. Pedestrian Signs D. Temporary Signs E. Gateway Signs F. Multi-tenant Buildings & Sites G. Drive-through Service Facilities H. Dynamic or Electronic Message Displays	Various sections from Article XX Signs Code	To supplement the general sign allowance, standards for specific types as well as standards for certain categories and sub types are included in this section. A specific note on temporary signs – the current standards have many sub-types of temporary signs that are cumbersome to implement, and several are content-specific (which presents legal issues). Alternatively, the new approach allocates an appropriate allowance for all temporary signs based on the scale of the lot, and then allows a property owner to allocate that as they chose subject to the general temporary sign standards and limits in this section.
<b>17-9-5 General Standards – All Signs</b> A. Public Health, Safety, & Maintenance B. General Design C. Specific Designs Prohibited	16-364 General Provisions 16-368 Prohibited signs	General location, design, and performance signs applicable to all sign types (i.e., maintenance, lighting, construction, location). The current list of “prohibited signs” is converted to specific design or performance measures that are prohibited.



<b>ARTICLE 9, SIGNS</b>		
<b>Proposed Sections</b>	<b>Current Sections</b>	<b>Notes:</b>
<b>17-9-6 Planned Unit Development Signs</b>	16-367 Master sign plan	Coordination with any flexibility offered through PUDs, comparable to the flexibility offered by other standards. Importantly, this sets the base district sign allowances as the standard absent any specific sign plan of deviation called out in any approved PUD plan documents.



<b>ARTICLE 10, SUPPLEMENTAL STANDARDS</b>		
<b>Proposed Sections</b>	<b>Current Sections</b>	<b>Notes:</b>
<b>17-10-1 Wireless Communications Facilities</b>	Chapter 16, Article XIX Wireless Communications	Reformatted and reorganized here with no substantive changes. Further edits may be necessary to either simplify the wording without substantive changes or to correspond with the new approach in other sections of the development code, based on final draft recommendations.
<b>17-10-2 Floodplain Management &amp; Flood Damage Prevention</b>	Chapter 17, Article XIV Flood Damage Prevention	Reformatted and reorganized here with no substantive changes, and changes directed by staff through a parallel effort. Further edits may be necessary to either simplify the wording without substantive changes or to correspond with the new approach in other sections of the development code, based on final draft recommendations.
<b>17-10-3 Natural Resources Extraction &amp; Energy Development</b>	Chapter 17, Article XI Oil & Gas Exploration and Production, Sections 181 - 207	Reformatted, simplified, and reorganized; incorporated changes based on compilation of peer (North Front Range) community codes that primarily defer to COGCC on all standards other than screening/buffering, and access. Further edits may be necessary to either simplify the wording without substantive changes or to correspond with the new approach in other sections of the development code, based on final draft recommendations. <ul style="list-style-type: none"> <li>Reflects staff edits and new approach to account for any natural resource extraction and energy development. Article will be expectedly expanded over time – i.e., Solar, Mining</li> </ul>





ARTICLE 11, DEFINITIONS		
Proposed Sections	Current Sections	Notes:
<b>17-11-1 Description of Uses</b> A. Residential Uses B. Public / Institutional uses C. Agriculture Uses D. Commercial Uses E. [sic] Manufacturing / Industrial Uses	Re-organize uses from the use table that are in definitions section above.	Updates use descriptions to correspond with new approach to permitted uses / use table. [See 17-4-1]
<b>17-11-2 Defined Terms</b>	16-12 Specific words and phrases 16-362 Definitions (Signs) 17-2 Definitions (subdivisions)	This section is a placeholder– it will be refined and finalized based on the final draft of the development code and based on remaining “non-use” definitions from the current code. Many are not used in the current code or are only used in other definitions or descriptions of uses. Others are restatements of standards from other sections, that do not necessarily define or clarify the term or usage. At the final draft a “merge and purge” of this list will occur: (1) eliminating any terms not used in the final draft; (2) eliminating terms that do not need definitions based on “plain language drafting approaches; and (3) updating new terms added to final draft that need a definition.
<b>17-11-3 Architecture &amp; Design Terms</b>	n/a - New	This is a new recommended section. With the increased emphasis on design, the code uses some subjective terms that defy exact definitions, or where overly-precise definitions and literal application of the definitions could hamper appropriate design. Therefore, this section is more like a “glossary” of the meanings of these terms, and it can be used as a design and/or interpretation aid.



# Town of Johnstown

## LAND USE & DEVELOPMENT CODE

Adoption Draft Public Hearing

Town Council

April 17, 2023

# PROJECT GOALS OVERVIEW

Item #14.

- Comprehensive framework
- Ensure quality development
- Accommodate diverse contexts
- Enable variety of housing
- Support *Johnstown Area Comprehensive Plan*




Town of Johnstown  
johnstown.colorado.gov | 970-587-4664

# FLEXIBILITY & CERTAINTY

## Conventional Approach: A Collection of Regulations

**Plan / Policy**



**Variance**

## Design Based Approach: A System of How We Build, and Why





# COMPREHENSIVE PLAN THEMES

Item #14.

## Johnstown is RESILIENT



- Preserve Natural Systems
- Build Housing Variety
- Adequate Public Facilities
- Concentrate Employment Hubs
- Promote Agriculture Heritage

## Johnstown is VIBRANT

- Design Diverse Neighborhoods
- Strengthen Walkable Downtown
- Neighborhood Activity Centers
- Community Corridors & Gateways

## Johnstown is CONNECTED

- Open Spaces + Gathering Places
- Multimodal Streetscape Design
- Connected Street Networks



Town of Johnstown

[johnstown.colorado.gov](http://johnstown.colorado.gov) | 970-587-4664



# PLAN CONFORMANCE REPORT

Item #14.

## Code Evaluation Themes

- Agricultural & Natural Systems
- Street Design & Networks
- Housing & Neighborhood Design
- Walkable Commercial Places



*Town of Johnstown*  
johnstown.colorado.gov | 970-587-4664

# CRITICAL ISSUES

Item #14.

## Agricultural

- preservation vs. integration with development
- ag-supportive infrastructure
- ag-supportive uses

## Public Space

- street networks and connectivity
- multimodal streets
- streetscape design
- open space

## Neighborhoods

- design & context
- housing variety
- walkability
- mixed-density

## Commercial Destinations

- walkable vs. car-oriented
- regional- vs. neighborhood-scale
- mix of uses, design, parking




*Town of Johnstown*


johnstown.colorado.gov | 970-587-4664



# IMPLEMENT COMP PLAN



FUTURE LAND USE MAP




ZONING MAP



# CODE STRUCTURE

## Structure

- Organization – logical framework
- Simplicity, understanding –
  - Plain language (avoid legalese)
  - Tables and graphics for clarity
- Design – scale, format, details... and use
- Flexibility –
  - Intent and design objectives
  - Ranges and alternatives
  - Procedures and criteria
- Approvals –
  - Streamline
  - Administrative vs. Quasi-Judicial Hearings
  - PUD – need clear standards & process



LAND USE AND DEVELOPMENT CODE UPDATE  
*Second Meeting*

SUMMARY OF CONTENTS:

<b>Article 1 General Provisions</b>	<b>Article 5 Residential Development &amp; Design</b>
17-1-1 Title	17-5-1 Intent & Applicability
17-1-2 Authority	17-5-2 Residential Development Standards
17-1-3 Purpose	17-5-3 Neighborhood Design
17-1-4 Applicability	17-5-4 Courtyard Pattern
17-1-5 Administration	17-5-5 Conservation Pattern
17-1-6 Interpretation	17-5-6 Manufactured & Small Format Housing District
17-1-7 Nonconformities	
17-1-8 Enforcement	<b>Article 6: Nonresidential Development &amp; Design</b>
	17-6-1 Intent & Applicability
<b>Article 2 Procedures</b>	17-6-2 Nonresidential Development Standards
Summary Table	17-6-3 Frontage Design
17-2-1 General – All Applications	17-6-4 Building Design
17-2-2 Platting	17-6-5 Open Space Design
17-2-3 Zone Change	17-6-6 Specific Frontage & Design Plans
17-2-4 Planned Development	
17-2-5 Site Development Plan	<b>Article 7 Access &amp; Parking</b>
17-2-6 Alternative Compliance	17-7-1 Intent & Applicability
17-2-7 Use by Special Review	17-7-2 Access & Circulation
17-2-8 Variances	17-7-3 Required Parking
17-2-9 Appeal of Administrative Decisions	17-7-4 Parking Design
17-2-10 Text Amendments	
17-2-11 Vacated Property Rights	<b>Article 8 Landscape Design</b>
17-2-12 Annexation & Establishment of Zone Districts	17-8-1 Intent & Applicability
	17-8-2 Plant Requirements
<b>Article 3 Subdivision &amp; Community Design</b>	17-8-3 Buffers & Screens
17-3-1 Street Design	17-8-4 Plant Specifications
17-3-2 Open & Civic Space Design	17-8-5 Fences & Walls
17-3-3 Blocks & Lots	
17-3-4 Required Improvements	<b>Article 9 Signs</b>
17-3-5 Community Facilities & Fees	17-9-1 Intent & Applicability
	17-9-2 Exempt Signs
<b>Article 4 Zone Districts &amp; Uses</b>	17-9-3 Permitted Sign Types & Allowances
17-4-1 Zone Districts	17-9-4 Standards for Specific Signs
17-4-2 Permitted Uses / Use Table	17-9-5 General Standards – All Signs
17-4-3 Specific Use Standards	
17-4-4 Accessory Uses	<b>Article 10 Supplemental Standards</b>
17-4-5 District Performance Standards	17-10-1 Wireless Communication Facilities
	17-10-2 Floodplain Management & Flood Damage Prevention
	17-10-3 Natural Resource Extraction & Energy Development
	<b>Article 11 Definitions</b>
	17-11-1 Description of Uses
	17-11-2 Defined Terms
	17-11-3 Design & Architecture Terms

APRIL 2023  
FINAL DRAFT

1

JOHNSTOWN, CO.



# SECTION MAP


- Article 1 - General Provisions
- Article 2 - Procedures
- Article 3 - Subdivision & Community Design
- Article 4 - Districts & Uses
- Article 5 - Residential Development & Design
- Article 6 - Non-residential Development & Design
- Article 7 - Access & Parking
- Article 8 - Landscape & Site Design
- Article 9 - Signs
- Article 10 - Supplemental Standards
- Article 11 - Definitions

ARTICLE 1, GENERAL PROVISIONS		
Proposed Sections	Current Sections	Notes:
17-1-1 Title	n/a	Basic section; wording changes to address combination of Chapter 16 (zoning) and Chapter 17 (subdivisions) into a single development code.
17-1-2 Authority A. Authority B. Jurisdiction	16-61 Authority 17-11 Control 17-12 Jurisdiction	Basic section to establish connection to Statutes and Town Charter. (coordinates some scattered references in current code).
17-1-3 Purposes	16-1 Declaration of Purpose (Zoning) 17-1 Declaration of Purpose (Subdivisions)	Revised to align more clearly with broad policies of the comprehensive plan, and set up more detailed hierarchy of non-regulatory, guiding language throughout the code that will be used to interpret standards and apply criteria: <ul style="list-style-type: none"> <li>• Purposes (broad, town-wide planning principles) – This section</li> <li>• Intent (general, topical goals and context application) – throughout, primarily at beginning of chapters or topical sections.</li> <li>• Design Objectives (specific, intended outcomes) – throughout, for specific sections particularly dealing with design standards.</li> </ul>
17-1-4 Applicability A. General Applicability B. Effective Date C. Transition Provisions D. Severability	16-42 Building Permits; 16-43 Application for Building Permit; 16-44 Certificates of zoning Compliance; 16-46 Construction and use to be as provided in plans permits. Chapter 16, Article VIII General Application of Regulations Sections 121, 122, 123, 124 16-161 General (Application of Individual Lot Regulations) 16-162 Use Regulations (Application of Individual Lot Regulations) 16-163 Lot Size (Application of Individual Lot Regulations)	Coordinate legal prerequisites and basic statements of where and how the regulations apply, what triggers zoning review, but then defer to Article 2, Procedures for the details of when / how different standards and applications apply. Transition provisions deal with the specifics of merging to the new code for past applications, and effect of prior code on existing development / pending applications. (Note: this coordinates with general rules on nonconformances.)
17-1-5 Administration A. Staff B. Planning & Zoning Commission C. Town Council D. Board of Adjustment	16-41 Administrative Official 16-81 Establishment (Board of Adjustment) 16-83 Powers and Duties (Board of Adjustment)	Organize all authority and decision-making roles in a single section and simplify. Note: the BoA has a more detailed section because it is established by and exists only within the development code; in contrast the Planning Commission and Town Council are established by Statute, Charter, or Municipal Code, and have roles outside of the development code.
17-1-6 Interpretation A. Rules of Construction B. Conflicts C. Computations of Time D. Interpretation of Zoning Map E. Non-regulatory Provisions F. Resources, Guides, & Industry Standards	16-11 Rules of construction of language 16-24 Interpretation of district boundaries 17-14 Interpretation	Expand on existing provisions to provide a broad range of interpretation rules. This mechanism and approach enables a "plain language" drafting style throughout the code (i.e., avoid soft and qualify language or other lengthy explanation of how something is interpreted in context.), and supports the flexibility and decision-making purpose for many other sections of the code.





# OVERALL DEVELOPMENT APPROACH



# ARTICLE 1 GENERAL PROVISIONS

Item #14.

## Article 1

### General Provisions

- 17-1-1 Title
- 17-1-2 Authority
- 17-1-3 Purposes
- 17-1-4 Applicability
- 17-1-5 Administration
- 17-1-6 Interpretation
- 17-1-7 Nonconformities
- 17-1-8 Enforcement

## Key Changes

- Reorganize / simplify technical sections
- Update “Purpose” section to better reflect Comprehensive Plan Policies
- Emphasize and coordinate interpretation elements to establish “plain language” approach throughout code
- Expand nonconformity elements and add nuance to specific situations



Town of Johnstown

johnstown.colorado.gov | 970-587-4664

# ARTICLE 2 PROCEDURES

Item #14.

## Article 2

### Applications & Procedures

- 17-2-1 General – All Applications
- 17-2-2 Platting
- 17-2-3 Rezoning
- 17-2-4 Planned Development
- 17-2-5 Site Development Plan
- 17-2-6 Alternative Compliance
- 17-2-7 Use by Special Review
- 17-2-8 Variances
- 17-2-9 Appeal of Administrative Decisions
- 17-2-10 Text Amendments
- 17-2-11 Vested Property Rights
- 17-2-12 Annexation & Establishment of Zone District(s)

## Key Changes

- Improve organization
  - Single “general – all applications” section
  - Table applies elements of general procedures
- Common structure for specific applications sections
  - Applicability
  - Criteria
  - Process
  - Effect of Decision
- Revised approach to PUDs / Planned Development (17-2-4)
  - More specificity for types of plans to support flexibility
  - Keys off of base zoning districts, standards, and types
- Site Plans - Administrative
- Improved administrative flexibility – Alternative Compliance



Town of Johnstown

johnstown.colorado.gov | 970-587-4664

# ARTICLE 3 SUBDIVISION & COMMUNITY DESIGN

Item #14.

## Article 3

### Subdivision & Community Design

- 17-3-1 Street Design
- 17-3-2 Open & Civic Space Design
- 17-3-3 Blocks & Lots
- 17-3-4 Required Improvements
- 17-3-5 Community Facilities & Fees

## Key Changes

- Emphasize streets as the primary community design element of the town
  - Connectivity and development patterns
  - Streetscape design & place-making
  - Complete street policies
- Emphasize different scales and designs of open space for a variety of contexts
  - Spacious & natural
  - Compact & formal
  - Integrated into connects systems / coordinated with streets
- Clarify required improvements – requirements, guarantees, process
- Incorporate current community facilities & fees




Town of Johnstown

johnstown.colorado.gov | 970-587-4664

# ALTERNATIVE STREETSCAPES


## Current Standards

- *Functional Class (arterial, collector, local)*
- *ROW & street width*



## Enhancement Alternatives

- *Street Design Types (context)*
- *Streetscape Elements - sidewalk, landscape/amenity bike lanes, parking, travel lanes*





# STREET TYPES & X-SECTIONS

- Standardize ROW width and street width by functional class
- Refined cross section for context and character, by street design & type


Table 3-2: Street Types & Cross-sections							
Street Type	ROW Width	Street Width [1]	Travel Lanes	Parking	Bicycle Facility	Landscape Amenity	Detached Sidewalk
<b>Major Arterial – 120' / 78'</b>							
Pedestrian Focus	120'	78'	4 @ 11'	8'	N/A – slow speed	9' amenity zone 18' center median	12'
Parkway / Bikeway	120'	78'	4 @ 11-12"	n/a	8-10' protected lane	10-12' tree strip 20' center median	8'-10'
Standard Street	120'	78'	4 @ 12' w/ center turn lane	n/a	n/a	10' tree strip	10'
<b>Minor Arterial – 110'/74'</b>							
<u>Pedestrian Focus</u>	110'	74'	4 @ 11'	8'	n/a – slow speed	5-10" amenity zone 10'-18' center median	10'
Parkway / Bikeway	110'	74'	4 @ 11-12"	n/a	8'-10' protected lane	8'-12' tree strip 10'-18' center median	6'-10'
Standard Street	110'	74'	4 @ 12' 2' outside shoulder	n/a	n/a	10' tree strip	5'
<b>Collector – 80' / 52'</b>							
Pedestrian / Bikeway	80'	52'	2 @ 11'	8'	7' protected lane	4' amenity zone	10'
Pedestrian Mixed-use Focus	80'	52'	2 @ 11'	8' (1 side) 22' angled (1 side)	n/a – slow speed	4' amenity zone	10'
Parkway / Bikeway	80'	52'	2 @ 11'	n/a	7' protected lane	8' tree strip 16' center median	6'
Standard Street	80'	52'	2 @ 12' 12' center turn lane	n/a	4' lane	8' tree strip 14' center median	6'
<b>Local – 60' / 32-36'</b>							
Neighborhood Connector	60'	32'	2 @ 9'	7'	n/a – slow/low volume	8' tree strip	6'
Pedestrian Street	60'	32'	2 @ 11' 2' shoulder (1 side)	8' (1 side)	n/a – slow speed	4' amenity zone	10'
Pedestrian Mixed-use Street	60'	36'	2 @ 10'	8'	n/a – slow speed	4' amenity zone	8'
Bikeway	60'	32'	2 @ 10'	n/a	6' lane	8' tree strip	6'
Standard Street	60'	36'	2 @ 12'	4'	n/a	6' tree strip	5'
<b>Lane 60' / 24'</b>							
Rural Local	60'	24'	2 @ 10' 2' outside shoulder	n/a	n/a	rural buffer with drainage	n/a
<b>Access Alley 30' / 20'</b>							
Residential Alley	30'	20'	16' yield lane	n/a	n/a	2' buffer	n/a
Non-residential Alley	30'	20'	2 @ 9'	n/a	n/a	1' buffer	n/a



# COMPLETE STREETS



**Major Arterial**  
120' ROW, 80' Street Width




**Collector**  
80' ROW, 52' Street Width

Table 3-3: Complete Street Design Guide		
Street Element	Size	Context & Application
Travel Lanes	12' +	High-speed / high-volume; generally avoid on city streets.
	11'	Applicable on major streets or routes where frequent truck or transit vehicles are expected.
	10'	Generally applicable on all city streets with through traffic.
	9'	Limited to low-volume streets, slow-speed streets, or where ROW is constrained.
	12' - 17' yield lanes	Limited to slow, low-volume streets in well-connected networks, where intermittent parking and occasional queuing areas allow two cars to pass.
Bicycle Lanes	n/a	Slow or low-volume streets where bicycles can mix with travel lanes.
	4' - 6' lane	Low-speed streets or constrained ROW (typically < 35mph)
	7'-10' protected lane	Important bike routes or higher speed streets (typically 35+ mph); 2' - 4' protected buffer; 4' - 8' bicycle travel way
	Off street facilities	High-speed / high-volume (typically 45+mph); or portions of trails system.
Parking	6'-7'	Limited to low-volume residential streets.
	7' 8'	Generally applicable to all residential and commercial areas where parking is necessary.
	14'-22' angled	Limited to high-activity streets to maximize parking; depth depends on angle of parking, availability of backing area or cueing lane, and other traffic circumstances.
Landscape Area	2' - 8' amenity zone	Walkable areas (typically paired with adjacent on-street parking) where hardscape, landscape, and street furniture extend sidewalks as social space.
	8'+ amenity zoned	Used for high-activity streets that prioritize social space in streetscapes (i.e., sidewalk dining, mini-courtyards); can accompany Open & Civic Space system credits
	1' - 4' landscape area	Avoid -difficult to grow and maintain plants or trees.
	5' - 6' tree strip	Limited to constrained ROW; small or ornamental trees only.
	7' - 8' tree strip	Generally applicable, sufficient for large shade trees.
	8' - 12' tree strip	Use on busy streets or where no on-street parking exists to provide greater pedestrian buffer.
	13'+ tree strip	Used on signature streets for enhanced landscape amenities; space can be shared with or shifted to medians' and may meet Open & Civic Space system credits (See 17-3-2.C. & D.).
	10' - 20' Median	Used on signature streets for enhanced landscape; can be accompanied with turn lanes and/or mid-street pedestrian refuge at intersections
20'+ Median	Used on higher-order signature streets; may meet Open & Civic Space system credits (See 17-3-2.C. & D.).	
Sidewalks	5'	Minimum, generally applicable standard (typical neighborhood streets)
	6' - 8'	Minimum for non-residential streets (if combined with amenity zone), and priority routes in neighborhoods (i.e. routes to schools, parks, or other destinations).
	8' - 10'	Used for non-residential streets, walkable areas (if combined with amenity zone); or higher density neighborhoods.
	10' +	Used for signature streets in walkable areas, where social spaces are desired in streetscapes, or as a multi-use bicycle / pedestrian path in other contexts.
	Detached	All sidewalks are "detached" to provide a buffer between pedestrians and the street or moving traffic; unless (a) on-street parking is prevalent and the amenity zone provides and expansion of the sidewalk; or (b) right-of-way constraints prevent a more complete street design.




# CONTEXT-BASED OPEN SPACE



Green



Natural Area



Square



Park



Courtyard / Plaza





# ARTICLE 4 DISTRICTS & USES

Item #14.

## Article 4 Districts & Uses

- 17-4-1 Establishment of Zone Districts
- 17-4-2 Permitted Uses / Use Table
- 17-4-3 Specific Use Standards
- 17-4-4 Accessory Uses
- 17-4-5 District Performance Standards

## Key Changes

- Improve intent of zone districts and link directly to comprehensive plan
- Renaming, repurposing, & new districts
  - 4 Residential Districts (RE, R-1, R-2, R-3)
  - 3 Mixed Use Districts (MU-DT, MU-NC, MU-RC)
  - 2 Industrial Districts (I-1 & I-2)
- Consolidate permitted use lists into table
  - Generalize similar uses (greater flexibility)
  - Distinguish with uses by scale / format (improved outcomes)
- Specific & accessory use standards



# ZONING DISTRICTS

**Table 17-4-2: Zone Districts Transitions**

Prior Code	This Code
<i>H-A Holding Agriculture</i>	<i>H-A Holding Agriculture</i>
	<i>RE – Rural / Estate</i>
<i>SF-1 Single-Family Residential</i>	<i>R-1 Single-family Neighborhood</i>
<i>SF-2 Single-Family Attached Residential</i>	<i>R-2 Mixed-density Neighborhood</i>
<i>MF-1 Multi-Family Residential</i>	<i>R-3 Multi-family Neighborhood</i>
<i>NC – Neighborhood Commercial</i>	<i>MU-NC Mixed-use Neighborhood Center</i>
<i>CB – Central Business District</i>	<i>MU-DT Mixed-use Downtown</i>
<i>Gateway Commercial District</i>	<i>MU-RC Mixed-use Regional Center</i>
<i>Gateway District</i>	<i>I – Industrial</i>
<i>I - Industrial District</i>	<i>I – Industrial</i>
<i>Recreation and Open Space</i>	<i>n/a – integrated into all districts</i>
<i>PUDs</i>	<i>[see Section 2.04</i>

- Retain – Ag or basis for “conservation pattern”
- New – Rural or basis for “conservation pattern”
- Revised – Recharacterized as basis for mixed-density neighborhoods
- Revised – Recharacterized for different scales / intensity of activity centers & corridors
- Combined – Due to similarities in uses and development standards





# ARTICLE 5 RESIDENTIAL DEVELOPMENT & DESIGN

Item #14.

## Article 5

### Residential Development & Design

- 17-5-1 Intent & Applicability
- 17-5-2 Residential Building Types
- 17-5-3 Neighborhood Design
- 17-5-4 Courtyard Pattern
- 17-5-5 Conservation Pattern
- 17-5-6 Manufactured & Small Format Housing District

## Key Changes

- Shift to a “building type” approach
  - Range of compatible building types
  - Promote greater mix within some districts
- New RE district – estate housing or rural conservation pattern
- Housing diversity guidelines
  - Minimum # of Building Types required for larger projects
  - Promote “missing middle” housing options integrated into neighborhoods
- Enable new patterns: Courtyard, Conservation (ag, open space, floodplain), small format housing
- Incorporate “design guidelines” into the Code
  - Improve design standards for different neighborhood contexts
- Min. 50’ setback from Plugged & Abandoned Wells; 250’ all other OG facilities to the buildable areas of a lot



# RESIDENTIAL BUILDING/LOT TYPES

Item #14.

**Table 5-1: Residential Building & Lot Standards**

Zoning Districts							Building / Lot Types	# of Units		Development Standards							
A	RE	R-1	R-2	R-3	MU	PD-M		Principal	Accessory	Minimum Lot Standards			Minimum Setbacks [4]			Building Height	
									Size	Width [1]	Lot Open Space	Front [2]	Interior Side	Corner Side [1]	Rear		
■	■						Detached House – Farmstead	1	1	40 ac.	200' +	n/a	35'	25'	35'	50'	35' / 2.5 stories
	■	■					Detached House – Estate Lot	1	1	40K s.f.	80' +	n/a	35'	25'	35'	50'	35' / 2.5 stories
		■	■				Detached House – Large Lot	1	1	12K s.f.	65'	50%	25'	7'	15'	20'	35' / 2.5 stories
		■	■	■			Detached House – Standard Lot	1	1	6K s.f.	50'	30%	25'	5'	10'	20'	35' / 2.5 stories
		◇	■	■			Detached House – Small Lot	1	n/a	4K s.f.	35'	20%	15'	4'	10'	8'	35' / 2.5 stories
			◇	◇		■	Detached House – Compact Lot	1	n/a	1.5K s.f.	28'	n/a	15'	4'	10'	8'	24' / 2 stories
			■	■			Duplex / Multi-unit House	2 - 6	n/a	6K s.f.; 2.5K s.f. per unit	50'	25%	25'	5'	10'	20'	35' / 2.5 stories
			■	■	■		Row House	3 - 8	n/a	1.5K s.f. per unit	18' per unit	15%	15'	5' [3]	10'	8'	40' / 3 stories
			□	■	■		Apartment – Small Lot	3 - 12	n/a	5K – 14K s.f.	50' – 100'	Per Table 3-5	15'	5' [3]	10'	20'	40' / 3 stories
				■	■		Apartment – Medium Lot	13 - 24	n/a	14K – 30K s.f.	100' – 200'	Per Table 3-5	25'	5' [3]	10'	20'	50' / 4 stories
				□	□		Apartment – Large Lot / Complex	25 +	n/a	30K + s.f. +	100' +	Per Table 3-5	25'	5' [3]	20'	20'	65' / 6 stories
■	■	■	■	■			Accessory Buildings	see 17-4-3.B		See Residential Accessory Buildings in Section 17-5-2.C							
						■	Small Format Housing Project			See Small Format & Manufactured Housing Projects in section 17-5-6.							



Low density / rural

New / Refined “Missing Middle” housing options



# COURTYARD LOTS W/ DETACHED

Item #14.



Town of Johnstown  
johnstown.colorado.gov | 970-587-4664



# CONSERVATION PATTERN

Item #14.



Conventional Pattern



Conservation Pattern

- Applicable to the HA and RE residential districts
- *Density bonuses*
- *Mix of Housing Types*
- *Escalates for greater consolidated conservation*
- *Agriculture, Rural, or Natural Spaces*




Town of Johnstown  
johnstown.colorado.gov | 970-587-4664



# SMALL FORMAT HOUSING

Item #14.



Town of Johnstown  
johnstown.colorado.gov | 970-587-4664




# DESIGN: FRONTAGE

Item #14.

## Elements:

- Building Placement
- Entry Feature (Type / Location)
- Driveway Width
- Garage Extent & Location
- Landscape
- Alternative Compliance



Suburban Frontage



Neighborhood Frontage





Terrace Frontage



# DESIGN: RESIDENTIAL BUILDING

## Elements:

- Wall / Roof Plane Limits: Massing
- Blank Wall Limits: Modulation
- Windows & Doors: Transparency
- Materials
- Variation
- Alternative Compliance



# ARTICLE 6 NON-RESIDENTIAL DEVELOPMENT & DESIGN

Item #14.

## Article 6

### Non-residential Development & Design

17-6-1 Intent & Applicability

17-6-2 Nonresidential Development  
Standards

17-6-3 Frontage Design

17-6-4 Building Design

17-6-5 Open Space Design

17-6-6 Specific Frontage & Design Plans

## Key Changes

- Emphasize scale and distinctions between districts (use & buildings)
- Mixed-use districts based on scale:
  - Neighborhood
  - Downtown
  - Regional
- Incorporate “design guidelines” into the Code
- Simplify requirements into basic standards, with two distinct contexts, car-oriented and walkable:
  - Frontage Design
  - Building Design
  - Open Space Design
- Min. 50’ setback from Plugged & Abandoned Wells; 250’ all other OG facilities to the buildable areas of a lot



Town of Johnstown


johnstown.colorado.gov | 970-587-4664



# DESIGN: FRONTAGE

## Elements:

- Front Building Line
- Required Front Building Line
- Access Spacing and Width
- Parking Location & Extent
- Landscape & Streetscape



Frontage A



Frontage B



Frontage C





Frontage D



# DESIGN: NON-RES BUILDING

Item #14.

- Wall Plane / Blank Wall Limits
- Front Entry Features
- Transparency (Windows)
- Materials



0' - 10'



11' - 25'



26' +



Town of Johnstown  
johnstown.colorado.gov | 970-587-4664



# CIVIC & OPEN SPACE DESIGN

Item #14.

Social Spaces



Building Spaces



Landscape / Screens



Public / Common



Town of Johnstown

[johnstown.colorado.gov](http://johnstown.colorado.gov) | 970-587-4664

# ARTICLE 7 ACCESS & PARKING

Item #14.

## Article 7

### Access & Parking

17-7-1 Intent & Applicability

17-7-2 Access & Circulation

17-7-3 Required Parking

17-7-4 Parking Design

## Key Changes

- Coordinate lot access with Frontage Types and Street Types and access management policies
- Promote more multi-modal access standards
- Consolidate parking rates in single table & improve flexibility
  - Exemption for MU-DT (Downtown) zone
  - Exceptions & credits (shared lots)
- Base design requirements for buffer & landscape, based on size & location of parking areas



Town of Johnstown

johnstown.colorado.gov | 970-587-4664

# ARTICLE 8 LANDSCAPE & SITE DESIGN

Item #14.

## Article 8

### Landscape & Site Design

17-8-1 Intent & Applicability

17-8-2 Landscape Requirements

17-8-3 Buffers & Screens

17-8-4 Plant Specifications

17-8-5 Fences & Walls

## Key Changes

- Incorporate design requirements into the Code
- Base requirements for landscape and buffers on function & design of site elements:
  - Streetscape
  - Frontage / foundation
  - Parking areas
  - Open / civic spaces
  - Buffers
  - Other unbuilt areas
  - Complete street policies
- Locally-appropriate performance standards & specifications
- Coordinate with ongoing work with Public Works Design Standards manual and landscape guidelines (in draft form)









Town of Johnstown

johnstown.colorado.gov | 970-587-4664



# L.S. DESIGN CONSIDERATIONS



*Streetscape*



*Frontages & Foundations*

*Parking Areas*



*Buffers & Screens*



# ARTICLE 9 SIGNS

Item #14.

## Article 9 Signs

17-9-1 Intent & Applicability

17-9-2 Exempt Signs

17-9-3 Permitted Sign Types &  
Allowances

17-9-4 Standards for Specific Signs

17-9-5 General Standards – All Signs

## Key Changes

- Compliance with federal court rulings (content neutral)
- Simplify sign types
- Base required size and design on current successful Town commercial areas
- Allowance based on the scale of the lot &/or building



Town of Johnstown

johnstown.colorado.gov | 970-587-4664



## Article 10

### Supplementary Standards

17-10-1 Wireless Communication Facilities

17-10-2 Floodplain Management & Flood  
Damage Preventions

17-10-3 Natural Resource Extraction &  
Energy Development

### Key Changes

- Few substantive changes
- Minimizes local regulation and defer to external partners
- Provides logical space to expand sections for Solar or Mining



Town of Johnstown

johnstown.colorado.gov | 970-587-4664

# PERMITTED USES: RESIDENTIAL TO AG

**Table 4-2: Permitted Uses**

P = Permitted, subject to general district standards  
 S = Permitted, only by special review and discretionary process  
 = Blank means the use is not permitted

	H-A	R-E	R-1	R-2	R-3	MU-NC	MU-DT	MU-RC	I-1	I-2	Specific Conditions
<b>Residential Uses</b>											
Household Living	One-unit Dwelling	P	P	P	P	P					
	Multi-unit Dwelling				P	P					
	Live / Work Dwelling				S	S	P	P	P		17-4-3.A
	Dwelling – Mixed-use					S	P	P	P		17-4-3.B
	Mfgd. / Small Format Home Community				PD	PD	PD	PD	PD		17-5-6
	Established Residential (all building types)						P	P	P	P	P
Group Living	Group Home – Small	P	P	P	P	P	S	S			17-4-3.C
	Residential Care – Limited	S	S	S	S	S	P	S	P		17-4-3.D
	Residential Care – General					S		S	P		17-4-3.D
	Residential Care – Institutional							S	S		
<b>Public / Institutional Uses</b>											
Assembly	Limited (< 400 capacity / < 2 ac.)	P	P	P	P	P	P	P	P	P	
	General (400–800 capacity / 2 – 5 ac.)					P	P	P	P	P	
	Large (800+ capacity / 5+ acre)							P	P		
Civic & Institutional Buildings	Government and Town	P	P	P	P	P	P	P	P		
	Library, public				P	P	P	P			
	Museum, cultural						P	P	P		
	School			P	P	P	P	P	P		
Park and Open Space	Athletic Field			S	S	S	S	S	P	P	P
	Recreation Center or Grounds			S	S	S	S	S	P	P	P
	Park, Trail, Civic Space (See 17-3-2)	P	P	P	P	P	P	P	P	P	
Utilities	Utility Major								S	P	
	Utility – Minor (principal use)			S	S	S	S	S	S	S	
<b>Agriculture Uses</b>											
Agri-tourism	Roadside Stands	P	S	S	S	S	S	S	P		
	Farmers Market	P	S			S	P	P	P		
	Community Farm	P	S	S							
Farming	Farming - Limited	P	S	S							
	Farming - General	P									
	Farming - Industrial	S								S	
	Agriculture Industrial Services								P	P	



**Table 4-2: Permitted Uses**

P = Permitted, subject to general district standards  
 S = Permitted, only by special review and discretionary process  
 = Blank means the use is not permitted

H-A	R-E	R-1	R-2	R-3	MU-NC	MU-DT	MU-RC	I-1	I-2	Specific Conditions
-----	-----	-----	-----	-----	-------	-------	-------	-----	-----	---------------------

# PERMITTED USES: COMMERCIAL

Commercial Uses		H-A	R-E	R-1	R-2	R-3	MU-NC	MU-DT	MU-RC	I-1	I-2	Specific Conditions
Animal Care / Sales	Limited - <3K - no boarding											P P P P P
	Small - 3K - 8K or limited boarding	S										P P P
	General - 8K - 30K or boarding	S										P P
Dependent Care	Large - Outdoor or > 30K	P										S P
	Dependent Care - Limited (< 3K)	S	S	S	S	S						P P P S
	Dependent Care - General (3K - 8K)							S	P			P P P S
Entertainment & Recreation	Dependent Care - Large (> 8K)											S S P S
	Indoor / Limited (< 8K)											S P P P S
	Indoor / General (8-30K+)											S P P S
Food & Beverage Service	Indoor / Large (30K+)											S S S S
	Outdoor											S S S S
	Restaurant - Limited (< 3K)											P P P P
Lodging	Restaurant - Small (3K - 8K)											S P P P
	Restaurant - General (> 8K)											S P P
	Bed & Breakfast (up to 5 rooms)	S	S							S		P P P 17-4-3E
Medical Service	Inn (6 to 40 rooms)											P P P
	Hotel / Motel (40+ Rooms)											S P S
	Limited - < 8K s.f.									S		P P P P S
Office	General - 8K - 30K s.f.											P P P
	Large - Hospital Complex - 30K+ s.f.											P P P
	Limited (<8K or < 33% of MU project)									S		P P P P P
Personal Service	General (8K - 30K)											P P P P
	Large (30K+)											P P P
	Limited (<3K or < 33% of MU project)									S		P P P P S
Retail	Small (3K - 8K)											P P P S
	General (8K-30K)											S P S
	Large (> 30K)											P S
Retail - Grocery Store	Retail - Outdoor & Equipment Sales											S S
	Small (< 8K)									S		P P P P
	General (8K - 30K)											P P P
Vehicle & Equipment Uses	Large (30K +)											P P
	Gas Station - Limited (1-8 Pumps)											S S P P P 17-4-3.G
	Gas Station - General (9-16 pumps)											S P P 17-4-3.G
	Gas Station - Large (17+ pumps)											S P P 17-4-3.G
	Automobile Repair - Limited											S S P P P 17-4-3.H
Car Wash and Automobile Detailing	Automobile Repair - Body Shop											P P
	Automobile, RV, Equip. Sales / Rental											S S
	Car Wash and Automobile Detailing											S S P



# PERMITTED USES: INDUSTRIAL

**Table 4-2: Permitted Uses**

P = Permitted, subject to general district standards  
 S = Permitted, only by special review and discretionary process  
 = Blank means the use is not permitted

	H-A	R-E	R-1	R-2	R-3	MU-NC	MU-DT	MU-RC	I-1	I-2	Specific Conditions
<i>Manufacturing / Industrial Uses</i>											
<i>Industrial Service</i>	<i>Contractors Office &amp; Fleet Services</i>										
	<i>Industrial Service, Light</i>										
	<i>Industrial Service, Heavy</i>										
	<i>Vehicle / Fleet Maintenance Facility</i>										
<i>Manufacturing</i>	<i>Limited / Artisan</i>										
	<i>Brewery, Distillery, or Winery</i>										
	<i>Manufacturing - Light</i>										
	<i>Manufacturing - Heavy</i>										
<i>Warehouse / Storage</i>	<i>Wholesale &amp; Distribution</i>										
	<i>Indoor Storage</i>										
	<i>Outdoor storage</i>										
	<i>Fuel Storage (principal use)</i>										
<i>Waste / Salvage</i>	<i>Automobile Wrecking / Salvage Yard</i>										
	<i>Hazardous Waste Handling</i>										
	<i>Recycling Operation, Enclosed</i>										
	<i>Recycling Operation, Unenclosed</i>										
	<i>Waste transfer Station</i>										







1101 BROAD ST. · MILLIKEN, CO 80543 · 970.587.4331 · FAX 970.587.2678

March 30, 2023

Matt LaCerf  
Town of Johnstown  
450 S. Parish Ave.  
Johnstown 80543

RE: Town of Johnstown/Milliken Hillsborough Ditch Company Water Court Change Case

Dear Shareholder,

Please join us for breakfast on Friday, April 7<sup>th</sup> at 7:30 am at Milliken Town Hall.

The purpose of this breakfast is to provide you with notification and also to invite you to include your Hillsborough Ditch Company Water Shares in a water court change case to be filed by the Towns of Johnstown and Milliken before the end of the calendar year. These shares are currently unchanged, which means the water cannot be used for municipal purposes i.e., potable drinking water. In order to allow municipal use, the Town must file a water court change case, and ultimately the outcome of this case will result in a water court decree that provides a yield for municipal purposes within the Towns of Johnstown and Milliken.

As shareholders of the Hillsborough Ditch Company, we would also like to invite you to participate in our change case by including your water certificate shares in this change case. As part of this change case, the Towns will not own your shares or have any rights to your shares. You, as the owner of the share, will still have the right to use it for any irrigation purposes you have previously used the water for on your land. The sole benefit for this is that if at some point in the future you decide that you do not want to use the water for agricultural and irrigation purposes, you would have the opportunity to utilize it for municipal purposes.

Currently, it is estimated that you receive approximately 120-acre feet of water for irrigation purposes for each share. We believe this amount will not be compromised if you take the water through a change case with the Town. We also believe that a favorable decree could result in



the ability of you to still utilize the 120-acre feet as you have historically until you no longer wish to use the water for this purpose. A changed use decree we hope will allow for the conversion of a portion of the water, there will be no fees applied to any legal or engineering costs.

PLEASE NOTE: that the inclusion of your Water Shares in the Towns change case has important legal ramifications. Therefore, you should consult with legal counsel regarding such ramifications before electing to include your Water Shares in the Towns change case.

If you have additional questions regarding this process, please contact me at your convenience.

Regards,

*Cheryl Powell*  
TB

Cheryl Powell  
Town Administrator

P.S. Other interested parties are encouraged to attend.



# Town of Johnstown

April 3, 2023

Uncle Benny's Building Supplies, LLC  
Benjamin R. Aste, Owner  
4737 Marketplace Dr.  
Johnstown CO 80534

Re: Extension of Temporary Staging & Storage Area, On-site

Dear Mr. Aste

Per the Incentive Agreement between the Town of Johnstown and Uncle Benny's Buildings Supplies, LLC, executed on May 17, 2022, Uncle Benny's was permitted to construct and operate a temporary storage and staging area on the portion of the property as shown on Exhibit B of the agreement. Per Section 2.b (vi), the temporary storage and staging area was to cease operations when the project opens for retail or by April 5, 2023, whichever occurred first. The Town was also given administrative discretion to extend the use of the temporary storage and staging area if requested.

Please consider this written approval that the Town is granting an extension for the use of the temporary storage and staging area for an additional 8 months starting from the date of April 5, 2023. No changes are permitted beyond the conditions and terms of the Economic Incentive Agreement between the Town and Uncle Benny's dated May 16, 2022. Uncle Benny's must cease all operations and usage of the temporary storage and staging area no later than November 5, 2023. The Town may at its sole discretion consider any additional extension which may be necessary.

Please keep in mind Uncle Benny's must still comply and is subject to all the terms and conditions within the executed incentive agreement and the memo provided on March 29, 2022 which details the allowed terms and restrictions for the temporary storage and staging area.

Regards,

  
Matt LeCerf  
Town Manager

Cc: Sarah Crosthwaite, Economic Development Manager  
Kim Meyer, Planning Director

The Community That Cares

johnstown.colorado.gov

P: 970.587.4664 | 450 S. Parish Ave, Johnstown CO 80534 | F: 970.587.0141



# Larimer County 2019 Community Health Improvement Plan Executive Summary



**Public Health**

# LETTER FROM THE DIRECTOR

In 2018, the Larimer County Department of Health and Environment gathered our community for an all day public health summit. Over 250 community members attended, representing a variety of interests and backgrounds. They learned about the health of Larimer County, some of the problems we face, and what the community is working on. Together, they worked to prioritize focus areas for our Community Health Improvement Plan. The community members chose two priority focus areas:

- Promote Mental and Emotional Wellbeing Across the Lifespan
- Provide Access to Quality Childcare



This summit was just the start to additional and ongoing community engagement around the health of Larimer County. Please, read through this document. This Community Health Improvement Plan is just that, the community’s plan. Throughout the next few years, we will work closely with our partner agencies and other community members to convene and move this plan forward. We’d very much like to have your input and collaboration through this process.

Thank you for your interest and support in promoting a healthy Larimer County. It takes a whole community to make change!

Tom Gonzales, MPH  
Public Health Director

Jennifer Lee  
President, Board of Health

The Community Health Improvement Plan (CHIP), is a 5-year plan that began after Colorado passed the Public Health Reauthorization Act in 2008. This legislation requires local public health agencies to create a health improvement plan, based on a community health assessment and with community input about priorities at least every five years.

The Larimer County 2019-2024 Community Health Improvement Plan development process focused on a data-driven prioritization process and meaningful community engagement to identify community needs and values, potential strategies, and community governed implementation of strategies to fill gaps. This effort involved compiling county-level health data to assess community health status, assessing capacity of public health partners to address community health issues, gathering input from community partners and community members, and identifying existing strategies and gaps.

The Larimer County’s Community Health Improvement Plan kicked off with the Healthy Larimer Summit on Jan. 24, 2018, that convened over 180 representatives of community agencies from diverse sectors. Participants looked at community health data and participated in both a group and individual prioritization process that helped identify the top community priority areas for the next five-year CHIP. Priority areas were then reviewed by the CHIP Leadership Committee and the Health Equity Committee before going to the Board of Health for final approval on March 15, 2018.

### Priority areas:

#### In an equitable and culturally responsive manner,

1. **Promote Mental and Emotional Wellbeing Across the Lifespan, focusing on Addressing Gaps in the Required Continuum of Care, Substance Use Disorder and Treatment, and Primary Prevention**
2. **Provide Access to Quality Childcare, focusing on Affordability, Recruitment and Retention of the Childcare Workforce, and Infant and Toddler Care**

The CHIP contains a detailed Action Plan for each of the two priority areas, each of which includes a five year focus and community-level indicators of success, goals, and strategies. The CHIP Team has developed formal partnerships with 50 other community entities, each of which is contributing to at least one strategy in the action plan. Working together, these agencies will make Larimer County an even better place to live, work, and play.

**Follow our progress or get involved at [Larimer.org/CHIP](http://Larimer.org/CHIP)**



A Community Health Improvement Plan is a community-driven and action oriented collaborative plan that focuses on select priority issues that require multiple sectors all working together to make a significant change in the community. CHIPs are created through a community-wide prioritization and planning process, utilizing community data in decision-making and is intended to serve as a community vision for health and a resource for organizations to ensure collaboration, promote across-sector strategic planning, and de-duplicate efforts.

## How to Use a CHIP

A CHIP is a strategic framework that organizations, collaborations, and coalitions can plug into to assist with partnership development, strategic planning, and applying for grants. It is intended to be a living document, and the most up to date strategies and metrics can be found on our website. The CHIP Team and the Healthy Larimer Committee support the work of other community partners and provide guidance in creating new strategies to fill gaps or create more equitable implementation of strategies to best meet the most impacted populations.

In order to make a significant impact in the CHIP priority areas, the CHIP team sees their role and the role of the CHIP in the following ways:

### Role of CHIP Team

**Support/Monitor** - The CHIP team will be supporting efforts in our community, focused on the CHIP priority areas, that are being done in a collaborative and streamlined way. The Team will be connecting additional partners to this work, promoting these efforts, and highlighting successes through the CHIP dashboard.

**Convene** - The CHIP Team can convene partners to assist with collaborative efforts to more effectively move the needle on identified CHIP outcomes. When there are multiple partners working on similar initiatives, the CHIP team can serve as a neutral party to convene stakeholders and discuss ways to collaborate, streamline efforts, and develop measurable strategies and outcomes. The strategies developed in this convening effort can be incorporated into the CHIP where the CHIP Team will take on a supporting role.

**Expand** - The CHIP team can take a leading role in expanding efforts to fill gaps in our communities related to the priority areas. This includes developing partnerships to create collaborative efforts, identifying backbone organizations, seeking out funding opportunities, and identifying best practices. In order to build momentum, the CHIP team may develop initial workgroups to expand efforts that lead to the development of strategies within CHIP priority areas.

## Role of the Healthy Larimer Committee

**Ensure Equitable Implementation of Strategies** - Using the community partner-developed CHIP Equity Process and Matrix, the Healthy Larimer Committee will have the opportunity to assess existing CHIP efforts to ensure they are implemented in the most equitable way, focusing on the impact of these strategies on the most under resourced populations. Once the assessment is complete, community partners will be encouraged to work with the Healthy Larimer Committee and the CHIP Equity Process and Toolkit to identify creative ways to ensure equity in their work.

### Identify Opportunities to Expand Efforts to Impact the Most Under Resourced Populations

- The Healthy Larimer Committee, with their wealth of knowledge through lived experience, will be able to identify gaps in our community efforts for specific under resourced populations, identify barriers for these populations, and identify creative ways to utilize community capacity to better reach populations that are most impacted.

## Roles of the CHIP


**Highlight Community Successes** - Through the CHIP dashboard, the great work of our community partners is highlighted in a public way. This provides a structure for CHIP partners to share their updated performance metrics to community members, community organizations, and policy makers to view CHIP partner successes all in one place.

**De-duplicate and Streamline Efforts** - The CHIP framework organized community efforts to be able to easily identify duplicative efforts so that community partners can streamline and collaborate to create efficient partnerships.

**Create Stronger Grant Applications** - Through participation in the CHIP process, community partners not only have the opportunity to include their role within the larger CHIP effort in their grant applications, but can utilize the CHIP framework to quickly identify partners across multiple sectors for a collaborative grant application.




In an equitable and culturally responsive manner, promote mental and emotional wellbeing across the lifespan; focusing on addressing gaps in the required continuum of care, substance use disorder and treatment, and primary prevention.



- CHIP Roles and Responsibilities
- Community Goals
- Community Outcomes
- CHIP Priority Area

In an equitable and culturally responsive manner, provide access to quality childcare



- CHIP Roles and Responsibilities
- Community Goals
- Community Outcomes
- CHIP Priority Area

# Larimer County 2019 Community Health Improvement Plan



**Public Health**



# LETTER FROM THE DIRECTOR

In 2018, the Larimer County Department of Health and Environment gathered our community for an all day public health summit. Over 250 community members attended, representing a variety of interests and backgrounds. They learned about the health of Larimer County, some of the problems we face, and what the community is working on. Together, they worked to prioritize focus areas for our Community Health Improvement Plan. The community members chose two priority focus areas:



- Promote Mental and Emotional Wellbeing Across the Lifespan
- Provide Access to Quality Childcare

This summit was just the start to additional and ongoing community engagement around the health of Larimer County. Please, read through this document. This Community Health Improvement Plan is just that, the community's plan. Throughout the next few years, we will work closely with our partner agencies and other community members to convene and move this plan forward. We'd very much like to have your input and collaboration through this process.

Thank you for your interest and support in promoting a healthy Larimer County. It takes a whole community to make change!

Tom Gonzales, MPH  
Public Health Director

Jennifer Lee  
President, Board of Health

The Community Health Improvement Plan (CHIP), is a 5-year plan that began after Colorado passed the Public Health Reauthorization Act in 2008. This legislation requires local public health agencies to create a health improvement plan, based on a community health assessment and with community input about priorities at least every five years.

The Larimer County 2019-2024 Community Health Improvement Plan development process focused on a data-driven prioritization process and meaningful community engagement to identify community needs and values, potential strategies, and community governed implementation of strategies to fill gaps. This effort involved compiling county-level health data to assess community health status, assessing capacity of public health partners to address community health issues, gathering input from community partners and community members, and identifying existing strategies and gaps.

The Larimer County's Community Health Improvement Plan kicked off with the Healthy Larimer Summit on Jan. 24, 2018, that convened over 180 representatives of community agencies from diverse sectors. Participants looked at community health data and participated in both a group and individual prioritization process that helped identify the top community priority areas for the next five-year CHIP. Priority areas were then reviewed by the CHIP Leadership Committee and the Health Equity Committee before going to the Board of Health for final approval on March 15, 2018.

### Priority areas:


#### In an equitable and culturally responsive manner,

- 1. Promote Mental and Emotional Wellbeing Across the Lifespan, focusing on Addressing Gaps in the Required Continuum of Care, Substance Use Disorder and Treatment, and Primary Prevention**
- 2. Provide Access to Quality Childcare, focusing on Affordability, Recruitment and Retention of the Childcare Workforce, and Infant and Toddler Care**

The CHIP contains a detailed Action Plan for each of the two priority areas, each of which includes a five year focus and community-level indicators of success, goals, and strategies. The CHIP Team has developed formal partnerships with 50 other community entities, each of which is contributing to at least one strategy in the action plan. Working together, these agencies will make Larimer County an even better place to live, work, and play.




In an equitable and culturally responsive manner, promote mental and emotional wellbeing across the lifespan; focusing on addressing gaps in the required continuum of care, substance use disorder and treatment, and primary prevention.



- CHIP Roles and Responsibilities
- Community Goals
- Community Outcomes
- CHIP Priority Area



In an equitable and culturally responsive manner, provide access to quality childcare



- CHIP Roles and Responsibilities
- Community Goals
- Community Outcomes
- CHIP Priority Area

## Contributing Organizations/ Partnerships/Coalitions in Promoting Mental and Emotional Wellbeing across the Lifespan

- Alliance for Suicide Prevention
- Child, Adolescent, and Young Adult Connections
- Connections
- Colorado State University
- Colorado State University Extension
- Grand Families Coalition
- Health District of Northern Larimer County
- Health Sector Partnership
- Imagine Zero Coalition
- Larimer County Co-Responder Program
- Larimer County Criminal Justice
- Larimer County Department of Health and Environment
- Larimer County Department of Human Services
- Larimer County Justice System
- Leap Coalition
- Mental Health Matters
- Mental Health Substance Use Alliance
- Northern Colorado Health Alliance
- Opioid Prevention Workgroup
- Park School District
- Partnership for Age Friendly Communities
- Partnership for Healthy Youth
- Poudre School District
- Pregnancy Related Depression Coalition
- Regional Health Connector
- Southern Larimer Prevention Partnership
- SummitStone Health Partners
- SummitStone Latinx Advisory Group
- Team Wellness & Prevention
- Thompson School District
- United Way of Larimer County

## Contributing Organizations/ Partnerships/Coalitions in Providing Access to Quality Childcare

- Early Childhood Council of Larimer County
- Estes Park Family Advisory Board
- Estes Valley Investment in Childhood Success
- Front Range Community College
- Larimer County Department of Health and Environment
- Larimer County Department of Human Services
- Poudre School District
- Talent 2.0 Taskforce
- Thompson School District

The Community Health Assessment focused on improving our understanding of the current health status of Larimer County residents. Between October and December 2016, the data subcommittee focused on compiling health data from secondary sources, more than 300 indicators were collected. This second iteration of the Community Health Assessment used the same framework identified in 2011, which is a framework modeled after the National Prevention Strategy: America’s Plan for Better Health and Wellness (NPS). The NPS focuses on four strategic directions and seven priorities to achieve the overarching goal to increase the number of Americans who are healthy at every stage of life. This goal and the framework were adapted to reflect our local issues. A comparison between the NPS and the framework adopted in Larimer County is shown in Table 2.

Although the Community Health Data dashboard is available to the community online at LarimerHealthTracker.org, a subcommittee was developed to identify areas of data that should be presented to the community in an oral presentation at the 2018 Summit. The following data, focusing on what influences health and behavioral health, provides an overview of what was presented to community partners and gives a quick snapshot of health in Larimer County. Full data presentations can be found on our website at [www.Larimer.org/health](http://www.Larimer.org/health).





Table 2

<p><b>NATIONAL PREVENTION STRATEGY GOAL:</b> Increase the number of Americans who are healthy at every stage of life.</p>	<p><b>LARIMER COUNTY GOAL:</b> Increase the number of Larimer County residents who are healthy at every stage of life.</p>
<p><b>Four Strategic Directions</b></p> <ul style="list-style-type: none"> <li>• Healthy and Safe Community Environments</li> <li>• Clinical and Community Preventive Services</li> <li>• Empowered People</li> <li>• Elimination of Health Disparities</li> </ul>	<p><b>Six Strategic Directions</b></p> <ul style="list-style-type: none"> <li>• Promoting a Healthy Social Environment</li> <li>• Promoting a Healthy Physical Environment</li> <li>• Strengthening Public Health and Health Care Prevention Efforts</li> <li>• Improving Access to Preventive Services and Treatment</li> <li>• Raising Healthy Children</li> <li>• Promoting Healthy Aging</li> </ul>
<p><b>Seven Priorities</b></p> <ul style="list-style-type: none"> <li>• Active Living</li> <li>• Healthy Eating</li> <li>• Reproduction and Sexual Health</li> <li>• Injury and Violence Free Living</li> <li>• Mental and Emotional Well-Being</li> <li>• Preventing Drug Abuse and Excessive Alcohol Use</li> <li>• Tobacco Free Living</li> </ul>	<p><b>Nine Health Issues</b></p> <ul style="list-style-type: none"> <li>• Active Living</li> <li>• Healthy Eating</li> <li>• Healthy Sexuality and Reproduction</li> <li>• Injury and Violence Free Living</li> <li>• Mental and Emotional Well-Being</li> <li>• Preventing Drug Abuse and Excessive Alcohol Use</li> <li>• Protecting Environmental Quality</li> <li>• Tobacco Free Living</li> <li>• Reducing Infectious Diseases</li> </ul>


**Overview of Larimer County Demographics**

Item #15.

93% of Larimer County community members reported to identify as white, 1% as African-American, 1% as American Indian/Alaska Native, and 2% to be Asian. 83% of Larimer County residents linself-identified as non-Hispanic white, and 11% self-identified as Hispanic of any race.<sup>1</sup>

91% report to speak English at home, while 5% report speaking Spanish, 2% report speaking an Indo-European language, and 1% report speaking an Asian language.<sup>2</sup>

In Larimer County, the median household income is \$59,805. The percent of residents living in poverty is 12%. This is higher than Colorado’s poverty rate of 11% and not far from the national rate of 12.7%.<sup>3</sup>




**Educational Attainment**

Families in Larimer County can expect to pay approximately \$12,000 per year for each child needing care.<sup>4</sup>


Since September 12, 2016, Larimer County has been unable to provide financial assistance through the Child Care Assistance Program for new children and has a waitlist. The waitlist is extensive and families must re-submit paperwork every 6 months to remain on the list.

There is a small supply of Early Childhood Education providers. It is estimated that nearly 5,000 children 0-2 years old have two parents working and need childcare; however, our licensed capacity is only 1,117 spots for 0-2-year-old. For 2.5 to 6-years-old, it is estimated that there are about 9,000 children in need of childcare and only about 6,000 spots.<sup>5</sup>



When looking at standardized Math and English testing for readiness, there is a significant difference in scores among white and Hispanic populations as early as 3rd grade, but also seen in 9th grade testing in all school districts in Larimer County.

Graduation Rate (%) for specific characteristics in Larimer County, compared to overall graduation rate (2018)



This disparity can also be seen when we look at students who are eligible for free and reduced lunch and those who are not, which can give us an idea of the impact of income. Those who qualified for free and reduced lunch score significantly lower in English and Math readiness as in 3rd grade and in 9th grade in all school districts.

This trend continues - Disparities of graduation rates for Hispanic youth and economically disadvantaged youth are also significantly different from the overall graduation rate.<sup>6</sup>

### Food Insecurity

The food bank reported that 42,880 Larimer County residents meet the definition of food insecure. The food bank alone provided 7.72 million meals, distributed 3.45 million pounds of fresh produce, and served 37,500 individuals in one year.

The number of food insecure seniors in Larimer county is growing every year. 8.4% of seniors are food insecure and 1 in 3 children in Larimer County is food insecure.<sup>7</sup>

### Housing Insecurity

While our median income in Larimer County is \$59,805, it is calculated that a household would need to earn at least \$65,800 to buy a house in Larimer County. This means that fewer than half of Larimer County residents have income at the level where they could afford to buy a house. The price of houses has grown in Larimer county in recent years. The median sales price for a single-family home in Larimer County is higher than the price for a house in Colorado overall, at \$350,000.<sup>8</sup>

For housing, the definition of cost burdened is if you are spending more than 30% of gross household income on rent or mortgage. More than half of Larimer County residents are paying more than 30% of their gross income **on rent**, and almost a third are spending more than 30% of their income on their **mortgage**.<sup>9</sup>

There were 1,659 children in Larimer County who were living in shelters, transitional housing, awaiting foster care, doubled up due to economic hardship, unsheltered or living in a hotel/motel during the 15-16 school year.<sup>10</sup>

### Behavioral Health

#### Mental Health

38.2% of adults report that their mental health was “not good” at least one day during the past

30 days. Furthermore, consistently since 2001, about one in five Larimer County adults (20%) report ever having been told by a doctor or other health care provider that they have depression, and another approximately one in 20 report another mental health problem or illness other than depression.<sup>11</sup>

31.2% percent of teens in Larimer County felt sad or hopeless almost every day for two weeks or more in the past 12 months. The LGB community is disproportionately affected with 66.2% feeling sad or hopeless.<sup>12</sup>

### Suicide

Between 2015 and 2017, there were 215 suicide deaths in Larimer County, with 10 of them being adolescents (ages 10-19). In 2015, the self-inflicted injury hospitalization rate for Larimer County was 71.1 per 100,000 population, compared with a rate of 61.1 per 100,000 for the state overall.<sup>14</sup>


Among teens in 2017, 15.9% reported to have considered suicide, and 5.7% reported to have attempted suicide. LGB teens were significantly more likely to have considered suicide (49.5%) or attempt suicide (16.5%).<sup>15</sup>

### Substance Use

In 2014, 25% of Larimer County adults surveyed reported binge drinking during the previous 30 days (defined as a male who had more than 5 drinks on one occasion or a woman who had more than 4 drinks on one occasion).<sup>16</sup>

Among high school students, 29.9% reported drinking in the past 30 days, and 15.4% reported binge drinking in the past 30 days. The LGB teens reported a higher percentage of drinking in


Percent of Youth Who Report Considering Attempting Suicide in 2015



Number of Suicides from 2004-16 in Larimer County




% of respondents reporting a diagnoses of depression



the past 30 days (36.5%) than heterosexual teens. These percentages are similar to Colorado. 19.6% percent of high school students have used marijuana in the past 30 days. Among LGB youth, 27.2% have used marijuana in the past 30 days.<sup>17</sup>

In 2015, there were 56 drugs of abuse in overdose deaths (rate of 16.8 deaths per 100,000).<sup>18</sup> This is well above the Healthy People 2020 target of 11.3 deaths per 100,000. It is estimated that 8.4% of people in Colorado over the age of 12 are dependant on alcohol and 2.8% are dependant of drugs, meaning that 9.2% of the population would meet the criteria for substance abuse treatment. In 2014, it is estimated that Larimer County treated 2,800 people, leaving over 28,000 people without care. Of those, it is estimated that 1,400 wanted treatment.<sup>19</sup>



## WHAT IS A COMMUNITY HEALTH IMPROVEMENT PLAN?

A Community Health Improvement Plan is a community-driven and action oriented collaborative plan that focuses on select priority issues that require multiple sectors all working together to make a significant change in the community. CHIPs are created through a community-wide prioritization and planning process, utilizing community data in decision-making and is intended to serve as a community vision for health and a resource for organizations to ensure collaboration, promote across-sector strategic planning, and de-duplicate efforts.

### How to Use a CHIP

A CHIP is a strategic framework that organizations, collaborations, and coalitions can plug into to assist with partnership development, strategic planning, and applying for grants. It is intended to be a living document, and the most up to date strategies and metrics can be found on our website. The CHIP Team and the Healthy Larimer Committee support the work of other community partners and provide guidance in creating new strategies to fill gaps or create more equitable implementation of strategies to best meet the most impacted populations.

In order to make a significant impact in the CHIP priority areas, the CHIP team sees their role and the role of the CHIP in the following ways:

### Role of CHIP Team

**Support/Monitor** - The CHIP team will be supporting efforts in our community, focused on the CHIP priority areas, that are being done in a collaborative and streamlined way. The Team will be connecting additional partners to this work, promoting these efforts, and highlighting successes through the CHIP dashboard.

**Convene** - The CHIP Team can convene partners to assist with collaborative efforts to more effectively move the needle on identified CHIP outcomes. When there are multiple partners working on similar initiatives, the CHIP team can serve as a neutral party to convene stakeholders and discuss ways to collaborate, streamline efforts, and develop measurable strategies and outcomes. The strategies developed in this convening effort can be incorporated into the CHIP where the CHIP Team will take on a supporting role.

**Expand** - The CHIP team can take a leading role in expanding efforts to fill gaps in our communities related to the priority areas. This includes developing partnerships to create collaborative efforts, identifying backbone organizations, seeking out funding opportunities, and identifying best practices. In order to build momentum, the CHIP team may develop initial workgroups to expand efforts that lead to the development of strategies within CHIP priority areas.



# DEVELOPMENT OF THE LARIMER CHIP

## Role of the Healthy Larimer Committee

**Ensure Equitable Implementation of Strategies** - Using the community partner-developed CHIP Equity Process and Matrix, the Healthy Larimer Committee will have the opportunity to assess existing CHIP efforts to ensure they are implemented in the most equitable way, focusing on the impact of these strategies on the most under resourced populations. Once the assessment is complete, community partners will be encouraged to work with the Healthy Larimer Committee and the CHIP Equity Process and Toolkit to identify creative ways to ensure equity in their work.

## Identify Opportunities to Expand Efforts to Impact the Most Under Resourced Populations

- The Healthy Larimer Committee, with their wealth of knowledge through lived experience, will be able to identify gaps in our community efforts for specific under resourced populations, identify barriers for these populations, and identify creative ways to utilize community capacity to better reach populations that are most impacted.

## Roles of the CHIP

**Highlight Community Successes** - Through the CHIP dashboard, the great work of our community partners is highlighted in a public way. This provides a structure for CHIP partners to share their updated performance metrics to community members, community organizations, and policy makers to view CHIP partner successes all in one place.

**De-duplicate and Streamline Efforts** - The CHIP framework organized community efforts to be able to easily identify duplicative efforts so that community partners can streamline and collaborate to create efficient partnerships.

**Create Stronger Grant Applications** - Through participation in the CHIP process, community partners not only have the opportunity to include their role within the larger CHIP effort in their grant applications, but can utilize the CHIP framework to quickly identify partners across multiple sectors for a collaborative grant application.



# Healthy Larimer



Following your lead for building a stronger community together

## Healthy Larimer Summit

Leadership at the Larimer County Department of Health and Environment and the CHIP Team, aware of the importance of community input in the prioritization process, determined the best strategy to identify the top public health priorities in Larimer County was through a large health summit with a goal to identify the 2019-2024 CHIP priority areas. In January 2018, the CHIP team convened over 180 community partners to The Healthy Larimer Summit, an all day event that featured data presentations, a partner resource fair, networking, and facilitated prioritization. During the morning session, community partners were presented with Larimer County Community Health Data through a series of presentations around four focus areas:

- What Influences Health?
  - This presentation focused on early childhood health, education, housing, and nutrition.
- Health Insurance and Access to Care
- Mental Health and Substance Abuse
- Built Environment and Environmental Quality


\*These data presentations are available on the Larimer County website.

## Facilitation Process

Following the data presentations, the afternoon session had partners go through an individual and facilitated group prioritization process to start the process of identifying the two main health priorities by the end of the Summit. The CHIP team strategically placed partners representing various public health systems in the community at tables with one facilitator and with partners outside of their professional network to encourage interaction with partners outside of their area of professional experience. Utilizing their professional and personal experience, individuals were asked to write down their top three community priorities on post-it notes and were asked to share their priorities with the rest of their table. Individuals then placed their priorities on a boards with a quadrant chart that measured feasibility and impact. Each person decided how feasible it was to address the health need and the impact addressing this health need would have on community residents. After each person ranked their priorities, the facilitator challenged the table to decide on one priority to report out to the rest of the community partners. This process involved partners, each from different sectors, to work together to identify one priority for their table.



Following the Summit the initial individual priorities identified by partners were grouped into the following categories to show the general health priorities.



All of the yellow bars are related to mental health and substance abuse. The next highest priorities related to housing, healthcare, and early childhood. The red bars, which are racism and LGBTQ+ health, show the importance of ensuring the health priority action areas are equitable and culturally appropriate.

After the tables worked together to identify one priority, each table reported out their priority, which resulted in 15 different identified priority areas. Each individual was given a tool to rank the 15 priorities against each other based on what priority they felt was more important. This gave individuals the opportunity to rank priorities that weren't identified at their table. Facilitators then collected the results of the individual prioritization and reported the results.

The top three priorities after the individual prioritization ranking process were:

1. Behavior/detox center with suicide prevention and general community engagement programs that include school involvement.
2. Emotional wellbeing and mental health resources and providers in the community with a culturally responsive emphasis.
3. Access to childcare.



### Continued work on CHIP Prioritization Process

#### The Leadership Team Review

The CHIP Leadership Team was formed after the Health Summit to provide further insight and approval for the priority areas identified by community partners. The Leadership Team was made up of leaders of large public health related organizations in Larimer County. The team reviewed the priority areas identified at the Summit and combined the top two priority areas into one CHIP priority with focus areas:

Promote Mental and Emotional Wellbeing Across the Lifespan

- Address gaps in required continuum of care
- Substance use disorder and treatment
- Primary prevention

The CHIP Leadership Team then reviewed the third priority identified at the Summit, access to child care, and added focus areas and emphasized quality. This resulted in the second priority area for CHIP:


- Provide Access to Quality Child Care
- Affordability
- Recruitment and retention of the childcare workforce
- Infant and toddler care

#### CHIP Equity Committee Review

Following the Leadership Team review, the revised priorities were then reviewed by an equity committee convened by the CHIP team that consisted of community partners focused on health equity. The committee proposed adding "In an equitable and culturally responsive manner" as a preface to the priorities, to maintain the focus on equity throughout the CHIP process.

#### Final Priority Review

Priorities received final and required approval by the Larimer County Board of Health at a public meeting on March 15, 2018.





# CHIP PROCESS AND PLAN DEVELOPMENT

Following the Board of Health review and approval of the CHIP priority areas, the CHIP Leadership Team focused on the process and plan development starting in March 2018. Development of the CHIP initially focused on three areas:

- Creation of the work plan with existing activities in the community including ownership and evaluation that identified gaps in efforts and possible suggestions of new work to fill gaps
- Development of the CHIP Health Equity Process and Matrix
- Community engagement and Healthy Larimer Committee recruitment


## Creation of the Work Plan

Development of a CHIP work plan that incorporated work already going on in Larimer County within the priority areas allowed for continued collaboration between CHIP and community partners, a clear understanding of where there were duplication of efforts, and identification of gaps. The CHIP team also focused on identifying evaluation metrics so that the community can celebrate the successes of small and large projects alike and organizations can support each other in meeting their targets.

## Goal Development - Promote Mental and Emotional Wellbeing Across the Lifespan

The CHIP team convened a meeting of community partners working within the CHIP priority area to identify existing work within the community as it related mental and emotional wellbeing. From this effort, seven goals were collaboratively developed.

To address gaps in the required continuum of care, the seven goals move through a continuum of care model starting with promotion and followed by prevention, treatment, and recovery (the CHIP is calling this after care).



To address primary prevention the initial goal addresses risk and protective factors. Sub Item #15. use was intentionally incorporated into each goal to ensure it remains a focus. Each goal also contains a focus on health equity and cultural consciousness to incorporate the preface “In a culturally responsive manner,” that comes before the CHIP priorities. The goals are the following:

Primary Prevention Goal:

With a focus on equity, increase environmental protective factors and decrease environmental risk factors for mental health/substance use and increase resiliency.



Moving through the continuum of care:

Promotion Goal:

1. Increase awareness and decrease stigma around mental health/substance use in a culturally responsive way.

Treatment Goals:

2. Increase culturally responsive preventative support efforts and referrals to non-clinical mental health/substance use support efforts.
3. Promote the importance of culturally conscious early clinical detection and screening for mental health/substance use needs.
4. With a focus on equity, streamline referral processes and resource repositories for easier and more appropriate mental health/substance use referrals and de-duplication of efforts.

5. Enhance and expand access to mental health/substance use resources and providers that are culturally and linguistically appropriate for our populations.

After Care Goal:

6. With a focus on equity, identify gaps and enhance best practice after care in mental health/substance use.



## Development of Objectives - Promote Mental and Emotional Wellbeing Across the Lifespan

Within each goal, objectives were created to further specify areas of focus within the goal. In order to address “across the lifespan” within the priority, the objectives were organized into four categories: older adults, adults, youth, and early childhood. Each age category has an objective that works to meet the overall goal. These categories were created to ensure that the CHIP maintains focus across the lifespan throughout implementation.

## Goal and Objective Development - Provide Access to Quality Childcare

Item #15.

The CHIP team convened a meeting of community partners working within the CHIP priority area of Providing Access to Quality Child Care to brainstorm the work that was going on in the community. With this list of efforts, the CHIP team developed the action plan, building out four outcomes that, in coordination, result in access to quality childcare, and eight goals. This Action Plan was sent back to the community partners for edits and final approval.



## Collaborative Strategy Identification

Once these goals and objectives were identified, the CHIP team again convened a community meeting with partners to review the goals and objectives. At this meeting, organizations and partnerships already working on promoting mental and emotional wellbeing across the lifespan and providing access to quality child care were asked to write out each of the strategies that they were working on and assign it to a particular objective. This gave the CHIP team and the representatives from organizations and partnerships a good idea of where work was already happening within the objectives and highlighted some major gaps. Additionally, for every strategy submitted, the organizations and partnerships were asked to provide at least one measurement of success. These measurements help visualize the successes within the community around all of these strategies. The CHIP team is collecting data around longer term community level data, such as suicide rates, percentage of people reporting needing mental health services, capacity of licensed child care facilities and number of families needing child care services to measure the longer term community level impacts of this work.




# HEALTH EQUITY PROCESS AND MATRIX DEVELOPMENT

The CHIP Equity Committee was formed because of the CHIP focus on equity and cultural responsiveness. This committee, made up of public health professionals in the community, was initially tasked with two major projects. First, developing guidelines to ensure that new CHIP strategies were developed and implemented in an equitable and culturally responsive manner. Second, developing an equity evaluation matrix that could serve as a tool in evaluating strategies for equity and cultural responsiveness for specific under resourced populations. While these tools will serve very specific purposes in the governing of new CHIP efforts, the CHIP Equity Committee developed the tools to be available for community organizations and partnerships already working in the priority areas to measure the equity and cultural responsiveness of their work. Members of the CHIP Equity Committee are able to provide assistance to organizations and coalitions wanting to work on improving their work for a specific population.

After the development of the CHIP Health Equity Process and Matrix (full version available on our website) the CHIP team rebranded the CHIP Health Equity Committee to the Healthy Larimer Committee. Focus and membership of the committees shifted from a committee charged with developing health equity processes by a team of public health professionals, to a CHIP advisory committee made up of community members drawing from their lived experience to make decisions.

## CHIP Health Equity Process



### 1. IDENTIFY

Clearly identify the range of social, economic, policy, system, and environmental conditions that influence health inequities among a group of people, using existing data tools, such as resource guides, program evaluations, and assessments to begin to understand and identify needs.

**Engage:** Listen to and build an understanding of the historical and current role of laws, policies, and practices that created and maintained the inequities being experienced. Incorporate the lived experiences of those in the affected groups, which will help further identify their needs that may or may not be reflected by existing data.

### 2. ASSESS COMMUNITY READINESS

Use data to support the identified needs, with consideration of the political will around this work for this population, and research if work like this has been done previously and its positive or negative effects on this population.

**Engage:** Through meaningful and trusting community engagement, assess community readiness around identified needs.

### 3. SHARE POWER

Support, and meaningfully engage, representatives from affected groups in partnerships, coalitions, or leadership teams. Lived experiences are valued and contribute to the co-development, adoption, and promotion of a shared agenda, narrative, and resources to address needs.

### 4. ANALYZE

Ensure the selection, design, and implementation of strategies are linked to inequities identified and will work to advance health equity. Use Health Equity Matrix and community-based participatory research and qualitative methods to ground-truth and bring to life quantitative data in order to lift community voice.

### 5. REVIEW

In partnership with community representatives for the targeted population, review evaluation and monitoring plans, and communication plans to ensure the effects will be measured.

Additionally, ensure that data, including substantial community input from residents, will be collected to analyze the desired effects of each strategy across population groups. If data, including community voice, is not showing desired community impact, the targeted population can change directions or stop work altogether.



A major element of equity in a community-driven plan is community engagement. The CHIP team partnered with The Larimer County Department of Health and Environment after the department received a grant for \$10,000 from the Colorado Trust, to support three different community engagement events at various locations around the county where residents were asked to provide input and suggestions around many areas of public health. The CHIP team designed their engagement activity to to empower community members from under resourced populations to identify potential strategies to promote mental and emotional wellbeing across the lifespan and provide access to quality childcare.



An interactive activity was used at community engagement events to get input around CHIP strategies. Community members were asked to answer two questions: 1) what should be done to improve access to quality child care, and 2) what should be done to improve mental health and wellbeing?

Answers were written on cards and taped next to the question to form a picture.

These three community engagement events kicked off the recruitment effort for the Healthy Larimer Committee, the resident advisory committee for interested community members to provide insight and guidance to the Community Health Improvement Plan and other LCDHE programs. Additional recruitment for the committee happened through outreach to community partners and additional marketing and promotion through flyers posted in public places and social media. Over 60 community members applied for the committee and 26 people were interviewed to fill up to 12 stipend committee spots. Community members were selected based on their willingness to use their lived experience to make decisions.

Final selection for the committee occurred in January 2019 and the first meeting of the committee will occur in February 2019. Committee members will be charged with discussing and developing strategies and action plans for the CHIP priority areas and take a leading role in identifying partners, exploring funding, and building capacity for implementation. Further development and onboarding of the committee will occur in the first part of 2019, with the goal of providing committee members the information and training that will prepare them for strategic decision making.

Through collaborative development, the CHIP Team has outlined the work being done in the priority areas of In an equitable and culturally responsive manner, promote mental and emotional well being across the lifespan and Provide Access to Quality Childcare. Interactive and continually updated work plans are available on the Larimer County website.

**Priority Area 1: In an equitable and culturally responsive manner, promote mental and emotional well being across the lifespan**

Reduce Self-Directed and Intrapersonal Violence

Measure	Target Population	Baseline	2024 Target <sup>20</sup>
Suicide death rate in youth (10-14 and 15-24) per 100,000 <sup>21</sup>	Youth	6.8 14.8	5.44 11.84
Suicide death rate per 100,000 (age-adjusted) <sup>22</sup>	All	20.9	16.72
# of suicides of Larimer County Residents in 2017 <sup>23</sup>	All	75	60
Hospitalization rate due to intentional injury per 100,000 <sup>24</sup>	All	71.1	56.9
% of high school students who reported to have seriously considered attempting suicide during the past 12 months <sup>25</sup>	Youth	15.9%	12.72%
% of adults reporting suicidal thoughts <sup>26</sup>	Adults	7%	5.6%

Increase Number of People who Receive Needed Care

Measure	Target Population	Baseline	2024 Target <sup>27</sup>
% of adults that have insurance that covers mental healthcare <sup>28</sup>	All	66%	73%
% of adults who put off mental healthcare for child due to cost <sup>29</sup>	Youth/Early Childhood	6%	5%
% of people (5 years and older) reporting to need mental health care but not receiving it in the past 12 months <sup>30</sup>	Youth, Adults, Older Adults	8%	7%
% of people (5 years and older) reporting to talk with a general doctor or primary care provider about mental health in the past 12 months <sup>31</sup>	Youth, Adults, Older Adult	17%	19%

Decrease Alcohol, Tobacco, and other Drug Use in Youth and Adults

Measure	Target Population	Baseline	2024 Target <sup>32</sup>
% of adolescents who have never had alcohol <sup>33</sup>	Youth	60.9%	67%
% of adults who are alcohol-free in the past 30 days <sup>34</sup>	Adults	24%	26%
% of adolescents who had never used marijuana <sup>35</sup>	All	67.6%	94%
% of adults who are marijuana-free in the past year <sup>36</sup>	Adults	68%	75%
% of adolescents who have not smoked cigarettes, e-vapor products, or used other tobacco products in the last 30 days <sup>37</sup>	Youth	58.7%	65%
% of adolescents who have had 5 or more drinks on 1 or more of the past 30 days <sup>38</sup>	Youth	15.4%	8.6%*
% of adults who binge drank 1 or more times in the past 30 days <sup>39</sup>	Adults	25%	24.2%*

**Goal 1: Increase environmental protective factors and decrease environmental risk factors for mental health and substance use and increase resiliency among residents of Larimer County.**

**Objective 1.1: Assess the gaps around environmental factors for older adults and identify the community capacity and interest for this work.**

Strategies:

- 1.1.1. Work with the Healthy Larimer Committee to identify priority areas within environmental risk and protective factors for the older adult community.
- 1.1.2. With the guidance of the Healthy Larimer Committee and the Larimer County Board of Health, identify potential community and national partners and assess the capacity and interest in creating a formal partnership around this work.
- 1.1.3. Working with interested community partners and with the guidance of the Healthy Larimer Committee, identify best practice and funding streams to implement strategies focused on environmental factors impacting the older adult community.
- 1.1.4. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on primary prevention for older adults.

**Objective 1.2: Engage in policy change around environmental factors that contribute to mental health and substance use, both as a protective and risk factor for adults.** Item #15.

Strategies:

- 1.2.1. Engage in tobacco policy change processes to reduce prevalence and initiation of tobacco use and exposure to secondhand smoke.
- 1.2.2. Build community support for ordinances, regulations, and requirements for establishments selling liquor, marijuana, or promoting prescription drug use
- 1.2.3. Create a collaborative Persistent Drunk Drivers Prevention Project
- 1.2.4. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on primary prevention.
- 1.2.5. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.

**Objective 1.3: Identify and impact environmental elements that promote substance use, including social norms and policy for youth.**

Strategies:

- 1.3.1. Engage in tobacco policy change processes to reduce prevalence and initiation of tobacco use and exposure to secondhand smoke.
- 1.3.2. Build community support for ordinances, regulations, requirements for establishments selling liquor, marijuana, or promoting prescription drug use.
- 1.2.3. Increase parent engagement and positive conversations around substance use with children through the Speak Now! Parent engagement series.
- 1.2.4. Increase perception that most youth are not using marijuana, alcohol, pills through a Youth Social Norms campaign.
- 1.2.5. Increase positive peer support and commitment within school through Sources of Strength.
- 1.2.6. Increase public knowledge/awareness around issues such as suicide and youth substance use.
- 1.2.7. Reduce youth problem behaviors (substance use, violence, delinquency, etc.) through reducing risk factors and increasing protective factors in Fort Collins and Estes Park.
- 1.2.8. Engage with youth to assess access to tobacco and vaping products.
- 1.2.9. Promote tobacco-free social norms, including school-based tobacco-free policies, community mobilization, or a combination of both, with focus on access to tobacco product strategies.
- 1.2.10. Use of statewide mass media materials to complement policy work focused on environmental risk and protective factors for youth.



- 1.2.11. Provide respite care to families and individuals who need it.
- 1.2.12. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on primary prevention for youth.
- 1.2.13. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.

**Objective 1.4: Expand the early childhood workforce and community capacity to meet the social development and emotional wellbeing needs of families and young children.**

Strategies:

- 1.4.1. Create a system that supports and sustains a culturally responsive family and child-serving workforce. (See CHIP focus area Provide Access to Quality Childcare for more details).
- 1.4.2. Promote infant mental health, including a healthy pregnancy, delivery, and first years.
- 1.4.3. Increase the number of ECE professionals working in the classroom (See CHIP focus area Provide Access to Quality Childcare for more details).
- 1.4.4. Address policy barriers to increase early childhood workforce. (See CHIP focus area Provide Access to Quality Childcare for more details).
- 1.4.5. Ensure that family and child-serving professionals have the skill sets to understand social and emotional development to effectively support families.
- 1.4.6. Assess the capacity and need for respite care to families and individuals who need it in our community.
- 1.4.7. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.
- 1.4.8. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on primary prevention for young children.

**Goal 2: Increase awareness and decrease stigma around mental health and substance use for all ages in Larimer County in a culturally responsive way, focusing on targeting early childhood, youth, specific adult populations, providers, and the Larimer County population overall.**

**Objective 2.1: Provide education to older adults, families of older adults, providers and the community about mental health needs of the aging population, including depression,**

**isolation, and dementia.**

Strategies:

- 2.1.1. Research the viewpoint of providers around mental health for older adults
- 2.1.2. Work with the Healthy Larimer Committee to identify priority areas that focus on education and awareness of the unique mental health needs of older adults
- 2.1.3. With the guidance of the Healthy Larimer Committee and the Larimer County Board of Health, identify potential community and national partners and assess the capacity and interest in creating a formal partnership around this work.
- 2.1.4. Working with interested community partners, and with the guidance of the Healthy Larimer Committee, identify best practice and funding streams to implement strategies focused on education and awareness of older adult mental health.
- 2.1.5. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on education and awareness of mental health in older adults.

**Objective 2.2: Provide education and awareness to the community and providers around mental health and emotional wellbeing, including substance use in the adult population.**

Strategies:

- 2.2.1 Promote suicide prevention webinars in Estes Park.
- 2.2.2. Provide Hope for Today trainings, a free community education program available to any group seeking to understand more about suicide, as well as ways to intervene and save a life.
- 2.2.3. Provide opioid provider education
- 2.2.4. Provide Mental Health First Aid, a free course available to anyone who would like to take it.
- 2.2.5. Raise awareness, improving knowledge/practices of treating people with substance use disorders, targeted at SummitStone, probation, and alternative sentencing organizations and their staff.
- 2.2.6. Increase awareness and decrease stigma about substance use disorders and people with Substance Use Disorders Public Awareness Campaign, targeted to adult/young adult Larimer County residents.
- 2.2.7. Provide QPR trainings to reduce suicidal behaviors by providing innovative, practical, and proven suicide prevention training.
- 2.2.8. Provide opioid awareness messaging to the public.
- 2.2.9. Reduce stigma and increase awareness around pregnancy related depression for women and families, through posters, brochures, and outreach.
- 2.2.10. Increase awareness and decrease stigma around mental health in Larimer County through presentations to the community.
- 2.2.11. Design and implement marketing materials to decrease stigma around seeking mental health services.

2.2.12. Develop and implement campaign around mental health facility ballot initiative.

2.2.13. Provide education that facilitates, promotes, or supports the adoption, implementation, or enforcement of local community or place-based smoke/vapor/tobacco-free policies.

2.2.14. Educate and train health care decision-makers about the health and economic burden imposed by tobacco use and the evidence base for clinical cessation interventions, and the importance of treating tobacco use as a chronic condition.

2.2.15. Develop a primary care provider “toolkit” of materials to instruct and provide information to PCP practices about resources for tobacco cessation, vaping, and marijuana.

2.2.16. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.

2.2.17. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on education and awareness of mental health in adults.

**Objective 2.3: Provide education and awareness around youth mental health and emotional wellbeing in Larimer County.**

Strategies:

2.3.1. Reduce stigma and increase awareness around adolescent depression screening.

2.3.2. Provide the RAPP Program for middle and high school, education and opportunity for referral around suicide.

2.3.4. Support an integrated approach across schools and departments to align efforts around mental, social, and emotional wellbeing in support of the Whole School Whole Child model.

2.3.5. Through education of our families, prevent stigma and address risk factors with youth being raised in kinship care.

2.3.6. Provide Youth Mental Health First Aid.

2.3.7. Provide a family/parent education speaker series on many different mental health needs.

2.3.8. Build public support for a district-wide social and emotional learning curriculum.

2.3.9. Provide education that facilitates, promotes, or supports the adoption, implementation, or enforcement of local community or place-based smoke/vapor/tobacco-free policies.

2.3.10. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.

2.3.11. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan,

focusing on education and awareness of mental health in youth.

**Objective 2.4: Increase knowledge of child development and early childhood needs in order to create and maintain community environments that are supportive of social development and emotional wellbeing for all families and young children.**

Strategies:

2.4.1. Promote social norms and policies that improve environments for social and emotional wellbeing.

2.4.2. Create universal access to parenting information around social and emotional development, with an emphasis on channels and locations already used by parents.

2.4.3. Expand access to training and community resources through an annual large forum and follow-up Community Conversations

2.4.4. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.

2.4.5. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on education and awareness of mental health in young children.

**Goal 3: Increase culturally responsive preventative support efforts and referrals to non-clinical supports for at risk individuals across the lifespan.**

**Objective 3.1: Assess the need and capacity, develop partnerships, and create and promote programs that support the mental health needs of older adults and their families, and promote and refer to existing groups.**

Strategies:

3.1.1. Work with the Healthy Larimer Committee to identify priority areas that focus on providing mental health supports efforts and referrals to non-clinical supports.

3.1.2. With the guidance of the Healthy Larimer Committee and the Larimer County Board of Health, identify potential community and national partners and assess the capacity and interest in creating a formal partnership around this work.

3.1.3. Working with interested community partners, and with the guidance of the Healthy Larimer Committee, identify best practice and funding streams to implement strategies focused on providing mental health supports efforts and referrals to non-clinical supports.

3.1.4. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on providing non-clinical supports for older adults.

**Objective 3.2: Assess the need for, create, and promote support groups for adult populations who are not already being served, especially focused on the under-resourced communities, and promote and refer to existing groups.**

Strategies:

- 3.2.1. Participate in provider training for appropriate mental health screening (including PRD, SU) and referrals.
- 3.3.2. Assess for, and implement and evaluate parent education and parent support groups for adoptive parents of traumatized children/youth (TAPT-IN).
- 3.3.3. Provide referral to support resources for women in Larimer County communities through outreach at school fairs, and posters and brochures.
- 3.3.4. Promote and support the widespread adoption of tobacco cessation interventions, including environmental approaches, in a variety of medical and social services settings.
- 3.3.5. Support the reduction of barriers to accessing cessation services by integrating treatment and referral processes into existing medical and social care settings and promoting availability of low or no cost cessation benefits.
- 3.3.6. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.
- 3.3.7. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on providing non-clinical supports for adults.

**Objective 3.3: Assess the need for, create, and promote support groups for youth populations who are not already being served, and promote and refer to existing groups.**

Strategies:

- 3.3.1. Have LCDHE Family Planning providers participate in provider training for appropriate mental health screening (including PRD, SU) and referrals.
- 3.3.2. In Estes Park School District, implement wellness plans that could include counselors and suicide prevention strategies.
- 3.3.3. Support the reduction of barriers to accessing cessation services by integrating treatment and referral processes into existing medical and social care settings and promoting availability of low or no cost cessation benefits.
- 3.3.4. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.
- 3.3.5. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on providing non-clinical supports for youth.

**Objective 3.4: Build and Strengthen community relationships to encourage social development and emotional wellbeing for families and young children.**

Strategies:

- 3.4.1. Leverage existing family networks and champions to increase support for families, including support for all types of caregiver networks.
- 3.4.2. Promote relationships among community professionals to build “no wrong door” approach in order to increase families’ access to services and referrals.
- 3.4.3. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.
- 3.4.4. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on providing non-clinical supports for young children.

**Goal 4: Increase the amount of early clinical detection and screening for mental health needs across the lifespan.**

**Objective 4.1: Increase early clinical detection and screening for mental health needs for older adults.**

Strategies:

- 4.1.1. Improve PASRR system
- 4.2.1. Promote Zero Suicide and CAMS training in health systems and with providers
- 4.2.2. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.
- 4.2.3. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on early clinical detection and screening for mental health needs in older adults.
- 4.2.4. Train Larimer County Clinical Staff in CAMS.

**Objective 4.2: Increase early clinical detection and screening for mental health needs for adults.**

Strategies:

- 4.2.1. Increase the screening for mental health upon police intervention.
- 4.2.2. Promote Zero Suicide and CAMS training in health systems and with providers.
- 4.2.3. Begin implementation of modified Zero Suicide framework within Larimer County



Department of Health and Environment.

4.2.4. Train Larimer County Clinical Staff in CAMS.

4.2.5. Expanding SBIRT ( Screening, Brief Intervention, and Referral to Treatment) model in Larimer County, targeted at primary care practices and practitioners.

4.2.6. Promote screening and tools for screening to providers and families.

4.2.7. Provide education and technical assistance to maximize opportunities to screen for tobacco use and link tobacco users to evidence-based tobacco dependence counseling and medications.

4.2.8. Educate and train health care decision makers about the health and economic burden imposed by tobacco use and the evidence base for clinical cessation interventions and the importance of treating tobacco use as a chronic condition.

4.2.9. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.

4.2.10. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on early clinical detection and screening for mental health needs in adults.

**Objective 4.3: Increase screening and referral for youth.**

Strategies:

4.3.1. Encourage adolescent depression screening as part of a well child exam

4.3.2. When contacting families on Medicaid/CHP+, promote early clinical detection in youth in kinship care, including mental health, suicide, and drug abuse.

4.3.3. Promote Zero Suicide and CAMS training in health systems and with providers

4.3.4. Promote identifying friends or self who could be at risk for suicide through the R.A.P.P program

4.3.5. In Estes Park Schools, implement screenings.

4.3.6. Provide education and technical assistance to maximize opportunities to screen for tobacco use and link tobacco users to evidence-based tobacco dependence counseling and medications.

4.3.7. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.

4.3.8. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on early clinical detection and screening for mental health needs in youth.

**Objective 4.4: Develop and utilize resources to support early identification of social and**

**emotional concerns for families**

Strategies:

4.4.1. Support a coordinated system for developmental monitoring and screening for children for social and emotional concerns.

4.4.2. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.

4.4.3. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on early clinical detection and screening for mental health needs in young children.

**Goal 5: Streamline referral processes and resource repositories for easier and more appropriate referral and de-duplication of efforts.**

**Objective 5.1: Identify best process for connecting older adults with appropriate resources and educate providers and community partners.**

Strategies:

5.1.1. Promote Senior Access Points information (larimerseniors.org & Office on Aging phone number) to connect older adults to mental health services.

5.1.2. Convene all parties creating resource guides and streamline efforts.

5.1.3. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.

5.1.4. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on connecting older adults with appropriate resources.

**Objective 5.2: Identify best process for connecting adults with appropriate resources and educate providers and community partners.**

Strategies:

5.2.1. Assist families with Medicaid/CHP+ in finding appropriate mental health resources

5.2.2. Create List of Mental Health providers in Estes Park

5.2.3. Refer those those in need to resources needed versus continuing the Criminal

Justice Cycle.

- 5.2.4. Continue the work of the AIM Program and Wellness Court
- 5.2.5. Continue to enhance the formal partnership between Criminal Justice and SummitStone, with SummitStone providing a re-entry specialist to connect individuals with outside mental health providers as they transition out of the CJ system
- 5.2.6. Promote the provider toolkit, which outlines best referral to treatment from provider to patients to ensure treatment is received and condition is treated for pregnancy related depression.
- 5.2.7. Expand the SBIRT model in Larimer County.
- 5.2.8. Increase referrals to appropriate tobacco treatment services.
- 5.2.9. Connect primary care providers to behavioral health resources to close the communication gap between primary care providers and behavioral health providers.
- 5.2.10. Provide HIPAA training to BH providers to increase comfort around sharing needed information with primary care providers.
- 5.2.11. Create and promote provider portal as a one stop shop for information around mental health for providers.
- 5.2.12. Provide education and technical assistance to maximize opportunities to screen for tobacco use and link tobacco users to evidence-based tobacco dependence counseling and medications.
- 5.2.13. Work with health systems to support the reduction of barriers to accessing cessation services by integrating treatment and referral processes into existing medical and social care settings and promoting availability of low or no cost cessation benefits, including those offered through the Colorado QuitLine and Medicaid.
- 5.2.14. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.
- 5.2.15. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on connecting adults with appropriate resources.
- 5.2.16. Convene all parties creating resource guides and streamline efforts.

**Objective 5.3 Identify best process for connecting youth with appropriate resources and educate providers and community partners.**

Strategies:

- 5.3.1. Through Healthy Communities, assist families with Medicaid/CHP+ in finding appropriate mental health resources.
- 5.3.2. Work with school liaisons to better coordinate with families, schools and TX providers.
- 5.3.3. Develop sustainable process for referrals from R.A.P.P.

5.3.4. Implement Trauma assessment and treatment recommendations for kids.

Item #15.

- 5.3.5. Include education about vaping and potential health impacts.
- 5.3.6. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.
- 5.3.7. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on connecting youth with appropriate resources
- 5.3.8. Convene all parties creating resource guides and streamline efforts.

**Objective 5.4 Develop and utilize resources to support appropriate referrals and intervention of social and emotional concerns for families and young children in Larimer County.**

Strategies:

- 5.4.1. Through Healthy Communities, assist families with Medicaid/CHP+ in finding appropriate mental health resources.
- 5.4.2. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.
- 5.4.3. Work with the Healthy Larimer Committee to identify priority areas that focus on supporting appropriate referrals and interventions for the social and emotional concerns for families and young children.
- 5.4.4. With the guidance of the Healthy Larimer Committee and the Larimer County Board of Health, identify potential community and national partners and assess the capacity and interest in creating a formal partnership around this work.
- 5.4.5. Working with interested community partners, and with the guidance of the Healthy Larimer Committee, identify best practice and funding streams to implement strategies focused on supporting appropriate referrals and interventions for the social and emotional concerns for families and young children.
- 5.4.6. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on connecting young children with appropriate resources

**Goal 6: Enhance and expand access to mental health resources and providers that are culturally and linguistically appropriate for our populations.**

**Objective 6.1: Assess the need for mental health providers skilled in working with older adults across the continuum of care and who accept medicare, and identify ways to fill those gaps.**

Strategies:

- 6.1.1. Assess the gap in behavioral health providers who accept Medicare.
- 6.1.2. Work with the Healthy Larimer Committee to identify priority areas that focus on enhancing and expanding culturally appropriate providers across the continuum of care who accept Medicare and are skilled in working with older adults.
- 6.1.3. With the guidance of the Healthy Larimer Committee and the Larimer County Board of Health, identify potential community and national partners and assess the capacity and interest in creating a formal partnership around this work.
- 6.1.4. Working with interested community partners, and with the guidance of the Healthy Larimer Committee, identify best practice and funding streams to implement strategies focused on enhancing and expanding culturally appropriate providers across the continuum of care who accept medicare and are skilled in working with older adults.
- 6.1.5. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on increasing access to mental health providers for older adults.

**Objective 6.2: Assess the need for mental health providers across the continuum of care, and identify ways to fill those gaps for adults.**

Strategies:

- 6.2.1. Assess the gap in behavioral health providers for adults across the continuum of care.
- 6.2.2. Promote Wellness Court/Aim Program for offenders with identified mental health issues.
- 6.2.3. Provide Medicaid resources for non-convicted but incarcerated
- 6.2.4. Enhance/improve approach to “frequent utilizers” of high cost, crisis, and acute services.
- 6.2.5. Coordinate prescription services in criminal justice system through treatment programs, short term programs, and intensive residential programs.
- 6.2.6. Support activities that focus on advancing health equity and eliminating tobacco-related health disparities by intentionally incorporating these activities into the work of each tobacco-related strategy area.
- 6.2.7. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on increasing access to mental health providers for adults.
- 6.2.8. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.
- 6.2.9. Increase access to Medication Assisted Treatment (MAT) in Larimer County.

**Objective 6.3: Assess the need for mental health providers across the continuum of care and identify ways to fill those gaps for youth.** Item #15.

Strategies:

- 6.3.1. Assess the gap in behavioral health providers for youth across the continuum of care.
- 6.3.2. Work with the Healthy Larimer Committee and the Larimer County Behavioral Health Division to identify way to fill gaps in the provision of services across the continuum of care.
- 6.3.3. With the guidance of the Healthy Larimer Committee and the Larimer County Board of Health, identify potential community and national partners, including the Larimer County Behavioral Health Division, and assess the capacity and interest in creating a formal partnership around this work.
- 6.3.4. Working with interested community partners, and with the guidance of the Healthy Larimer Committee, identify best practice and funding streams to implement strategies that fill gaps in the provision of services across the continuum of care for youth.
- 6.3.5. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on increasing access to mental health providers for youth.

**Objective 6.4: Mobilize and coordinate system of support for early intervention and intensive and therapeutic interventions for families and young children in Larimer County.**

Strategies:

- 6.4.1. Identify and mobilize supports for caregivers of high needs children.
- 6.4.2. Utilize a family centered and culturally-responsive approach to support families and children in need of intensive intervention.
- 6.4.3. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.
- 6.4.4. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on increasing access to mental health providers for young children.

**Goal 7: Identify gaps and enhance best practice aftercare in Larimer County.**

**Objective 7.1: Identify gaps and enhance best practice aftercare for older adults in Larimer County.**



Strategies:

- 7.1.1. Work with the Healthy Larimer Committee to identify gaps and enhance best practice in after care for older adults in Larimer County.
- 7.1.2. With the guidance of the Healthy Larimer Committee and the Larimer County Board of Health, identify potential community and national partners, and assess the capacity and interest in creating a formal partnership around this work.
- 7.1.3. Working with interested community partners, and with the guidance of the Healthy Larimer Committee, identify best practice and funding streams to implement strategies that focus on enhanced aftercare for older adults in Larimer County.
- 7.1.4. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on enhancing aftercare for older adults in Larimer County.

**Objective 7.2: Identify gaps and enhance best practice aftercare for adults in Larimer County.**

Strategies:

- 7.2.1. Work with the Healthy Larimer Committee to identify gaps and enhance best practice in after care for adults in Larimer County.
- 7.2.2. With the guidance of the Healthy Larimer Committee and the Larimer County Board of Health, identify potential community and national partners, and assess the capacity and interest in creating a formal partnership around this work.
- 7.2.3. Working with interested community partners, and with the guidance of the Healthy Larimer Committee, identify best practice and funding streams to implement strategies that focus on enhanced aftercare for adults in Larimer County.
- 7.2.4. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on enhancing aftercare for adults in Larimer County.

**Objective 7.3: Identify gaps and enhance best practice aftercare for youth in Larimer County.**

Strategies:

- 7.3.1. Work with the Healthy Larimer Committee to identify gaps and enhance best practice in after care for youth in Larimer County.
- 7.3.2. With the guidance of the Healthy Larimer Committee and the Larimer County Board of Health, identify potential community and national partners, and assess the capacity and interest in creating a formal partnership around this work.
- 7.3.3. Working with interested community partners, and with the guidance of the Healthy Larimer Committee, identify best practice and funding streams to implement strategies that focus on enhanced aftercare for youth in Larimer County.

- 7.4.4. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on enhancing aftercare for youth in Larimer County. Item #15.

**Objective 7.4: Identify gaps and enhance best practice aftercare for young children in Larimer County.**

Strategies:

- 7.4.1. Work with the Healthy Larimer Committee to identify gaps and enhance best practice in after care for young children in Larimer County.
- 7.4.2. With the guidance of the Healthy Larimer Committee and the Larimer County Board of Health, identify potential community and national partners, and assess the capacity and interest in creating a formal partnership around this work.
- 7.4.3. Working with interested community partners, and with the guidance of the Healthy Larimer Committee, identify best practice and funding streams to implement strategies that focus on enhanced aftercare for young children in Larimer County.
- 7.4.4. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote mental and emotional wellbeing across the lifespan, focusing on enhancing aftercare for young children in Larimer County.

**Priority Area 2: In an equitable and culturally responsive manner, Provide Access to Quality Child Care**

Access to Quality Child Care

Measure	Target Population	Baseline	2024 Target
Ratio of estimated # of young children in need of Childcare to # of Licenced Childcare Spots <sup>40</sup>	Early Childhood, Families	1.9	1.5 <sup>41</sup>
Average cost per year per child for childcare <sup>42</sup>	Early Childhood, Families	\$12,000	N/A
# of C-CAP Dollars to support families in need of financial support for childcare	Early Childhood, Families	\$5,371,661	N/A
% of programs at a Level 2 or higher Colorado Shines score <sup>43</sup>	Early Childhood, Families	59%	65%

Recruitment and Retention of the Child Care Workforce

Measure	Target Population	Baseline	2024 Target
% of ECE Directors reporting staffing challenges <sup>44</sup>	Early Childhood, Families	65%	

Infant and Toddler Care

Measure	Target Population	Baseline	2024 Target
Ratio of # of infant and toddler in need of Childcare to # of Licenced Infant and Toddler Childcare Spots <sup>45</sup>	Early Childhood, Families	3.9	1.5 <sup>46</sup>

Outcome 1: Provide Quality support for Early Childhood Educators

**Goal 1.1. Provide technical support for licensed programs to enhance the quality of the care they provide.**

Strategies:

- 1.1.1. For licensed child care programs, provide coaching and quality improvement dollars.
- 1.1.2. For level 1 licensed programs, provide support to increase to level 2, including training for staff, and self assessment technical assistance.
- 1.1.3. Continue to support Quality Improvement efforts for licensed program
- 1.1.4 Working with the Larimer County Board of Health, support policies at the local, state, and national level that provide technical support for licensed program, enhancing the quality of the care they provide.
- 1.1.5. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.

**Goal 1.2. Provide professional development opportunities for Early Childhood care and education providers to enhance quality early childhood care and education**

Strategies:

- 1.2.1 Provide trainings and workshops for early childhood care and education providers.
- 1.2.2. Provide scholarships to early childhood care and education providers for credentially classes.
- 1.2.3. Provide Quality Improvement Resources to programs.
- 1.2.4. Working with the Larimer County Board of Health, support policies at the local, state, and national level that provides professional development opportunities for Early

Childhood care and education providers.

1.2.5. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.

**Goal 1.3. Provide additional opportunities to enhance early childhood care and education experience to ECE providers**

Strategies:

- 1.3.1. Provide enrichment opportunities free of cost to early childhood care and education centers.
- 1.3.2. Work with the Healthy Larimer Committee to identify gaps in the provision of opportunities to enhance early childhood care and education experiences to ECE providers.
- 1.3.3. With the guidance of the Healthy Larimer Committee and the Larimer County Board of Health, identify potential community and national partners, and assess the capacity and interest in creating a formal partnership around this work.
- 1.3.4. Working with interested community partners, and with the guidance of the Healthy Larimer Committee, identify best practice and funding streams to provide opportunities to enhance early childhood care and education experiences to ECE providers.
- 1.3.5. Working with the Larimer County Board of Health, support policies at the local, state, and national level that provides opportunities to enhance early childhood care and education experiences to ECE providers.

**Outcome 2: Recruit and retain quality early childhood care and education providers to enhance capacity of licensed early childhood care and education positions for young children 0-5.**

**Goal 2.1. Recruit new early child care providers for the early care and education workforce.**

Strategies:

- 2.1.1. Run a campaign and provide information to recruit FCCH providers.
- 2.1.2. Market and recruit for newly created alternative pathways for entering the ECE field.
- 2.1.3. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote the recruitment of new early childhood care and education providers into the workforce.
- 2.1.4. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to



promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.

### **Goal 2.2. Support newly recruited teachers by enhancing work environments.**

Strategies:

- 2.2.1. Train quality mentor teachers for new ECE cohort participants.
- 2.2.2. Develop and implement a cultural competency training curriculum for ECE programs employing cohort participants.
- 2.2.3. Working with the Larimer County Board of Health, support policies at the local, state, and national level that promote enhanced work environments for newly recruited teachers.
- 2.2.4. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.

### **Goal 2.3. Create new additional pathways for people entering the ECE field**

Strategies:

- 2.3.1. Develop and submit a community level waiver to allow programs at a level 3 or higher Colorado Shines score to hire provisional early childhood teachers, who have not yet completed all qualifications, with the expectation that they will become qualified within 12 months.
- 2.3.2. Develop and submit a community level waiver that would reduce the number of hours participants in the cohort program need to qualify as an EC teacher.
- 2.3.3. Design and implement a cohort program for college students in ECE introductory courses.
- 2.3.4. Design and implement a federally qualified apprenticeship program for high school students interested in early childhood education.
- 2.3.5. Working with the Larimer County Board of Health, support policies at the local, state, and national level that create additional pathways for people entering the Early Childhood Care and Education field.
- 2.3.6. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.

Outcome 3: Identify and advocate for policy and strategies that impacts early childhood care and education capacity and affordability

### **Goal 3.1. Respond to and advocate for policies that impact early childhood and education capacity and affordability**

Item #15.

Strategies:

- 3.1.1 Utilize ECCLC waiver authority, as appropriate, to address community wide early childhood care and education regulatory barriers.
- 3.1.2 Identify a set of policy recommendations for communities around capacity.
- 3.1.3. Advocate for House bill 18-14-20, that will allow for a special taxing district for early childhood care and education so that individuals living in unincorporated spaces will be contributing to any approved taxes to support early childhood care and education.
- 3.1.4. Explore and identify tax-based funding solutions for the crisis in Estes Park.
- 3.1.5. Provide Estes Town Board recommendations that would support early childhood care and education for the strategic plan.
- 3.1.6. Provide information to parents about the importance of quality early childhood care and education.
- 3.1.7. Working with the Larimer County Board of Health, support policies at the local, state, and national level that impact early childhood care education capacity and affordability.
- 3.1.8. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.

### **Goal 3.2. Explore additional policies and strategies that impact early childhood care and education capacity and affordability and identify solutions.**

Strategies:

- 3.2.1. Utilize a task force of both early childhood care and education industry representation and non-traditional partners, including business and other non-traditional leaders (Bohemian/businesses), to analyze the issues around capacity and affordability and identify solutions.
- 3.2.2. Create a policy scan of local, state, and federal policies that could affect child care centers and in-home care and identify particularly difficult navigation points, barriers to early childhood care and education centers and homes, and policies that may contradict one another.
- 3.2.3. Design and implement a cost effective business model for early childhood care and education in Estes Park to share resources and alleviate costs.
- 3.2.4. Create an ECE enterprise fund large enough to support matching grant opportunities in Estes Park.
- 3.2.5. Working with the Larimer County Board of Health, support policies at the local,

state, and national level that impact early childhood care and education capacity and affordability and identify solutions.

3.2.6. Working with the Healthy Larimer Committee, assess existing work for equity, utilizing the Health Equity Matrix, propose enhancements around existing strategies to promote equity, identify gaps, and determine if developing and implementing additional strategies is a priority.

Outcome 4: Alleviate the cost burden of early childhood care and education for families

**Goal 4.1. Provide direct financial assistance to families for early childhood care and education.**

Strategies:

4.1.1. Provide public dollars to families in need to assist with early childhood care and education.

4.1.2. Provide scholarships to Estes Park families.

4.1.3. Provide information to families to connect them to early childhood care and education and scholarship opportunities.

4.1.4. Work with the Healthy Larimer Committee to identify gaps in financial assistance for early childhood care and education.

4.1.5. With the guidance of the Healthy Larimer Committee and the Larimer County Board of Health, identify potential community and national partners, and assess the capacity and interest in creating a formal partnership around this work.

4.1.6. Working with interested community partners, and with the guidance of the Healthy Larimer Committee, identify best practice and funding streams to implement strategies that focus providing financial assistance to families for early childhood care and education.


4.1.7. Working with the Larimer County Board of Health, support policies at the local, state, and national level that increases financial assistance to families for early care and education.

## EVALUATION OF THE CHIP ACTION PLAN

Item #15.

While the overall success of the Community Health Improvement Plan will be determined by an increase or decrease in community-level metrics in the next 5 years, it is also important to have continuous monitoring and evaluation of strategies within the Community Health Improvement Plan to keep track of short-term successes and opportunities for enhanced collaboration. The CHIP Team, in collaboration with community partners, utilized the CDC Evaluation Framework as a basis for evaluating the CHIP work.

The CHIP Team, after engaging community partners, developing the work plan framework, and identifying strategies, worked with each community partner involved in the CHIP to develop evaluation metrics for their strategies. Community partners will be continuously reporting on metrics throughout the five years of the plan implementation timeline and the CHIP Team and the Healthy Larimer Committee will be facilitating collaborative performance update and quality improvement opportunity discussions with representatives from the involved community agencies and organizations.



The Larimer County Board of Health serves as the high level governing entity of the Community Health Improvement Plan. The Board signed off on the priority areas of the CHIP in March 2018 and approved the final CHIP in February 2019. The Board of Health can determine how involved they would like to be in CHIP efforts and may be asked by the CHIP team for approval on advocating for policy changes around CHIP priorities as needed though the five-year implementation. Larimer County Department of Health and Environment supports the Community Health Improvement Plan. Many programs within the Health Department are written into the plan and the Department as a whole is focused on supporting these priority areas both internally and in the community.


### Leadership Committee

The CHIP Leadership Committee was formed to provide further insight and approval for the priority areas identified by community partners. This committee met once to provide guidance and approval on priority areas. Although some members of this Leadership Committee will continue to be involved with CHIP, the committee does not have a governing role moving forward.

### Healthy Larimer Committee

The Healthy Larimer Committee serves as the community-level advisory board for CHIP. The committee is made up of community members in Larimer County who are willing to share their lived experience to guide CHIP efforts. Although the Larimer County Board of Health provides final sign-off on the CHIP, the Healthy Larimer Committee will be the highly involved advisory group that makes the smaller ongoing recommendations for CHIP. As CHIP continues to move into development and implementation of strategies, the Healthy Larimer Committee will advise on strategies to ensure implementation in an equitable and culturally responsive manner.

# CHIP Structure





## ONGOING CHIP EFFORT

The strategies prioritized by the CHIP Equity Committee will be written into the work plan, and the CHIP team will work on forming partnerships, securing funding, and developing evaluation protocol, as directed by the Equity Committee to further develop and implementing these strategies in an equitable and culturally responsive manner. Although the CHIP team will help drive these efforts at the beginning, LCDHE does not need to be the backbone organization to move these priority areas forward if another more appropriate organization/coalition is identified and willing to move the strategy forward

The CHIP team will continue to support ongoing community efforts being led by other coalitions and organizations, including consistent monitoring and evaluation, partnership development, funding and best practice research, and promoting of opportunities for equity and cultural responsiveness. The new strategies, as well as existing efforts, are documented and updated on the Community Health Improvement Plan work plans as well as on the Community Health Improvement Plan Dashboard, available at <http://bit.ly/LCDHECHIPprogress>. Additionally, a detailed plan for the CHIP Team's internal work and goals is available at <http://bit.ly/CHIPworkplan>.

## INTEGRATION WITH STATEWIDE PLAN

This plan follows the Colorado Health Assessment and Planning System (CHAPS) created by the Office of Planning and Partnerships at CDPHE and aligns with the assessment and planning goal of the statewide health improvement plan.

## FINANCIAL RESOURCES

Larimer County Department of Health and Environment continually seeks ways to develop and sustain funding sources for the delivery of core services and additional programming to meet the needs of the community.





1. United States Census. Available at: <https://www.census.gov/quickfacts/fact/table/larimercountycolorado/PST045218>
2. United States Census Fact Finder. Available at: <https://factfinder.census.gov/>
3. Larimer County Economic Development Report 2017. Available at: [larimerworkforce.org/wp-content/uploads/WDB-Economic-and-Workforce-Health-Report-Updated-February-2017-.pdf](http://larimerworkforce.org/wp-content/uploads/WDB-Economic-and-Workforce-Health-Report-Updated-February-2017-.pdf)
4. Early Childhood Council of Larimer County. Available at: <https://ecclc.org/app/uploads/2018/10/Average-Cost-of-Care-in-Larimer-County-09.2018-1.pdf>
5. Early Childhood Council of Larimer County Cost Report. Available at: [https://drive.google.com/file/d/1It5IHOF6coEAS\\_IKO5hkHChEfz8n7YaA/view](https://drive.google.com/file/d/1It5IHOF6coEAS_IKO5hkHChEfz8n7YaA/view)
6. Colorado Department of Education. CMAS - Mathematics, English Language Arts, Science and Social Studies Data and Results <https://www.cde.state.co.us/assessment/cmas-dataandresults>
7. Food Bank for Larimer County. Available at: <https://foodbanklarimer.org/hungers-impact/>
8. Larimer County Economic Development Report 2017. Available at: [larimerworkforce.org/wp-content/uploads/WDB-Economic-and-Workforce-Health-Report-Updated-February-2017-.pdf](http://larimerworkforce.org/wp-content/uploads/WDB-Economic-and-Workforce-Health-Report-Updated-February-2017-.pdf)
9. Health District of Northern Colorado Community Health Assessment. Available at: [LarimerHealthTracker.org](http://LarimerHealthTracker.org)
10. [http://www.cde.state.co.us/dropoutprevention/homeless\\_data](http://www.cde.state.co.us/dropoutprevention/homeless_data)
11. Health District of Northern Colorado Community Health Assessment. Available at: [LarimerHealthTracker.org](http://LarimerHealthTracker.org)
12. Colorado Department of Public Health and Environment [Internet]. Healthy Kids Colorado Survey. High School Data 2015. Region 2. Available at: [http://www.chd.dphe.state.co.us/topics.aspx?q=Adolescent\\_Health\\_Data](http://www.chd.dphe.state.co.us/topics.aspx?q=Adolescent_Health_Data)
13. Colorado Violent Death Reporting System. Available at: <https://www.colorado.gov/pacific/cdphe/colorado-violent-death-reporting-system>
14. The Colorado Health and Hospital Association Injury Hospitalization Dataset. Available at: <http://www.cohid.dphe.state.co.us/>
15. Colorado Department of Public Health and Environment [Internet]. Healthy Kids Colorado Survey. High School Data 2015. Region 2. Available at: [http://www.chd.dphe.state.co.us/topics.aspx?q=Adolescent\\_Health\\_Data](http://www.chd.dphe.state.co.us/topics.aspx?q=Adolescent_Health_Data)
16. Health District of Northern Colorado Community Health Assessment. Available at: [LarimerHealthTracker.org](http://LarimerHealthTracker.org)
17. Colorado Department of Public Health and Environment [Internet]. Healthy Kids Colorado Survey. High School Data 2015. Region 2. Available at: [http://www.chd.dphe.state.co.us/topics.aspx?q=Adolescent\\_Health\\_Data](http://www.chd.dphe.state.co.us/topics.aspx?q=Adolescent_Health_Data)
18. Larimer County Coroner Report, 2015. Available at: <https://www.larimer.org/coroner>
19. The Health District of Northern Larimer County [Internet]. Critical Behavior and Health Services Report. Available at: [http://www.healthdistrict.org/sites/default/files/critical-](http://www.healthdistrict.org/sites/default/files/critical-behavioral-health-services-report-final-april-2016_1.pdf)

- [behavioral-health-services-report-final-april-2016\\_1.pdf](http://www.healthdistrict.org/sites/default/files/critical-behavioral-health-services-report-final-april-2016_1.pdf)
20. Target Values are determined by the Colorado National Collaborative work to decrease suicide burden by 20% by 2024.
21. Colorado Violent Death Reporting System. Available at: <https://www.colorado.gov/pacific/cdphe/colorado-violent-death-reporting-system>
22. Colorado Violent Death Reporting System. Available at: <https://www.colorado.gov/pacific/cdphe/colorado-violent-death-reporting-system>
23. Colorado Violent Death Reporting System. Available at: <https://www.colorado.gov/pacific/cdphe/colorado-violent-death-reporting-system>
24. The Colorado Health and Hospital Association Injury Hospitalization Dataset. Available at: <http://www.cohid.dphe.state.co.us/>
25. Colorado Department of Public Health and Environment [Internet]. Healthy Kids Colorado Survey. High School Data 2015. Region 2. Available at: [http://www.chd.dphe.state.co.us/topics.aspx?q=Adolescent\\_Health\\_Data](http://www.chd.dphe.state.co.us/topics.aspx?q=Adolescent_Health_Data)
26. Health District of Northern Colorado Community Health Assessment. Available at: [LarimerHealthTracker.org](http://LarimerHealthTracker.org)
27. Target Values were calculated using Larimer County’s Strategic Plan goal that includes increase health by 2% annually.
28. Health District of Northern Colorado Community Health Assessment. Available at: [LarimerHealthTracker.org](http://LarimerHealthTracker.org)
29. Health District of Northern Colorado Community Health Assessment. Available at: [LarimerHealthTracker.org](http://LarimerHealthTracker.org)
30. Colorado Health Institute. Colorado Health Access Survey. Available at: <https://www.coloradohealthinstitute.org/data>
31. Colorado Health Institute. Colorado Health Access Survey. Available at: <https://www.coloradohealthinstitute.org/data>
32. Target Values were calculated using Larimer County’s Strategic Plan goal that includes increase health by 2% annually, except for those with an \*. (\* target values were pulled from Healthy People 2020 Goals).
33. Colorado Department of Public Health and Environment [Internet]. Healthy Kids Colorado Survey. High School Data 2015. Region 2. Available at: [http://www.chd.dphe.state.co.us/topics.aspx?q=Adolescent\\_Health\\_Data](http://www.chd.dphe.state.co.us/topics.aspx?q=Adolescent_Health_Data)
34. Health District of Northern Colorado Community Health Assessment. Available at: [LarimerHealthTracker.org](http://LarimerHealthTracker.org)
35. Colorado Department of Public Health and Environment [Internet]. Healthy Kids Colorado Survey. High School Data 2015. Region 2. Available at: [http://www.chd.dphe.state.co.us/topics.aspx?q=Adolescent\\_Health\\_Data](http://www.chd.dphe.state.co.us/topics.aspx?q=Adolescent_Health_Data)
36. Health District of Northern Colorado Community Health Assessment. Available at: [LarimerHealthTracker.org](http://LarimerHealthTracker.org)
37. Colorado Department of Public Health and Environment [Internet]. Healthy Kids Colorado Survey. High School Data 2015. Region 2. Available at: [http://www.chd.dphe.state.co.us/topics.aspx?q=Adolescent\\_Health\\_Data](http://www.chd.dphe.state.co.us/topics.aspx?q=Adolescent_Health_Data)



38. Colorado Department of Public Health and Environment [Internet]. Healthy Kids Colorado Survey. High School Data 2015. Region 2. Available at: [http://www.chd.dphe.state.co.us/topics.aspx?q=Adolescent\\_Health\\_Data](http://www.chd.dphe.state.co.us/topics.aspx?q=Adolescent_Health_Data)
39. Health District of Northern Colorado Community Health Assessment. Available at: [LarimerHealthTracker.org](http://LarimerHealthTracker.org)
40. Early Childhood Council of Larimer County Cost Report. Available at: [https://drive.google.com/file/d/1lt5IHOF6coEAS\\_IKO5hkHChEfz8n7YaA/view](https://drive.google.com/file/d/1lt5IHOF6coEAS_IKO5hkHChEfz8n7YaA/view)
41. Larimer County Strategic Plan 2019-2024.
42. Early Childhood Council of Larimer County. Available at: <https://ecclc.org/app/uploads/2018/10/Average-Cost-of-Care-in-Larimer-County-09.2018-1.pdf>
43. [https://drive.google.com/file/d/1lt5IHOF6coEAS\\_IKO5hkHChEfz8n7YaA/view](https://drive.google.com/file/d/1lt5IHOF6coEAS_IKO5hkHChEfz8n7YaA/view)
44. Early Childhood Council. Staffing Challenges 2012-2016 Presentation.
45. Early Childhood Council of Larimer County Cost Report. Available at: [https://drive.google.com/file/d/1lt5IHOF6coEAS\\_IKO5hkHChEfz8n7YaA/view](https://drive.google.com/file/d/1lt5IHOF6coEAS_IKO5hkHChEfz8n7YaA/view)
46. Larimer County Strategic Plan 2019-2024.

# FRONT RANGE FIRE RESCUE

Item #15.

## 2022 ANNUAL REPORT



**COURAGE      COMPASSION      PROFESSIONALISM**

# Mission, Vision and Values

## Mission

Front Range Fire Rescue is an all-hazards emergency response and prevention agency. We are committed to providing outstanding service to our community through fire prevention, public education, fire suppression, emergency medical services, and disaster management.


## Vision

Members of Front Range Fire Rescue are committed to providing the highest quality service to the citizens and guests of the District. The vision that drives all members to continually strive to embrace the concept of continuous improvement and deliver the best citizen service possible is this:

*To further evolve a culture and a structure that outlasts us and that meets and exceeds the District's anticipated growth. To be recognized by our citizens and external stakeholders as an outstanding public service agency. To be an "employer of choice" for our current and future members.*

## Values

**Courage, Compassion, Professionalism**



# FRONT RANGE FIRE RESCUE



*From the Desk of Fire Chief Michael West*

January 1, 2023, marked a significant milestone at Front Range Fire Rescue; It was the 5<sup>th</sup> anniversary of the District. The District started as an Authority when the Milliken and Johnstown Fire Protection Districts joined forces in 2015. Then, after our residents' vote in 2017, it merged into the Front Range Fire District on this date in 2018.

In the last few years, we have set a foundation to prepare for the growth and change that our area is experiencing.

- We have increased career staff to respond quickly to your emergencies. We rely less on part-time staff that FRFR frequently trained only to leave for other jobs after a few months. Our attrition rate is now one of the lowest in the region. Over the next few years, we will continue to grow our ranks in preparation for future call volume.
- Our facilities have been updated to allow for more modern facilities for our firefighters and our partners from UC Health. In 2023 we will update Station 1 in Johnstown to allow for more office space, living space, and better training opportunities for future needs.
- We have written and continue to update our strategic plan and our FRFR Way document. Front Range Fire Rescue has a distinctive culture that we continue to develop.
- We have increased our presence in the community through social media, our new website, and more community outreach.
- We have enhanced automatic aid agreements with nearly all of our surrounding agencies. In 2023, we anticipate completing that process with all of our neighbors. There is no place for artificial boundaries in today's fire service, and our citizens deserve the fastest response possible.
- We have procured the property for Station 4 and will look to add the property for Station 5 this year. We are enhancing our training capabilities by looking for property for a new training facility.
- Our members are more thoroughly trained, educated, and compensated for the critical work they do for our citizens. Our new firefighters attend the Front Range Fire Consortium academy to start, and we have a comprehensive training program that takes them even further. A significant change has been the robust succession plan that we have added. This assures that our future leadership continues to raise the bar of service.
- Our financial footing is solid, with our reserves providing stability in uncertain times and being used to fund our future growth through careful data-driven analysis.

Our past has built a strong foundation for us to grow into the future. Without the decades of local volunteers and citizens who started our parent organizations, we would not be where we are today. We would have been behind the growth curve without the vision of our Board members, past and present, in creating this District. Our citizens can be proud of their firefighters and the service they provide. I am excited about our next chapter, and FRFR looks forward to continuing to serve you with Courage, Compassion, and Professionalism.

Yours in service,  
Michael West  
Fire Chief



# 2022 ACCOMPLISHMENTS

## NEW THERMAL IMAGING CAMERAS



FRFR completed a comprehensive evaluation of new Thermal Imaging Cameras (TICs) in 2022. Contrary to the scenes shown in popular movies and television shows, the inside of a burning building is filled with sight-obscuring smoke.

It's far from a campfire. Because of that, our firefighters navigate by using touch and walls as a road map. TICs have been used in the fire service for the last three decades to "see" through the smoke. They have revolutionized fire operations.

Some of FRFR's old TICs were among the first models offered in the fire service. This upgrade to the latest technology will give our members even more information to extinguish fires and save lives quickly. A cooperative purchase with Loveland Fire Rescue Authority saved us a great deal of money and will improve interoperability.



## DEPUTY CHIEF OF OPERATIONS

We promoted Chief Nat Kronholm to Deputy Chief of operations. In addition, we hired three new recruits. All three recently graduated from Front Range Fire Consortium Fire Academy in December and are now assigned as probationary firefighters.



## PANCAKE BREAKFASTS

In 2022 the Pancake breakfasts returned to both Johnstown and Milliken. The Roosevelt Baseball Team volunteered to prepare and serve food at both events.





# LIFE SAFETY & FIRE PREVENTION

## PUBLIC EDUCATION/COMMUNITY OUTREACH

	2021	2022
Car Seat Service	20	14
Blood Pressure Checks	10	20
Station Tour/Apparatus Demo	18	4
Education Sessions	14	9
Other Outreach Efforts	13	22
<b>ANNUAL COUNT</b>	<b>75</b>	<b>69</b>
<b>ANNUAL HOURS</b>	<b>88</b>	<b>101</b>
<b>INDIVIDUAL CONTACTS</b>	<b>2077</b>	<b>2874</b>




Deputy Chief Ty Drage




		2021			2022		
<b>INSPECTIONS</b>	<b>EXISTING CONSTRUCTION</b>	<b>#</b>	<b>Square Feet</b>	<b>Hours</b>	<b>#</b>	<b>Square Feet</b>	<b>Hours</b>
	General Inspection	130	2,227,424	242	106	1,936,591	238
	HazMat Inspection	13	52,349	23	31	2,422,822	60
	Re-inspection	3	35,030	3	5	294,960	8
	Complaint & Service Call	20	372,119	34	10	1,051,807	19
	Pre-Plans	40	442,194	71	72	772,016	116
	<b>NEW CONSTRUCTION</b>	<b>#</b>	<b>Square Feet</b>	<b>Hours</b>	<b>#</b>	<b>Square Feet</b>	<b>Hours</b>
	Building Construction	14	96,435	22	22	451,001	39
	Fire Alarm System	9	69,086	17	31	1,750,687	72
	Fire Protection Systems	23	149,411	45	44	3,002,903	84
HazMat Storage/Use	10	335,647	13	13	1,051,475	26	
<b>PLAN REVIEWS</b>	<b>PLAN REVIEWS</b>	<b>#</b>	<b>Square Feet</b>	<b>Hours</b>	<b>#</b>	<b>Square Feet</b>	<b>Hours</b>
	New Developments	34	228,096,188	85	37	134,575,136	116
	Site Plans	68	83,012,729	167	71	95,356,015	224
	Building Permits	29	1,434,884	119	81	3,604,125	264
	Fire Alarm Systems	37	457,507	29.5	33	1,987,719	87
	Fire Protection Systems	28	1,009,736	72	30	1,398,332	92
	HazMat Storage/Use	16	2,187,797	51	21	3,109,945	52
	Special Events or Hazards	18	1,619,100	45	38	8,144,500	113

# 2022 FINANCIAL STEWARDSHIP

## 2022 REVENUE \$ 5,575,423



## 2022 EXPENSES \$ 5,286,442



### EARLY BOND PAY-OFF!

Milliken Voters passed our \$1.5 million bond in 2003, then refinanced it in 2011. The bond helped construct Station 2 on South Irene Avenue in Milliken.


In 2022, Front Range Fire Rescue paid off that bond. This early payoff was accomplished thanks to the FRFR Board of Directors' conservative financial oversight and our district's growth. By paying off this debt early, we were able to save our citizens a considerable amount of interest. For those residents inside the former Milliken Fire Protection District boundary, you will see one less tax levy from Front Range Fire Rescue in 2023. Thank you for your continued support!

# 2022 RESPONSE & STATISTICS

## 2022 Incidents 2,762


# of Incidents by Hour of the Day

Incident Category ● Fire ● EMS ● Other



# of Incidents by Weekday and Incident Category


● Fire ● EMS ● Other




Top Stations by # of Incidents




# of Incidents by Shift



# of Incidents by Category




# of Incidents over Time



## Calls by Zone

■ 2021 ■ 2022





# TRAINING





**Cody Hinkle**  
Battalion Chief-Training

2022 was a busy year for our members in the way of training. Over 7,000 hours were logged, or about 250 per member. Besides the recruit academy and our probationary training manual for our new hires, the following topics were covered;

- Ice Rescue Training
- Officer development work and fireground command simulations
- Firefighter safety and survival
- Wellness training that included nutrition and peer support classes
- Live fire training with our automatic aid partners
- New SCBA orientation
- Driver operator training
- Hazmat training as part of our regional Hazmat Team
- Continuing education for our EMS certifications

The fire service is ever-evolving, and our members are constantly striving to hone their skills and knowledge to take care of our citizens' next emergency.



# OUR MEMBERS

## STAFFING UPDATE

### New Hires

Firefighter Chris Ingram  
Firefighter Eli Kershaw  
Firefighter Jacob Villa

### Promotions

Deputy Chief Nat Kronholm  
Battalion Chief Cody Hinkle  
Battalion Chief Zack Kirchner  
Lieutenant Nate Aldersea  
Engineer Zach Rodriguez  
Engineer Adam Nieto

10 YEARS



Battalion Chief Shane Doyon

Congratulations to these members who serve our District!



5 YEARS



Deputy Chief Ty Drage



Engineer Steve Lester



Firefighter Amanda Olig



Admin Cindy Heese





- In 2023, we will update Station 1 in Johnstown to allow for more office space, living space, and better training opportunities for future needs
- As an enhancement to the Emergency Plan we have with the Towns of Johnstown and Milliken, we are assigning a Battalion Chief to the new Emergency Manager position later in 2023
- Finalize property selection and purchase for Station 5 and a long term training ground solution
- Begin to add personnel in preparation for Fire Prevention demands and our next staffed fire company
- Improve our health and safety programs to include cancer screening and retiree health benefits for current members



During 2022, the FRFR leadership team worked extensively with the members of our Citizens Advisory Group to transition that group into a stand-alone non-profit foundation. We are currently working with legal counsel to file the necessary documents with the IRS to establish the FRFR Foundation as a 501(c)(3) entity.

The mission of the Front Range Fire Rescue Foundation is to improve the quality of life for citizens, visitors and emergency responders by supporting and enhancing safety education and outreach efforts within the FRFR service area.

We believe that the activities of the Foundation will improve public health and safety by providing a focus for enhanced safety education and outreach throughout the community. We think that community-focused education and outreach, targeted on the specific needs of our diversified community members, will allow FRFR to improve the overall well-being of the communities we serve.









# BOARD OF DIRECTORS




**PRESIDENT**  
WEST DISTRICT



**VICE PRESIDENT**  
EAST DISTRICT



**TREASURER**  
EAST DISTRICT




**SECRETARY**  
WEST DISTRICT



**DIRECTOR**  
AT LARGE

The public is welcome to attend all regularly scheduled board meetings, held on the second Tuesday evening of the month at 6:00 pm. For more information please go to our website [www.frfr.colorado.gov](http://www.frfr.colorado.gov)

## FRONT RANGE FIRE RESCUE



### CONTACT INFORMATION

970.587.4464

[INFO@FRFR.CO](mailto:INFO@FRFR.CO)

FOLLOW US ON

[www.frfr.colorado.gov](http://www.frfr.colorado.gov)

February 21, 2023

The regular meeting of the Glenn A. Jones, M.D. Memorial Library Board was called to order at 7:15 pm. Debi Sauer, Jenna Hall, Corina Strickland, Sheryl Ballard and Director Kristi Plumb were in attendance. Chad Young was absent.

The January 2023 minutes were approved. The financial report for January was reviewed and approved as follows:

January beginning balance	\$ 25,284.72	Petty Cash beginning balance	\$ 485.01
Inflow	98,038.45		-0-
Outflow	20,032.43		50.00
Ending balance	\$ 103,290.74		\$ 435.01

CO Trust: \$ 6,364,597.50

Treasurer Debi reports that we were overpaid last year from JT mill levy-2023 payment will be reduced by overage.

Director’s Report: Artist-in-Residence: Rita Valentine DePalatis displayed her cross stitch talent-old fashioned samplers.

Building: Floor behind front desk remains on FP warranty list-Kristi will confer Tyler regarding options. Sign possibilities for MakerSpace and conference room-Kristi will price.

MakerSpace: To reimburse our purchases, HPLD has an outstanding invoice of \$16,077. Once paid, HPLD will own the machines/licenses/warranties/liabilities to allow usage of the District internet. Currently, we are operating the most successful MakerSpace in the district!

Milliken: Kristi has received one bid from several inquiries for ventilation fan. She will converse with Town about time line for necessary electrical work. Janitorial work is serviced through the Town of Milliken, but building needs an intense cleaning. Bid of \$600 received from our current providers for one time deep clean. Kristi will research possible monthly clean.

Library of Things (LoT): Two record players purchased-one for building, one for loaning. Vinyl purchases are being researched-plan to reach 40-50 to appeal to diverse audience. Juvenile STEAM kits are most abused-missing pieces.

2022 Highlights: 1465.8 pounds collected for Milliken Food Pantry/2 Covid and Flu Clinics - 71 vaccines administered/95 retired flags collected for VFW/25 pairs of used glasses given to Lion’s Club/1416 for SRP/Accessibility Project completed/MakerSpace opened in August/Library of Things doubled in size/August visit from Alexander Hamilton-Chautauqua speaker/Library Staff participated in Johnstown’s BBQ Day parade (third place float), Milliken Beef n’ Bean parade (Honored Organization) and Milliken Festival of Lights parade/celebrated our 55<sup>th</sup> birthday on October 17<sup>th</sup>/red storage shed erected in October/joined United Way Diaper Distribution Program/Christmas Caring gift collection/answered 121 letters to Santa

2023 Goal: Check out more items...January 2023 up 655 from January 2022!

Employee Handbook Updates were discussed.

Meeting adjourned at 9:30 pm. Next meeting will be March 21, 2023.

January statistics:	Johnstown—door count: 6237	circulation—8067
	Milliken—door count: 332	circulation—357

Respectfully submitted, Sheryl Ballard, secretary

JONES MEMORIAL LIBRARY CASH FLOW REPORT - FEB 2023			Y-T-D	2023 BUDGET		Notes
BEGINNING CHECKING BALANCE		\$ 103,290.74	\$ -	\$ 20,000.00	To Date	
INFLOWS	Donations/Grants	\$ 225.00	\$ 225.00	\$ 3,500.00		
	Interest	\$ 82.02	\$ 47,996.50	\$ 75,000.00		
	Misc Income	\$ 5,947.89	\$ 5,980.12	\$ 7,500.00		
	<i>Investments</i>	\$ -	\$ -	\$ -		
	Town of Johnstown	\$ 103,786.43	\$ 201,680.62	\$ 1,243,246.00		
	High Plains Library District	\$ 3,285.22	\$ 3,285.22	\$ 811,068.00		
INFLOWS TOTAL		\$ 113,326.56	\$ 259,167.46	\$ -		
TOTAL AVAILABLE FUNDS		\$ 216,617.30		\$ 2,160,314.00		
OUTFLOWS	Advertising	\$ 1,508.00	\$ 3,443.00	\$ 22,000.00		
	Books - 250	\$ 3,235.89	\$ 6,640.53	\$ 50,000.00	516	
	DVD/Audio - 29	\$ 682.71	\$ 1,035.07	\$ 15,000.00	43	
	Library of Things	\$ 163.96	\$ 221.67	\$ 5,000.00		
	Collection Fees/Bad Debts	\$ -	\$ -	\$ 2,000.00		
	Computer Expenses	\$ -	\$ -	\$ 5,000.00		
	Equipment & Furniture	\$ -	\$ -	\$ 40,000.00		
	Maker Space	\$ 267.78	\$ 1,894.70	\$ 20,000.00		
	Gifts Given	\$ 208.82	\$ 328.20	\$ 2,500.00		
	Insurance, Bldg. Contents	\$ -	\$ -	\$ 5,000.00		
	<i>Investments</i>	\$ -	\$ -	\$ 339,314.00		
	Legal Fees/Consulting Fees	\$ -	\$ -	\$ 10,000.00		
	Maintenance	\$ 2,481.68	\$ 5,250.00	\$ 60,000.00		
	Memberships/Licenses	\$ 83.88	\$ 83.88	\$ 2,500.00		
	Milliken Location	\$ -	\$ -	\$ 20,000.00		
	Outreach	\$ -	\$ 129.72	\$ 10,000.00		
	Professional Enrichment	\$ -	\$ -	\$ 5,000.00		
	Programming	\$ 2,557.67	\$ 6,124.61	\$ 200,000.00		MS \$721.54
	Salaries/Compensation/Perks	\$ 1,347.58	\$ 1,347.58	\$ 600,000.00		
	Health Ins./Retirement	\$ -	\$ -	\$ 72,000.00		
	Workers' Comp	\$ -	\$ -	\$ 5,000.00		
	Subscriptions, Periodicals	\$ -	\$ 99.99	\$ 5,000.00		
	Supplies, Janitorial	\$ 106.72	\$ 341.04	\$ 3,000.00		
	Supplies/Expenses, Library	\$ 736.08	\$ 929.77	\$ 12,000.00		
	Telephone	\$ 545.11	\$ 1,068.31	\$ 10,000.00		
	Utilities	\$ 4,866.30	\$ 9,936.54	\$ 40,000.00		
	Capital Improvement	\$ -	\$ -	\$ 600,000.00		
OUTFLOWS TOTAL		\$ 18,792.18	\$ 38,874.61	\$ 2,160,314.00		
ENDING CHECKING BALANCE		\$ 197,825.12				

Item #15.



						Notes
BEGINNING PETTY CASH BALANCE		\$ 435.01				Item #15.
Programming		\$ -				
ENDING PETTY CASH BALANCE		\$ 435.01				
<b>COLORADO TRUST INVESTMENT</b>			<b>Y-T-D</b>			
BEGINNING BALANCE		\$ 6,364,597.50				
Dividend - 4.7379%		\$ 23,171.58	\$ 47,802.45			
Contribution		\$ -				
Withdrawal		\$ -				
ENDING BALANCE		\$ 6,387,769.08				